

NOTICE

All drawings located at the end of the document.

**1998 ANNUAL ROCKY FLATS CLEANUP AGREEMENT
(RFCA)**

GROUNDWATER MONITORING REPORT

for the

Rocky Flats Environmental Technology Site

November 30, 1999



Rocky Mountain
Remediation Service
... protecting the environment

RECORD CENTER

DOCUMENT CLASSIFICATION
REVIEW WAIVER PER
CLASSIFICATION OFFICE

ADMIN RECORD

SW-A-003446

X 549 Y 541

TABLE OF CONTENTS

1.0	INTRODUCTION	1
1.1	Site Description.....	1
1.2	Geology and Hydrogeology	3
1.2.1	Introduction	3
1.2.2	Stratigraphy.....	3
1.2.2.1	Rocky Flats Alluvium	6
1.2.2.2	Other Surficial Deposits	6
1.2.2.3	Arapahoe Formation	7
1.2.2.4	Laramie and Fox Hills Sandstone Formations.....	7
1.2.2.5	Pierre Formation	7
1.2.3	Geologic Structure.....	8
1.2.4	Hydrogeology.....	8
1.2.4.1	Definition of the Uppermost Aquifer for the Site	8
1.2.4.2	Groundwater Occurrence and Distribution.....	10
1.2.4.3	Groundwater Flow	11
1.2.4.4	Hydraulic Conductivity	12
1.3	Environmental History.....	13
1.3.1	Rocky Flats Cleanup Agreement.....	14
1.3.2	Integrated Monitoring Plan for Groundwater.....	15
1.3.3	Changes to the Groundwater Monitoring Program.....	22
2.0	GROUNDWATER DATA QUALITY ASSESSMENT.....	24
2.1	Methods	24
2.2	Discussion of Analyte Groups.....	44
2.2.1	Metals.....	44
2.2.2	Radionuclides.....	46
2.2.3	Volatile Organic Compounds.....	47
2.2.4	Water Quality Parameters.....	48
2.3	Data Summary for RFCA-Designated Wells Sampled in 1998.....	49
2.3.1	Data Screening.....	49
2.3.2	Values Above Tier I and Tier II Action Level Criteria.....	50
2.3.2.1	Boundary Wells	50
2.3.2.2	Drainage Wells	78
2.3.2.3	Performance Monitoring Wells	78
2.3.2.4	Plume Definition Wells.....	83
2.3.2.5	Plume Extent Wells	83
2.3.3	Upgradient Versus Downgradient Well Comparisons.....	90
2.3.3.1	Spatial Distribution of Groundwater Constituents	91
2.3.3.2	Statistical Evaluation of Groundwater Constituents.....	101
2.4	Discussion of Groundwater Plumes.....	104
2.4.1	Volatile Organic Compound Plumes.....	106
2.4.2	Nitrate Plumes.....	107
3.0	GROUNDWATER FLOW CONDITIONS DURING 1998	108
3.1	Potentiometric Surface Maps	108
3.2	Average Linear Flow Velocities.....	109
3.3	Well Hydrographs and Water Level Change Maps	113
4.0	GROUNDWATER EVALUATIONS.....	117
4.1	Industrial Area Plume.....	117
4.1.1	Introduction	117

4.1.2	Hydrogeology.....	119
4.1.3	Evaluation of Sampling Results.....	119
4.1.4	Plume Flux Calculations.....	127
4.1.5	Conclusions and Recommendations.....	128
4.2	PU&D Yard Plume Investigations.....	130
4.3	Carbon Tetrachloride Plume.....	134
4.3.1.1	Footing Drain Outfall Samples.....	140
4.3.1.2	Natural Attenuation.....	143
4.3.2	Electron Donors.....	145
4.3.2.1	Semivolatile Organic Suite.....	145
4.3.2.2	Total Organic Carbon and Dissolved Organic Carbon.....	145
4.3.3	Electron Acceptors.....	147
4.3.3.1	Carbon Tetrachloride.....	147
4.3.3.2	Dissolved Oxygen.....	150
4.3.3.3	Nitrate and Sulfate.....	150
4.3.4	Metabolic By-Products.....	152
4.3.4.1	Ferrous Iron.....	152
4.3.4.2	Sulfide.....	152
4.3.4.3	Methane.....	153
4.3.4.4	Chloride.....	153
4.3.5	Conclusions and Recommendations.....	153
4.3.5.1	Sampling Recommendations.....	154
5.0	BUILDING D&D.....	155
5.1	Building 123.....	156
5.2	Buildings 444, 771, and 886.....	158
5.3	Building 779.....	158
6.0	GROUNDWATER CHARACTERIZATION ACTIVITIES.....	161
6.1	Mound Plume/SW059.....	161
6.2	Solar Evaporation Ponds Nitrate/Uranium Plume.....	163
6.3	B-Ponds/East Trenches Plume.....	167
6.4	903 Pad/Ryan's Pit Plume.....	170
6.5	903 Pad.....	173
6.6	T-1 Trench Excavation.....	175
7.0	OTHER GROUNDWATER PROGRAM ACTIVITIES.....	178
7.1	Well Control Program.....	178
7.2	Real Time Groundwater Monitoring Network.....	178
7.3	Well Abandonment and Installation.....	182
8.0	CONCLUSIONS AND FUTURE ACTIVITIES.....	185
9.0	REFERENCES.....	187

FIGURES

Figure 1- 1.	Location of Rocky Flats Environmental Technology Site.....	2
Figure 1- 2.	Rocky Flats Environmental Technology Site Map.....	4
Figure 1- 3.	Generalized Stratigraphic Column for the Rocky Flats Area.....	5
Figure 1- 4.	Generalized Geological Cross Section of the Front Range and the Rocky Flats Areas.....	9
Figure 2-1.	Sulfate Trend Plot for Well 10294.....	58
Figure 2-2.	Tritium Trend Plot for Well 10394.....	58
Figure 2-3.	Nickel Trend Plot for Well 6486.....	58
Figure 2-4.	Nickel Trend Plot for Well 6586.....	59

Figure 2-5. Tetrachloroethene Trend Plot for Well 00897.....	59
Figure 2-6. Trichloroethene Trend Plot for Well 00897.....	59
Figure 2-7. Methylene Chloride Trend Plot for Well 00897.....	60
Figure 2-8. Tetrachloroethene Trend Plot for Well 02291.....	60
Figure 2-9. Carbon Tetrachloride Trend Plot for Well 11891.....	60
Figure 2-10. Tetrachloroethene Trend Plot for Well 11891.....	61
Figure 2-11. Carbon Tetrachloride Trend Plot for Well 12191.....	61
Figure 2-12. Tetrachloroethene Trend Plot for Well 12191.....	61
Figure 2-13. Trichloroethene Trend Plot for Well 3687.....	62
Figure 2-14. Carbon Tetrachloride Trend Plot for Well 3687.....	62
Figure 2-15. Trichloroethene Trend Plot for Well 05691.....	62
Figure 2-16. Carbon Tetrachloride Trend Plot for Well 05691.....	63
Figure 2-17. Tetrachloroethene Trend Plot for Well 12691.....	63
Figure 2-18. Carbon Tetrachloride Trend Plot for Well 12691.....	63
Figure 2-19. Selenium Trend Plot for Well 10592.....	64
Figure 2-20. Selenium Trend Plot for Well 10792.....	64
Figure 2-21. Selenium Trend Plot for Well 10992.....	64
Figure 2-22. Nitrate Trend Plot for Well 10992.....	65
Figure 2-23. Trichloroethene Trend Plot for Location 891COLWEL.....	65
Figure 2-24. Tetrachloroethene Trend Plot for Location 891COLWEL.....	65
Figure 2-25. Selenium Trend Plot for Location 891COLWEL.....	66
Figure 2-26. Trichloroethene Trend Plot for Well 07391.....	66
Figure 2-27. Tetrachloroethene Trend Plot for Well 07391.....	66
Figure 2-28. Uranium-238 Trend Plot for Well 07391.....	67
Figure 2-29. Tetrachloroethene Trend Plot for Location SW13494.....	67
Figure 2-30. Trichloroethene Trend Plot for Well 22896.....	67
Figure 2-31. Carbon Tetrachloride Trend Plot for Well 03991.....	68
Figure 2-32. Tetrachloroethene Trend Plot for Well 03991.....	68
Figure 2-33. Trichloroethene Chloride trend Plot for Well 03991.....	68
Figure 2-34. Trichloroethene Trend Plot for Well 04991.....	69
Figure 2-35. Methylene Chloride Trend Plot for Well 04991.....	69
Figure 2-36. Methylene Chloride Trend Plot for Well 06091.....	69
Figure 2-37. Tetrachloroethene Trend Plot for Well 06091.....	70
Figure 2-38. Nitrate Trend Plot for Well 06091.....	70
Figure 2-39. Manganese Trend Plot for Well 23296.....	70
Figure 2-40. Trichloroethene Trend Plot for Well 1786.....	71
Figure 2-41. Vinyl Chloride Plot for Well 3586.....	71
Figure 2-42. Methylene Chloride Trend Plot for Well P219489.....	71
Figure 2-43. Nitrate Trend Plot for Well 1786.....	72
Figure 2-44. Nitrate Trend Plot for Well B208289.....	72
Figure 2-45. Nitrate Trend Plot for Well P218389.....	72
Figure 2-46. Nitrate Trend Plot for Well P219489.....	73
Figure 2-47. Nickel Trend Plot for Well 1386.....	73
Figure 2-48. Selenium Trend Plot for Well 1786.....	73
Figure 2-49. Manganese Trend Plot for Well 3586.....	74
Figure 2-50. Manganese Trend Plot for Well B208789.....	74
Figure 2-51. Trichloroethene Trend Plot for Well 1986.....	74
Figure 2-52. Trichloroethene Trend Plot for Well 22696.....	75
Figure 2-53. Trichloroethene Trend Plot for Well 22796.....	75
Figure 2-54. Manganese Trend Plot for Well 1986.....	75
Figure 2-55. Manganese Trend Plot for Well 7086.....	76
Figure 2-56. Manganese Trend Plot for Well 22796.....	76
Figure 2-57. Selenium Chloride Trend Plot for Well 10994.....	76
Figure 2-58. Manganese Trend Plot for Well P114389.....	77
Figure 2-59. Methylene Chloride Trend Plot for Well 5387.....	77

Figure 2- 60. Arsenic in Selected Downgradient Wells at Present Landfill.....	95
Figure 2- 61. Cadmium in Selected Downgradient Wells at Present Landfill.....	95
Figure 2- 62. Fluoride in Selected Downgradient Wells at Present Landfill.....	95
Figure 2- 63. Iron in Selected Downgradient Wells at Present Landfill.....	96
Figure 2- 64. Lithium in Selected Downgradient Wells at Present Landfill.....	96
Figure 2- 65. Manganese in Selected Downgradient Wells at Present Landfill.....	96
Figure 2- 66. Molybdenum in Selected Downgradient Wells at Present Landfill.....	97
Figure 2- 67. Nitrate in Selected Downgradient Wells at Present Landfill.....	97
Figure 2- 68. Selenium in Selected Downgradient Wells at Present Landfill.....	97
Figure 2- 69. Strontium (metal) in Selected Downgradient Wells at Present Landfill.....	98
Figure 2- 70. Sulfate in Selected Downgradient Wells at Present Landfill.....	98
Figure 2- 71. Total Dissolved Solids in Selected Downgradient Wells at Present Landfill.....	98
Figure 2- 72. Uranium-233/234 in Selected Downgradient Wells at Present Landfill.....	99
Figure 2- 73. Uranium-235 in Selected Downgradient Wells at Present Landfill.....	99
Figure 2- 74. Uranium-238 in Selected Downgradient Wells at Present Landfill.....	99
Figure 2- 75. Zinc in Selected Downgradient Wells at Present Landfill.....	100
Figure 4- 1. North Industrial Area Potentiometric Surface.....	118
Figure 4- 2. North Industrial Area Trichloroethene in Groundwater Wells.....	121
Figure 4- 3. North Industrial Area Carbon Tetrachloride in Groundwater Wells.....	122
Figure 4- 4. North Industrial Area Chloroform in Groundwater Wells.....	123
Figure 4- 5. North Industrial Area 1,1-Dichloroethene in Groundwater Wells.....	124
Figure 4- 6. North Industrial Area Vinyl Chloride in Groundwater Wells.....	125
Figure 4- 7. PU&D Yard 1997 Groundwater VOC Plume.....	131
Figure 4- 8. Groundwater Intercept and Diversion System Layout at the Present Sanitary Landfill 1998.....	133
Figure 4- 9. Location Map IHSS 118.1 Wells.....	141
Figure 4- 10. Nitrate, DOC, TOC, Sulfide, Ferrous Iron and DO Concentrations at IHSS 118.1.....	146
Figure 4- 11. Carbon Tetrachloride and Chloroform Concentrations at IHSS 118.1.....	148
Figure 4- 12. Methylene Chloride, Chloromethane and Methane Concentrations at IHSS 118.1.....	149
Figure 4- 13. Chloride and Sulfate Concentrations at IHSS 118.1.....	151
Figure 5- 1. Building 123 Location Map with D&D Monitoring Wells.....	157
Figure 5- 2. Building 779 Location Map with D&D Monitoring Wells.....	159
Figure 6- 1. Mound Site Plume Area.....	162
Figure 6- 2. Plan View of Reactive Barrier Treatment System Solar Ponds Plume.....	165
Figure 6- 3. East Trenches Plume Study Area.....	168
Figure 6- 4. 903 Pad/Ryan's Pit Area Location Map.....	171
Figure 6- 5. VOC Investigation Borehole Location Map 903 Pad.....	174
Figure 6- 6. Trench 1 Site Location.....	176
Figure 7- 1. Real-Time Groundwater Monitoring Well Locations.....	180
Figure 7- 2. Well Abandonments and Completions.....	183

TABLES

Table 1-1. Groundwater Monitoring Wells.....	17
Table 1-2. Monitoring Well Sample Suites.....	19
Table 2- 1. Summary of Samples Collected Groundwater 1998.....	25
Table 2- 2. RFCA - Relative Percent Differences and Duplicate Error Ratios.....	29
Table 2-3. Summary of RPD and DER Results.....	36
Table 2-4. Comparison of Analytical Methods and Detection Limits.....	37
Table 2-5. Rinsate QC Results with Detections.....	39
Table 2-6. Comparison of Required and Actual Samples Collected.....	42
Table 2-7. Summary of Validation and Verification Completeness.....	43
Table 2- 8. 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells.....	51
Table 2- 9. RFCA-Designated Wells with No Analytes Above Tier II Action Levels.....	57
Table 2- 10. Well Completion Information and Sampling Summary for Present Sanitary Landfill Wells.....	92

Table 2- 11. Groundwater Sample and Detection Summary for Present Sanitary Landfill Wells	102
Table 2- 12. Comparative Statistics for Groundwater Analytes with <50 Percent Sample Non-Detections Present Sanitary Landfill	105
Table 3- 1. Average Linear Flow Velocities for the Industrial Area and Vicinity.....	111
Table 4- 1. Volatile Organic Compounds in Groundwater No. IA Plume	120
Table 4- 2. Flux Calculation Data	129
Table 4- 3. Groundwater Intercept System Analytical Data present Sanitary Landfill/PU&DYard.....	135
Table 4- 4. Sample Types/Analytical Methods	142
Table 4- 5. Checklist for Determination of Biodegradation.....	144

PLATES

PLATE 1.	IMP Monitoring Well Location Map
PLATE 2.	Potentiometric Surface of Consolidated Surficial Deposits - Second Quarter, 1998
PLATE 3.	Potentiometric Surface of Consolidated Surficial Deposits - Fourth Quarter, 1998
PLATE 4.	Radionuclides in Groundwater, RFCA Wells, 1998
PLATE 5.	VOCs in Groundwater, RFCA Wells, 1998
PLATE 6.	Water Quality Paramters in Groundwater, RFCA Wells, 1998
PLATE 7.	Nitrate Concentration in Groundwater, 1991-1998 Avg.
PLATE 8.	Water Level Change Map, 1996-1998, 2nd Quarter Data
PLATE 9.	Water Level Change Map, 1996-1998, 4th Quarter Data
PLATE 10.	VOCs Composite Plume Map
PLATE 11.	Real-Time Groundwater Monitoring Locations Data with Precipitation Data

APPENDICES

Appendix A.	1998 Water Level Data
Appendix B.	Well Hydrographs
Appendix C.1.	1998 Monitoring Well Logs
Appendix C.2.	1998 Well Construction Diagrams

EXECUTIVE SUMMARY

This report, which is required annually by the Rocky Flats Cleanup Agreement (RFCA, 1996), summarizes the groundwater compliance activities and results at the Rocky Flats Environmental Technology Site (RFETS) for calendar year (CY) 1998. The report is presented in one volume which contains text, tables, figures, plates and appendices.

Section 1 serves as a brief introduction to the report and summarizes the Site environmental history and hydrogeologic setting. Section 2, Data Analysis, discusses the groundwater quality data collected in CY98 and contains a data quality assessment regarding the precision, accuracy, representativeness, completeness, and comparability (PARCC parameters) of analytical data. In addition, Section 2 contains updated composite plume maps for volatile organic compounds (VOCs) and nitrate. Section 3 presents groundwater flow conditions during CY98, and compares them to groundwater flow conditions documented during CY96. Hydrologic conditions during calendar year 1996 are considered to represent a sitewide baseline to be used in assessing annual changes to the groundwater flow system in the remaining years of plant closure and post-closure monitoring. Section 4, Groundwater Evaluations, discusses the evaluation activities that are in progress for areas of the Site having reportable concentration values or where it is known that contaminant plumes have reached surface water. Section 5 presents a summary of decontamination and decommissioning (D&D) activities, with respect to groundwater, that have taken place during 1998. Section 6 presents a summary of other CY98 groundwater characterization activities at RFETS that involved groundwater issues. Section 7 serves to outline other Groundwater Program activities including the Well Control Program (WCP), the real time groundwater monitoring network, 1998 well abandonment and installation activities, and a summary of activities at the Present Landfill. Section 8 presents conclusions and recommendations for future groundwater characterization activities. Section 9 lists all references that are cited in the text of this document.

There are four appendices to this report. Appendix A consists of CY98 water level data. Appendix B presents well hydrographs. Appendix C.1 presents 1998 borehole logs. Appendix C.2 presents 1998 well construction logs

1.0 INTRODUCTION


This Annual Groundwater Monitoring Report summarizes the groundwater monitoring activities and results at Rocky Flats Environmental Technology Site RFETS for calendar year 1998 (CY98), as required in the Rocky Flats Cleanup Agreement (RFCA), and outlined in the Integrated Monitoring Plan (IMP) (K-H, 1998a). Section 1 serves as a brief introduction to the report. Section 2 discusses the groundwater quality data collected in CY98. Section 3 presents baseline hydrogeologic data for the recently defined RFCA groundwater monitoring network. Section 4 discusses the groundwater evaluation activities that are in process. Section 5 discusses Building Decontamination and Decommissioning (D&D) with respect to groundwater issues. Sections 6 and 7 give a brief summary of pre-remedial characterization and other activities at RFETS in CY98 that involve groundwater.

1.1 Site Description

Rocky Flats Environmental Technology Site is located 16 miles northwest of Denver in Jefferson County, Colorado. The Site is a U.S. government-owned and contractor-operated facility that encompasses approximately 6,550 acres of federally-owned land (Figure 1-1). Site ownership, however, does not include surface and subsurface minerals or water rights. Site construction was initiated in 1951 and operations were begun in 1952.

Prior to the current closure mission, RFETS was part of the nationwide nuclear weapons research, development, and production complex. The plant produced metal components for nuclear weapons from plutonium, uranium, beryllium, and stainless steel. Other production activities included chemical recovery and purification of recyclable transuranic radionuclides, metal fabrication and assembly, and related quality control functions. The plant conducted research and development programs in metallurgy, machining, nondestructive testing, coatings, remote engineering, chemistry, and physics. Parts manufactured at the Site were shipped offsite for final assembly.

Major plant structures, including all production buildings, are located within a centralized 400-acre Industrial Area (IA) of the Site that is surrounded by a 6,150-acre Buffer Zone. Industrial activity immediately adjoining the Site includes present and/or prior coal and clay mining, petroleum recovery, natural classified-aggregate quarrying, and fabricated-aggregate mining. Other activities include cattle ranching and wind energy research. Several irrigation ditches traverse the Site, transmitting water for



**Figure 1-1 Location of
Rocky Flats Environmental Technology Site
(RFETS)**

downstream agricultural, industrial, and municipal purposes. Three ephemeral streams drain the Site and flow eastward (see Figure 1-2).

1.2 Geology and Hydrogeology

1.2.1 Introduction

The Site is situated approximately two miles east of the Front Range of Colorado (Figure 1-1), on the western margin of the Colorado Piedmont section of the Great Plains Physiographic Province (Spencer, 1961). Haun and Kent (1965) have summarized the geologic history of the Colorado Rocky Mountain region, which includes the Site area. The elevation at the Site is approximately 6,000 feet above mean sea level (MSL). The Industrial Area of the Site is located on an alluvial-covered pediment. The upper surface of the alluvium slopes easterly 1 to 2 degrees. Most of the surrounding area in the Buffer Zone is more prominently dissected with intermittent streams. These small, eastward flowing streams include Rock Creek, Walnut Creek, Woman Creek, and several surface water diversion ditches.

1.2.2 Stratigraphy

The stratigraphic sequence that underlies the Site extends from the crystalline Precambrian gneiss, schist, and granitoids at 3,000 feet below MSL to the unconsolidated Quaternary deposits at the surface approximately 6,000 feet above MSL. Based upon aerial photographic interpretation, field geologic mapping, coal and aggregate mine development, petroleum exploration in the vicinity, and numerous borehole investigations, a substantial amount of lithologic information has been gained about the Site. The generalized lithologic section in the Rocky Flats area is shown in Figure 1-3.

Bedrock formations from the uppermost Cretaceous Pierre, Fox Hills, Laramie, and Arapahoe Formations are present and exposed at the surface or lie beneath the Site. The Quaternary Rocky Flats Alluvium, and to a limited extent Verdos Alluvium, unconformably overlie the Cretaceous Arapahoe and Laramie Formations in the central portion of the Site. The unconsolidated surficial deposits, combined with the weathered portion of subcropping bedrock formations, form the sequence of rocks that have the greatest importance regarding groundwater flow and contaminant transport at the Site.

Final 1998 Annual RFCA Groundwater Monitoring Report




Figure 1-3
Generalized Stratigraphic
Column for the Rocky Flats Area



Rocky Mountain Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 464
Golden, CO 80402-0464

1.2.2.1 Rocky Flats Alluvium

Scott (1975) has identified several Quaternary alluvial formation pediment covers in the vicinity of the Site. The Rocky Flats Alluvium is an unconsolidated deposit derived from quartzites and granites of the Coal Creek Canyon provenance west of the Site. The deposit diminishes from west to east with thicknesses ranging from approximately 100 feet to less than one foot. In the central portion of the Site the deposit is approximately 15 to 25 feet thick. The Rocky Flats Alluvium is a heterogeneous deposit dominantly composed of angular to subrounded, poorly-sorted, coarse, bouldery-gravel with a clay and sand matrix. Clay, silt, and sand lenses as well as varying amounts of caliche are also present.

Exposures of Rocky Flats Alluvium in the aggregate quarries north and west of the Site exhibit some large scale cross-stratification. Depositional processes include fluvial and debris-flow transport (Shroba and Carrara, 1994) infilling paleotopographic lows and leaving a widespread surface of erosion with extremely low relief.

1.2.2.2 Other Surficial Deposits

In addition to the pediment-forming alluvial deposits, younger Quaternary units consisting of colluvium, landslide alluvium, and valley fill alluvium mantle the hillslopes and valley bottoms below the pediment surface. Colluvial deposits are derived from Arapahoe and Laramie Formations and older alluvial deposits. This unit consists of sheetwash, soil creep, and landslide materials with a total thickness of 3 to 16 feet (Shroba and Carrara, 1994). These deposits locally flank the Rocky Flats Alluvium and generally extend to lower parts of the slopes along the principal drainages.

Landslide deposits more commonly flank the Rocky Flats Alluvium. They are often bounded by headwall scarps and lobate toes at the downslope margins. Seeps issuing from the base of the Rocky Flats Alluvium contribute to landslide colluvium generation. The landslide units include earth flows, slumps, and debris flows with thicknesses estimated between 10 to 33 feet (Shroba and Carrara, 1994).

Valley-fill alluvial deposits, present in the bottoms of modern stream channels, flood plains, and terraces, are composed of clay, silt, sand, and gravel. They are commonly less than 10 feet thick but can be tens of feet thick. Usually these deposits contain more sand and are more well-sorted than the Rocky Flats Alluvium.

1.2.2.3 Arapahoe Formation

The Arapahoe Formation is composed of claystone and silty claystone with lenticular sandstone in the basal portion of the formation. The Arapahoe Formation is generally less than 25 feet thick in the Site area, occurring as erosional remnants of fine grained sandstone above the Laramie Formation at various locations on Site (EG&G, 1995a). This basal Arapahoe Formation sandstone, which is currently defined as the No. 1 Sandstone, is of concern as a potential contamination pathway, especially where it subcrops beneath the alluvial/bedrock unconformity.

1.2.2.4 Laramie and Fox Hills Sandstone Formations

The Laramie Formation is approximately 600 to 800 feet thick and is composed of a lower sandstone/claystone/coal interval and an upper, thick claystone interval. Within the upper claystone interval, thin, lenticular sandstone lenses (i.e., Sandstones 2 through 5 in the 1991 Geologic Characterization Report (EG&G, 1991a)) occur. The discontinuous nature of these sandstone lenses coupled with the large claystone layer that encloses them mitigates their potential for transmitting groundwater contamination in both a horizontal and vertical direction.

The Fox Hills sandstone is primarily fine-grained sandstone with thin siltstone and claystone interbeds and an approximate thickness of between 75 and 125 feet. The Fox Hills sandstone crops out and subcrops along a narrow, north-south trending pattern in the extreme western part of the Site, upgradient from known sources of contamination.

The permeable lower sandstones and coals of the Laramie, combined with the permeable sandstones of the Fox Hills, constitute a regional aquifer system known as the Laramie-Fox Hills aquifer. This aquifer system is an important water source in the South Platte River Basin (Pearl, 1980), and is the sole water supply for some residents in the Rocky Flats area. This aquifer lies approximately 500 to 600 feet below the Industrial Area and is protected from possible contamination by the intervening Laramie Formation claystones.

1.2.2.5 Pierre Formation

The Pierre Formation is a 7,500-foot thick, dark gray, silty bentonitic shale that acts as a lower confining layer for the Laramie-Fox Hills aquifer in the Denver Basin. This thick marine shale unit subcrops only in the extreme western part of the Site.

1.2.3 Geologic Structure

The Site is located along the western margin of the Denver Basin, an asymmetric basin with a steeply east-dipping western flank and a gentle eastern flank. The interpretation of the subsurface structure is generalized in the east-west geological cross section of the Site area presented in Figure 1-4. A monoclinial fold limb exposed west of the Site is the most significant surficial structural feature in the Site area. Along the west limb of the fold, an angular unconformity exists between the Upper Cretaceous bedrock and the base of the Quaternary Rocky Flats Alluvium.

No active faults have been identified at the Site. Several high angle bedrock faults have been inferred to exist in the IA based on various stratigraphic and borehole correlation criteria. These faults appear to have only a limited hydrologic significance with regard to vertical groundwater movement and contaminant transport (RMRS, 1996a).

1.2.4 Hydrogeology

This section presents the basic concepts about the hydrogeologic conditions at the Site that affect groundwater monitoring and protection. Characterization of the hydrogeologic setting is based on the currently accepted conceptual geologic and hydrogeologic models described in the Sitewide Geoscience Characterization Study (EG&G, 1995a; 1995b; 1995c). These conceptual geologic and hydrogeologic models are used to predict the direction and rate of groundwater flow, identify potential pathways for contaminant migration, and determine the extent of contaminant plumes given varying physical, chemical, and biological factors.

1.2.4.1 Definition of the Uppermost Aquifer for the Site

The term *aquifer* as defined by 40 CFR Section 260.10 is a “geologic formation, group of formations, or a part of a formation that is capable of yielding a significant amount of water to a well or spring.” An *uppermost aquifer* is also defined as “the geologic formation nearest the natural ground surface that is an aquifer, as well as lower aquifers that are hydraulically interconnected with this aquifer within the facility’s boundary.” Geologic materials with similar hydrologic properties comprise a hydrostratigraphic unit (HSU) (Fetter, 1988). For purposes of this report, the uppermost aquifer or upper hydrostratigraphic unit (UHSU) consists of the unconfined saturated zone, in which unconsolidated and consolidated groundwater-bearing strata are in hydraulic communication. The UHSU consists of the following geologic units: Rocky Flats Alluvium, valley-fill alluvium, colluvium, landslide deposits, weathered

Geologic Units

Qv	Verdos Alluvium
Ka	Rocky Flats Alluvium
Kl	Arapahoe Formation
Kth	Laramie Formation
Kp	Fox Hills Sandstone
Kn	Pierre Shale/Hygiene Member
Kb	Niobrara Formation
Kd	Benton Shale
Kf	Dakota Group
Kp	Morrison Formation
Ly	Lykins Formation
Ly	Lyons & Fountain Formations
Met	Undivided Igneous & Metamorphic Units




Figure 1-4
Generalized Geologic Cross Section of the
Front Range and the Rocky Flats Area

Structural interpretation from EG&G, 1995a.

Rocky Mountain Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 464
Golden, CO 80402-0464

99-0465

Arapahoe and Laramie Formation bedrock, and all sandstones within the Arapahoe and upper Laramie Formations in hydraulic communication with the overlying unconsolidated surficial deposits. The UHSU is considered to be equivalent to the uppermost aquifer at the Site.

Beneath the surficial materials and the consolidated sandstones of the UHSU are the geologic units of the lower hydrostratigraphic unit (LHSU). The LHSU consists of the consolidated, unweathered bedrock zone of the Arapahoe and upper Laramie Formations not in hydraulic communication with the overlying UHSU. The Arapahoe and upper Laramie Formations comprising the geologic units of the LHSU consist of lesser amounts of sandstone and greater amounts of adjacent claystones. Because of the low permeability of the claystones, they behave as aquitards restricting hydraulic communication with the UHSU. The lower Laramie and Fox Hills Sandstone Formations comprise a stratigraphically lower and third hydrostratigraphic unit beneath the site. Groundwaters of the three hydrostratigraphic units are hydraulically separated beneath the IA. They do converge, however, and are in mutual contact immediately upgradient near the western margin of the Site due to monoclinal folding and erosional proximity. Initially, background geochemical characterization of the UHSU and LHSU revealed that these units have statistically different groundwater chemistry concluding with the delineation of separate hydrostratigraphic units (EG&G, 1993a). In addition, possible communication of the hydrostratigraphic units along other geologic structures is currently being assessed. More detailed differentiation of the LHSU will be achieved as new hydrogeologic and geochemical data are generated from Site investigations currently proposed or in progress.

1.2.4.2 Groundwater Occurrence and Distribution

The Site is located in a regional groundwater recharge area (EG&G, 1991a). Groundwater recharge occurs from the infiltration of incident precipitation and as base flow near the upgradient area of the Site drainage basin that extends west to Coal Creek. Groundwater recharge occurs from the infiltration of precipitation and from stream, ditch, and pond seepage. Much of the groundwater that discharges from the UHSU to streams and seeps evaporates as it is being discharged. Limited investigation of the former OU2 area during the period of July through October 1993 indicated that the precipitation component of recharge was lost to evapotranspiration demands (EG&G, 1993b).

In the western part of the Site, where the thickness of the Rocky Flats Alluvium reaches 100 feet, the depth to the water table is 50 to 70 feet below the surface. The depth to water generally becomes shallower from west to east as the alluvial material thins and the confining claystones are closer to the ground surface. At the head of stream drainages and along valley sides, seeps are common at the base of

the Rocky Flats Alluvium where it is in contact with claystones of the Arapahoe/Laramie Formations, and where the Arapahoe Formation sandstone crops out. In general, the unconsolidated surficial materials are thicker in the western, higher elevations at the Site. Accordingly, the saturated thickness of these materials also thins eastward. The potentiometric surface of groundwater in unconsolidated surficial deposits has been mapped and is shown on Plates 2 and 3. The periods illustrated represent the times of year when static water levels are expected to be both high and low. Areas of unsaturated and seasonally unsaturated alluvium and colluvium are indicated east and northeast of the IA.

Groundwater in the Arapahoe Formation sandstone units, which subcrop beneath the alluvial material, is not confined when in contact with the surficial materials. In this setting, a hydraulic connection exists between the bedrock sandstone and the alluvial material allowing the bedrock groundwater to exist under unconfined conditions as part of the UHSU. The subcropping Arapahoe Formation No. 1 Sandstone, located in the eastern portion of the IA and in the area between South Walnut Creek and Woman Creek, is part of the UHSU (EG&G, 1991a). The upper discontinuous sandstones of the Laramie Formation also subcrop beneath alluvium and colluvium, but in limited areas in the valleys and along valley slopes. Groundwater in the lenticular sandstone units of the Laramie Formation occurs under confined conditions over scattered areas of the Site.

Groundwater levels in UHSU wells fluctuate in response to seasonal recharge events. Approximately 15 percent of the groundwater monitoring wells are commonly dry during at least one of the quarterly sampling events. Of the remaining wells, approximately half cannot yield sufficient water volume (4.5 gallons) necessary for a full suite of laboratory samples. Sampling crews must return later after wells have recovered to obtain additional sample volumes.

1.2.4.3 Groundwater Flow

The shallow groundwater flow regime at the Site is illustrated by the configuration of potentiometric contours in Plates 2 and 3. These maps indicate that groundwater flow is largely controlled by the topography of the bedrock surface. Groundwater in the ridge tops generally flows toward the east-northeast. In areas where the ridge tops are dissected by east-northeast trending stream drainages, groundwater flows to the north or south toward the bottom of the valleys. In the valley bottoms, groundwater flows to the east, generally following the course of the stream. Shallow groundwater flow is primarily lateral due to the low permeability of the underlying claystone bedrock.

A potential for vertical groundwater flow, although limited by the low permeability of bedrock claystones, is indicated by the presence of strong downward vertical hydraulic gradients between the

UHSU and underlying bedrock units. This situation implies a condition of poor hydraulic communication. For example, vertical gradients on the order of 0.79 to 1.05 ft/ft have been calculated between colluvial and bedrock sandstones. The vertical groundwater flux through claystones is assumed to be small, on the order of 10^{-10} to 10^{-7} cm/sec, based on calculations provided in RMRS (1996a). Fracturing, where evident, is most abundant in the weathered bedrock zone, but is observed to decrease with depth in unweathered bedrock. Preferential vertical groundwater flow and contaminant transport along fractures or fault zones does not appear to represent a viable pathway for contaminant migration based on an assessment of available data (RMRS, 1996a).

1.2.4.4 Hydraulic Conductivity

The UHSU at the Site has a relatively low to moderate hydraulic conductivity that typically yields small amounts of water to groundwater monitoring wells. The UHSU exhibits a wide-range of hydraulic conductivities because of the diverse nature of the individual geologic units that comprise this unit. Summary statistics for UHSU hydraulic conductivities (EG&G, 1995c, Table G-2) indicate a range of 5.0×10^{-2} cm/sec to 3×10^{-8} cm/sec. Listed in order of decreasing geometric mean hydraulic conductivity, the relative ranking of individual units of the UHSU is presented as follows: valley-fill alluvium (2.5×10^{-3} cm/sec); Arapahoe No. 1 sandstone (7.9×10^{-4} cm/sec); Rocky Flats Alluvium (2.1×10^{-4} cm/sec); colluvium (9.3×10^{-5} cm/sec); weathered Laramie Formation sandstones (3.9×10^{-5} cm/sec); and weathered Laramie Formation claystones (8.8×10^{-7} cm/sec).

Hydraulic conductivities for LHSU materials are generally the lowest measured at the Site with geometric mean values for individual lithologic groups ranging from 1.6×10^{-7} to 5.8×10^{-7} cm/sec (EG&G, 1995c, Table G-2). The low permeability and 600+ foot thickness of the upper Laramie Formation claystones act as an effective aquitard that restricts downward vertical groundwater flow and contaminant transport to the Laramie-Fox Hills aquifer (RMRS, 1996a).

In summary, the following major geologic and hydrologic parameters influence groundwater flow at the Site (EG&G, 1995a; 1995b):

- (1) Topography controls the surface waters of the upslope drainage basin which in part recharges groundwater and the three principal streams draining the Site. The majority of shallow groundwater is intercepted by these drainages.
- (2) The lithology and permeability of the unconsolidated surficial deposits permit meteoric waters to recharge the water table. The water table is contained in alluvium and weathered bedrock.
- (3) Paleotopography of the bedrock pediment, which is less permeable than the overlying

unconsolidated surficial deposits, serves to focus groundwater movement along bedrock "lows."

- (4) Paleoweathering of shallow bedrock materials has enhanced the permeability of the upper 10 to 60 feet relative to unweathered bedrock.

The permeability of bedrock units, composed primarily of claystone with lesser amounts of siltstone and sandstone, is generally several orders of magnitude less than for unconsolidated surficial deposits. The 600+ feet of unweathered bedrock between the shallow groundwater flow system and deep regional Laramie-Fox Hills aquifer provides an effective barrier to vertical groundwater and contaminant movement.

1.3 Environmental History

Processing and fabrication of weapons-related components began at the Site in 1952 and continued through 1989. Fabrication of stainless steel components continued, however, in one building through the early 1990's. During operation, environmental protection measures were established that seemed consistent with prudent environmental management. However, some activities resulted in the environmental contamination of portions of the Site. Efforts to document the extent of Site contamination are in progress, in accordance with the Resource Conservation and Recovery Act (RCRA), the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), and the RFCA, a cooperative agreement between U.S. Department of Energy (DOE), U.S. Environmental Protection Agency (EPA), and Colorado Department of Public Health and Environment (CDPHE). In addition, a historical release report (HRR) (DOE, 1992a) has been developed that documents knowledge gained to date about contamination arising from past practices. The HRR is updated on an annual basis with the knowledge gained from ongoing monitoring and investigative activities on site. The additional information is submitted on an annual basis to the EPA and CDPHE as addenda to the original document.

Documented areas of soil contamination have been designated as Individual Hazardous Substance Sites (IHSSs). Many of these IHSSs have been characterized as part of the Remedial Investigation/Feasibility Study (RI/FS) process which was conducted under the Interagency Agreement (IAG, 1991) between DOE, CDPHE and EPA. Some IHSSs have already been remediated and others are currently scheduled for excavation and treatment by the Environmental Restoration Department in accordance with a Site environmental remediation priority ranking system.

Groundwater investigations at the Site have determined that some IHSSs have released hazardous and radionuclide contaminants to groundwater. The most widespread contamination is that of volatile organic compounds (VOCs). Plate 10 shows the distribution of VOC contamination in the UHSU. Plume

definition is inexact however, because of limitations in well coverage, variability of hydrostratigraphic conditions, and local variations in groundwater transport velocity. Previously published plume maps for individual constituents can be found in the 1993 Well Evaluation Report (EG&G, 1994a), the annual RCRA Groundwater reports (EG&G, 1992, 1993c, 1994b, 1995d; RMRS/KH, 1996) and in individual OU RI/RFI reports.

Compared to all other contaminants, groundwater VOC plumes at RFETS have the greatest potential to impact surface water, based on spatial distribution and concentration considerations. These plumes have been defined on the basis of concentration values above the RFCA Tier II Action Level for individual constituents. Action levels at RFETS are derived from and are similar to regulated maximum concentration limits (MCLs). To delineate areas of highly contaminated groundwater, the Tier I groundwater action levels of 100 x Tier II Action Levels were compared against all groundwater data for the most common VOCs in groundwater. Values above Tier I and Tier II Action Levels were plotted and are shown on Plate 10. The most probable sources were identified using the results of recent field sampling programs and correlating this with our knowledge of Site processes (see RMRS, 1996b). A flow diagram (RMRS, 1996b) illustrates the method used to locate the contaminant plumes and corresponding sources, and to assist in determining which areas should be evaluated for potential remedial action. Other contaminants will also be addressed where there is a potential impact to surface water above action levels.

Six VOC groundwater contaminant plumes have been identified where contaminant concentrations are above Tier I Action Levels. These groundwater contaminant plumes include the IHSS 119.1 Plume, Mound Plume, 903 Pad and Ryan's Pit Plume, Carbon Tetrachloride Plume, East Trenches Area Plume, and Industrial Area Plume. In addition, there are two plumes with contaminant concentrations above Tier II Action Levels that have the potential to impact surface water. These plumes are the Present Landfill and the Property Utilization and Disposal (PU&D) Yard (RMRS, 1996b).

In addition to the VOC plumes, there are other constituents with concentrations above action levels in groundwater. Evaluation of metals anomalies has been curtailed pending re-evaluation of background thresholds that will be done in FY99.

1.3.1 Rocky Flats Cleanup Agreement

The RFCA was officially adopted on July 19, 1996 (RFCA, 1996). The RFCA replaces the IAG as the environmental cleanup agreement for RFETS. The RFCA outlines the goals, objectives, and strategies that will lead to the RFETS cleanup and closure mission objectives. The Action Level Framework (ALF)

attachment to the RFCA contains specific requirements for environmental monitoring and reporting, and it sets action levels for contaminant concentrations in groundwater and in other media. The IMP is required under RFCA to further define the monitoring programs for the Site.

To align the groundwater monitoring program with the new RFETS mission and RFCA requirements, the monitoring network was evaluated in 1996. A data quality objective (DQO) process was used to determine what decisions were necessary for groundwater and the function of each well in the network in supporting those decisions. DOE, CDPHE, EPA, and stakeholders were directly involved in decisions involving the monitoring network. Results of this evaluation are presented in the IMP which is discussed below.

1.3.2 Integrated Monitoring Plan for Groundwater

The Integrated Monitoring Plan (IMP) is a summary document that outlines the goals for groundwater monitoring (and other environmental media), and describes the various components of the groundwater monitoring program (K-H, 1998a). To evaluate groundwater monitoring needs, one must know the RFCA ALF for groundwater, the Site history and areas of contamination, the physical and hydrogeologic setting of the Site, the effect of contaminated areas on groundwater, and the nature of the groundwater contaminant plumes. This information is presented in the IMP Background Document (K-H, 1998b). Appendices A, B, C, and D of the groundwater section of the Background Document cover these previous topics. Appendix E of the groundwater section lists the wells that will be monitored for water quality or for groundwater flow.

In the past, two plans have been required at RFETS to comply with DOE Order 5400.1 (DOE, 1988, Page III-2), a Groundwater Protection & Management Program Plan and a Groundwater Monitoring Plan. These two plans have historically been combined into one document, the Groundwater Protection and Monitoring Program Plan (GPMPP) (EG&G, 1993d), which defines and describes the groundwater protection and monitoring programs at the Site. In addition, an assessment groundwater monitoring plan was required under RCRA for the interim status units on Site. This Plan is called the Groundwater Assessment Plan (GWAP) (DOE, 1993a). Other monitoring plans have been developed to address groundwater monitoring requirements as outgrowths of various CERCLA Interim Measure/Interim Remedial Action (IM/IRA) decision documents. The IMP will serve as the Groundwater Monitoring Plan for the Site, and it will replace the requirements found in the group of plans named above. It will also revise the requirements of the routine groundwater monitoring portion of the IA IM/IRA decision document (DOE, 1994) and the French Drain Performance Monitoring Plan (DOE, 1992b).

The original IMP was published in May 1997. The IMP and IMP Background Document are updated annually with any changes to the monitoring programs

The groundwater monitoring network, as defined in the IMP (K-H, 1998a), has eight categories of monitoring wells. Table 1-1 lists the wells in the current monitoring program. Table 1-2 presents the analytical suites associated with each well in the program. The decision rules presented in the original IMP have been retained for determining Tier I and II exceedances of groundwater Action Levels. The well types and decision rules are defined below:

Boundary (B) Monitoring Wells

These wells monitor groundwater leaving the eastern Site boundary. A reportable exceedance occurs if a measured concentration is above a Tier II action level **and** the background Mean plus 2 Standard Deviations (M2SDs). When there are no previous historical data, **or** a value is greater than the M2SD of the historical concentration in the well when there have been historical exceedances of Tier II action levels, the required action is to initiate monthly sampling. Appropriate parties (DOE, CDPHE and EPA) are notified and possible impacts to surface water are evaluated if contaminant levels are above action levels, by the above criteria, for three consecutive months.

D&D (DD) Monitoring Wells

These wells monitor for releases to groundwater from decontamination and decommissioning (D&D) activities. A concentration value is reportable when a measured concentration is above the M2SD of the established historical baseline concentration downgradient of the building(s). The required action is to inform appropriate parties and initiate an evaluation of the situation.

Plume Definition (PD) Monitoring Wells

These wells are located within known contaminant plumes and are above Tier II action levels, but are below the Tier I action levels established in the ALF. A value is reportable when a measured concentration is above a Tier I action level, **and** the background M2SD, **and** the M2SD of the historical concentration in the well. The required action is to reclassify as a Tier I reportable well and evaluate possible impacts to groundwater.

Plume Extent (PE) Monitoring Wells

These wells are located at the edges of known groundwater contaminant plumes, along pathways to surface water. These wells monitor for an increase in concentrations that may result in future impacts to surface water. A value is reportable if a measured concentration is above a Tier II action level **and** the

TABLE 1-1
GROUNDWATER MONITORING WELLS

WELL NO	REQURNC	CLASS	PLUME/AREA	DRIVERS	ORMATIO	PURPOSE
5387	Semiannual	PE	881 Hillside	RFCA	AL	Plume Extent south of the 881 Hillside Plume
4887	Semiannual	PE	881 Hillside	RFCA	AL	Plume Extent south of the 881 Hillside Plume
4787	Semiannual	PE	881 Hillside	RFCA	AL	Plume Extent south of the 881 Hillside Plume
00797	Semiannual	PM	881 Hillside	RFCA	AL	Performance Monitoring for 881 Footing Drain Sump
11092	Semiannual	PM	881 Hillside	FCA, IM/IRA -F	AL	Performance Monitoring for the French Drain
10892	Semiannual	PM	881 Hillside	FCA, IM/IRA -F	AL	Performance Monitoring for the French Drain
10792	Semiannual	PM	881 Hillside	FCA, IM/IRA -F	AL	Performance Monitoring for the French Drain
10692	Semiannual	PM	881 Hillside	FCA, IM/IRA -F	AL	Performance Monitoring for the French Drain
10592	Semiannual	PM	881 Hillside	FCA, IM/IRA -F	AL	Performance Monitoring for the French Drain
0487	Semiannual	PD	881 Hillside	RFCA	AL	Plume Definition well for the 881 Hillside Plume
91COLGA	Quarterly	PM	881 Hillside	RFCA/IM/IRA -FD	NA	Performance Monitoring of groundwater in collection sump in French Drain
91COLWE	Quarterly	PM	881 Hillside	RFCA/IM/IRA -FD	AL	Performance Monitoring of groundwater in collection well on 881 Hillside
SW13494	Quarterly	PM	881 Hillside	RFCA/IM/IRA -FD	NA	Performance Monitoring of groundwater in footing drain seep below Bldg. 881
6386	Semiannual	PD	903 Pad	RFCA	AL	Plume Definition well monitoring pathway to Woman Cr. in the 903 Pad/Ryans Pit Pl
6286	Semiannual	PD	903 Pad	RFCA	BD/UHSU	Plume Definition well monitoring pathway to Woman Cr. in the 903 Pad/Ryans Pit Pl
3087	Semiannual	PD	903 Pad	RFCA	BD	Plume Definition well monitoring pathway to Woman Cr. in the 903 Pad/Ryans Pit Pl
2987	Semiannual	PD	903 Pad	RFCA	AL	Plume Definition well monitoring pathway to Woman Cr. in the 903 Pad/Ryans Pit Pl
23196	Semiannual	PE	903 Pad	RFCA	AL	Plume Extent well monitoring the southward migration of the Ryans Pit/903 Pad Plume
23096	Semiannual	PE	903 Pad	RFCA	AL	Plume Extent well monitoring the southern migration of the Ryans-OU2 VOA Plume
07391	Semiannual	PM	903 Pad	RFCA	ALBD	Performance Monitoring well monitoring effects of remediation downgradient of Ryan
00491	Semiannual	PD	903 Pad	RFCA	BDIUHSU	Plume Definition well monitoring the 903 Pad VOC Plume
02297	Semiannual	DD	Bldg 779	FCA, IM/IRA for I	AL	D&D monitoring downgradient of Bldg. 779
02497	Semiannual	DD	Bldg 779	FCA, IM/IRA for I	AL	D&D monitoring downgradient of Bldg. 779
02397	Semiannual	DD	Bldg 779	FCA, IM/IRA for I	AL	D&D monitoring upgradient of Bldg. 779
22996	Semiannual	DD	Bldg 886	FCA, IM/IRA for I	AL	Building D&D well monitoring potential rad contamination near 886 lab
10198	Semiannual	DD	Bldg. 123	RFCA -IM/IRA	AL	D & D Monitoring for Building 123 D&D
10298	Semiannual	DD	Bldg. 123	RFCA -IM/IRA	AL	D & D Monitoring for Building 123 D&D
10398	Semiannual	DD	Bldg. 123	RFCA -IM/IRA	AL	D & D Monitoring for Building 123 D&D
10498	Semiannual	DD	Bldg. 123	RFCA -IM/IRA	AL	D & D Monitoring for Building 123 D&D
10598	Semiannual	DD	Bldg. 123	RFCA -IM/IRA	AL	D & D Monitoring for Building 123 D&D
41691	Semiannual	B	Boundary	RFCA, AIP	AL	Boundary Well - in the Walnut Cr. Drainage at the Indiana Street Boundary
41591	Semiannual	B	Boundary	RFCA, AIP	AL	Boundary Well - in small drainage near east access gate
10394	Semiannual	B	Boundary	RFCA, AIP	AL	Boundary Well - in the Woman Cr. Drainage at the Indiana Street Boundary
10294	Semiannual	B	Boundary	RFCA, AIP	AL	Boundary Well - in drainage below Pond D-2 in the southeast corner of the Site
06491	Semiannual	B	Boundary	RFCA, AIP	BDIUHSU	Boundary Well - in small drainage east of the Site at Indiana St.
0386	Semiannual	B	Boundary	RFCA, AIP	BDIUHSU	Boundary Well - in small drainage north of the east access gate
P219169	Semiannual	PD	Carbon Tet	RFCA, RCRA	BD	Plume Definition well for VOC contamination comming from Carbon Tet Plume
P203389	Semiannual	PD	Carbon Tet	RFCA, RCRA	BD	Plume Definition well in the Carbon Tet Plume
P209289	Semiannual	PD	Carbon Tet	RFCA, RCRA	AL	Plume Definition well in the Carbon Tet Plume
12191	Semiannual	PM	East Trenches	RFCA	BDIUHSU	Performance Monitoring at edge of T3 soil excavation
23296	Semiannual	PE	East Trenches	RFCA	AL	Plume Extent well monitoring the northern migration of the East Trenches Area Plume
10194	Semiannual	PE	East Trenches	RFCA	AL	Plume Extent well monitoring the southern migration of the East Trenches Plume
06091	Semiannual	PE	East Trenches	RFCA	AL/BD	Plume Extent well monitoring the northeast migration of the East Trenches Plume
05091	Semiannual	PE	East Trenches	RFCA	AL	Plume Extent well monitoring the eastward migration of the East Trenches Plume
04991	Semiannual	PE	East Trenches	RFCA	AL	Plume Extent well monitoring the eastward migration of the East Trenches Plume
04591	Semiannual	PE	East Trenches	RFCA	AL	Plume Extent well monitoring the southward migration of the East Trenches Plume
04091	Semiannual	PE	East Trenches	RFCA	AL	Plume Extent well monitoring the northward migration of the East Trenches Plume
03991	Semiannual	PD	East Trenches	RFCA	AL	Plume Definition well monitoring the East Trenches Plume
11891	Semiannual	PM	East Trenches	RFCA	BDIUHSU	Performance Monitoring well monitoring effects of remediation downgradient of Trench
3687	Semiannual	PM	East Trenches	RFCA	BDIUHSU	Performance Monitoring well monitoring effects of remediation downgradient of Trench
12691	Semiannual	PM	East Trenches	RFCA	BDIUHSU	Performance Monitoring well monitoring effects of remediation downgradient of Trench

PE = Plume Extent Wells
PD = Plume Definition Wells
PM = Performance Monitoring Wells
B = Boundary Wells
D = Drainage Wells
DD = D & D Monitoring Wells

TABLE 1-1
GROUNDWATER MONITORING WELLS

05691	Semiannual	PM	East Trenches	RFCA	AL	Performance Monitoring well monitoring effects of remediation downgradient of Trench
05391	Semiannual	PD	East Trenches	RFCA	AL	Plume Definition well monitoring eastward concentration of VOCs from the East Trench
10994	Semiannual	PE	IA/Old Landfill	RFCA	AL	Plume Extent IA VOA Plume/Old Landfill Plume near Woman Cr.
7086	Semiannual	PE	IA/Old Landfill	RFCA	AL	Plume Extent well monitoring IA Plume and Old Landfill Plume pathway in Woman Cr.
P416889	Semiannual	PD	Ind. Area	FCA, IM/IRA for I	AL	Plume Definition of IA Plume south of Bldg. 664 along pathway to Woman Cr.
P416789	Semiannual	PD	Ind. Area	FCA, IM/IRA for I	AL	Plume Definition of IA Plume south of 400 area along pathway to Woman Cr.
P416689	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent to monitor southern migration of IA Plume south of Bldg. 440
P314289	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent to monitor the southern migration of IA Plume near Bldg. 850
P313589	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent to monitor the eastward migration of IA Plume near Bldg. 881
P114389	Semiannual	PE	Ind. Area	RFCA	AL	Plume Extent well monitoring eastward migration of IA Plume
6186	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent well monitoring southward migration of IA Plume
43392	Semiannual	PE	Ind. Area	RFCA	AL	Plume Extent well monitoring the northward migration of IA VOA Plume
22896	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent well monitoring the northward migration of Carbon Tet Plume
22796	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent well monitoring the westward migration of the Carbon Tet Plume
22696	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent well monitoring the northern migration of the IA Plume
22596	Semiannual	PE	Ind. Area	FCA, IM/IRA for I	AL	Plume Extent well monitoring the northern migration of the IA Plume
2186	Semiannual	PE	Ind. Area	RFCA	BD/UHSU	Plume Extent well monitoring the northern migration of the IA Plume
1986	Semiannual	PE	Ind. Area	RFCA	AL	Plume Extent well monitoring the northern migration of the IA Plume
B206989	Quarterly	RCRA	Landfill	RFCA, RCRA	BD/UHSU	RCRA/Plume Extent well monitoring downgradient of Landfill Plume
77392	Semiannual	PD	Landfill	RFCA, RCRA	AL	Plume Definition well monitoring the eastward migration of the PU&D Yard Plume
52994	Quarterly	RCRA	Landfill	RFCA, RCRA	AL	RCRA/Plume Extent well monitoring downgradient of Landfill Plume
52894	Quarterly	RCRA	Landfill	RFCA, RCRA	AL	RCRA/Plume Extent well monitoring downgradient of Landfill Plume
4087	Quarterly	RCRA	Landfill	RFCA, RCRA	AL	RCRA/Plume Extent well monitoring downgradient of Landfill Plume
02291	Semiannual	PM	Mound	RFCA	BD/UHSU	Performance Monitoring on the Mound Source remediation
00897	Semiannual	PM	Mound	RFCA	BD/UHSU	Performance Monitoring on the Mound Source remediation
3586	Semiannual	PE	Mound	RFCA	AL	Plume Extent well tracking migration of Solar Ponds nitrate Plume
75992	Semiannual	PE	oundIE, Trench	RFCA	AL	Plume Extent well monitoring So. Walnut Cr. Drainage below Mound Site Plume
08091	Semiannual	PE	oundIE, Trench	RFCA	AL	Plume Extent well monitoring the southern migration of Mound and East Trenches P
6486	Semiannual	D	NA	RFCA	AL	Drainage well monitoring the Woman Cr. drainage downgradient of the 881 Hillside
5587	Semiannual	D	NA	RFCA	AL	Drainage well monitoring the Woman Cr. drainage south of the 881 Hillside Plume
38591	Semiannual	D	NA	RFCA	AL	Drainage well in Woman Cr. Drainage below 881 Hillside Plume
6586	Semiannual	D	NA	RFCA	AL	Drainage well monitoring the No. side Woman Cr. below 903Pad/Ryanis Pit Plume
00997	Semiannual	D	NA	RFCA	AL	Drainage Well - below Pond B-4 in South Walnut Creek Drainage
1386	Semiannual	D	NA	RFCA	AL	Plume Definition well monitoring the migration of the SEP Nitrate and Carbon Tet Pl
00197	Semiannual	PE	Old Landfill	RFCA	AL	Plume Extent well monitoring the Industrial Area Plume
00397	Semiannual	PE	PU&D	RFCA	AL	Plume Extent well monitoring the PU&D Yard Plume
02197	Semiannual	PE	PU&D	RFCA	AL	Plume Extent well monitoring the PU&D Yard Plume
70493	Quarterly	RCRA	PU&D	RFCA, RCRA	BD/UHSU	RCRA upgradient/Plume Definition well monitoring the edge of the PU&D Yard Plume
70393	Quarterly	RCRA	PU&D	RFCA, RCRA	AL	RCRA upgradient/Plume Definition well monitoring the edge of the PU&D Yard Plume
70193	Quarterly	RCRA	PU&D	RFCA, RCRA	BD/UHSU	RCRA upgradient/Plume Extent well monitoring the PU&D Yard Plume
5887	Quarterly	RCRA	PU&D	RFCA, RCRA	AL	RCRA upgradient/Plume Extent well monitoring the PU&D Yard Plume - LF
78992	Semiannual	PE	PU&D/Landfill	RFCA, RCRA	AL	Plume Extent well monitoring the eastward migration of the PU&D Yard/Landfill Plume
00597	Semiannual	PD	PU&D/Landfill	RFCA, RCRA	AL	Plume Definition well monitoring the Landfill/PU&D yard Plume
00297	Semiannual	PD	Solar Ponds	RFCA	AL	Plume Definition well monitoring the southern migration of the Solar Ponds Plume
P219489	Semiannual	PE	Solar Ponds	RFCA	AL	Plume Extent well monitoring the northern migration of the SEP Nitrate Plume
P218389	Semiannual	PE	Solar Ponds	RFCA	AL	Plume Extent well monitoring the northern migration of the SEP Nitrate Plume
B208289	Semiannual	PE	Solar Ponds	RFCA	BD/UHSU	Plume Extent well monitoring the northeast migration of the SEP Nitrate Plume
3386	Semiannual	PE	Solar Ponds	RFCA	AL	Plume Extent well monitoring the southern migration of the SEP Nitrate and Carbon
1786	Semiannual	PE	Solar Ponds	RFCA	AL	Plume Definition well monitoring the migration of the SEP Nitrate and Carbon Tet Pl
B208789	Semiannual	PE	Solar Ponds	RFCA	AL	Plume Extent well monitoring the northeast migration of the SEP Nitrate Plume
P209489	Semiannual	PD	Solar Ponds	RFCA	BD/UHSU	Plume Definition well for the Carbon Tet Plume

PE = Plume Extent Wells
PD = Plume Definition Wells
PM = Performance Monitoring Wells
B = Boundary Wells
D = Drainage Wells
DD = D D Monitoring Wells

TABLE 1-2
MONITORING WELL SAMPLE SUITES

WELLNO	FREQUENCY	PLUME/AREA	VOC Suite	METALS Suite	TRITIUM	PU/AM	SR 89/90	URANIUM	NITRATE	FLUORIDE	SULPHATE	CYANIDE	CESIUM	CHLORIDE	SULFIDE	DOC/TOC	METHANE
89JCOLWEL	Quarterly	881 Hillside	X	X				X									
SW13494	Quarterly	881 Hillside	X	X				X									
5387	Semiannual	881 Hillside	X	X				X	X		X						
4887	Semiannual	881 Hillside	X	X				X	X		X						
4787	Semiannual	881 Hillside	X	X				X	X		X						
00797	Semiannual	881 Hillside	X	X				X	X		X						
11092	Semiannual	881 Hillside	X	X				X	X		X						
10992	Semiannual	881 Hillside	X	X				X	X		X						
10792	Semiannual	881 Hillside	X	X				X	X		X						
10692	Semiannual	881 Hillside	X	X				X	X		X						
10592	Semiannual	881 Hillside	X	X				X	X		X						
0487	Semiannual	881 Hillside	X	X				X	X		X						
89JCOLGAL	Quarterly	881 Hillside	X	X				X									
6386	Semiannual	903 Pad	X	X		X		X	X		X						
6286	Semiannual	903 Pad	X	X		X		X	X		X						
3087	Semiannual	903 Pad	X	X		X		X	X		X						
2987	Semiannual	903 Pad	X	X		X		X	X		X						
23196	Semiannual	903 Pad	X	X		X		X	X		X						
23096	Semiannual	903 Pad	X	X		X		X	X		X						
07391	Semiannual	903 Pad	X	X		X		X	X		X						
00491	Semiannual	903 Pad	X	X		X		X	X		X						
02297	Semiannual	Bldg 779	X	X		X		X	X								
02497	Semiannual	Bldg 779	X	X		X		X	X								
02397	Semiannual	Bldg 779	X	X		X		X	X								
22996	Semiannual	Bldg 886	X	X		X	X	X									
10198	Semiannual	Bldg 123	X	X		X		X	X			X	X				
10298	Semiannual	Bldg 123	X	X		X		X	X			X	X				
10398	Semiannual	Bldg 123	X	X		X		X	X			X	X				
10498	Semiannual	Bldg 123	X	X		X		X	X			X	X				
10598	Semiannual	Bldg 123	X	X		X		X	X			X	X				
41691	Semiannual	Boundary	X	X	X	X	X	X	X	X	X						
41591	Semiannual	Boundary	X	X	X	X	X	X	X	X	X						
10394	Semiannual	Boundary	X	X	X	X	X	X	X	X	X						
10294	Semiannual	Boundary	X	X	X	X	X	X	X	X	X						
06491	Semiannual	Boundary	X	X	X	X	X	X	X	X	X						
0386	Semiannual	Boundary	X	X	X	X	X	X	X	X	X						
P219189	Semiannual	Carbon Tet	X	X	X	X	X	X	X	X	X						
P209389	Semiannual	Carbon Tet	X	X	X	X	X	X	X	X	X						
P209289	Semiannual	Carbon Tet	X	X	X	X	X	X	X	X	X						
1386	Semiannual	Drainage	X	X	X	X	X	X	X	X	X						
6486	Semiannual	Drainage	X	X	X	X	X	X	X	X	X						
5587	Semiannual	Drainage	X	X	X	X	X	X	X	X	X						
38591	Semiannual	Drainage	X	X	X	X	X	X	X	X	X						
6586	Semiannual	Drainage	X	X	X	X	X	X	X	X	X						
00997	Semiannual	Drainage	X	X	X	X	X	X	X	X	X						
23296	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
10194	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
06091	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
05091	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
04991	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
04591	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
04091	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
03991	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						
11891	Semiannual	East Trenches	X	X	X	X	X	X	X	X	X						

TABLE 1-2
MONITORING WELL SAMPLE SUITES

WELLNO	FREQUENCY	PLUME/AREA	VOC Suite	METALS Suite	TRITIUM	PU/AM	SR 89/90	URANIUM	NITRATE	FLUORIDE	SULPHATE	CYANIDE	CESIUM	CHLORIDE	SULFIDE	DO/TOC	METHANE
3687	Semiannual	East Trenches	X	X		X		X	X								
12691	Semiannual	East Trenches	X	X		X		X	X								
05691	Semiannual	East Trenches	X	X		X		X	X								
05391	Semiannual	East Trenches	X	X		X		X	X								
12191	Semiannual	East Trenches	X	X		X		X	X								
10994	Semiannual	LA/Old Landfill	X	X		X	X	X	X		X						
7086	Semiannual	IA/Old Landfill	X	X		X	X	X	X		X						
P416889	Semiannual	Ind. Area	X	X		X		X	X								
P416789	Semiannual	Ind. Area	X	X		X		X	X								
P416689	Semiannual	Ind. Area	X	X		X		X	X								
P314289	Semiannual	Ind. Area	X	X		X		X	X								
P313589	Semiannual	Ind. Area	X	X		X		X	X								
P114389	Semiannual	Ind. Area	X	X		X		X	X								
6186	Semiannual	Ind. Area	X	X		X		X	X								
43392	Semiannual	Ind. Area	X	X		X		X	X								
22896	Semiannual	Ind. Area	X	X		X		X	X								
22796	Semiannual	Ind. Area	X	X		X		X	X								
22696	Semiannual	Ind. Area	X	X		X		X	X								
22596	Semiannual	Ind. Area	X	X		X		X	X								
2186	Semiannual	Ind. Area	X	X		X		X	X								
1986	Semiannual	Ind. Area	X	X		X		X	X								
B206989	Quarterly	Landfill	X	X	X	X		X	X	X	X						
77392	Semiannual	Landfill	X	X		X		X	X	X	X						
52994	Quarterly	Landfill	X	X	X	X		X	X	X	X						
52894	Quarterly	Landfill	X	X	X	X		X	X	X	X						
4087	Quarterly	Landfill	X	X	X	X		X	X	X	X						
02291	Semiannual	Mound	X	X		X		X	X								
00897	Semiannual	Mound	X	X		X		X	X								
3586	Semiannual	Mound	X	X		X		X	X								
75992	Semiannual	Mound/E. Trench	X	X		X	X	X	X								
08091	Semiannual	Mound/E. Trench	X	X		X	X	X	X								
00197	Semiannual	Old Landfill	X	X	X	X		X	X	X	X						
00397	Semiannual	PU&D	X	X		X		X	X	X	X						
02197	Semiannual	PU&D	X	X	X	X		X	X	X	X						
70493	Quarterly	PU&D	X	X	X	X		X	X	X	X						
70393	Quarterly	PU&D	X	X	X	X		X	X	X	X						
70193	Quarterly	PU&D	X	X	X	X		X	X	X	X						
5887	Quarterly	PU&D	X	X	X	X		X	X	X	X						
76992	Semiannual	PU&D/Landfill	X	X	X	X		X	X	X	X						
00597	Semiannual	PU&D/Landfill	X	X	X	X		X	X	X	X						
00297	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
P219489	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
P218389	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
B208289	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
3386	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
1786	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
B208789	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						
P209489	Semiannual	Solar Ponds	X	X	X	X	X	X	X	X	X						

background M2SD. When there are no previous historical data, or a value is greater than the M2SD of the historical concentration in the well when there have been historical values above Tier II action levels, the required action is to initiate monthly sampling. Appropriate parties are notified and possible impacts to surface water are evaluated if contaminant levels are above action levels, by the above criteria, for three consecutive months.

Drainage (D) Monitoring Wells

These wells are located in stream drainages, downgradient of contaminant plumes. They have the same programmatic requirements as PE wells under the IMP.

A value is reportable when a measured concentration is above the Tier II action level **and** the background M2SD. When there are no historical data, or a value is greater than the M2SD of the historical concentration in the well when there have been historical values above Tier II action levels, the required action is to initiate monthly sampling. Appropriate parties are notified and possible impacts to surface water are evaluated if values are above action levels, by the above criteria, for three consecutive months.

Performance Monitoring (PM) Wells

These wells monitor the effect of a remediation or source removal action, as required in the ALF. If an increasing trend in the concentration of a contaminant is noted, then the appropriate parties are notified and an evaluation of the situation is initiated.

RCRA Monitoring Wells

These wells monitor downgradient groundwater contaminant concentrations at RCRA units. If the mean concentration of a contaminant in a downgradient well is greater than the mean concentration in upgradient wells **and** concentrations at the well show an upward trend with time, a report will be made to appropriate agencies and an investigation will be initiated to investigate possible causes.

Plume Degradation Monitoring Wells

These wells monitor the downgradient portions of groundwater plumes or plume sources to establish whether natural processes are degrading (also called attenuating) the nature and extent of the plume prior to entering the surface water environment. In areas where monitoring can document a natural attenuation process for a plume, other remediation activities may not be necessary. These wells would differ from plume extent wells in that the analyte suite may include parameters that focus on measuring the attenuation process. Also, these wells would not only look at concentration of contaminants but would look at the breakdown products from these contaminants in the evaluation process. If significant natural attenuation can be substantiated, then a non-remedial decision can be promulgated for the plume.

Groundwater reporting has been integrated under the IMP. Four quarterly reports are produced annually that document concentration values above RFCA Action Levels. Also documented are changes in water quality for wells not monitored for comparison to action levels. A RFCA Annual Groundwater Report is also required to summarize all actions taken for groundwater compliance within each calendar year.

For documented values above action levels and Site background in the designated monitoring wells in the program, an evaluation of impact to surface water is required. These evaluations are determined on a case by case basis depending on the data requirements necessary to do the impact analysis. Section 4.0 of this report discusses the status of the current evaluations that were implemented based on elevated concentrations in 1996.

1.3.3 Changes to the Groundwater Monitoring Program

Additions to the Groundwater Monitoring Network

Wells have been added to the Site monitoring network based on the results of groundwater evaluations and remediation activities. Plate 1 shows the locations for these monitoring wells.

The Mound plume passive treatment system was completed in FY98. This system was constructed in the area of seep location SW59 and plume extent well 3586, both of which contained detections of VOCs above Tier II action levels. A performance monitoring network will be installed in FY99 to evaluate the effectiveness of the treatment system in reducing the VOC load to South Walnut Creek.

A D&D monitoring network was established around Building 123, which was demolished in FY98. Five monitoring wells were installed and are numbered 10198 through 10598. Two of the wells were located upgradient and the other three are located downgradient of the building. These wells were also used to characterize the potential under building contamination that might be affecting groundwater at the Site

An investigation of the northern extent of the IA Plume was conducted in 1998. Based on the results of the investigation VOC contamination was interpreted to be more extensive than previously thought. As a result, it may be necessary to re-evaluate the monitoring network in this area. Please refer to Section 4.1 for additional information on this investigation.

A real time water level monitoring network was initiated for the Site in 1998 to help qualify the affects of storm events and other recharge events on groundwater flow and transport. Twenty-five wells originally identified for water level measurements in the IMP were converted to real time monitoring stations that will record water levels six times per day. Please refer to Section 7.2 for additional information on this activity.

The sampling frequency for monitoring wells at the Present Landfill was changed from semiannual to quarterly. This change was necessary to have enough data points so that an upgradient to downgradient comparison of mean concentrations of contaminants could be calculated.

2.0 GROUNDWATER DATA QUALITY ASSESSMENT

2.1 Methods

The quality of the analytical data is assessed in terms of five data-quality parameters: precision, accuracy, representativeness, completeness, and comparability (PARCC) (EPA, 1992a). This section summarizes the types of data available to assess the PARCC parameters.

The RFETS groundwater monitoring program, as established in the IMP, consists of 98 wells that are sampled at a semi-annual frequency (K-H, 1998a). A total of 232 well sampling visits were conducted during 1998. All samples specified in the IMP were collected unless well disposition was prohibitive (i.e. dry or went dry during sampling). Table 2-1 presents a summary of sample collection and well disposition.

Quality Control (QC) samples consisting of real/duplicate pairs and rinsate samples were collected from 18 sites. The frequency for field QC sampling of 1 site in 5.4 exceeded the target rate of 1 site in 20 over the course of the 1998 sampling program. PARCC analysis of the 1998 QC data is presented in the sections that follow. Data used to evaluate the PARCC parameters are summarized in this report, and are presented in full in the quarterly monitoring reports (RMRS 1998a; 1998b; 1999a; and 1999b).

Precision

Precision is a measure of the reproducibility of analytical results. Precision is expressed quantitatively by the relative percent difference (RPD) between duplicate field samples for VOCs, metals, and water quality parameters as defined by the following equation:

$$RPD = \frac{\xi(S-D)\xi}{(S+D)/2} \times 100 \quad \text{where,} \quad \begin{array}{l} S = \text{Sample Result} \\ D = \text{Duplicate or Lab Replicate Result} \end{array}$$

With respect to Radionuclides the RFETS Groundwater Program uses the following "Duplicate Error Ratio" (DER) equation:

$$DER = \frac{\xi S - D \xi}{[(TPU_S^2 + TPU_D^2)]^{1/2}} \quad \text{where,} \quad \begin{array}{l} TPU_S = \text{total propagated uncertainty of the sample} \\ TPU_D = \text{total propagated uncertainty of the duplicate or lab replicate} \\ S = \text{sample result} \\ D = \text{duplicate or lab replicate result} \end{array}$$

Table 2-1
Summary of Samples Collected
Groundwater 1998

Wells	VOC's				Metals				Radiocliides								Water Quality Parameters																											
									Pu/Am				U-isotopes				Tritium				Sr-89/90				NO ₃ /NO ₂				TDS				Sulfate				Fluoride							
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4								
00197	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D		
00297	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D		
00397	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D		
00491	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
00597	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
00797	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
00897	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
00997	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
02197	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
02291	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S		
02297	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	S	D	
02397	S	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	S	D	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S
02497	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
0386	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
03991	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
04091	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
04591	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
0487	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
04991	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
05091	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
05391	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
05691	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
06091	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
06491	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
07391	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
08091	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	D	S	S	S	S	D	S	S	S	S	S	S	S	S	S	S	S	S	S	
10194	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	
10294	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	

Table 2-1
Summary of Samples Collected
Groundwater 1998

Wells	VOC's				Metals				Radiocluides								Water Quality Parameters																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
									Pu/Am				U-isotopes				Tritium				Sr-89/90				NO ₃ /NO ₂				TDS				Sulfate				Fluoride																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
1386																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		

Table 2-1
Summary of Samples Collected
Groundwater 1998

Wells	VOC's				Metals				Radiocluclides				Water Quality Parameters											
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Pu/Am	U-isotopes	Tritium	Sr-89/90	NO ₃ /NO ₂	TDS	Sulfate	Fluoride								
75992			S				S		S															
76992			S				S																	
77392	D	S		D	D	S		D		D	S													
891COLGAL		S	S	S		S	S	S		S														
891COLWEL		S	S	S		S	S	S		S														
B206989	S	S	S	S	S	I	I	S		I	S		S											
B208289	S	S	S	S	I	S	S	S		I	S		S											
B208789		S	S	S		S	S	S		S														
P114389		S	S		S		S																	
P209289		D		D		D		D		D														
P209389	S	S		S	S	S		S		S														
P209489		S		S		S		S		S														
P218389	S	S		D	S	S		D		I	S		S											
P219189	S	S		S	I	I		I		I	S		S											
P219489	S	S		S	I	I		I		I	S		S											
P313589	S	S		S	S		S																	
P314289	S	S		S	I		S																	
P416689	S	S		S		S		S		I														
P416789	S	S		I		S		I		I														
416889	S	S		S	S	S		S																
SW059		S				S				S														
SW13494		S	S	S		S	S	S		S														

Blank indicates no sample required or attempted.

S Indicates site was sampled.

D Indicates well was dry.

I Indicates well produced insufficient water to collect sample.

Because TPU is only reported for Tritium (H_3) analyses in the lab reports, 2-Sigma Error has been substituted for TPU in the Uranium and Americium/Plutonium calculations made for this report.

A RPD/DER is not calculated for duplicate samples for which the analytical result for either member is qualified as undetected by the laboratory. This includes "U" qualified data for volatile organic compounds and "U" and "B" qualified data for inorganic compounds. The data flag "U" indicates that the analyte was not present above the detection limit (IDL). The data flag "B" for inorganics indicates that the value is larger than the instrument detection limit but less than the method detection limit. Results in these categories have inherently poor reproducibility and are described qualitatively.

The RPDs or DERs calculated for each real/duplicate pair having detections can be found in Table 2-2. The QC criterion for RPDs is $\leq 30\%$, for DERs the criterion is ≤ 1.96 . Table 2-3 gives a summary of the overall precision compliance for RPDs and DERs.

Accuracy

Accuracy is a measure of how closely an analytical result corresponds to the "true" concentration in a sample. Accuracy, as applied to groundwater analytical data from RFETS, is described in RF/RMRS-98-200, *Evaluation of Data for Usability in Final Reports (August 1998)* as a comparison of required analytical methods and detection limits with actual methods and detection limit for each analyte (K-H, 1998a). Table 2-4 presents the contract-required detection limits (CRDLs) for the various analytes.

Representativeness

The discussion of representativeness in this section is limited to an evaluation of whether analytical results for field samples are truly representative of environmental concentrations or whether they may have been influenced by the introduction of contamination during collection and handling. The potential introduction of contamination is evaluated by examination of the analytical results for equipment rinsates (Table 2-5). Equipment rinsates are used to assess the efficacy of the decontamination process and possible cross-contamination between environmental samples. They are samples of volatile free ASTM Type II water ("distilled" water) that have been poured over or through decontaminated sampling equipment and subsequently handled in the same manner as environmental samples.

Although rinsates are used specifically as indicators of cross-contamination during decontamination of equipment, they are carried through the entire sampling, shipping, and laboratory process and are, consequently, also good indicators of potential contamination introduced during any of these steps.

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Location	Sample Date	Analyte	Real Result	Real Result Qual	Real Valid	Dup Result	Dup Result Qual	Dup Valid	Units	Difference Real-Dup	Average (Real+Dup)/2	RPD Diff/Avg x100
Water Quality Parameters												
11891	3/5/98	Nitrate/Nitrite	5.9		V1	507			mg/L	501.10	256.45	195.40
12191	3/5/98	Nitrate/Nitrite	6.2		I	6		J1	mg/L	0.20	6.10	3.28
11891	3/5/98	Total Diss Solids	480		I	460			mg/L	20.00	470.00	4.26
12191	3/5/98	Total Diss Solids	540		I	580		V1	mg/L	40.00	560.00	7.14
12191	4/28/98	Nitrate/Nitrite	6.5			6.9			mg/L	0.40	6.70	5.97
12191	4/28/98	Total Diss Solids	790			770			mg/L	20.00	780.00	2.56
P209489	5/14/98	Fluoride	0.26			0.26			mg/L	0.00	0.26	0.00
P209489	5/14/98	Nitrate/Nitrite	120	N		120	N	I	mg/L	0.00	120.00	0.00
P209489	5/14/98	Sulfate	91			88			mg/L	3.00	89.50	3.35
P209489	5/14/98	Total Diss Solids	1400			1300			mg/L	100.00	1350.00	7.41
3586	6/5/98	Fluoride	0.41		V1	0.4			mg/L	0.01	0.41	2.47
3586	6/5/98	Nitrate/Nitrite	0.12		V1	0.12			mg/L	0.00	0.12	0.00
3586	6/5/98	Sulfate	180		V1	190			mg/L	10.00	185.00	5.41
3586	6/5/98	Total Diss Solids	990		J1	970			mg/L	20.00	980.00	2.04
11891	6/11/98	Nitrate/Nitrite	5.6		V1	5.7		V1	mg/L	0.10	5.65	1.77
11891	6/11/98	Total Diss Solids	510		V1	510		V1	mg/L	0.00	510.00	0.00
70193	7/14/98	Fluoride	0.23			0.17			mg/L	0.06	0.20	30.00
70193	7/14/98	Nitrate/Nitrite	1.9			1.9			mg/L	0.00	1.90	0.00
70193	7/14/98	Sulfate	25			20			mg/L	5.00	22.50	22.22
70193	7/14/98	Total Diss Solids	230			210			mg/L	20.00	220.00	9.09
03991	8/6/98	Nitrate/Nitrite	6.2			6.8			mg/L	0.60	6.50	9.23
03991	8/6/98	Total Diss Solids	550			560			mg/L	10.00	555.00	1.80
10498	8/12/98	Nitrate/Nitrite	25		V1	27			mg/L	2.00	26.00	7.69
05091	8/26/98	Nitrate/Nitrite	7.3			6.9			mg/L	0.40	7.10	5.63
05091	8/26/98	Total Diss Solids	600			570			mg/L	30.00	585.00	5.13
5887	8/31/98	Fluoride	0.17			0.17			mg/L	0.00	0.17	0.00
5887	8/31/98	Nitrate/Nitrite	2.2			2			mg/L	0.20	2.10	9.52
5887	8/31/98	Sulfate	24			24			mg/L	0.00	24.00	0.00
5887	8/31/98	Total Diss Solids	210			210			mg/L	0.00	210.00	0.00
3586	10/20/98	Total Diss Solids	1000		V1	1000			mg/L	0.00	1000.00	0.00
11891	11/19/98	Nitrate/Nitrite	6.3		V1	7.2		J1	mg/L	0.90	6.75	13.33
11891	11/19/98	Total Diss Solids	510		V1	560		V1	mg/L	50.00	535.00	9.35
70193	11/30/98	Fluoride	0.3		V1	0.31			mg/L	0.01	0.31	3.28
70193	11/30/98	Nitrate/Nitrite	2.1		V1	2.2			mg/L	0.10	2.15	4.65
70193	11/30/98	Sulfate	22		V1	22			mg/L	0.00	22.00	0.00
70193	11/30/98	Total Diss Solids	170		J1	170			mg/L	0.00	170.00	0.00
02291	12/4/98	Nitrate/Nitrite	6.4		V1	5.4			mg/L	1.00	5.90	16.95
02291	12/4/98	Total Diss Solids	420		V1	390			mg/L	30.00	405.00	7.41
5887	12/14/98	Fluoride	0.2		V1	0.2			mg/L	0.00	0.20	0.00
70393	12/14/98	Fluoride	0.16		V1	0.16			mg/L	0.00	0.16	0.00
5887	12/14/98	Nitrate/Nitrite	3.4		V1	3.4			mg/L	0.00	3.40	0.00
70393	12/14/98	Nitrate/Nitrite	5.8		V1	5.5			mg/L	0.30	5.65	5.31
5887	12/14/98	Sulfate	31		V1	30			mg/L	1.00	30.50	3.28
70393	12/14/98	Sulfate	28		V1	28			mg/L	0.00	28.00	0.00
5887	12/14/98	Total Diss Solids	160		V1	160			mg/L	0.00	160.00	0.00
70393	12/14/98	Total Diss Solids	160		V1	140			mg/L	20.00	150.00	13.33
12191	12/15/98	Nitrate/Nitrite	8.3		V1	7.4			mg/L	0.90	7.85	11.46
12191	12/15/98	Total Diss Solids	520		V1	570			mg/L	50.00	545.00	9.17

Note: RPD values greater than the 30% QC criterion are indicated in bold font.

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Well	Sample Date	Analyte	Real Result	Real Result Qual	Real 2Sigma Error	Real Valid	Dup Result	Dup 2Sigma Error	Dup Valid	Units	Dup Result Qual	Difference Real-Dup	Square Root (2sigReal + 2sigDup)	DER Diff/SqrRt
Radionuclides														
02291	12/4/98	Uranium-233/234	2.13		0.635	V	3.03	0.884		pCi/L		0.90	1.09	0.83
0386	2/26/98	Americium-241	0.002		0.012		0.01	0.014		pCi/L		0.01	0.02	0.43
0386	2/26/98	Plutonium-239/240	-0.004		0.016		0.004	0.014		pCi/L		0.01	0.02	0.38
0386	2/26/98	Uranium-233/234	10.3		1.36		10.3	1.40		pCi/L		0.00	1.95	0.00
0386	2/26/98	Uranium-235	0.283		0.190		0.266	0.190		pCi/L		0.02	0.27	0.06
0386	2/26/98	Uranium-238	8.05		1.14		8.35	1.20		pCi/L		0.30	1.66	0.18
0386	8/25/98	Americium-241	0.003		0.015		0.005	0.006		pCi/L		0.00	0.02	0.12
0386	8/25/98	Plutonium-239/240	0.002		0.003		0	0.006		pCi/L		0.00	0.01	0.30
0386	8/25/98	Tritium	-137		190		-67.7	192		pCi/L		69.30	270.12	0.26
0386	8/25/98	Uranium-233/234	10.1		1.48		10.8	1.55		pCi/L		0.70	2.14	0.33
0386	8/25/98	Uranium-235	0.534		0.281		0.206	0.170		pCi/L		0.33	0.33	1.00
0386	8/25/98	Uranium-238	8.23		1.27		7.71	1.22		pCi/L		0.52	1.76	0.30
03991	8/6/98	Americium-241	0.009		0.016		0.003	0.016		pCi/L		0.01	0.02	0.27
03991	8/6/98	Plutonium-239/240	-0.001		0.010		0.001	0.006		pCi/L		0.00	0.01	0.17
03991	8/6/98	Uranium-233/234	2.09		0.521		2.06	0.515		pCi/L		0.03	0.73	0.04
03991	8/6/98	Uranium-235	-0.014		0.028		0.104	0.138		pCi/L		0.12	0.14	0.84
03991	8/6/98	Uranium-238	1.38		0.410		1.08	0.363		pCi/L		0.30	0.55	0.55
05091	2/27/98	Uranium-233/234	4.21		0.739		4.38	0.746		pCi/L		0.17	1.05	0.16
05091	2/27/98	Uranium-238	2.39		0.527		1.79	0.439	V	pCi/L		0.60	0.69	0.87
05091	8/26/98	Americium-241	0.012		0.018		0.008	0.016		pCi/L		0.00	0.02	0.17
05091	8/26/98	Plutonium-239/240	0.006		0.010		-0.001	0.008		pCi/L		0.01	0.01	0.55
05091	8/26/98	Uranium-233/234	5.06		0.981		4.14	0.830		pCi/L		0.92	1.29	0.72
05091	8/26/98	Uranium-235	0.103		0.142		0.147	0.148		pCi/L		0.04	0.21	0.21
05091	8/26/98	Uranium-238	3.06		0.714		2.32	0.580		pCi/L		0.74	0.92	0.80
10294	2/10/98	Plutonium-239/240	0.0075	J	0.00359		0.00244	0.00829		pCi/L		0.01	0.01	0.56
10294	2/10/98	Uranium-233/234	25.144		1.78		27.9	1.78		pCi/L		2.76	2.52	1.09
10294	2/10/98	Uranium-235	0.8554	J	0.328		0.865	0.317		pCi/L		0.01	0.46	0.02
10294	2/10/98	Uranium-238	17.9772		1.51		24	1.65		pCi/L		6.02	2.24	2.69
10294	7/29/98	Tritium	-47.3		118		-47.1	118		pCi/L		0.20	166.88	0.00
10294	7/29/98	Uranium-233/234	21.6128		2.133		18.5942	1.5712		pCi/L		3.02	2.65	1.14
10294	7/29/98	Uranium-235	1.1801		0.5039		0.6239	0.2874		pCi/L	J	0.56	0.58	0.96
10294	7/29/98	Uranium-238	16.2807		1.8501		16.5896	1.4841		pCi/L		0.31	2.37	0.13
11891	3/5/98	Americium-241	0.065		0.042		0.11	0.064		pCi/L	J	0.05	0.08	0.59
11891	3/5/98	Uranium-233/234	2.25		0.421		2.32	0.459		pCi/L		0.07	0.62	0.11
11891	3/5/98	Uranium-235	0.124	J	0.078		0.118	0.087		pCi/L	J	0.01	0.12	0.05
11891	3/5/98	Uranium-238	1.32		0.295		1.58	0.360		pCi/L		0.26	0.47	0.56
11891	6/11/98	Uranium-235	0.1208	J	0.0655		0.2723	0.145		pCi/L	J	0.15	0.16	0.95
11891	6/11/98	Uranium-238	1.4137		0.2249		1.15	0.2975	J	pCi/L		0.26	0.37	0.71
11891	11/19/98	Plutonium-239/240	0.036		0.019	V1	0.046	0.019	V1	pCi/L		0.01	0.03	0.37
12191	3/5/98	Uranium-233/234	2.36		0.456		2.09	0.415	VI	pCi/L		0.27	0.62	0.44
12191	3/5/98	Uranium-238	1.49		0.338		1.04	0.269	VI	pCi/L		0.45	0.43	1.04
12191	4/28/98	Uranium-233/234	1.6303		0.3391		1.8459	0.3412		pCi/L		0.22	0.48	0.45
12191	4/28/98	Uranium-238	1.2716		0.2981		1.2971	0.2902		pCi/L		0.03	0.42	0.06
12191	12/15/98	Uranium-233/234	2.1		0.679	V1	2.2	0.667		pCi/L		0.10	0.95	0.11
12191	12/15/98	Uranium-238	1.13		0.439	VI	1.08	0.403		pCi/L		0.05	0.60	0.08
3586	3/16/98	Uranium-233/234	3.01		0.650		2.28	0.570		pCi/L		0.73	0.86	0.84
3586	3/16/98	Uranium-238	1.91		0.491		2.73	0.637		pCi/L		0.82	0.80	1.02
3586	6/5/98	Americium-241	0.0108	J	0.0068		0.0101	0.0078		pCi/L	J	0.00	0.01	0.07
3586	6/5/98	Uranium-233/234	2.2001		0.2752		2.2748	0.2711		pCi/L		0.07	0.39	0.19
3586	6/5/98	Uranium-235	0.1072	J	0.0604		0.1299	0.066		pCi/L	J	0.02	0.09	0.25
3586	6/5/98	Uranium-238	1.6167		0.2357		1.5891	0.2259		pCi/L		0.03	0.33	0.08
3586	10/20/98	Uranium-233/234	2.44		0.741	V	2.28	0.687		pCi/L		0.16	1.01	0.16
3586	10/20/98	Uranium-238	2.02		0.643	V	1.77	0.570		pCi/L		0.25	0.86	0.29
41591	2/26/98	Americium-241	0.007		0.012		0.018	0.015		pCi/L		0.01	0.02	0.57
41591	2/26/98	Plutonium-239/240	0.014		0.016		0.008	0.011		pCi/L		0.01	0.02	0.31
41591	2/26/98	Uranium-233/234	10.5		1.38		10.9	1.40		pCi/L		0.40	1.97	0.20
41591	2/26/98	Uranium-235	0.316		0.202		0.347	0.211		pCi/L		0.03	0.29	0.11
41591	2/26/98	Uranium-238	8.2		1.16		7.56	1.09		pCi/L		0.64	1.59	0.40
41591	8/27/98	Americium-241	0.015		0.016		0.004	0.020		pCi/L		0.01	0.03	0.43
41591	8/27/98	Plutonium-239/240	0		0.009		-0.001	0.007		pCi/L		0.00	0.01	0.09
41591	8/27/98	Tritium	-328		180		-130	180		pCi/L		198.00	254.56	0.78
41591	8/27/98	Uranium-233/234	9.05		1.37		9.61	1.56		pCi/L		0.56	2.08	0.27
41591	8/27/98	Uranium-235	0.602		0.307		0.19	0.190		pCi/L		0.41	0.36	1.14
41591	8/27/98	Uranium-238	8.32		1.29		9.17	1.51		pCi/L		0.85	1.99	0.43
5887	8/31/98	Tritium	-324		174		-266	160		pCi/L		58.00	236.38	0.25
5887	12/14/98	Uranium-233/234	0.071	J	0.083	V1	0.073	0.086		pCi/L	J	0.00	0.12	0.02
70193	2/26/98	Uranium-233/234	0.025		0.049		0.206	0.147		pCi/L		0.18	0.15	1.17
70193	2/26/98	Uranium-235	0.018		0.066		0	0.000		pCi/L		0.02	0.07	0.27
70193	2/26/98	Uranium-238	0.367		0.192		0.434	0.214		pCi/L		0.07	0.29	0.23

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Well	Sample Date	Analyte	Real Result	Real Result Qual	Real 2Sigma Error	Real Valid	Dup Result	Dup 2Sigma Error	Dup Valid	Units	Dup Result Qual	Difference Real-Dup	Square Root (2sigReal + 2sigDup)	DER Diff/SqrRt
Radionuclides														
70193	7/14/98	Tritium	-16		121		-112	118		pCi/L		96.00	169.01	0.57
70193	11/30/98	Uranium-238	0.238	J	0.166	V	0.248	0.174		pCi/L	J	0.01	0.24	0.04
70393	8/26/98	Tritium	-200		184		-97.6	183		pCi/L		102.40	259.51	0.39
70393	8/26/98	Uranium-233/234	0.095		0.109		0.145	0.130		pCi/L		0.05	0.17	0.29
70393	8/26/98	Uranium-235	0.005		0.076		0.032	0.064		pCi/L		0.03	0.10	0.27
70393	8/26/98	Uranium-238	0.265		0.170		0.067	0.092		pCi/L		0.20	0.19	1.02
891COLGAL	8/20/98	Uranium-233/234	5.96		1.06		6.25	1.09		pCi/L		0.29	1.52	0.19
891COLGAL	8/20/98	Uranium-235	0.302		0.216		0.112	0.130		pCi/L		0.19	0.25	0.75
891COLGAL	8/20/98	Uranium-238	5.17		0.969		3.96	0.809		pCi/L		1.21	1.26	0.96
891COLWEL	8/20/98	Uranium-233/234	11.7		1.64		11.7	1.68		pCi/L		0.00	2.35	0.00
891COLWEL	8/20/98	Uranium-235	0.334		0.214		0.301	0.215		pCi/L		0.03	0.30	0.11
891COLWEL	8/20/98	Uranium-238	8.59		1.30		7.66	1.23		pCi/L		0.93	1.79	0.52
P209489	5/14/98	Tritium	265.96	J	138		382.134	143		pCi/L	J	116.17	198.73	0.58
P209489	5/14/98	Uranium-233/234	13.3387		0.966		13.3111	1.00		pCi/L		0.03	1.39	0.02
P209489	5/14/98	Uranium-235	0.657	J	0.214		1.1792	0.300		pCi/L		0.52	0.37	1.42
P209489	5/14/98	Uranium-238	10.6819		0.864		12.3758	0.965		pCi/L		1.69	1.30	1.31
SW13494	11/2/98	Uranium-233/234	3.15		0.889	V1	4.71	0.886		pCi/L		1.56	1.26	1.24
SW13494	11/2/98	Uranium-235	0.154	J	0.145	V1	0.342	0.230		pCi/L		0.19	0.27	0.69
SW13494	11/2/98	Uranium-238	2.28		0.692	V1	3.88	0.782		pCi/L		1.60	1.04	1.53

Note: DER values greater than the 1.96 QC criterion are indicated in bold font.

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Location	Sample Date	Analyte	Real Result	Real Result Qual	Real Valid	Dup Result	Dup Result Qual	Dup Valid	Units	Difference Real-Dup	Average (Real+Dup)/2	RPD	Diff/Avg x100
Volatile Organic Compounds													
02291	12/4/98	1,1,1-Trichloroethane	3		V	4			ug/L	1.00	3.50		28.57
02291	12/4/98	1,1-Dichloroethane	2		V	2			ug/L	0.00	2.00		0.00
02291	12/4/98	1,1-Dichloroethene	6		J	6			ug/L	0.00	6.00		0.00
02291	12/4/98	Chloroform	3		V	3		UJ	ug/L	0.00	3.00		0.00
02291	12/4/98	cis-1,2-Dichloroethene	17		V	20		V	ug/L	3.00	18.50		16.22
02291	12/4/98	Methylene Chloride	0.9	BJ	JB	0.8	BJ		ug/L	0.10	0.85		11.76
02291	12/4/98	Tetrachloroethene	3400	D	V	5700	D	J1	ug/L	2300.00	4550.00		50.55
02291	12/4/98	Trichloroethene	450	D	V	620	D	V1	ug/L	170.00	535.00		31.78
03991	8/6/98	Carbon Tetrachloride	40	D		41	D	V1	ug/L	1.00	40.50		2.47
03991	8/6/98	Chloroform	2	D		2		UJ1	ug/L	0.00	2.00		0.00
03991	8/6/98	Tetrachloroethene	11			11			ug/L	0.00	11.00		0.00
03991	8/6/98	Trichloroethene	6			6			ug/L	0.00	6.00		0.00
05091	8/26/98	Carbon Tetrachloride	0.8	J		0.7	J		ug/L	0.10	0.75		13.33
05091	8/26/98	Chromium	2.4			2.3		V1	ug/L	0.10	2.35		4.26
05091	8/26/98	Tetrachloroethene	3			3		V	ug/L	0.00	3.00		0.00
10498	8/12/98	Tetrachloroethene	9			15			ug/L	6.00	12.00		50.00
10498	8/19/98	Methylene Chloride	0.6	J	J1	0.6	J		ug/L	0.00	0.60		0.00
10498	8/19/98	Tetrachloroethene	5			4			ug/L	1.00	4.50		22.22
11891	3/5/98	1,1,1-Trichloroethane	3			3			ug/L	0.00	3.00		0.00
11891	3/5/98	1,1-Dichloroethene	3			4			ug/L	1.00	3.50		28.57
11891	3/5/98	Carbon Tetrachloride	460			460	D		ug/L	0.00	460.00		0.00
11891	3/5/98	Chloroform	13			14			ug/L	1.00	13.50		7.41
11891	3/5/98	cis-1,2-Dichloroethene	15			16			ug/L	1.00	15.50		6.45
11891	3/5/98	Tetrachloroethene	250			260	D		ug/L	10.00	255.00		3.92
11891	3/5/98	Trichloroethene	54			60	D		ug/L	6.00	57.00		10.53
11891	6/11/98	1,1,1-Trichloroethane	1			1			ug/L	0.00	1.00		0.00
11891	6/11/98	1,1-Dichloroethene	2			2		J	ug/L	0.00	2.00		0.00
11891	6/11/98	Carbon Tetrachloride	180	D		160	D	V1	ug/L	20.00	170.00		11.76
11891	6/11/98	Chloroform	8			9		J	ug/L	1.00	8.50		11.76
11891	6/11/98	cis-1,2-Dichloroethene	9	JD		9		I	ug/L	0.00	9.00		0.00
11891	6/11/98	Tetrachloroethene	92	D		86	D	V1	ug/L	6.00	89.00		6.74
11891	6/11/98	Trichloroethene	24			26		J	ug/L	2.00	25.00		8.00
11891	11/19/98	1,1,1-Trichloroethane	0.7	J	J1	2			ug/L	1.30	1.35		96.30
11891	11/19/98	1,1-Dichloroethene	1		J1	3		V1	ug/L	2.00	2.00		100.00
11891	11/19/98	Carbon Tetrachloride	430	D	V1	430	D	J1	ug/L	0.00	430.00		0.00
11891	11/19/98	Chloroform	5		J1	15		V1	ug/L	10.00	10.00		100.00
11891	11/19/98	cis-1,2-Dichloroethene	20	DJ	J1	21	DJ	V1	ug/L	1.00	20.50		4.88
11891	11/19/98	Tetrachloroethene	500	D	V1	210	D	V1	ug/L	290.00	355.00		81.69
11891	11/19/98	Trichloroethene	80	D	J1	46	D	J1	ug/L	34.00	63.00		53.97
12191	3/5/98	1,1,1-Trichloroethane	2			3		J1	ug/L	1.00	2.50		40.00
12191	3/5/98	1,1-Dichloroethene	2			3		V1	ug/L	1.00	2.50		40.00
12191	3/5/98	Carbon Tetrachloride	240			220	D		ug/L	20.00	230.00		8.70
12191	3/5/98	Chloroform	5			6		V1	ug/L	1.00	5.50		18.18
12191	3/5/98	cis-1,2-Dichloroethene	10			10		V1	ug/L	0.00	10.00		0.00
12191	3/5/98	Tetrachloroethene	290			280	D		ug/L	10.00	285.00		3.51
12191	3/5/98	Trichloroethene	53			46	D		ug/L	7.00	49.50		14.14
12191	4/28/98	1,1,1-Trichloroethane	6			5		UJ1	ug/L	1.00	5.50		18.18
12191	4/28/98	1,1-Dichloroethene	7			6		V1	ug/L	1.00	6.50		15.38
12191	4/28/98	Carbon Tetrachloride	220			220		V1	ug/L	0.00	220.00		0.00
12191	4/28/98	Chloroform	11			10		V1	ug/L	1.00	10.50		9.52
12191	4/28/98	cis-1,2-Dichloroethene	9			8		V1	ug/L	1.00	8.50		11.76
12191	4/28/98	Tetrachloroethene	210			190		V1	ug/L	20.00	200.00		10.00
12191	4/28/98	Trichloroethene	27			24		V1	ug/L	3.00	25.50		11.76
12191	12/15/98	Carbon Tetrachloride	140		J	140			ug/L	0.00	140.00		0.00
12191	12/15/98	Chloroform	5		J	5			ug/L	0.00	5.00		0.00
12191	12/15/98	cis-1,2-Dichloroethene	8		J	6			ug/L	2.00	7.00		28.57
12191	12/15/98	Methylene Chloride	3	B	UJ	3	B		ug/L	0.00	3.00		0.00
12191	12/15/98	Tetrachloroethene	170		J	170			ug/L	0.00	170.00		0.00
12191	12/15/98	Trichloroethene	25		J	24			ug/L	1.00	24.50		4.08
3586	6/5/98	1,1,1-Trichloroethane	1			1			ug/L	0.00	1.00		0.00
3586	6/5/98	1,1-Dichloroethene	19			19			ug/L	0.00	19.00		0.00
3586	6/5/98	cis-1,2-Dichloroethene	9			8			ug/L	1.00	8.50		11.76
3586	6/5/98	trans-1,2-Dichloroethene	0.6	J		0.5	J	UJ1	ug/L	0.10	0.55		18.18
3586	6/5/98	Trichloroethene	1			1			ug/L	0.00	1.00		0.00
3586	6/5/98	Vinyl Chloride	14			14			ug/L	0.00	14.00		0.00
3586	10/20/98	1,1,1-Trichloroethane	1		V1	1			ug/L	0.00	1.00		0.00
3586	10/20/98	1,1-Dichloroethene	39		V1	40			ug/L	1.00	39.50		2.53
3586	10/20/98	Benzene	0.8	J	J1	0.9	J		ug/L	0.10	0.85		11.76
3586	10/20/98	cis-1,2-Dichloroethene	10		V1	12			ug/L	2.00	11.00		18.18
3586	10/20/98	Methylene Chloride	0.7	BJ	JB1	0.8	BJ		ug/L	0.10	0.75		13.33
3586	10/20/98	trans-1,2-Dichloroethene	0.8	J	V1	0.8	J		ug/L	0.00	0.80		0.00
3586	10/20/98	Trichloroethene	0.7	J	V1	0.8	J		ug/L	0.10	0.75		13.33
3586	10/20/98	Vinyl Chloride	34		V1	39			ug/L	5.00	36.50		13.70
5887	8/31/98	Chromium	2			2			ug/L	0.00	2.00		0.00

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Location	Sample Date	Analyte	Real Result	Real Result Qual	Real Valid	Dup Result	Dup Result Qual	Dup Valid	Units	Difference Real-Dup	Average (Real+Dup)/2	RPD	Diff/Avg x100
Volatile Organic Compounds													
70193	7/14/98	1,1,1-Trichloroethane	0.2	J		0.2	J		R1	ug/L	0.00	0.20	0.00
70193	7/14/98	Methylene Chloride	2	J		1	J			ug/L	1.00	1.50	66.67
70193	9/29/98	Methylene Chloride	4			4				ug/L	0.00	4.00	0.00
70393	12/14/98	1,1,1-Trichloroethane	28		J	30				ug/L	2.00	29.00	6.90
70393	12/14/98	1,1-Dichloroethene	14		J	16				ug/L	2.00	15.00	13.33
70393	12/14/98	Carbon Tetrachloride	0.7	J	J	0.8	J		J1	ug/L	0.10	0.75	13.33
70393	12/14/98	Tetrachloroethene	7		J	7				ug/L	0.00	7.00	0.00
70393	12/14/98	Trichloroethene	21		J	22				ug/L	1.00	21.50	4.65
891COLGAL	8/20/98	Methylene Chloride	0.7	J		0.8	J			ug/L	0.10	0.75	13.33
891COLGAL	8/20/98	Trichloroethene	0.7	J		1				ug/L	0.30	0.85	35.29
891COLWEL	8/20/98	1,1,1-Trichloroethane	0.6	J		0.7	J			ug/L	0.10	0.65	15.38
891COLWEL	8/20/98	1,1-Dichloroethene	3			3				ug/L	0.00	3.00	0.00
891COLWEL	8/20/98	Carbon Tetrachloride	12			12				ug/L	0.00	12.00	0.00
891COLWEL	8/20/98	Chloroform	0.8	J		0.9	J			ug/L	0.10	0.85	11.76
891COLWEL	8/20/98	Methylene Chloride	0.8	J		0.8	J			ug/L	0.00	0.80	0.00
891COLWEL	8/20/98	Tetrachloroethene	13			13				ug/L	0.00	13.00	0.00
891COLWEL	8/20/98	Trichloroethene	100	D		100	D		V1	ug/L	0.00	100.00	0.00
P209489	5/14/98	1,1-Dichloroethene	0.6	J		1	D			ug/L	0.40	0.80	50.00
P209489	5/14/98	Carbon Tetrachloride	52	D		44	D		UJ1	ug/L	8.00	48.00	16.67
P209489	5/14/98	Chloroform	20	D		17	D		V1	ug/L	3.00	18.50	16.22
P209489	5/14/98	cis-1,2-Dichloroethene	10	D		10			V1	ug/L	0.00	10.00	0.00
P209489	5/14/98	Methylene Chloride	6	B		6	D			ug/L	0.00	6.00	0.00
P209489	5/14/98	Tetrachloroethene	3	D		3			V1	ug/L	0.00	3.00	0.00
P209489	5/14/98	Trichloroethene	63	D		55	D		V1	ug/L	8.00	59.00	13.56
SW13494	11/2/98	cis-1,2-Dichloroethene	2		V1	0.9	J			ug/L	1.10	1.45	75.86
SW13494	11/2/98	Methylene Chloride	5	B	UJ1	2				ug/L	3.00	3.50	85.71
SW13494	11/2/98	Tetrachloroethene	40		V1	18				ug/L	22.00	29.00	75.86
SW13494	11/2/98	Trichloroethene	3		V1	1				ug/L	2.00	2.00	100.00

Note: RPD values greater than the 30% QC criterion are indicated in bold font.

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Location	Sample Date	Analyte	Real Result	Real Result Qual	Real Valid	Dup Result	Dup Result Qual	Dup Valid	Units	Difference Real-Dup	Average (Real+Dup)/2	RPD Diff./Avg x100
Metals												
02291	12/4/98	Barium	172	E		194	E	J	ug/L	22.00	183.00	12.02
02291	12/4/98	Calcium	65700	E		73900	E	J	ug/L	8200.00	69800.00	11.75
02291	12/4/98	Magnesium	19100	E		21400	E	J	ug/L	2300.00	20250.00	11.36
02291	12/4/98	Sodium	16200	E		17900	E	UJ	ug/L	1700.00	17050.00	9.97
02291	12/4/98	Strontium	563	E		637	E	J	ug/L	74.00	600.00	12.33
02291	12/4/98	Thallium	1.1	N		1.5	N	I	ug/L	0.40	1.30	30.77
03991	8/6/98	Barium	239			234			ug/L	5.00	236.50	2.11
03991	8/6/98	Calcium	124000	E		122000	E	J	ug/L	2000.00	123000.00	1.63
03991	8/6/98	Magnesium	13900			13500			ug/L	400.00	13700.00	2.92
03991	8/6/98	Sodium	16200	E		16000	E	UJ1	ug/L	200.00	16100.00	1.24
03991	8/6/98	Strontium	498			487			ug/L	11.00	492.50	2.23
05091	8/26/98	Barium	168			167		V	ug/L	1.00	167.50	0.60
05091	8/26/98	Calcium	100000			101000		V1	ug/L	1000.00	100500.00	1.00
05091	8/26/98	Magnesium	16300			16700		V1	ug/L	400.00	16500.00	2.42
05091	8/26/98	Sodium	31300			30300		J1	ug/L	1000.00	30800.00	3.25
05091	8/26/98	Strontium	588			587			ug/L	1.00	587.50	0.17
10498	8/12/98	Aluminum	50.8	E	J1	43.3	E	V1	ug/L	7.50	47.05	15.94
10498	8/12/98	Calcium	32000			34300			ug/L	2300.00	33150.00	6.94
10498	8/12/98	Chromium	2.9	N	J1	2.9	N	I	ug/L	0.00	2.90	0.00
10498	8/12/98	Copper	4.8			5			ug/L	0.20	4.90	4.08
10498	8/12/98	Lead	1.8			1.9			ug/L	0.10	1.85	5.41
10498	8/12/98	Manganese	52			45.9			ug/L	6.10	48.95	12.46
10498	8/12/98	Selenium	2.7	N	J1	2.7	N	I	ug/L	0.00	2.70	0.00
10498	8/12/98	Sodium	146000			136000			ug/L	10000.00	141000.00	7.09
10498	8/12/98	Zinc	29.4		UJ1	56.4			ug/L	27.00	42.90	62.94
11891	3/5/98	Barium	224		V1	221			ug/L	3.00	222.50	1.35
11891	3/5/98	Calcium	121000		V1	120000			ug/L	1000.00	120500.00	0.83
11891	3/5/98	Magnesium	11400		V1	11300			ug/L	100.00	11350.00	0.88
11891	3/5/98	Sodium	18800		V1	18800			ug/L	0.00	18800.00	0.00
11891	3/5/98	Strontium	422		V1	418			ug/L	4.00	420.00	0.95
11891	6/11/98	Barium	224			210		J	ug/L	14.00	217.00	6.45
11891	6/11/98	Calcium	117000			110000		UJ1	ug/L	7000.00	113500.00	6.17
11891	6/11/98	Magnesium	11800			10900		V1	ug/L	900.00	11350.00	7.93
11891	6/11/98	Selenium	2.4	N*		1.4	N*	I	ug/L	1.00	1.90	52.63
11891	6/11/98	Sodium	31200	E		29500	E	V1	ug/L	1700.00	30350.00	5.60
11891	6/11/98	Strontium	407	N		381	N	I	ug/L	26.00	394.00	6.60
11891	11/19/98	Barium	220		V1	213		V1	ug/L	7.00	216.50	3.23
11891	11/19/98	Calcium	111000		V1	108000		V1	ug/L	3000.00	109500.00	2.74
11891	11/19/98	Magnesium	11100		V1	10700		V1	ug/L	400.00	10900.00	3.67
11891	11/19/98	Sodium	18000		V1	17700		V1	ug/L	300.00	17850.00	1.68
11891	11/19/98	Strontium	404		V1	392		UJ1	ug/L	12.00	398.00	3.02
12191	3/5/98	Calcium	134000		I	135000		V1	ug/L	1000.00	134500.00	0.74
12191	3/5/98	Magnesium	10700		I	10700		J1	ug/L	0.00	10700.00	0.00
12191	3/5/98	Sodium	12300		I	12400		V1	ug/L	100.00	12350.00	0.81
12191	3/5/98	Strontium	431		I	433		UJ1	ug/L	2.00	432.00	0.46
12191	4/28/98	Barium	165			157		V1	ug/L	8.00	161.00	4.97
12191	4/28/98	Calcium	133000			125000		V1	ug/L	8000.00	129000.00	6.20
12191	4/28/98	Magnesium	10300			9720			ug/L	580.00	10010.00	5.79
12191	4/28/98	Sodium	12700			12100			ug/L	600.00	12400.00	4.84
12191	4/28/98	Strontium	399			380			ug/L	19.00	389.50	4.88
12191	12/15/98	Barium	181		V1	194			ug/L	13.00	187.50	6.93
12191	12/15/98	Calcium	121000		V1	129000			ug/L	8000.00	125000.00	6.40
12191	12/15/98	Strontium	390		V1	419			ug/L	29.00	404.50	7.17
3586	6/5/98	Aluminum	20.8			40.1			ug/L	19.30	30.45	63.38
3586	6/5/98	Arsenic	2.8			2.7			ug/L	0.10	2.75	3.64
3586	6/5/98	Calcium	131000			129000			ug/L	2000.00	130000.00	1.54
3586	6/5/98	Iron	2380			2370			ug/L	10.00	2375.00	0.42
3586	6/5/98	Magnesium	34500			34200			ug/L	300.00	34350.00	0.87
3586	6/5/98	Manganese	4180			4110			ug/L	70.00	4145.00	1.69
3586	6/5/98	Sodium	162000	E		157000	E	V1	ug/L	5000.00	159500.00	3.13
3586	6/5/98	Strontium	828	N		814	N	I	ug/L	14.00	821.00	1.71
3586	10/20/98	Arsenic	2.4		V	2.6			ug/L	0.20	2.50	8.00
3586	10/20/98	Calcium	134000		J	129000			ug/L	5000.00	131500.00	3.80

Table 2-2
Relative Percent Differences (RPDs) and Duplicate Error Ratios (DERs)
Groundwater 1998

Location	Sample Date	Analyte	Real Result	Real Result Qual	Real Valid	Dup Result	Dup Result Qual	Dup Valid	Units	Difference Real-Dup	Average (Real+Dup)/2	RPD Diff./Avg x100
Metals												
3586	10/20/98	Iron	2310		J	2190			ug/L	120.00	2250.00	5.33
3586	10/20/98	Magnesium	37500		J	35600			ug/L	1900.00	36550.00	5.20
3586	10/20/98	Manganese	4270		J	4060			ug/L	210.00	4165.00	5.04
3586	10/20/98	Sodium	163000		J	156000			ug/L	7000.00	159500.00	4.39
3586	10/20/98	Strontium	932		J	886			ug/L	46.00	909.00	5.06
5887	5/26/98	Calcium	18300			17500			ug/L	800.00	17900.00	4.47
5887	5/26/98	Copper	3.6			3.3			ug/L	0.30	3.45	8.70
5887	5/26/98	Selenium	1.7			1.3			ug/L	0.40	1.50	26.67
5887	5/26/98	Sodium	6040	E		5870	E	VI	ug/L	170.00	5955.00	2.85
5887	8/31/98	Calcium	20300			20200			ug/L	100.00	20250.00	0.49
5887	8/31/98	Sodium	7190			6890			ug/L	300.00	7040.00	4.26
5887	12/14/98	Aluminum	20.4		UJ1	18			ug/L	2.40	19.20	12.50
5887	12/14/98	Calcium	20400		VI	19500			ug/L	900.00	19950.00	4.51
5887	12/14/98	Chromium	3.1		VI	3.2			ug/L	0.10	3.15	3.17
5887	12/14/98	Copper	4.6		VI	4.5			ug/L	0.10	4.55	2.20
70193	7/14/98	Aluminum	35.2			28.2			ug/L	7.00	31.70	22.08
70193	7/14/98	Calcium	23300			25600			ug/L	2300.00	24450.00	9.41
70193	7/14/98	Selenium	3.9			4.9			ug/L	1.00	4.40	22.73
70193	7/14/98	Sodium	13400			13500			ug/L	100.00	13450.00	0.74
70193	11/30/98	Aluminum	41.5	*		49.7	*		ug/L	8.20	45.60	17.98
70193	11/30/98	Calcium	20700	E		19700	E	VI	ug/L	1000.00	20200.00	4.95
70193	11/30/98	Sodium	10800	E		10700	E	VI	ug/L	100.00	10750.00	0.93
70193	11/30/98	Strontium	240	E		138	E	VI	ug/L	102.00	189.00	53.97
70393	8/26/98	Aluminum	19.1			19.2			ug/L	0.10	19.15	0.52
70393	8/26/98	Calcium	20300			20800			ug/L	500.00	20550.00	2.43
70393	8/26/98	Sodium	13200			12900			ug/L	300.00	13050.00	2.30
70393	12/14/98	Calcium	18000		VI	16800			ug/L	1200.00	17400.00	6.90
891COLGAL	8/20/98	Arsenic	1.7			1.8			ug/L	0.10	1.75	5.71
891COLGAL	8/20/98	Barium	73.7			140		J1	ug/L	66.30	106.85	62.05
891COLGAL	8/20/98	Calcium	61800			114000			ug/L	52200.00	87900.00	59.39
891COLGAL	8/20/98	Selenium	15	N		14.3	N	1	ug/L	0.70	14.65	4.78
891COLGAL	8/20/98	Strontium	523			996			ug/L	473.00	759.50	62.28
891COLGAL	8/20/98	Zinc	115			121			ug/L	6.00	118.00	5.08
891COLWEL	8/20/98	Barium	68.5			69.7			ug/L	1.20	69.10	1.74
891COLWEL	8/20/98	Calcium	167000			170000			ug/L	3000.00	168500.00	1.78
891COLWEL	8/20/98	Magnesium	37200			37900			ug/L	700.00	37550.00	1.86
891COLWEL	8/20/98	Nickel	24.1			24			ug/L	0.10	24.05	0.42
891COLWEL	8/20/98	Selenium	470	N		457	N	1	ug/L	13.00	463.50	2.80
891COLWEL	8/20/98	Sodium	143000			141000			ug/L	2000.00	142000.00	1.41
891COLWEL	8/20/98	Strontium	1280			1310			ug/L	30.00	1295.00	2.32
P209489	5/14/98	Antimony	2	N*		1.3	N*	1	ug/L	0.70	1.65	42.42
P209489	5/14/98	Cadmium	0.36	N		0.3	N	1	ug/L	0.06	0.33	18.18
P209489	5/14/98	Calcium	136000			135000			ug/L	1000.00	135500.00	0.74
P209489	5/14/98	Magnesium	23500			23200			ug/L	300.00	23350.00	1.28
P209489	5/14/98	Sodium	229000			232000			ug/L	3000.00	230500.00	1.30
P209489	5/14/98	Strontium	644			638			ug/L	6.00	641.00	0.94
SW13494	11/2/98	Barium	140	E		162		VI	ug/L	22.00	151.00	14.57
SW13494	11/2/98	Calcium	80300	E		95000		UJ1	ug/L	14700.00	87650.00	16.77
SW13494	11/2/98	Sodium	42500	E		50400		VI	ug/L	7900.00	46450.00	17.01
SW13494	11/2/98	Strontium	602	E		723		J1	ug/L	121.00	662.50	18.26
SW13494	11/2/98	Zinc	57.5			50.9			ug/L	6.60	54.20	12.18

Note: RPD values greater than the 30% QC criterion are indicated in bold font.

Table 2-3
Summary of RPD and DER Results
Groundwater 1998

Analytical Suite	QC Criterion for RPD or DER Value	Number of RPD/DER Pairs Calculated	Number of Duplicates Within RPD or DER Criterion	Overall Precision Compliance
Metals	less than 30%	114	105	92.1%
Volatile Organic Compounds	less than 30%	102	85	83.3%
Radionuclides	less than 1.96	88	87	98.9%
Water Quality Parameters	less than 30%	48	47	97.9%

Note: Calculations not made for results qualified as undetected for any analyte. This includes "R" validated data, "U" qualified VOC, data, and "U" and "B" qualified inorganic data.

Table 2-4
Comparison of Analytical Methods and Detection Limits
Groundwater 1998

CAS#	Analyte	Required Analytical Method	Actual Analytical Method	Required CRDL	Percent at or Below Required CRDL	Units
Volatile Organic Compounds						
630-20-6	1,1,1,2-Tetrachloroethane	EPA 524.2	EPA 524.2	1	98%	ug/L
71-55-6	1,1,1-Trichloroethane	EPA 524.2	EPA 524.2	1	99%	ug/L
79-34-5	1,1,2,2-Tetrachloroethane	EPA 524.2	EPA 524.2	1	100%	ug/L
79-00-5	1,1,2-Trichloroethane	EPA 524.2	EPA 524.2	1	100%	ug/L
75-34-3	1,1-Dichloroethane	EPA 524.2	EPA 524.2	1	99%	ug/L
75-35-4	1,1-Dichloroethene	EPA 524.2	EPA 524.2	1	100%	ug/L
563-58-6	1,1-Dichloropropene	EPA 524.2	EPA 524.2	1	98%	ug/L
87-61-6	1,2,3-Trichlorobenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
96-18-4	1,2,3-Trichloropropane	EPA 524.2	EPA 524.2	1	98%	ug/L
120-82-1	1,2,4-Trichlorobenzene	EPA 524.2	EPA 524.2	1	99%	ug/L
95-63-6	1,2,4-Trimethylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
96-12-8	1,2-Dibromo-3-chloropropane	EPA 524.2	EPA 524.2	1	100%	ug/L
106-93-4	1,2-Dibromoethane	EPA 524.2	EPA 524.2	1	98%	ug/L
95-50-1	1,2-Dichlorobenzene	EPA 524.2	EPA 524.2	1	99%	ug/L
107-06-2	1,2-Dichloroethane	EPA 524.2	EPA 524.2	1	100%	ug/L
78-87-5	1,2-Dichloropropane	EPA 524.3	EPA 524.2	1	100%	ug/L
95-47-6	1,2-Xylene	EPA 524.4	EPA 524.2	1	96%	ug/L
000-00-0	1,3- and 1,4-Xylene	EPA 524.5	EPA 524.2	1	96%	ug/L
108-67-8	1,3,5-Trimethylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
541-73-1	1,3-Dichlorobenzene	EPA 524.2	EPA 524.2	1	99%	ug/L
142-28-9	1,3-Dichloropropane	EPA 524.2	EPA 524.2	1	98%	ug/L
106-46-7	1,4-Dichlorobenzene	EPA 524.2	EPA 524.2	1	99%	ug/L
594-20-7	2,2-Dichloropropane	EPA 524.2	EPA 524.2	1	98%	ug/L
95-49-8	2-Chlorotoluene	EPA 524.2	EPA 524.2	1	98%	ug/L
106-43-4	4-Chlorotoluene	EPA 524.2	EPA 524.2	1	98%	ug/L
99-87-6	4-Isopropyltoluene	EPA 524.2	EPA 524.2	1	98%	ug/L
71-43-2	Benzene	EPA 524.2	EPA 524.2	1	100%	ug/L
108-86-1	Bromobenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
74-97-5	Bromochloromethane	EPA 524.2	EPA 524.2	1	98%	ug/L
75-27-4	Bromodichloromethane	EPA 524.2	EPA 524.2	1	99%	ug/L
75-25-2	Bromoform	EPA 524.2	EPA 524.2	1	99%	ug/L
74-83-9	Bromomethane	EPA 524.2	EPA 524.2	1	100%	ug/L
56-23-5	Carbon Tetrachloride	EPA 524.2	EPA 524.2	1	99%	ug/L
108-90-7	Chlorobenzene	EPA 524.2	EPA 524.2	1	99%	ug/L
75-00-3	Chloroethane	EPA 524.2	EPA 524.2	1	98%	ug/L
67-66-3	Chloroform	EPA 524.2	EPA 524.2	1	98%	ug/L
74-87-3	Chloromethane	EPA 524.2	EPA 524.2	1	100%	ug/L
156-59-2	cis-1,2-Dichloroethene	EPA 524.2	EPA 524.2	1	98%	ug/L
10061-01-5	cis-1,3-Dichloropropene	EPA 524.2	EPA 524.2	1	100%	ug/L
124-48-1	Dibromochloromethane	EPA 524.2	EPA 524.2	1	100%	ug/L
74-95-3	Dibromomethane	EPA 524.2	EPA 524.2	1	98%	ug/L
75-71-8	Dichlorodifluoromethane	EPA 524.2	EPA 524.2	1	98%	ug/L
100-41-4	Ethylbenzene	EPA 524.2	EPA 524.2	1	99%	ug/L
87-68-3	Hexachlorobutadiene	EPA 524.2	EPA 524.2	1	100%	ug/L
98-82-8	Isopropylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
75-09-2	Methylene Chloride	EPA 524.2	EPA 524.2	1	99%	ug/L
91-20-3	Naphthalene	EPA 524.2	EPA 524.2	1	99%	ug/L
104-51-8	n-Butylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
103-65-1	n-Propylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
135-98-8	sec-Butylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
100-42-5	Styrene	EPA 524.2	EPA 524.2	1	99%	ug/L
98-06-6	tert-Butylbenzene	EPA 524.2	EPA 524.2	1	98%	ug/L
127-18-4	Tetrachloroethene	EPA 524.2	EPA 524.2	1	99%	ug/L
108-88-3	Toluene	EPA 524.2	EPA 524.2	1	99%	ug/L
1330-20-7	Total Xylenes	EPA 524.2	EPA 524.2	1	100%	ug/L

Table 2-4
Comparison of Analytical Methods and Detection Limits
Groundwater 1998

CAS#	Analyte	Required Analytical Method	Actual Analytical Method	Required CRDL	Percent at or Below Required CRDL	Units
156-60-5	trans-1,2-Dichloroethene	EPA 524.2	EPA 524.2	1	99%	ug/L
10061-02-6	trans-1,3-Dichloropropene	EPA 524.2	EPA 524.2	1	100%	ug/L
79-01-6	Trichloroethene	EPA 524.2	EPA 524.2	1	96%	ug/L
75-69-4	Trichlorofluoromethane	EPA 524.2	EPA 524.2	1	98%	ug/L
75-01-4	Vinyl Chloride	EPA 524.2	EPA 524.2	1	100%	ug/L
Metals						
7429-90-5	Aluminum	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	17	100%	ug/L
7440-36-0	Antimony	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	1	54%	ug/L
7440-38-2	Arsenic	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	1	44%	ug/L
7440-39-3	Barium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	100	100%	ug/L
7440-41-7	Beryllium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	1	100%	ug/L
7440-43-9	Cadmium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	0.3	48%	ug/L
7440-70-2	Calcium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	5000	100%	ug/L
7440-47-3	Chromium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	2	100%	ug/L
7440-48-4	Cobalt	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	50	100%	ug/L
7440-50-8	Copper	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	3	100%	ug/L
7439-89-6	Iron	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	100	100%	ug/L
7439-92-1	Lead	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	1	66%	ug/L
7439-93-2	Lithium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	100	100%	ug/L
7439-95-4	Magnesium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	5000	100%	ug/L
7439-96-5	Manganese	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	15	100%	ug/L
7439-97-6	Mercury	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	0.1	93%	ug/L
7439-98-7	Molybdenum	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	30	100%	ug/L
7440-02-0	Nickel	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	20	100%	ug/L
7440-09-7	Potassium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	5000	100%	ug/L
7782-49-2	Selenium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	1	45%	ug/L
7440-22-4	Silver	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	0.1	55%	ug/L
7440-23-5	Sodium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	5000	100%	ug/L
7440-24-6	Strontium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	200	100%	ug/L
7440-28-0	Thallium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	0.5	59%	ug/L
7440-31-5	Tin	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	200	100%	ug/L
11-09-6	Uranium	CLP-SOW-Dissolved	CLP-SOW (Dissolved)	NR	NR	ug/L
7440-62-2	Vanadium	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	40	100%	ug/L
7440-66-6	Zinc	CLP-SOW-Dissolved	CLP-SOW (Diss. & Total)	20	100%	ug/L
Radionuclides						
14596-10-2	Americium-241	Alpha Spec. (EPA A-001)	Alpha Spec. (EPA A-001)	0.03	100%	pCi/L
10-12-8	Plutonium-239/240	Alpha Spec. (EPA A-001)	Alpha Spec. (EPA A-001)	0.03	100%	pCi/L
11-10-9	Strontium-89/90	Gas Flow (EPA 900.0)	Gas Flow (EPA 900.0)	1	100%	pCi/L
10028-17-8	Tritium	Liquid Scint. (EPA A-002)	Liquid Scint. (EPA A-002)	400	100%	pCi/L
11-08-5	Uranium-233/234	Alpha Spec. (EPA A-001)	Alpha Spec. (EPA A-001)	1	100%	pCi/L
15117-96-1	Uranium-235	Alpha Spec. (EPA A-001)	Alpha Spec. (EPA A-001)	1	100%	pCi/L
7440-61-1	Uranium-238	Alpha Spec. (EPA A-001)	Alpha Spec. (EPA A-001)	1	100%	pCi/L
Water Quality Parameters						
16984-48-8	Fluoride	EPA 300.0	EPA 300.0	0.5	100%	mg/L
C-005	Nitrate/Nitrite	EPA 353.1	EPA 353.1	0.05	63%	mg/L
10-33-3	Total Dissolved Solids	EPA 160.1	EPA 160.1	10	100%	mg/L
14808-79-8	Sulfate as SO ₄	EPA 375.1	EPA 375.1, 300.0	5	63%	mg/L

**Table 2-5
Rinsate QC Results with Detections
Groundwater 1999**

Location	Sample Date	Sample Number	Analyte	Tier 2	Result	Units	Lab Qual.	Detect Limit	Dilution	Validation Qual.
Volatile Organic Compounds										
02291	12/4/98	GW06194TE	Methylene Chloride	5	2	ug/L	B	1	1	UJ
02397	11/5/98	GW06171TE	Chloromethane	2.32	0.9	ug/L	J	1	1	J1
02397	11/5/98	GW06171TE	Methylene Chloride	5	4	ug/L	B	1	1	UJ1
05091	8/26/98	GW05924TE	Chloromethane	2.32	0.9	ug/L	J	1		V1
05091	8/26/98	GW05924TE	Trichloroethene	5	0.7	ug/L	J	1		J1
10498	8/19/98	GW06077TE	Methylene Chloride		0.7	ug/L	J	1		J1
12191	12/15/98	GW06140TE	Toluene	1000	0.5	ug/L	J	1	1	J
3586	10/20/98	GW06148TE	Methylene Chloride	5	0.9	ug/L	BJ	1	1	JB1
891COLGAL	8/20/98	GW06069TE	Methylene Chloride	5	0.7	ug/L	J	1		J1
891COLGAL	8/20/98	GW06069TE	Trichloroethene	5	0.7	ug/L	J	1		V1
891COLWEL	8/20/98	GW06068TE	Trichloroethene	5	0.5	ug/L	J	1		V1
P209489	5/14/98	GW06005TE	Chloromethane	2.32	0.7	ug/L	J	1		V1
P209489	5/14/98	GW06005TE	Trichloroethene	5	0.7	ug/L	J	1		V1
SW13494	8/19/98	GW06067TE	Methylene Chloride	5	0.5	ug/L	J	1		J1
Metals										
02291	12/4/98	GW06194TE	Thallium	2	2	ug/L	N	0.15	1	UJ1
03991	8/6/98	GW05917TE	Cadmium	5	2.6	ug/L	N	0.05		J1
10498	8/12/98	GW06066TE	Aluminum	106000	39.3	ug/L	E	0.25		UJ1
11891	6/11/98	GW05942TE	Aluminum	106000	23	ug/L	*	10		UJ1
11891	6/11/98	GW05942TE	Zinc	11000	22	ug/L	E	0.1		J1
70193	11/30/98	GW06189TE	Thallium	2	2.5	ug/L	N	0.15	1	UJ1
891COLWEL	8/20/98	GW06068TE	Aluminum	106000	77.7	ug/L	E	0.25		J1
891COLWEL	8/20/98	GW06068TE	Selenium	50	1	ug/L	N	0.20		J1
P209489	5/14/98	GW06005TE	Aluminum	106000	42.7	ug/L	E	0.25		J1
P209489	5/14/98	GW06005TE	Lead	15	1.6	ug/L	EN	0.05		J1
SW13494	8/19/98	GW06067TE	Aluminum	106000	27.1	ug/L	E	0.25		UJ1
Radionuclides										
02291	12/4/98	GW06194TE	Uranium-238	0.768	0.276	pCi/L	J	0.068		V
03991	8/6/98	GW05917TE	Americium-241	0.145	0.014	pCi/L	J	0.005		V1
03991	8/6/98	GW05917TE	Uranium-238	0.768	0.172	pCi/L	J	0.078		V1
11891	3/5/98	GW05805TE	Plutonium-239/240	0.151	0.026	pCi/L	J	0.015		
11891	6/11/98	GW05942TE	Americium-241	0.145	0.0101	pCi/L	J	0.0031		V
11891	11/19/98	GW06176TE	Uranium-233/234	1.07	0.194	pCi/L	J	0.066		V1
12191	4/28/98	GW05946TE	Plutonium-239/240	0.151	0.0093	pCi/L	J	0.005		V1
12191	4/28/98	GW05946TE	Uranium-233/234	1.07	0.4115	pCi/L	J	0.0484		V1
12191	4/28/98	GW05946TE	Uranium-238	0.768	0.1073	pCi/L	J	0.0484		V1
12191	12/15/98	GW06140TE	Americium-241	0.145	0.015	pCi/L	J	0.014		V1
12191	12/15/98	GW06140TE	Plutonium-239/240	0.151	0.004	pCi/L	J	0.004		V1
12191	12/15/98	GW06140TE	Uranium-238	0.768	0.073	pCi/L	J	0.066		V1
3586	3/16/98	GW05818TE	Plutonium-239/240	0.151	0.15	pCi/L	J	0.088		
3586	6/5/98	GW05966TE	Americium-241	0.145	0.0087	pCi/L	J	0.0037		V
3586	6/5/98	GW05966TE	Uranium-233/234	1.07	0.1029	pCi/L	J	0.0309		V
70193	7/14/98	GW05989TE	Uranium-233/234	1.07	0.1206	pCi/L	J	0.0544		V1
70193	11/30/98	GW06189TE	Uranium-233/234	1.07	0.163	pCi/L	J	0.063		V
P209489	5/14/98	GW06005TE	Plutonium-239/240	0.151	0.0141	pCi/L	J	.0047		

Table 2-5
Rinsate QC Results with Detections
Groundwater 1999

Location	Sample Date	Sample Number	Analyte	Tier 2	Result	Units	Lab Qual.	Detect Limit	Dilution	Validation Qual.
Water Quality Parameters										
03991	8/6/98	GW05917TE	Nitrate/Nitrite	10	0.05	mg/L		0.05		V1
03991	8/6/98	GW05917TE	Total Diss Solids		12	mg/L		10		V1
05091	8/26/98	GW05924TE	Total Diss Solids		24	mg/L		10		V1
11891	11/19/98	GW06176TE	Total Diss Solids		10	mg/L		10		V1
12191	4/28/98	GW05946TE	Total Diss Solids		18	mg/L		10		
3586	10/20/98	GW06148TE	Nitrate/Nitrite	10	1.3	mg/L		0.05	5	V1

Other aspects of representativeness such as numbers of samples and spatial distribution are fixed in the IMP (K-H, 1998a). All wells that were required to be sampled were visited in 1998. Plate 1 presents the locations sampled for reference to the spatial distribution of the samples.

Completeness

Table 2-6 compares the actual number of samples collected in 1998 to the required number of samples. As a result of dry wells or wells with such low productivity as to prohibit sample collection, the completeness goal of 90% was not met for any of the analyte groups.

Completeness is a quantitative measure of data quality expressed as the percentage of valid or acceptable data obtained from a measurement system. Table 2-7 summarizes the validation completeness evaluation. Detailed validation and verification data for all analytes and samples are provided in the 1998 quarterly reports (RMRS 1998a, 1998b, 1999a, and 1999b). A completeness metric was calculated using the following formula:

$$\text{Completeness} = Dp_u = \frac{DP_t - DP_n}{DP_t} \times 100 \text{ (in percent)} \quad \text{The completeness criterion is } \geq 90\%.$$

Where:

- Dp_u = Percentage of usable data points
- DP_n = Non-usable data points
- DP_t = Total number of data points

Comparability

During 1998 planned analytical methods for VOCs, water quality parameters, and radionuclides remained consistent over the entire year (see below for metals). Table 2-4 lists the required methods for the various analytes. Laboratory analyses were performed according to standard CLP protocols and results should be comparable to data produced by similar methods.

In the third quarter of 1998, sampling procedure was modified in order to reduce the amount of purge water generated at certain wells and also enhance the quality of the samples collected. Some wells with adequate recharge rates have had submersible pumps installed. Pump equipped wells allow for micropurging at the time of sampling. Micropurging, where pump discharge rates are set low to prevent an increase in turbidity, has several advantages. Less water is needed to purge the pump system compared to purging with a bailer, and there is less purge water to dispose of. Because the pump intake port is placed opposite the center of the screened interval in the well, collection of water entering the well bore directly from the aquifer minimizes the dilution of the formation water with stagnant well water.

Table 2-6
Comparison of Required and Actual Samples Collected
Groundwater 1998

Sample Types		Required Number of Visits	Actual Number of Visits*	Actual Number of Samples Collected	Deviation	Percent of Samples Successfully Collected (or Wells Visited)	Discrepancy Justification
Groundwater Wells (Visits)		232	232	NA	0	100.0	NA
VOC's		232	232	200	-32	86.2	Dry
Metals		202	202	151	-51	74.8	Dry or Insw
Radionuclides							
	Pu/Am	126	126	82	-44	65.1	Dry or Insw
	U-isotope	204	204	145	-59	71.1	Dry or Insw
	Tritium	83	83	54	-29	65.1	Dry or Insw
	Strontium	46	46	17	-29	37.0	Dry or Insw
Water Quality Parameters							
	Nitrate	186	186	148	-38	79.6	Dry or Insw
	TDS	211	211	148	-63	70.1	Dry or Insw
	Sulfate	125	125	71	-54	56.8	Dry or Insw
	Fluoride	93	93	50	-43	53.8	Dry or Insw

*Does not reflect multiple visits to dry wells.

Dry = Well did not recharge after purging. No samples collected.

Insw = Insufficient water to collect complete sample suite.

Table 2-7
Summary of Validation and Verification Completeness
Groundwater 1998

	All Analyses	VOC's	Metals			Radionuclides					Water Quality Parameters				
			SUM	Diss.	Total	SUM	U-iso	Pu/Am	Tritium	Str _{90/90}	SUM	NO ₃ /NO ₂	TDS	SO ₄	Fluoride
Total number of Data Points (DP_t)	20595	14659	4506	3939	567	919	588	226	88	17	511	187	182	81	61
Usable Data Points (DP_u)	20129	14281	4419	3853	566	918	588	225	88	17	511	187	182	81	61
Non-usable Data Points (DP_n)	466	378	87	86	1	1	0	1	0	0	0	0	0	0	0
Percent of Usable Data Points	97.7%	97.4%	98.1%	97.8%	99.8%	100%	100%	99.6%	100%	100%	100%	100%	100%	100%	100%
Data Validation or Verification not Provided	5106	3775	715	715	0	485	319	111	45	10	131	38	50	24	19
Data Points Validated	1502	726	640	480	160	136	89	37	8	2	0	0	0	0	0
Percent of Total Data Points	7.3%	5.0%	14.2%	12.2%	28.2%	14.8%	15.1%	16.4%	9.1%	11.8%	0.0%	0.0%	0.0%	0.0%	0.0%
Data Points Verified	12606	8778	3151	2746	405	297	180	77	35	5	380	149	132	57	42
Percent of Total Data Points	61.2%	59.9%	69.9%	69.7%	71.4%	32.3%	30.6%	34.1%	39.8%	29.4%	74.4%	79.7%	72.5%	70.4%	68.9%
Percent of Total Data Points Validated or Verified	68.5%	64.8%	84.1%	81.9%	100%	47.1%	45.7%	50.4%	48.9%	41.2%	74.4%	79.7%	72.5%	70.4%	68.9%

Usable data points contain verification qualifiers J1, JB1, U1, UJ1, or V1.

Usable data points contain validation qualifiers J, JB, U, UJ, or V.

Non-usable data points contain the validation/verification qualifiers R or R1.

Based on the high percentage of Usable Data Points, data that have not been validated or verified are considered usable.

QC criteria defined in IMP:

Percent of usable data points >90%.

Percent of total number of data points validated >25%

Percent of total number of data points verified >75%

Finally, because of low pump discharge rates and consequent minimal mixing in the well bore, low turbidity samples may be collected without filtering.

The installation of submersible pumps and initiation of micropurging without sample filtering resulted in a change in analytical method for metals. Pump equipped wells are sampled and analyzed for total metals because no filter is used during sample collection. Analyses of this type correspond to line item code SS05B001 and analytical method CLP-SOW-Total. Bailed well samples are analyzed for dissolved metals using line item code SS05B007 and analytical method CLP-SOW-Dissolved.

2.2 Discussion of Analyte Groups

2.2.1 Metals

Precision

There were 184 real/duplicate pair samples within the 1495 real sample records in the data set for metals in 1998 (1 in 8.125). Of the 184 real/duplicate pairs there were 114 instances of detections in which a RPD could be calculated (Table 2-1). One hundred and five of the calculated RPDs were within the QC criterion of 30% (Table 2-2). With 92.1% of the RPDs meeting the QC criterion, precision for dissolved metal analysis is within the acceptable goal of 85%.

The recommended frequency for duplicate samples is 1 in 20 on a per-well basis. In 1998, 14 of 202 wells sampled were analyzed for metals as real/duplicate pairs, a ratio of 1 in 14.2. Thus duplicate sample frequency was within the requirements on both a per-well and per-analysis basis.

Accuracy

All metal analyses were performed using contract-required methods during 1998. Contract-required methods stipulate the CLP-SOW method for analysis of dissolved metals. As shown on Table 2-4, analyses were run using this method for all samples. Additional analyses were run using CLP-SOW for total metals. The total metals analyses were run as necessary in support of various groundwater evaluations, and to analyze samples collected with dedicated pumps using the low-flow (micropurging) techniques described in Section 2.1. Based on the Table 2-4 summary, methods used during 1998 for analysis of metals meet or exceed the requirements of RF/RMRS-98-200, *Evaluation of Data for Usability in Final Reports, August 1998*.

Table 2-4 presents a summary of the comparison of required to actual detection limits for analyses of samples collected in 1998. Reported detection limits (RDLs) for nineteen metals were at or below CRDLs for 100 percent of the analyses performed. Eight analytes had RDLs for which some percentage

of the analyses were above CRDLs. The analytes were, antimony with acceptable RDLs in 54% of the analyses, arsenic (44%), cadmium (48%), lead (66%), mercury (93%), selenium (45%), silver (55%), and thallium (59%). Discussion and data accuracy evaluations for specific samples and analyses are presented in the quarterly reports.

Representativeness

There were 434 rinsate records versus 4449 real sample records for metals in 1998 (1 in 10.25). Most metals rinsate results were either "U" (non-detection) or "B" (detection was less than the CRDL but greater than the IDL) qualified indicating that in general no metals contamination was introduced during sampling and/or shipping activities. As shown on Table 2-5, metals were detected in 11 rinsate analyses. All but two analyses (thallium at Wells 02291 and 70193) yielded results below Tier II limits.

Completeness

The Integrated Monitoring Plan (DOE, 1998) requires that samples be analyzed for metals in 98 wells. Sampling for metals was attempted in all the required wells during 1998 (Table 2-1). Eleven wells were dry or went dry during sampling; resulting in 51 metals samples that could not be collected. Of the 202 metals sample events required by the IMP, 151 were successfully completed during 1998, a success rate of 74.8% (Table 2-6). The goal, which assumes adequate groundwater production from the monitoring wells, is at least 90% successfully sampled.

Validation of metals results was performed on 14.2% (640 of 4,506 analyses), which is below the 25% criterion defined in the IMP. The verification rate of 69.9% (3,151 of 4,506 analyses) was also below the verification criterion of 75% (Table 2-7). A total of 715 metals analyses were neither validated nor verified. Of the analyses that were validated or verified, 87 were rejected (R-validated, or R1-verified), and 3,704 analyses were judged to be acceptable and usable. Because of the relatively low number of rejected analyses, the 715 records not validated or verified are considered adequate for calculating the percentage of usable metals data. Consequently, the metals results were found to be acceptable for 98.1% (4,419 of 4,506) of the analyses (Table 2-7). The assumption is made that the 715 records can be considered usable since the percentage of rejected data of 2.2% (87 of 3,791 analyses) is small.

Comparability

No changes were made to analytical procedures during 1998. Thus analyses from 1998 are comparable to previous analyses.

2.2.2 Radionuclides

Precision

The data set for dissolved radionuclides contains 396 duplicate records versus 677 real records (1 in 1.71). A DER could be calculated for 88 of the 396 duplicate/real pairs (Table 2-2). All but one of the DER values (U-238 in Well 10294 at 2.69pCi/L) is below the 1.96 precision limit. As shown on Table 2-3, the precision metric was met in 98.9% of radionuclide duplicate/real samples.

Accuracy

All radionuclide analyses were performed using the proper contract required methods during 1998 (Table 2-4). With respect to analytical methods, the 1998 results are accurate.

Required detection limits for the 677 radionuclide analyses performed during 1998 were met in all cases (Table 2-4). As such, the accuracy of radionuclide analyses is good.

Representativeness

There were 84 rinsate records from radionuclide samples collected at 10 locations in 1998 (Table 2-5). Eighteen rinsate analyses yielded detectable values. All, however, were below Tier II Action Levels. Based on 79% of rinsate results being undetected, there is little indication of introduced contamination during sampling activities being a concern for 1998 radionuclide data.

Completeness

As shown on Table 2-6, 126 plutonium/ameridium, 204 uranium isotope, 83 tritium, and 46 strontium_{89/90} samples were to have been collected for analyses. All the required samples were collected or attempted. The success rate varied due to dry wells or wells that went dry during sampling. The percentages of successful sample collection were 65.1% for Pu/Am, 71.1% for U-isotopes, 65.1% for tritium, and 37% for strontium_{89/90}. The goal is 90%, groundwater conditions permitting.

Of 919 radionuclide analyses, 14.8% (136) were validated and 32.3% (297) were verified (Table 2-7). Both percentages are below the 25% validation and 75% verification criteria. Only one analysis (0.02%) of the 433 that were validated or verified was rejected. Data validation or verification was provided for 47.1% of the radionuclide analyses. As shown on Table 2-7, 99.99% (918 of 919) of radionuclide analyses are usable. With the caveat that not all validation and verification data were provided, the radionuclide analyses are thought to be complete.

Comparability

No changes were made to analytical procedures during 1998. Thus the radionuclide analyses presented here are assumed to be comparable to previous analyses.

2.2.3 Volatile Organic Compounds

Precision

There were 1,540 duplicate records versus 11,964 real records for VOCs in 1998, representing a ratio of 1 in 7.7 analyses. RPDs were calculated for the 102 duplicate/real pairs that had detections (Table 2-2). Eighty-five RPD values were less than the QC criterion of 30%, which equates to 83.3% meeting the QC criterion during 1998 (Table 2-3). As can be seen on Table 2-2, the majority of VOC RPD values above 30% are for samples with concentration at or near CRDLs, where analytical precision is inherently low. Given that consideration, the analyses of VOCs for 1998 are adequately precise.

Accuracy

All VOC analyses performed in 1998 employed contract-required methods (Table 2-4). With respect to analytical methods, the results are accurate.

As shown on Table 2-4, the majority of the 60 VOCs analyzed in 1998 met CRDLs. The range was between 96% and 100%, with an average of 98.7%.

The higher than required CRDLs for some VOCs result from several wells that are known to contain significant concentrations of VOCs. The laboratories run dilution analyses for samples from those wells. To protect instrumentation, the laboratories do not run 1x dilutions on the samples from wells having significant VOC contamination. CRDLs were not met for any of the VOC analytes from samples collected at those wells. Further discussion and additional data are provided in the quarterly reports (RMRS 1998a, 1998b, 1999a, and 1999b).

Representativeness

There were 1,099 rinsate records from 13 wells for VOCs in 1998. Of those records, 14 rinsate analyses contained VOCs at detectable concentrations (Table 2-5). Considering all rinsate analyses, 98.7% yielded non-detectable concentrations. As such, the VOC samples are judged to be representative.

Completeness

During 1998, the required 232 VOCs samples were collected or attempted (Table 2-6). Of those, 200 samples were collected, yielding a success rate of 86.2%. Because dry well conditions precluded collection of 32 samples, the goal of 90.0% was not reached for VOCs in 1998.

There were 14,659 VOC analyses performed in 1998. Of those, 5.0% of the analyses (726) were validated, and 59.9% (8,778) were verified (Table 2-7). Both percentages are below the 25% validation and 75% verification criteria. Of the 9,505 analyses for which validation or verification was performed, 4.0% (378) were rejected and are considered unusable data. Overall, 97.4% of VOC analyses are usable, assuming that the 3,778 analyses that were not validated or verified are usable.

Comparability

As stated above, no changes were made to analytical procedures during 1998. Thus the VOC analyses presented here are assumed to be comparable to previous analyses.

2.2.4 Water Quality Parameters

Precision

There were 50 duplicate sample records versus 427 real sample records for collected water quality parameters during 1998 (1 in 8.5). Forty-eight of the real/duplicate pairs could be used to calculate RPD values (Table 2-2). As shown on Table 2-3, 47 of the values (97.9%) were within the QC criterion of 30%. The one RPD that was greater than the criterion was calculated for the real/duplicate pair for nitrate/nitrite at Well 11891. Review of the analytical data indicates that the sample had a concentration that was two orders of magnitude higher than historical concentrations at that well. Samples collected in quarters immediately before and after had concentrations that were comparable to historical concentrations. As such, the elevated concentration appears to be a single anomalous value. Overall, the data indicates good precision for water quality parameter analyses.

Accuracy

All water quality parameter analyses were performed using the proper contract required analytical methods in 1998 (Table 2-4). With respect to methods, the results for the first quarter are accurate.

Analytical data indicate that the contract-required detection limits were met for all analyses of fluoride and total dissolved solids (TDS)(Table 2-4). The CRDL for nitrate/nitrite and sulfate (as SO₄) were met in 63% of the analyses.

Representativeness

There were 37 equipment rinsate analyses for water quality parameters in 1998. Thirty-one of the analyses were non-detects. As shown on Table 2-5, two nitrate/nitrite rinsate analyses and four TDS analyses had detectable concentrations. Neither of the nitrate/nitrite concentrations were above Tier II

Action Levels. The water quality parameter analyte group yielded non-detectable results in 83.4% of the rinsate analyses. No significant introduced contamination is indicated.

Completeness

As shown on Table 2-6, 186 nitrate/nitrite, 211 TDS, 125 sulfate, and 93 fluoride samples were to have been collected for analysis. All of the required samples were collected or attempted to be collected. The success rate varied because of dry wells or wells that went dry during sampling. The percentages of successful sample collection were 79.6% for nitrate/nitrite, 70.1% for TDS, 56.8% sulfate, and 53.8% fluoride. The goal is 90%, groundwater conditions permitting.

None of the 511 water quality parameter analyses performed in 1998, were validated. Verification was done on 74.4% (380) analyses (Table 2-7). As such, data validation or verification was provided for 74.4% of the water quality parameter results. As shown on Table 2-7, all of the analyses were verified as usable. Given that there were no rejected data, and that the 131 unvalidated and unverified analyses are acceptable, 100% of the 1998 water quality parameter data are usable.

Comparability

As stated above no changes were made to analytical procedures during 1998. Thus the water quality parameter analyses presented here are assumed to be comparable to previous analyses.

2.3 Data Summary for RFCA-Designated Wells Sampled in 1998

2.3.1 Data Screening

RFCA groundwater analytical data for 1998 were utilized for assessing compliance with RFCA well classifications as set forth in the data quality objectives section of the IMP. As most well categories rely on Tier I or Tier II action level criteria to trigger further action, the Tier II action level criteria have been adopted for reducing the data set to a manageable size for presentation and discussion. Non-Tier I and Tier II action level based well categories, including D&D and RCRA monitoring well networks, are evaluated separately in Section 2.3.3 using an upgradient to downgradient groundwater quality comparison approach. Although performance monitoring wells do not employ Tier I or Tier II action levels for determining a course of action, these criteria were used to select contaminants for assessing trends consistent with the DQO requirements for this well category.

Table 2-8 presents a summary of results for contaminants with concentrations greater than Tier II action levels. These values have been previously reported in the 1998 RFCA Quarterly Groundwater Monitoring Reports (RMRS, 1998a, 1998b, 1999a, 1999b). In total, seventy two RFCA-designated monitoring wells (excluding RCRA and D&D wells) had concentrations of one or more analytes above Tier II action levels, while 14 RFCA-designated wells yielded no results above Tier II action levels. Plates 4 through 6 are box plots that display the results of selected analytes (i.e., radionuclides, VOCs, and water quality parameters) at monitoring wells that had at least one analyte above Tier II action levels. The wells with contaminant concentrations below Tier II action levels (excluding RCRA and D&D wells) are listed in Table 2-9. A listing of all analytical results from RFCA-designated wells are provided in the quarterly reports.

Historical trends of contaminants of concern for selected Boundary, Drainage, Performance Monitoring, Plume Definition, and Plume Extent wells are shown in Figures 2-1 through 2-59. The contaminant trend plots for Boundary, Drainage, Plume Definition, and Plume Extent wells were chosen from organic compounds that exceeded Tier I and II action levels, and other analytes that exceeded both Tier I and II action levels and background M2SD concentrations. Background values for inorganics and radionuclides were adopted from the 1993 Background Geochemical Characterization Report (DOE, 1993b) and the draft Background Comparison for Radionuclides in Groundwater (DOE, 1997a). Trend plots of contaminants found in Performance monitoring wells were generally chosen for the contaminants with the highest Tier II ratios. The following sections present a compilation of the data and information first provided in the quarterly reports.

The decision rules that are described in general terms in Section 1.3 define the conditions under which values above action levels become "Reportable".

2.3.2 Values Above Tier I and Tier II Action Level Criteria

2.3.2.1 Boundary Wells

Six RFCA designated Boundary wells, 0386, 06491, 10294, 10394, 41591, and 41691, were sampled in 1998. Only sulfate, detected in well 10294, was above the Tier II action level and the background M2SD benchmark. Although the values are reportable, concentrations have remained below historic M2SD, and trends have not been upward (Table 2-8 and Figure 2-1).

Table 2-8 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells

Well Class	Location	Sample Date	Analyte	Result	Units	Q	Tier II	Tier II Ratio	Back-ground M2SD	Back-ground Ratio	Above Back-ground?	Historic M2SD	Historic Ratio	Above Historic?	Reportable?	Well Class
Boundary		0386	2/26/98 Uranium-233/234	10.30	pCi/L		1.07	9.63	60.7	0.17					No	Boundary
		0386	2/26/98 Uranium-238	8.35	pCi/L		0.768	10.87	41.8	0.20					No	Boundary
		0386	8/25/98 Uranium-233/234	10.80	pCi/L		1.07	10.09	60.7	0.18					No	Boundary
		0386	8/25/98 Uranium-238	8.23	pCi/L		0.768	10.72	41.8	0.20					No	Boundary
		06491	2/19/98 Uranium-233/234	27.80	pCi/L		1.07	25.98	60.7	0.46					No	Boundary
		06491	2/19/98 Uranium-235	1.17	pCi/L		1.01	1.16	1.79	0.65					No	Boundary
		06491	2/19/98 Uranium-238	18.00	pCi/L		0.768	23.44	41.8	0.43					No	Boundary
		06491	7/20/98 Uranium-233/234	27.56	pCi/L		1.07	25.75	60.7	0.45					No	Boundary
		06491	7/20/98 Uranium-238	17.22	pCi/L		0.768	22.43	41.8	0.41					No	Boundary
		10294	2/10/98 Sulfate	830.00	mg/L		500	1.66	435.6	1.91	Yes	700	1.19	Yes	Yes	Boundary
		10294	2/10/98 Uranium-233/234	27.90	pCi/L		1.07	26.07	60.7	0.46					No	Boundary
		10294	2/10/98 Uranium-238	24.00	pCi/L		0.768	31.25	41.8	0.57					No	Boundary
		10294	7/29/98 Uranium-233/234	21.61	pCi/L		1.07	20.20	60.7	0.36					No	Boundary
		10294	7/29/98 Uranium-235	1.18	pCi/L		1.01	1.17	1.79	0.66					No	Boundary
		10294	7/29/98 Uranium-238	16.59	pCi/L		0.768	21.60	41.8	0.40					No	Boundary
		10394	7/27/98 Uranium-233/234	3.42	pCi/L		1.07	3.19	60.7	0.06					No	Boundary
		10394	7/27/98 Uranium-238	2.35	pCi/L		0.768	3.05	41.8	0.06					No	Boundary
		41591	2/26/98 Uranium-233/234	10.90	pCi/L		1.07	10.19	60.7	0.18					No	Boundary
		41591	2/26/98 Uranium-238	8.20	pCi/L		0.768	10.68	41.8	0.20					No	Boundary
		41591	8/27/98 Uranium-233/234	9.61	pCi/L		1.07	8.98	60.7	0.16					No	Boundary
		41591	8/27/98 Uranium-238	9.17	pCi/L		0.768	11.94	41.8	0.22					No	Boundary
		41691	3/11/98 Uranium-233/234	1.10	pCi/L		1.07	1.03	60.7	0.02					No	Boundary
		41691	3/11/98 Uranium-238	0.89	pCi/L	J	0.768	1.15	41.8	0.02					No	Boundary
		41091	7/30/98 Uranium-233/234	1.56	pCi/L		1.07	1.46	60.7	0.03					No	Boundary
		41691	7/30/98 Uranium-238	1.89	pCi/L		0.768	2.47	41.8	0.05					No	Boundary
		00997	3/3/98 Uranium-233/234	13.30	pCi/L		1.07	12.43	60.7	0.22					No	Drainage
		00997	3/3/98 Uranium-238	8.34	pCi/L		0.768	10.86	41.8	0.20					No	Drainage
		00997	7/27/98 Uranium-233/234	5.76	pCi/L		1.07	5.39	60.7	0.09					No	Drainage
		00997	7/27/98 Uranium-238	4.30	pCi/L		0.768	5.59	41.8	0.10					No	Drainage
Drainage		38591	2/24/98 Uranium-233/234	18.90	pCi/L		1.07	17.66	60.7	0.31					No	Drainage
		38591	2/24/98 Uranium-238	12.10	pCi/L		0.768	15.76	41.8	0.29					No	Drainage
		5587	5/20/98 Methylene Chloride	6.00	ug/L	B	5	1.20				8.1	0.74		No	Drainage
		6486	2/24/98 Nickel	151.00	ug/L		100	1.51	21.37	7.07	Yes	62.02	2.43	Yes	Yes	Drainage
		6486	2/25/98 Uranium-233/234	5.05	pCi/L		1.07	4.72	60.7	0.08					No	Drainage
		6486	2/25/98 Uranium-238	3.16	pCi/L		0.768	4.11	41.8	0.08					No	Drainage
		6486	7/14/98 Uranium-233/234	7.61	pCi/L		1.07	7.11	60.7	0.13					No	Drainage
		6486	7/14/98 Uranium-238	4.19	pCi/L		0.768	5.45	41.8	0.10					No	Drainage
		6586	6/16/98 Nickel	871.00	ug/L		100	8.71	21.37	40.76	Yes	78.78	11.06	Yes	Yes	Drainage
		6586	7/28/98 Nickel	603.00	ug/L		100	6.03	21.37	28.22	Yes	78.78	7.65	Yes	Yes	Drainage
		6586	7/28/98 Uranium-233/234	2.05	pCi/L		1.07	1.92	60.7	0.03					No	Drainage
		6586	7/28/98 Uranium-238	1.91	pCi/L		0.768	2.49	41.8	0.05					No	Drainage
		6586	8/24/98 Nickel	570.00	ug/L		100	5.70	21.37	26.67	Yes	78.78	7.24	Yes	Yes	Drainage
Performance Monitoring		00797	2/23/98 Sulfate	507.00	mg/L		500	1.01	435.6	1.16	Yes				No	Perf Monitoring
		00797	2/23/98 Uranium-233/234	8.67	pCi/L		1.07	8.10	60.7	0.14					No	Perf Monitoring
		00797	2/23/98 Uranium-238	7.55	pCi/L		0.768	9.83	41.8	0.18					No	Perf Monitoring
		00797	7/29/98 Uranium-233/234	9.53	pCi/L		1.07	8.90	60.7	0.16					No	Perf Monitoring
		00797	7/29/98 Uranium-238	8.31	pCi/L		0.768	10.82	41.8	0.20					No	Perf Monitoring
		00897	3/9/98 Tetrachloroethene	14000.00	ug/L		5	2800.00							No	Perf Monitoring
		00897	3/9/98 Trichloroethene	2000.00	ug/L		5	400.00							No	Perf Monitoring
		00897	3/9/98 Uranium-233/234	3.96	pCi/L		1.07	3.70	60.7	0.07					No	Perf Monitoring
		00897	3/9/98 Uranium-238	2.61	pCi/L		0.768	3.40	41.8	0.06					No	Perf Monitoring
		00897	6/16/98 Methylene Chloride	12000.00	ug/L		5	2400.00							No	Perf Monitoring
		00897	6/16/98 Tetrachloroethene	20000.00	ug/L		5	4000.00							No	Perf Monitoring
		00897	6/16/98 Trichloroethene	2000.00	ug/L	J	5	400.00							No	Perf Monitoring
		00897	6/16/98 Uranium-233/234	4.92	pCi/L		1.07	4.59	60.7	0.08					No	Perf Monitoring
		00897	6/16/98 Uranium-238	2.84	pCi/L		0.768	3.69	41.8	0.07					No	Perf Monitoring
		00897	11/19/98 Tetrachloroethene	7400.00	ug/L	D	5	1480.00							No	Perf Monitoring
		00897	11/19/98 Trichloroethene	990.00	ug/L	D	5	198.00							No	Perf Monitoring
		00897	11/19/98 Uranium-233/234	3.57	pCi/L	B	1.07	3.34	60.7	0.06					No	Perf Monitoring
		00897	11/19/98 Uranium-238	2.88	pCi/L	B	0.768	3.75	41.8	0.07					No	Perf Monitoring
		02291	3/10/98 Tetrachloroethene	4200.00	ug/L		5	840.00				4201.94	1.00	Yes	No	Perf Monitoring
		02291	3/10/98 Trichloroethene	660.00	ug/L		5	132.00				453.73	1.45	Yes	No	Perf Monitoring
		02291	3/10/98 Uranium-233/234	2.61	pCi/L		1.07	2.44	60.7	0.04					No	Perf Monitoring
		02291	3/10/98 Uranium-238	1.67	pCi/L		0.768	2.17	41.8	0.04					No	Perf Monitoring
		02291	5/22/98 Uranium-233/234	2.19	pCi/L		1.07	2.05	60.7	0.04					No	Perf Monitoring
		02291	5/22/98 Uranium-238	1.41	pCi/L		0.768	1.84	41.8	0.03					No	Perf Monitoring
		02291	12/4/98 Methylene Chloride	2100.00	ug/L	BD	5	420.00							No	Perf Monitoring
		02291	12/4/98 Tetrachloroethene	5700.00	ug/L	D	5	1140.00				4201.94	1.36	Yes	No	Perf Monitoring
		02291	12/4/98 Trichloroethene	620.00	ug/L	D	5	124.00				453.73	1.37	Yes	No	Perf Monitoring
		02291	12/4/98 Uranium-233/234	3.03	pCi/L		1.07	2.83	60.7	0.05					No	Perf Monitoring
		02291	12/4/98 Uranium-238	1.97	pCi/L	B	0.768	2.57	41.8	0.05					No	Perf Monitoring
		05691	3/9/98 Carbon Tetrachloride	98.00	ug/L		5	19.60				561.21	0.17		No	Perf Monitoring
		05691	3/9/98 Tetrachloroethene	23.00	ug/L		5	4.60				149.64	0.15		No	Perf Monitoring

Table 2-8 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells

Well Class	Location	Sample Date	Analyte	Result	Units	Q	Tier II	Tier II Ratio	Back-ground M2SD	Back-ground Ratio	Above Back-ground?	Historic M2SD	Historic Ratio	Above Historic?	Reportable?	Well Class
		05691	3/9/98 Trichloroethene	11.00	ug/L		5	2.20				95.59	0.12		No	Perf Monitoring
		05691	3/9/98 Uranium-233/234	3.82	pCi/L		1.07	3.57	60.7	0.06					No	Perf Monitoring
		05691	3/9/98 Uranium-238	2.39	pCi/L		0.768	3.11	41.8	0.06					No	Perf Monitoring
		05691	7/13/98 Carbon Tetrachloride	100.00	ug/L		5	20.00				561.21	0.18		No	Perf Monitoring
		05691	7/13/98 Methylene Chloride	5.00	ug/L	J	5	1.00							No	Perf Monitoring
		05691	7/13/98 Tetrachloroethene	22.00	ug/L		5	4.40				149.64	0.15		No	Perf Monitoring
		05691	7/13/98 Uranium-233/234	2.36	pCi/L		1.07	2.21	60.7	0.04					No	Perf Monitoring
		05691	7/13/98 Uranium-238	1.72	pCi/L		0.768	2.23	41.8	0.04					No	Perf Monitoring
		05691	9/29/98 Carbon Tetrachloride	130.00	ug/L	D	5	26.00				561.21	0.23		No	Perf Monitoring
		05691	9/29/98 Tetrachloroethene	29.00	ug/L	D	5	5.80				149.64	0.19		No	Perf Monitoring
		05691	9/29/98 Trichloroethene	16.00	ug/L	D	5	3.20				95.59	0.17		No	Perf Monitoring
		07391	3/17/98 Trichloroethene	27000.00	ug/L		5	5400.00				158350	0.17		No	Perf Monitoring
		07391	3/17/98 Uranium-233/234	20.00	pCi/L		1.07	18.69	60.7	0.33					No	Perf Monitoring
		07391	3/17/98 Uranium-238	49.20	pCi/L		0.768	64.06	41.8	1.18	Yes	43.4	1.13	Yes	Yes	Perf Monitoring
		07391	8/24/98 1,1,1-Trichloroethane	1700.00	ug/L		200	8.50				2724.6	0.62		No	Perf Monitoring
		07391	8/24/98 Chloroform	3000.00	ug/L	B	100	30.00				4439.22	0.68		No	Perf Monitoring
		07391	8/24/98 Chloroform	18000.00	ug/L	DB	100	180.00				4439.22	4.05	Yes	No	Perf Monitoring
		07391	8/24/98 Methylene Chloride	1200.00	ug/L	B	5	240.00							No	Perf Monitoring
		07391	8/24/98 Methylene Chloride	35000.00	ug/L	DB	5	7000.00							No	Perf Monitoring
		07391	8/24/98 Nitrate/Nitrite	17.00	mg/L		10	1.70	4.664	3.64	Yes	20	0.85		No	Perf Monitoring
		07391	8/24/98 Tetrachloroethene	3200.00	ug/L		5	640.00				3030.17	1.06	Yes	No	Perf Monitoring
		07391	8/24/98 Trichloroethene	160000.00	ug/L	D	5	32000.00				158350	1.01	Yes	No	Perf Monitoring
		07391	8/25/98 Uranium-233/234	25.60	pCi/L		1.07	23.93	60.7	0.42					No	Perf Monitoring
		07391	8/25/98 Uranium-235	1.29	pCi/L		1.01	1.28	1.79	0.72					No	Perf Monitoring
		07391	8/25/98 Uranium-238	58.70	pCi/L		0.768	76.43	41.8	1.40	Yes	43.4	1.35	Yes	Yes	Perf Monitoring
		10592	6/15/98 Selenium	137.00	ug/L		50	2.74	43.72	3.13	Yes	343.94	0.40		No	Perf Monitoring
		10592	6/15/98 Uranium-233/234	10.90	pCi/L		1.07	10.19	60.7	0.18					No	Perf Monitoring
		10592	6/15/98 Uranium-238	7.62	pCi/L		0.768	9.92	41.8	0.18					No	Perf Monitoring
		10592	11/16/98 Methylene Chloride	9.00	ug/L		5	1.80							No	Perf Monitoring
		10592	11/16/98 Selenium	126.00	ug/L		50	2.52	43.72	2.88	Yes	343.94	0.37		No	Perf Monitoring
		10592	11/16/98 Uranium-233/234	11.90	pCi/L	B	1.07	11.12	60.7	0.20					No	Perf Monitoring
		10592	11/16/98 Uranium-238	8.36	pCi/L	B	0.768	10.88	41.8	0.20					No	Perf Monitoring
		10692	2/27/98 Uranium-233/234	16.40	pCi/L		1.07	15.33	60.7	0.27					No	Perf Monitoring
		10692	2/27/98 Uranium-238	12.00	pCi/L		0.768	15.63	41.8	0.29					No	Perf Monitoring
		10692	7/15/98 Uranium-233/234	16.67	pCi/L		1.07	15.58	60.7	0.27					No	Perf Monitoring
		10692	7/15/98 Uranium-238	10.02	pCi/L		0.768	13.04	41.8	0.24					No	Perf Monitoring
		10792	5/20/98 Selenium	116.00	ug/L		50	2.32	43.72	2.65	Yes				No	Perf Monitoring
		10792	5/20/98 Uranium-233/234	4.49	pCi/L		1.07	4.20	60.7	0.07					No	Perf Monitoring
		10792	5/20/98 Uranium-238	2.87	pCi/L		0.768	3.74	41.8	0.07					No	Perf Monitoring
		10792	11/17/98 Selenium	59.40	ug/L		50	1.19	43.72	1.36	Yes				No	Perf Monitoring
		10792	11/17/98 Uranium-233/234	4.13	pCi/L	B	1.07	3.86	60.7	0.07					No	Perf Monitoring
		10792	11/17/98 Uranium-238	4.17	pCi/L	B	0.768	5.43	41.8	0.10					No	Perf Monitoring
		10792	12/9/98 Selenium	52.70	ug/L		50	1.05	43.72	1.21	Yes				No	Perf Monitoring
		10992	8/18/98 Nitrate/Nitrite	24.00	mg/L		10	2.40	4.664	5.15	Yes	37.16	0.65		No	Perf Monitoring
		10992	8/18/98 Selenium	371.00	ug/L	N	50	7.42	43.72	8.49	Yes				No	Perf Monitoring
		10992	8/19/98 Uranium-233/234	7.22	pCi/L		1.07	6.75	60.7	0.12					No	Perf Monitoring
		10992	8/19/98 Uranium-238	5.82	pCi/L		0.768	7.58	41.8	0.14					No	Perf Monitoring
		11092	11/17/98 Methylene Chloride	8.00	ug/L		5	1.60							No	Perf Monitoring
		11891	3/5/98 Carbon Tetrachloride	460.00	ug/L	D	5	92.00				737.11	0.62		No	Perf Monitoring
		11891	3/5/98 Tetrachloroethene	260.00	ug/L	D	5	52.00				319.91	0.81		No	Perf Monitoring
		11891	3/5/98 Trichloroethene	60.00	ug/L	D	5	12.00				407.56	0.15		No	Perf Monitoring
		11891	3/5/98 Uranium-233/234	2.32	pCi/L		1.07	2.17	60.7	0.04					No	Perf Monitoring
		11891	3/5/98 Uranium-238	1.58	pCi/L		0.768	2.06	41.8	0.04					No	Perf Monitoring
		11891	6/11/98 Carbon Tetrachloride	210.00	ug/L		5	42.00				737.11	0.28		No	Perf Monitoring
		11891	6/11/98 Tetrachloroethene	140.00	ug/L		5	28.00				319.91	0.44		No	Perf Monitoring
		11891	6/11/98 Trichloroethene	26.00	ug/L		5	5.20				407.56	0.06		No	Perf Monitoring
		11891	6/11/98 Uranium-233/234	2.50	pCi/L		1.07	2.33	60.7	0.04					No	Perf Monitoring
		11891	6/11/98 Uranium-238	1.41	pCi/L		0.768	1.84	41.8	0.03					No	Perf Monitoring
		11891	11/19/98 Carbon Tetrachloride	430.00	ug/L	D	5	86.00				737.11	0.58		No	Perf Monitoring
		11891	11/19/98 Tetrachloroethene	500.00	ug/L	D	5	100.00				319.91	1.56	Yes	No	Perf Monitoring
		11891	11/19/98 Trichloroethene	80.00	ug/L	D	5	16.00				407.56	0.20		No	Perf Monitoring
		11891	11/19/98 Uranium-233/234	2.59	pCi/L	B	1.07	2.42	60.7	0.04					No	Perf Monitoring
		11891	11/19/98 Uranium-238	1.71	pCi/L	B	0.768	2.23	41.8	0.04					No	Perf Monitoring
		12191	3/5/98 Carbon Tetrachloride	240.00	ug/L		5	48.00				435.97	0.55		No	Perf Monitoring
		12191	3/5/98 Tetrachloroethene	290.00	ug/L		5	58.00				486.46	0.60		No	Perf Monitoring
		12191	3/5/98 Trichloroethene	53.00	ug/L		5	10.60				67.86	0.78		No	Perf Monitoring
		12191	3/5/98 Uranium-233/234	2.36	pCi/L		1.07	2.21	60.7	0.04					No	Perf Monitoring
		12191	3/5/98 Uranium-238	1.49	pCi/L		0.768	1.94	41.8	0.04					No	Perf Monitoring
		12191	4/28/98 1,1-Dichloroethene	7.00	ug/L		7	1.00							No	Perf Monitoring
		12191	4/28/98 Carbon Tetrachloride	220.00	ug/L		5	44.00				435.97	0.50		No	Perf Monitoring
		12191	4/28/98 Tetrachloroethene	210.00	ug/L		5	42.00				486.46	0.43		No	Perf Monitoring
		12191	4/28/98 Trichloroethene	27.00	ug/L		5	5.40				67.86	0.40		No	Perf Monitoring
		12191	4/28/98 Uranium-233/234	1.85	pCi/L		1.07	1.73	60.7	0.03					No	Perf Monitoring
		12191	4/28/98 Uranium-238	1.30	pCi/L		0.768	1.69	41.8	0.03					No	Perf Monitoring
		12191	12/15/98 Carbon Tetrachloride	140.00	ug/L		5	28.00				435.97	0.32		No	Perf Monitoring
		12191	12/15/98 Tetrachloroethene	170.00	ug/L		5	34.00				486.46	0.35		No	Perf Monitoring
		12191	12/15/98 Trichloroethene	25.00	ug/L		5	5.00				67.86	0.37		No	Perf Monitoring

Performance Monitoring

Table 2-8 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells

Well Class	Location	Sample Date	Analyte	Result	Units	Q	Tier II	Tier II Ratio	Back-ground M2SD	Back-ground Ratio	Above Back-ground?	Historic M2SD	Historic Ratio	Above Historic?	Reportable?	Well Class
Performance Monitoring		12191	12/15/98	Uranium-233/234	2.20	pCi/L		1.07	2.06	60.7	0.04				No	Perf Monitoring
		12191	12/15/98	Uranium-238	1.13	pCi/L		0.768	1.47	41.8	0.03				No	Perf Monitoring
		12691	2/26/98	Carbon Tetrachloride	480.00	ug/L		5	96.00			2968.95	0.16		No	Perf Monitoring
		12691	2/26/98	cis-1,2-Dichloroethene	70.00	ug/L		70	1.00			85.9	1.06	Yes	No	Perf Monitoring
		12691	2/26/98	Tetrachloroethene	140.00	ug/L		5	28.00			646.52	0.22		No	Perf Monitoring
		12691	2/26/98	Trichloroethene	68.00	ug/L		5	13.60			362.45	0.19		No	Perf Monitoring
		12691	2/26/98	Uranium-233/234	2.58	pCi/L		1.07	2.41	60.7	0.04				No	Perf Monitoring
		12691	2/26/98	Uranium-238	2.11	pCi/L		0.768	2.75	41.8	0.05				No	Perf Monitoring
		12691	8/5/98	Carbon Tetrachloride	370.00	ug/L	D	5	74.00			2968.95	0.12		No	Perf Monitoring
		12691	8/5/98	Methylene Chloride	21.00	ug/L	D	5	4.20						No	Perf Monitoring
		12691	8/5/98	Tetrachloroethene	68.00	ug/L	D	5	13.60			646.52	0.11		No	Perf Monitoring
		12691	8/5/98	Trichloroethene	49.00	ug/L	D	5	9.80			362.45	0.14		No	Perf Monitoring
		12691	8/5/98	Uranium-233/234	2.44	pCi/L		1.07	2.28	60.7	0.04				No	Perf Monitoring
		12691	8/5/98	Uranium-238	1.66	pCi/L		0.768	2.16	41.8	0.04				No	Perf Monitoring
		3687	3/10/98	1,1-Dichloroethene	16.00	ug/L		7	2.29			187	0.09		No	Perf Monitoring
		3687	3/10/98	Carbon Tetrachloride	430.00	ug/L		5	86.00			1255.4	0.34		No	Perf Monitoring
		3687	3/10/98	Tetrachloroethene	290.00	ug/L		5	58.00			814.46	0.36		No	Perf Monitoring
		3687	3/10/98	Trichloroethene	6000.00	ug/L		5	1200.00			993.25	6.04	Yes	No	Perf Monitoring
		3687	3/10/98	Uranium-233/234	1.68	pCi/L		1.07	1.57	60.7	0.03				No	Perf Monitoring
		3687	3/10/98	Uranium-238	0.81	pCi/L	J	0.768	1.06	41.8	0.02				No	Perf Monitoring
		3687	5/26/98	1,1-Dichloroethene	53.00	ug/L	E	7	7.57			187	0.28		No	Perf Monitoring
		3687	5/26/98	Carbon Tetrachloride	250.00	ug/L	E	5	50.00			1255.4	0.20		No	Perf Monitoring
		3687	5/26/98	Chloroform	510.00	ug/L	E	100	5.10						No	Perf Monitoring
		3687	5/26/98	Methylene Chloride	1600.00	ug/L	JOB	5	320.00						No	Perf Monitoring
		3687	5/26/98	Tetrachloroethene	460.00	ug/L	JD	5	92.00			814.46	0.56		No	Perf Monitoring
		3687	5/26/98	Trichloroethene	6300.00	ug/L	D	5	1260.00			993.25	6.34	Yes	No	Perf Monitoring
		3687	5/26/98	Uranium-233/234	1.37	pCi/L		1.07	1.28	60.7	0.02				No	Perf Monitoring
		3687	5/26/98	Uranium-238	0.81	pCi/L	J	0.768	1.06	41.8	0.02				No	Perf Monitoring
		3687	10/26/98	1,1-Dichloroethene	120.00	ug/L	E	7	17.14			187	0.64		No	Perf Monitoring
		3687	10/26/98	Carbon Tetrachloride	640.00	ug/L	E	5	128.00			1255.4	0.51		No	Perf Monitoring
		3687	10/26/98	Chloroform	4700.00	ug/L	D	100	47.00						No	Perf Monitoring
		3687	10/26/98	Methylene Chloride	11.00	ug/L		5	2.20						No	Perf Monitoring
		3687	10/26/98	Tetrachloroethene	780.00	ug/L	E	5	156.00			814.46	0.96		No	Perf Monitoring
		3687	10/26/98	Trichloroethene	53000.00	ug/L	D	5	10600.00			993.25	53.36	Yes	No	Perf Monitoring
		3687	10/26/98	Uranium-233/234	1.52	pCi/L	B	1.07	1.42	60.7	0.03				No	Perf Monitoring
		3687	10/26/98	Uranium-238	0.87	pCi/L	J	0.768	1.14	41.8	0.02				No	Perf Monitoring
		891COLGAL	6/10/98	Uranium-233/234	5.10	pCi/L		1.07	4.76	60.7	0.08				No	Perf Monitoring
		891COLGAL	6/10/98	Uranium-238	3.99	pCi/L		0.768	5.20	41.8	0.10				No	Perf Monitoring
		891COLGAL	8/20/98	Uranium-233/234	6.25	pCi/L		1.07	5.84	60.7	0.10				No	Perf Monitoring
		891COLGAL	8/20/98	Uranium-238	5.17	pCi/L		0.768	6.73	41.8	0.12				No	Perf Monitoring
		891COLGAL	11/4/98	Uranium-233/234	6.54	pCi/L		1.07	6.11	60.7	0.11				No	Perf Monitoring
		891COLGAL	11/4/98	Uranium-238	4.34	pCi/L		0.768	5.65	41.8	0.10				No	Perf Monitoring
		891COLWEL	6/10/98	Carbon Tetrachloride	21.00	ug/L		5	4.20						No	Perf Monitoring
		891COLWEL	6/10/98	Methylene Chloride	190.00	ug/L	DB	5	38.00						No	Perf Monitoring
		891COLWEL	6/10/98	Selenium	620.00	ug/L		50	12.40	43.72	14.18	Yes			No	Perf Monitoring
		891COLWEL	6/10/98	Tetrachloroethene	29.00	ug/L		5	5.80						No	Perf Monitoring
		891COLWEL	6/10/98	Trichloroethene	230.00	ug/L	D	5	46.00						No	Perf Monitoring
		891COLWEL	6/10/98	Uranium-233/234	10.89	pCi/L		1.07	10.17	60.7	0.18				No	Perf Monitoring
		891COLWEL	6/10/98	Uranium-238	7.97	pCi/L		0.768	10.38	41.8	0.19				No	Perf Monitoring
		891COLWEL	8/20/98	Carbon Tetrachloride	12.00	ug/L		5	2.40						No	Perf Monitoring
		891COLWEL	8/20/98	Methylene Chloride	15.00	ug/L	D	5	3.00						No	Perf Monitoring
		891COLWEL	8/20/98	Selenium	470.00	ug/L	N	50	9.40	43.72	10.75	Yes			No	Perf Monitoring
		891COLWEL	8/20/98	Tetrachloroethene	13.00	ug/L		5	2.60						No	Perf Monitoring
		891COLWEL	8/20/98	Trichloroethene	100.00	ug/L	D	5	20.00						No	Perf Monitoring
		891COLWEL	8/20/98	Uranium-233/234	11.70	pCi/L		1.07	10.93	60.7	0.19				No	Perf Monitoring
		891COLWEL	8/20/98	Uranium-238	8.59	pCi/L		0.768	11.18	41.8	0.21				No	Perf Monitoring
		891COLWEL	11/2/98	Carbon Tetrachloride	6.00	ug/L		5	1.20						No	Perf Monitoring
		891COLWEL	11/2/98	Methylene Chloride	380.00	ug/L	BD	5	76.00						No	Perf Monitoring
		891COLWEL	11/2/98	Selenium	480.00	ug/L	*	50	9.60	43.72	10.98	Yes			No	Perf Monitoring
		891COLWEL	11/2/98	Tetrachloroethene	40.00	ug/L	D	5	8.00						No	Perf Monitoring
		891COLWEL	11/2/98	Trichloroethene	280.00	ug/L	D	5	56.00						No	Perf Monitoring
		891COLWEL	11/2/98	Uranium-233/234	10.40	pCi/L		1.07	9.72	60.7	0.17				No	Perf Monitoring
		891COLWEL	11/2/98	Uranium-238	7.83	pCi/L		0.768	10.20	41.8	0.19				No	Perf Monitoring
		SW059	6/4/98	Carbon Tetrachloride	150.00	ug/L	D	5	30.00						No	Perf Monitoring
		SW059	6/4/98	Methylene Chloride	8.00	ug/L	BJD	5	1.60						No	Perf Monitoring
		SW059	6/4/98	Tetrachloroethene	48.00	ug/L	D	5	9.60						No	Perf Monitoring
		SW059	6/4/98	Trichloroethene	58.00	ug/L	D	5	11.60						No	Perf Monitoring
		SW059	6/4/98	Uranium-233/234	4.02	pCi/L		1.07	3.75	60.7	0.07				No	Perf Monitoring
		SW059	6/4/98	Uranium-238	3.01	pCi/L		0.768	3.93	41.8	0.07				No	Perf Monitoring
		SW13494	6/19/98	Tetrachloroethene	35.00	ug/L		5	7.00						No	Perf Monitoring
		SW13494	6/19/98	Uranium-233/234	4.08	pCi/L		1.07	3.82	60.7	0.07				No	Perf Monitoring
		SW13494	6/19/98	Uranium-238	2.71	pCi/L		0.768	3.53	41.8	0.06				No	Perf Monitoring
		SW13494	8/19/98	Tetrachloroethene	18.00	ug/L		5	3.60						No	Perf Monitoring
		SW13494	8/19/98	Uranium-233/234	4.71	pCi/L		1.07	4.40	60.7	0.08				No	Perf Monitoring
		SW13494	8/19/98	Uranium-238	3.88	pCi/L		0.768	5.05	41.8	0.09				No	Perf Monitoring
		SW13494	11/2/98	Methylene Chloride	5.00	ug/L	B	5	1.00						No	Perf Monitoring
		SW13494	11/2/98	Tetrachloroethene	40.00	ug/L		5	8.00						No	Perf Monitoring
		SW13494	11/2/98	Uranium-233/234	3.15	pCi/L		1.07	2.94	60.7	0.05				No	Perf Monitoring
		SW13494	11/2/98	Uranium-238	2.28	pCi/L		0.768	2.97	41.8	0.05				No	Perf Monitoring

Table 2-8 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells

Well Class	Location	Sample Date	Analyte	Result	Units	Q	Tier II	Tier II Ratio	Back-ground M2SD	Back-ground Ratio	Above Back-ground?	Historic M2SD	Historic Ratio	Above Historic?	Reportable?	Well Class
Plume Definition		00491	7/13/98 Carbon Tetrachloride	160.00	ug/L		5	32.00				545	0.29		No	Plume Definition
		00491	7/13/98 Tetrachloroethene	18.00	ug/L		5	3.60				54	0.33		No	Plume Definition
		00491	7/13/98 Trichloroethene	43.00	ug/L		5	8.60				153	0.28		No	Plume Definition
		00491	7/13/98 Uranium-233/234	10.12	pCi/L		1.07	9.48	60.7	0.17					No	Plume Definition
		00491	7/13/98 Uranium-238	5.14	pCi/L		0.768	6.70	41.8	0.12					No	Plume Definition
		00491	9/28/98 Carbon Tetrachloride	200.00	ug/L	D	5	40.00				545	0.37		No	Plume Definition
		00491	9/28/98 Methylene Chloride	6.00	ug/L	D	5	1.20							No	Plume Definition
		00491	9/28/98 Tetrachloroethene	37.00	ug/L	D	5	7.40				54	0.69		No	Plume Definition
		00491	9/28/98 Trichloroethene	82.00	ug/L	D	5	16.40				153	0.54		No	Plume Definition
		00597	3/3/98 1,1-Dichloroethene	9.00	ug/L		7	1.29							No	Plume Definition
		00597	3/3/98 Nitrate/Nitrite	10.10	mg/L		10	1.01	4.664	2.17	Yes				No	Plume Definition
		00597	3/3/98 Trichloroethene	6.00	ug/L		5	1.20							No	Plume Definition
		00597	7/28/98 1,1-Dichloroethene	13.00	ug/L		7	1.86							No	Plume Definition
		00597	7/28/98 Nitrate/Nitrite	10.00	mg/L		10	1.00	4.664	2.14	Yes				No	Plume Definition
		00597	7/28/98 Trichloroethene	6.00	ug/L		5	1.20							No	Plume Definition
		0487	3/4/98 Selenium	125.00	ug/L		50	2.50	43.72	2.86	Yes	699.76	0.18		No	Plume Definition
		0487	3/4/98 Trichloroethene	66.00	ug/L		5	13.20				5685.56	0.01		No	Plume Definition
		0487	3/4/98 Uranium-233/234	16.00	pCi/L		1.07	14.95	60.7	0.26					No	Plume Definition
		0487	3/4/98 Uranium-238	12.90	pCi/L		0.768	16.80	41.8	0.31					No	Plume Definition
		0487	7/29/98 Methylene Chloride	8.00	ug/L	DB	5	1.60							No	Plume Definition
		0487	7/29/98 Selenium	86.90	ug/L		50	1.74	43.72	1.99	Yes	699.76	0.12		No	Plume Definition
		0487	7/29/98 Trichloroethene	63.00	ug/L	D	5	12.60				5685.56	0.01		No	Plume Definition
		0487	7/29/98 Uranium-233/234	16.52	pCi/L		1.07	15.44	60.7	0.27					No	Plume Definition
		0487	7/29/98 Uranium-238	13.39	pCi/L		0.768	17.44	41.8	0.32					No	Plume Definition
		05391	2/18/98 Carbon Tetrachloride	13.00	ug/L		5	2.60				32.88	0.40		No	Plume Definition
		05391	2/18/98 Uranium-233/234	2.70	pCi/L		1.07	2.52	60.7	0.04					No	Plume Definition
		05391	2/18/98 Uranium-238	0.92	pCi/L		0.768	1.20	41.8	0.02					No	Plume Definition
		05391	7/7/98 Uranium-233/234	1.64	pCi/L		1.07	1.53	60.7	0.03					No	Plume Definition
		05391	7/7/98 Uranium-238	1.24	pCi/L		0.768	1.62	41.8	0.03					No	Plume Definition
		2987	6/2/98 Nickel	1770.00	ug/L		100	17.70	21.37	82.83	Yes	1742	1.02	Yes	No	Plume Definition
		2987	6/2/98 Selenium	361.00	ug/L		50	7.22	43.72	8.26	Yes	406	0.89		No	Plume Definition
		2987	6/2/98 Uranium-233/234	11.76	pCi/L		1.07	10.99	60.7	0.19					No	Plume Definition
		2987	6/2/98 Uranium-238	6.67	pCi/L		0.768	11.28	41.8	0.21					No	Plume Definition
		2987	10/22/98 Nickel	955.00	ug/L		100	9.55	21.37	44.69	Yes	1742	0.55		No	Plume Definition
		2987	10/22/98 Selenium	251.00	ug/L		50	5.02	43.72	5.74	Yes	406	0.62		No	Plume Definition
		2987	10/22/98 Sulfate	830.00	mg/L		500	1.66	435.6	1.91	Yes				No	Plume Definition
		2987	10/22/98 Uranium-233/234	12.70	pCi/L		1.07	11.87	60.7	0.21					No	Plume Definition
		2987	10/22/98 Uranium-238	9.30	pCi/L		0.768	12.11	41.8	0.22					No	Plume Definition
		3087	5/21/98 Uranium-233/234	1.17	pCi/L		1.07	1.09	60.7	0.02					No	Plume Definition
		3087	10/28/98 Trichloroethene	5.00	ug/L		5	1.00							No	Plume Definition
		6286	2/24/98 Carbon Tetrachloride	8.00	ug/L		5	1.60				9.76	0.82		No	Plume Definition
		6286	2/24/98 Selenium	60.90	ug/L		50	1.22	43.72	1.39	Yes	65.96	0.92		No	Plume Definition
		6286	2/25/98 Uranium-233/234	4.70	pCi/L		1.07	4.39	60.7	0.08					No	Plume Definition
		6286	2/25/98 Uranium-238	3.91	pCi/L		0.768	5.09	41.8	0.09					No	Plume Definition
		6286	7/8/98 Carbon Tetrachloride	6.00	ug/L		5	1.20				9.76	0.61		No	Plume Definition
		6286	7/8/98 Uranium-233/234	3.23	pCi/L		1.07	3.01	60.7	0.05					No	Plume Definition
		6286	7/8/98 Uranium-238	2.79	pCi/L		0.768	3.64	41.8	0.07					No	Plume Definition
		6386	7/14/98 Uranium-233/234	8.60	pCi/L		1.07	8.04	60.7	0.14					No	Plume Definition
		6386	7/14/98 Uranium-238	6.71	pCi/L		0.768	8.73	41.8	0.16					No	Plume Definition
		6386	9/28/98 Methylene Chloride	8.00	ug/L		5	1.60							No	Plume Definition
		77392	6/9/98 Uranium-233/234	21.73	pCi/L		1.07	20.31	60.7	0.36					No	Plume Definition
		77392	6/9/98 Uranium-238	12.34	pCi/L		0.768	16.06	41.8	0.30					No	Plume Definition
		77392	6/10/98 Fluoride	5.10	mg/L		4	1.28	1.55	3.29	Yes				No	Plume Definition
Plume Definition		P209489	2/18/98 1,1-Dichloroethene	29.00	ug/L	D	7	4.14				88.48	0.33		No	Plume Definition
		P209489	5/13/98 Carbon Tetrachloride	52.00	ug/L	D	5	10.40				83.26	0.62		No	Plume Definition
		P209489	5/13/98 Methylene Chloride	6.00	ug/L	D	5	1.20							No	Plume Definition
		P209489	5/13/98 Trichloroethene	63.00	ug/L	D	5	12.60				90.4	0.70		No	Plume Definition
		P209489	5/14/98 Nitrate/Nitrite	120.00	mg/L	N	10	12.00	4.664	25.73	Yes	316.24	0.38		No	Plume Definition
		P209489	5/14/98 Uranium-233/234	13.34	pCi/L		1.07	12.47	60.7	0.22					No	Plume Definition
		P209489	5/14/98 Uranium-235	1.18	pCi/L		1.01	1.17	1.79	0.68					No	Plume Definition
		P209489	5/14/98 Uranium-238	12.38	pCi/L		0.768	16.11	41.8	0.30					No	Plume Definition
		P209489	12/16/98 Nitrate/Nitrite	180.00	mg/L		10	18.00	4.664	38.59	Yes	316.24	0.57		No	Plume Definition
		P209489	12/16/98 Uranium-233/234	18.10	pCi/L		1.07	16.92	60.7	0.30					No	Plume Definition
		P209489	12/16/98 Uranium-238	15.10	pCi/L		0.768	19.66	41.8	0.36					No	Plume Definition
		P219189	1/6/98 1,1-Dichloroethene	17.00	ug/L		7	2.43				46.76	0.36		No	Plume Definition
		P219189	6/16/98 1,1-Dichloroethene	30.00	ug/L		7	4.29				46.76	0.64		No	Plume Definition
		P219189	6/16/98 Carbon Tetrachloride	7.00	ug/L		5	1.40							No	Plume Definition
		P219189	6/16/98 Uranium-233/234	56.15	pCi/L		1.07	52.48	60.7	0.93					No	Plume Definition
		P219189	6/16/98 Uranium-235	3.14	pCi/L		1.01	3.11	1.79	1.76	Yes				No	Plume Definition
		P219189	6/16/98 Uranium-238	43.87	pCi/L		0.768	57.12	41.8	1.05	Yes				No	Plume Definition
		P219189	11/3/98 1,1-Dichloroethene	18.00	ug/L		7	2.57				46.76	0.38		No	Plume Definition
		P416789	3/24/98 Tetrachloroethene	5.00	ug/L		5	1.00				7.63	0.66		No	Plume Definition
		P416789	3/24/98 Trichloroethene	10.00	ug/L		5	2.00				26.19	0.38		No	Plume Definition
		P416889	3/9/98 Tetrachloroethene	6.00	ug/L		5	1.20				77.7	0.08		No	Plume Definition
		P416889	6/2/98 Tetrachloroethene	30.00	ug/L		5	6.00				77.7	0.39		No	Plume Definition
		P416889	10/28/98 Tetrachloroethene	29.00	ug/L		5	5.80				77.7	0.37		No	Plume Definition
		P416889	10/28/98 Uranium-233/234	1.30	pCi/L	B	1.07	1.21	60.7	0.02					No	Plume Definition

Table 2-8 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells

Well Class	Location	Sample Date	Analyte	Result	Units	Q	Tier II	Tier II Ratio	Back-ground M2SD	Back-ground Ratio	Above Back-ground?	Historic M2SD	Historic Ratio	Above Historic?	Reportable?	Well Class
Plume Extent		03991	8/6/98 Carbon Tetrachloride	41.00	ug/L	D	5	8.20				27.22	1.51	Yes	Yes	Plume Extent
		03991	8/6/98 Tetrachloroethene	11.00	ug/L		5	2.20				6.38	1.72	Yes	Yes	Plume Extent
		03991	8/6/98 Trichloroethene	6.00	ug/L		5	1.20				19.03	0.32		No	Plume Extent
		03991	8/6/98 Uranium-233/234	2.09	pCi/L		1.07	1.95	60.7	0.03					No	Plume Extent
		03991	8/6/98 Uranium-238	1.38	pCi/L		0.768	1.80	41.8	0.03					No	Plume Extent
		04091	2/25/98 Uranium-233/234	2.48	pCi/L		1.07	2.32	60.7	0.04					No	Plume Extent
		04091	2/25/98 Uranium-238	1.52	pCi/L		0.768	1.98	41.8	0.04					No	Plume Extent
		04091	5/27/98 Uranium-233/234	2.24	pCi/L		1.07	2.10	60.7	0.04					No	Plume Extent
		04091	5/27/98 Uranium-238	1.49	pCi/L		0.768	1.94	41.8	0.04					No	Plume Extent
		04091	10/19/98 Uranium-233/234	2.29	pCi/L		1.07	2.14	60.7	0.04					No	Plume Extent
		04091	10/19/98 Uranium-238	1.19	pCi/L		0.768	1.55	41.8	0.03					No	Plume Extent
		04591	3/13/98 Uranium-233/234	2.98	pCi/L		1.07	2.79	60.7	0.05					No	Plume Extent
		04591	3/13/98 Uranium-238	1.38	pCi/L		0.768	1.80	41.8	0.03					No	Plume Extent
		04591	8/24/98 Uranium-233/234	2.15	pCi/L		1.07	2.01	60.7	0.04					No	Plume Extent
		04591	8/24/98 Uranium-238	1.11	pCi/L		0.768	1.45	41.8	0.03					No	Plume Extent
		04991	2/24/98 Uranium-233/234	5.84	pCi/L		1.07	5.46	60.7	0.10					No	Plume Extent
		04991	2/24/98 Uranium-238	3.54	pCi/L		0.768	4.61	41.8	0.08					No	Plume Extent
		04991	6/9/98 Methylene Chloride	5.00	ug/L	B	5	1.00							No	Plume Extent
		04991	6/9/98 Uranium-233/234	5.09	pCi/L		1.07	4.75	60.7	0.08					No	Plume Extent
		04991	6/9/98 Uranium-238	2.86	pCi/L		0.768	3.72	41.8	0.07					No	Plume Extent
		04991	10/27/98 Methylene Chloride	6.00	ug/L		5	1.20							No	Plume Extent
		04991	10/27/98 Trichloroethene	6.00	ug/L		5	1.20							Yes	Plume Extent
		04991	10/27/98 Uranium-233/234	6.42	pCi/L	B	1.07	6.00	60.7	0.11					No	Plume Extent
		04991	10/27/98 Uranium-238	4.27	pCi/L	B	0.768	5.56	41.8	0.10					No	Plume Extent
		05091	2/27/98 Uranium-233/234	4.38	pCi/L		1.07	4.09	60.7	0.07					No	Plume Extent
		05091	2/27/98 Uranium-238	2.39	pCi/L		0.768	3.11	41.8	0.06					No	Plume Extent
		05091	8/26/98 Uranium-233/234	5.06	pCi/L		1.07	4.73	60.7	0.08					No	Plume Extent
		05091	8/26/98 Uranium-238	3.06	pCi/L		0.768	3.98	41.8	0.07					No	Plume Extent
		06091	3/4/98 Carbon Tetrachloride	5.00	ug/L		5	1.00				4.44	1.13	Yes	No	Plume Extent
		06091	3/4/98 Uranium-233/234	4.00	pCi/L		1.07	3.74	60.7	0.07					No	Plume Extent
		06091	3/4/98 Uranium-238	2.82	pCi/L		0.768	3.67	41.8	0.07					No	Plume Extent
		06091	4/23/98 Uranium-233/234	2.09	pCi/L		1.07	1.95	60.7	0.03					No	Plume Extent
		06091	4/23/98 Uranium-238	1.25	pCi/L		0.768	1.63	41.8	0.03					No	Plume Extent
		06091	10/29/98 Carbon Tetrachloride	6.00	ug/L		5	1.20				4.44	1.35	Yes	No	Plume Extent
		06091	10/29/98 Methylene Chloride	17.00	ug/L		5	3.40							Yes	Plume Extent
		06091	10/29/98 Nitrate/Nitrite	12.00	mg/L		10	1.20	4.664	2.57	Yes				Yes	Plume Extent
		06091	10/29/98 Uranium-233/234	3.39	pCi/L	B	1.07	3.17	60.7	0.06					No	Plume Extent
		06091	10/29/98 Uranium-238	2.16	pCi/L	B	0.768	2.81	41.8	0.05					No	Plume Extent
		08091	6/17/98 Uranium-233/234	7.88	pCi/L		1.07	7.37	60.7	0.13					No	Plume Extent
		08091	6/17/98 Uranium-238	3.19	pCi/L		0.768	4.15	41.8	0.08					No	Plume Extent
		10194	3/4/98 Uranium-233/234	2.46	pCi/L		1.07	2.30	60.7	0.04					No	Plume Extent
		10194	3/4/98 Uranium-238	1.25	pCi/L		0.768	1.63	41.8	0.03					No	Plume Extent
		10194	7/20/98 Uranium-233/234	2.26	pCi/L		1.07	2.11	60.7	0.04					No	Plume Extent
		10194	7/20/98 Uranium-238	1.58	pCi/L		0.768	2.06	41.8	0.04					No	Plume Extent
		10994	7/14/98 Selenium	285.00	ug/L		50	5.70	43.72	6.52	Yes	1097.2	0.26		No	Plume Extent
		10994	7/14/98 Uranium-233/234	7.52	pCi/L		1.07	7.02	60.7	0.12					No	Plume Extent
		10994	7/14/98 Uranium-238	5.03	pCi/L		0.768	6.55	41.8	0.12					No	Plume Extent
		1386	5/27/98 Nickel	326.00	ug/L		100	3.26	21.37	15.26	Yes	308.75	1.06	Yes	Yes	Plume Extent
		1386	5/27/98 Strontium-89/90	1.17	pCi/L		0.852	1.37	2.85	0.41					No	Plume Extent
		1386	5/27/98 Uranium-233/234	8.94	pCi/L		1.07	8.35	60.7	0.15					No	Plume Extent
		1386	5/27/98 Uranium-238	7.08	pCi/L		0.768	9.22	41.8	0.17					No	Plume Extent
		1386	6/19/98 Nickel	305.00	ug/L		100	3.05	21.37	14.27	Yes	308.75	0.99		No	Plume Extent
		1386	7/15/98 Nickel	521.00	ug/L		100	5.21	21.37	24.38	Yes	308.75	1.69	Yes	Yes	Plume Extent
		1386	8/19/98 Nickel	979.00	ug/L		100	9.79	21.37	45.81	Yes	308.75	3.17	Yes	Yes	Plume Extent
		1386	10/14/98 Nickel	904.00	ug/L		100	9.04	21.37	42.30	Yes	308.75	2.93	Yes	Yes	Plume Extent
		1386	10/14/98 Uranium-233/234	7.01	pCi/L		1.07	6.55	60.7	0.12					No	Plume Extent
		1386	10/14/98 Uranium-238	6.90	pCi/L		0.768	8.98	41.8	0.17					No	Plume Extent
		1786	4/23/98 Nitrate/Nitrite	510.00	mg/L		10	51.00	4.664	109.35	Yes	689.31	0.74		No	Plume Extent
		1786	4/23/98 Selenium	126.00	ug/L		50	2.52	43.72	2.88	Yes	290.81	0.43		No	Plume Extent
		1786	4/23/98 Uranium-233/234	40.74	pCi/L		1.07	38.08	60.7	0.67					No	Plume Extent
		1786	4/23/98 Uranium-235	1.46	pCi/L		1.01	1.45	1.79	0.82					No	Plume Extent
		1786	4/23/98 Uranium-238	28.67	pCi/L		0.768	37.33	41.8	0.69					No	Plume Extent
		1786	10/28/98 Nitrate/Nitrite	570.00	mg/L		10	57.00	4.664	122.21	Yes	689.31	0.83		No	Plume Extent
		1786	10/28/98 Selenium	169.00	ug/L		50	3.38	43.72	3.87	Yes	290.81	0.58		No	Plume Extent
		1786	10/28/98 Trichloroethene	6.00	ug/L		5	1.20							No	Plume Extent
		1786	10/28/98 Uranium-233/234	33.20	pCi/L		1.07	31.03	60.7	0.55					No	Plume Extent
		1786	10/28/98 Uranium-238	26.60	pCi/L	B	0.768	34.64	41.8	0.64					No	Plume Extent
		1986	3/23/98 Manganese	2050.00	ug/L		183	11.20	162.33	12.63	Yes	3304	0.62		No	Plume Extent
		1986	6/17/98 Manganese	3690.00	ug/L		183	20.16	162.33	22.73	Yes	3304	1.12	Yes	Yes	Plume Extent
		1986	10/27/98 Manganese	2610.00	ug/L		183	14.26	162.33	16.08	Yes	3304	0.79		No	Plume Extent
		1986	10/27/98 Trichloroethene	28.00	ug/L		5	5.60							No	Plume Extent
		1986	10/27/98 Uranium-233/234	2.44	pCi/L	B	1.07	2.28	60.7	0.04					No	Plume Extent
		1986	10/27/98 Uranium-238	2.02	pCi/L	B	0.768	2.63	41.8	0.05					No	Plume Extent
		1986	11/23/98 Manganese	2590.00	ug/L		183	14.15	162.33	15.96	Yes	3304	0.78		No	Plume Extent
		1986	12/16/98 Manganese	2330.00	ug/L		183	12.73	162.33	14.35	Yes	3304	0.71		No	Plume Extent
		2186	12/2/98 Uranium-233/234	1.42	pCi/L		1.07	1.33	60.7	0.02					No	Plume Extent
		2186	12/2/98 Uranium-238	1.04	pCi/L	B	0.768	1.35	41.8	0.02					No	Plume Extent
		22696	8/31/98 Trichloroethene	10.00	ug/L		5	2.00							No	Plume Extent

Table 2-8 1998 Groundwater Values Above Tier II Action Levels and Standard Framework Criteria (ALF) in RFCA - Designated Wells

Well Class	Location	Sample Date	Analyte	Result	Units	Q	Tier II	Tier II Ratio	Back-ground M2SD	Back-ground Ratio	Above Back-ground?	Historic M2SD	Historic Ratio	Above Historic?	Reportable?	Well Class
Plume Extent		22796	6/16/98	Manganese	1150.00	ug/L	*	183	6.28	162.33	7.08				No	Plume Extent
		22796	6/16/98	Trichloroethene	29.00	ug/L		5	5.80						No	Plume Extent
		22796	12/1/98	Manganese	391.00	ug/L		183	2.14	162.33	2.41	Yes			No	Plume Extent
		22796	12/1/98	Uranium-233/234	3.03	pCi/L		1.07	2.83	60.7	0.05				No	Plume Extent
		22796	12/1/98	Uranium-238	1.89	pCi/L	B	0.768	2.46	41.8	0.05				No	Plume Extent
		22896	3/23/98	Manganese	361.00	ug/L		183	1.97	162.33	2.22	Yes			No	Plume Extent
		22896	3/23/98	Nickel	1050.00	ug/L		100	10.50	21.37	49.13	Yes			No	Plume Extent
		22896	3/23/98	Trichloroethene	3400.00	ug/L		5	680.00						No	Plume Extent
		22896	9/1/98	Chromium	248.00	ug/L		100	2.48	12.44	19.94	Yes			No	Plume Extent
		22896	9/1/98	Trichloroethene	2400.00	ug/L	D	5	480.00						No	Plume Extent
		23096	2/26/98	Uranium-233/234	1.90	pCi/L		1.07	1.78	60.7	0.03				No	Plume Extent
		23096	2/26/98	Uranium-238	2.85	pCi/L		0.768	3.71	41.8	0.07				No	Plume Extent
		23096	8/17/98	Uranium-233/234	2.55	pCi/L		1.07	2.38	60.7	0.04				No	Plume Extent
		23096	8/17/98	Uranium-238	2.97	pCi/L		0.768	3.87	41.8	0.07				No	Plume Extent
		23196	2/25/98	Nitrate/Nitrite	10.20	mg/L		10	1.02	4.664	2.19	Yes			Yes	Plume Extent
		23296	3/24/98	Carbon Tetrachloride	13.00	ug/L		5	2.60						No	Plume Extent
		23296	3/24/98	cis-1,2-Dichloroethene	78.00	ug/L		70	1.11						No	Plume Extent
		23296	3/24/98	Tetrachloroethene	17.00	ug/L		5	3.40						No	Plume Extent
		23296	3/24/98	Trichloroethene	690.00	ug/L		5	138.00						No	Plume Extent
		23296	3/24/98	Uranium-233/234	18.30	pCi/L		1.07	17.10	60.7	0.30				No	Plume Extent
		23296	3/24/98	Uranium-238	13.10	pCi/L		0.768	17.06	41.8	0.31				No	Plume Extent
		23296	8/31/98	cis-1,2-Dichloroethene	100.00	ug/L	E	70	1.43						No	Plume Extent
		23296	8/31/98	Manganese	327.00	ug/L		183	1.79	162.33	2.01	Yes			Yes	Plume Extent
		23296	8/31/98	Tetrachloroethene	10.00	ug/L		5	2.00						No	Plume Extent
		23296	8/31/98	Trichloroethene	280.00	ug/L	D	5	56.00						No	Plume Extent
		23296	8/31/98	Uranium-233/234	11.50	pCi/L		1.07	10.75	60.7	0.19				No	Plume Extent
		23296	8/31/98	Uranium-238	8.47	pCi/L		0.768	11.03	41.8	0.20				No	Plume Extent
		3586	3/16/98	Uranium-233/234	3.01	pCi/L		1.07	2.81	60.7	0.05				No	Plume Extent
		3586	3/16/98	Uranium-238	2.73	pCi/L		0.768	3.55	41.8	0.07				No	Plume Extent
		3586	6/5/98	Manganese	4180.00	ug/L		183	22.84	162.33	25.75	Yes	4357	0.96	No	Plume Extent
		3586	6/5/98	Uranium-233/234	2.27	pCi/L		1.07	2.13	60.7	0.04				No	Plume Extent
		3586	6/5/98	Uranium-238	1.62	pCi/L		0.768	2.11	41.8	0.04				No	Plume Extent
		3586	6/5/98	Vinyl Chloride	14.00	ug/L		2	7.00			776	0.02		No	Plume Extent
		3586	10/20/98	Manganese	4270.00	ug/L		183	23.33	162.33	26.30	Yes	4357	0.98	No	Plume Extent
		3586	10/20/98	Uranium-233/234	2.44	pCi/L		1.07	2.28	60.7	0.04				No	Plume Extent
		3586	10/20/98	Uranium-238	2.02	pCi/L		0.768	2.63	41.8	0.05				No	Plume Extent
		3586	10/20/98	Vinyl Chloride	39.00	ug/L		2	19.50			776	0.05		No	Plume Extent
		5387	2/26/98	Uranium-233/234	9.52	pCi/L		1.07	8.90	60.7	0.16				No	Plume Extent
		5387	2/26/98	Uranium-238	8.03	pCi/L		0.768	10.46	41.8	0.19				No	Plume Extent
		5387	6/2/98	Uranium-233/234	11.26	pCi/L		1.07	10.53	60.7	0.19				No	Plume Extent
		5387	6/2/98	Uranium-238	7.30	pCi/L		0.768	9.50	41.8	0.17				No	Plume Extent
		5387	11/17/98	Methylene Chloride	8.00	ug/L		5	1.60						Yes	Plume Extent
		7086	2/27/98	Manganese	326.00	ug/L		183	1.78	162.33	2.01	Yes	761	0.43	No	Plume Extent
		7086	2/27/98	Uranium-233/234	1.10	pCi/L		1.07	1.03	60.7	0.02				No	Plume Extent
		7086	2/27/98	Uranium-238	0.88	pCi/L		0.768	1.15	41.8	0.02				No	Plume Extent
		7086	7/28/98	Manganese	309.00	ug/L		183	1.69	162.33	1.90	Yes	761	0.41	No	Plume Extent
		75992	7/7/98	Methylene Chloride	10.00	ug/L	B	5	2.00						No	Plume Extent
		75992	7/7/98	Strontium-89/90	1.02	pCi/L		0.852	1.20	2.85	0.36				No	Plume Extent
		75992	7/7/98	Uranium-233/234	10.46	pCi/L		1.07	9.78	60.7	0.17				No	Plume Extent
		75992	7/7/98	Uranium-238	8.17	pCi/L		0.768	10.64	41.8	0.20				No	Plume Extent
		B208289	2/24/98	Nitrate/Nitrite	47.70	mg/L		10	4.77	4.664	10.23	Yes	60.44	0.79	No	Plume Extent
		B208289	6/3/98	Nitrate/Nitrite	27.00	mg/L		10	2.70	4.664	5.79	Yes	60.44	0.45	No	Plume Extent
		B208289	6/3/98	Selenium	2880.00	ug/L		50	57.60	43.72	65.87	Yes			Yes	Plume Extent
		B208289	11/16/98	Selenium	3220.00	ug/L		50	64.40	43.72	73.65	Yes			Yes	Plume Extent
		B208789	5/27/98	Manganese	454.00	ug/L		183	2.48	162.33	2.80	Yes	624.21	0.73	No	Plume Extent
		B208789	5/27/98	Uranium-233/234	14.33	pCi/L		1.07	13.39	60.7	0.24				No	Plume Extent
		B208789	5/27/98	Uranium-238	11.44	pCi/L		0.768	14.90	41.8	0.27				No	Plume Extent
		B208789	11/19/98	Manganese	622.00	ug/L		183	3.40	162.33	3.83	Yes	624.21	1.00	Yes	Plume Extent
		B208789	11/19/98	Uranium-233/234	10.70	pCi/L	B	1.07	10.00	60.7	0.18				No	Plume Extent
		B208789	11/19/98	Uranium-238	8.06	pCi/L	B	0.768	10.49	41.8	0.19				No	Plume Extent
		P114389	6/19/98	Manganese	568.00	ug/L		183	3.10	162.33	3.50	Yes	663.52	0.86	No	Plume Extent
		P114389	7/21/98	Manganese	549.00	ug/L		183	3.00	162.33	3.38	Yes	663.52	0.83	No	Plume Extent
		P114389	8/18/98	Manganese	711.00	ug/L		183	3.89	162.33	4.38	Yes	663.52	1.07	Yes	Plume Extent
		P218389	1/20/98	Nitrate/Nitrite	10.00	mg/L		10	1.00	4.664	2.14	Yes			No	Plume Extent
		P218389	6/16/98	Uranium-233/234	1.98	pCi/L		1.07	1.85	60.7	0.03				No	Plume Extent
		P218389	6/16/98	Uranium-238	1.55	pCi/L		0.768	2.02	41.8	0.04				No	Plume Extent
		P219489	1/7/98	Nitrate/Nitrite	42.00	mg/L		10	4.20	4.664	9.01	Yes	38	1.11	Yes	Plume Extent
		P219489	6/10/98	Uranium-233/234	5.67	pCi/L		1.07	5.30	60.7	0.09				No	Plume Extent
		P219489	6/10/98	Uranium-238	3.88	pCi/L		0.768	5.05	41.8	0.09				No	Plume Extent
		P219489	11/3/98	Methylene Chloride	6.00	ug/L	B	5	1.20						No	Plume Extent
		P219489	11/3/98	Nitrate/Nitrite	47.00	mg/L		10	4.70	4.664	10.08	Yes	38	1.24	Yes	Plume Extent
		P314289	7/21/98	Manganese	330.00	ug/L		183	1.80	162.33	2.03	Yes			Yes	Plume Extent
		P314289	7/21/98	Nickel	140.00	ug/L		100	1.40	21.37	6.55	Yes			Yes	Plume Extent

**Table 2- 9. RFCA-Designated Wells with No Analytes
Above Tier II Action Levels**




Well Number	IMP Well Class
00197*	PLUME EXTENT
00297*	PLUME DEFINITION
00397*	PLUME EXTENT
02197*	PLUME EXTENT
22596	PLUME EXTENT
22996	PLUME EXTENT
3386	PLUME EXTENT
43392	PLUME EXTENT
4787*	PLUME EXTENT
4887	PLUME EXTENT
6186	PLUME EXTENT
76992	PLUME EXTENT
P209289*	PLUME DEFINITION
P313589	PLUME EXTENT

• Indicates well was dry throughout 1998

The uranium isotopes U-233/234, U-235, and U-238 were detected above Tier II action levels in all six Boundary wells. All of the uranium isotope analytical results were below the background M2SD benchmarks, and are not considered reportable values. Monthly confirmation sampling for tritium at well 10394, initiated in 1998 as a result of an above Tier II action level result (1,130 pCi/L) reported for the November 25, 1997, sampling event, failed to confirm the presence of tritium in this well at above Tier II action levels (Figure 2-2). It is, therefore, concluded that the tritium exceedance was a spurious analytical result.

Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells




RF/RMRS-99-433.UN



Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean

Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-7



2-8



2-9




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN

2-10



2-11



2-12






Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-13



2-14



2-15




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-16



2-17



2-18




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-19



2-20



2-21




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-22



2-23




2-24




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean

Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

2-25



2-26



2-27






Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-28



2-29



2-30




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-31



2-32



2-33




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-34



2-35




2-36




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean

Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

2-37



2-38



2-39






Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-40



2-41



2-42




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-43



2-44



2-45




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-46



2-47



2-48




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-49



2-50






2-51



Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean

Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN




82

Heavy mixed dashed lines = Tier II Action Level
 Light uniform dashed lines = Historic +/- Standard Deviations
 (-Std. Dev. not shown if <0)
 Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN


2-55



2-56



2-57




Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean


Figure 2-1 Through 2-59
Trend Plots For Selected Analytes and Wells

RF/RMRS-99-433.UN

2-58



2-59



Heavy mixed dashed lines = Tier II Action Level
Light uniform dashed lines = Historic +/- Standard Deviations
(-Std. Dev. not shown if <0)
Light mixed dashed lines = Historic Mean

2.3.2.2 Drainage Wells

Five Drainage wells, 6486, 6586, 5587, 38591, and 00997, were sampled in 1998. Nickel was reported above the Tier II action level, background M2SD, and historic M2SD for samples collected from wells 6486 and 6586 (Table 2-8). Figures 2-3 and 2-4 show an increasing trend for nickel in wells 6486 and 6586 beginning in the third quarter 1996 and continuing through 1998. As such, nickel in these wells represent reportable values.

According to the IMP, an evaluation of surface water impacts is required at this stage of the process, although the reason for a nickel exceedance at these wells has not been ascertained. At these concentrations, nickel is not known to be a widespread contaminant. The localized nature of nickel at these wells suggest that the high nickel concentrations may be caused by sampling artifacts related to the stainless steel composition of the well casing, changes in sampling procedures, and/or the well geochemical environment. Well sampling techniques at these wells have changed over the past few years, so sampling artifacts caused by changes in purging or sampling technique may explain the high concentrations. Corrosion of well screen (316 stainless steel) and centralizer (304 stainless steel) materials may also be a factor given the fourteen year old age of the wells.

In FY2000, an evaluation of nickel concentrations at wells 6486 and 6586 will be undertaken, including a reexamination of sampling procedures and a downhole television camera survey of well casing and screen conditions to check for corrosion. In addition, a paired PVC Geoprobe well will be installed next to each well and sampled for metals to confirm the presence or absence of nickel in groundwater at these locations. Reproduceable nickel detections above the Tier II action level and historic M2SD concentration at the proposed new well points will then cause the initiation of a surface water impact evaluation developed to investigate the extent of nickel contamination and determine whether nickel represents a potential threat to the surface water quality of Woman Creek. Until the sampling artifact evaluation is completed, these wells will be sampled as part of routine sampling operations.

The uranium isotopes U-233/234 and U-238 were detected above Tier II action levels in four Drainage wells, 00997, 38591, 6486, and 6586. All of the uranium results were below the background benchmarks and, as such, are not reportable values.

2.3.2.3 Performance Monitoring Wells

Performance monitoring wells monitor the effect of a remedial action or source removal on downgradient groundwater quality. As such, contaminant trends over time are the basis for determining reportable values. In considering results for Performance monitoring wells, Tier II action levels and background

benchmarks are applied only to determine which analytes are to be monitored using trend charts. Eighteen Performance monitoring wells, including four special groundwater monitoring stations associated with the French Drain (COLWELL and COLGAL), Mound (SW059), and B881 footing drain (SW13494), were sampled in 1998. The wells have been grouped by project to facilitate an interpretation of the results.

Mound

Wells 00897 and 02291 monitor downgradient groundwater quality along the proximal and medial portions of the Mound plume near the site of the former Mound source remediation project. From Table 2-8, the contaminants primarily associated with these wells are PCE, TCE, and possibly methylene chloride. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels but below background levels, thus the values do not qualify as reportable results.

Figures 2-5 through 2-7 illustrate the concentration trends of PCE, TCE, and methylene chloride for well 00897 and Figure 2-8 illustrates the PCE concentration trend in well 02291. There was an insufficient number of values to plot methylene chloride for well 00887. Due to the short monitoring period since well 00897 was installed, there is currently an insufficient amount of data to evaluate the trend of PCE and TCE in this well. Some seasonality may be evident in the data with contaminants attaining peak concentrations during the spring months. PCE and TCE in well 02291 indicate erratic, but generally upward, trends that began well before the initiation of source removal activities in 1997. It is expected that the upward trend of these contaminants will eventually reverse and decline as the effects of the Mound source removal are manifested in source area groundwater. Tentatively, the high methylene chloride value (12,000 µg/L) reported for well 00897 is attributed to laboratory contamination that was magnified by dilutions (2,500x) necessary to quantify TCE.

Trench T-3

Wells 11891 and 12191 monitor downgradient groundwater quality associated with the Trench T-3 source remediation project. From Table 2-8, the contaminants primarily associated with these wells are PCE and carbon tetrachloride, with lesser concentrations of TCE. 1,1-Dichloroethene was detected once above the Tier II action level concentration in well 12191, but at a relatively low concentration (7 µg/L) compared to the other VOC contaminants. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels but below background levels, thus the values are not considered to be reportable.

For assessing concentration trends, only the major contaminants, PCE and carbon tetrachloride, were selected for trend plotting, as these contaminants are expected to adequately monitor groundwater quality

conditions in the vicinity of the trench. The 1998 carbon tetrachloride and PCE results for wells 11891 and 12191, shown in Figures 2-9 through 2-12, are consistent with the historical concentrations of these contaminants, with the possible exception of fourth quarter 1998 PCE in well 11891. Concentration trends for these contaminants are essentially flat and unchanged over time. The significance of the fourth quarter 1998 spike in PCE concentration in well 11891 will be assessed with subsequent data collected during routine groundwater sampling in 1999.

Trench T-4

The potential impact of the Trench T-4 source remediation project on alleviating groundwater contamination is monitored by downgradient Performance monitoring wells 3687, 05691, and 12691. Volatile organic groundwater contamination in well 3687, ranked by Tier II ratios, consists principally of TCE, PCE, and carbon tetrachloride, with lower Tier II ratios of 1,1-dichloroethene, chloroform, and possibly methylene chloride. TCE concentrations consistently exceed Tier I action levels, while PCE and carbon tetrachloride each exhibit single instances of Tier I exceedances. Wells 05691 and 12691 contain basically the same suite of major organic contaminant as well 3687, though in lower concentrations and different proportions. However, detectable concentrations of 1,1-dichloroethene and chloroform above Tier II action levels were not found in either well. A single detection of cis-1,2-dichloroethene was reported for well 12691 at the Tier II action level of 70 µg/L. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels but below background levels in all three wells, thus the values are not considered to be reportable.

Based mainly on Tier II ratio rank, trend plots, shown in Figures 2-13 through 2-18, were prepared to evaluate historical groundwater concentration trends at Trench T-4: wells 3687 and 05691 (TCE and carbon tetrachloride), and well 12691 (PCE and carbon tetrachloride). In all plots, the contaminant concentration trends are either flat or slightly declining. Moderate increases in TCE and carbon tetrachloride concentrations are apparent in the fourth quarter 1998 at well 3687, but the presence of similar, possibly seasonal, peaks in both plots suggest that the up turn may only represent a short-term transient effect that is controlled by local hydrologic conditions. The significance of the fourth quarter 1998 spike in TCE and carbon tetrachloride concentrations in well 3687 will be assessed with subsequent data collected during routine groundwater sampling in 1999.

French Drain

Performance monitoring wells assigned to the French Drain include downgradient wells 10592, 10692, 10792, 10992, and 11092; the 881 Hillside collection well, 891COLWEL; and the 881 Hillside collection gallery, 891COLGAL. Except for single occurrences of methylene chloride in wells 10592 and 11092,

VOCs characteristic of the 881 Hillside groundwater plume (IHSS 119.1), as indicated by the contaminants present in 891COLWEL, were not detected above Tier II action level concentrations in any of the Performance monitoring wells positioned downgradient of the French Drain. VOC contamination above Tier II action levels in 891COLWEL consists mainly of TCE with lower concentrations of PCE, carbon tetrachloride, and possibly methylene chloride. No VOC contamination above Tier II action levels was detected in 891COLGAL.

Selenium was detected above Tier II action levels and background M2SD in wells 10592, 10792, and 10992, with the highest concentrations reported for well 10992 located directly downgradient of the 881 Hillside plume. An above Tier II action level and background M2SD concentration of nitrate/nitrite, an historical 881 Hillside plume contaminant, was detected in only one well, 10992 (nitrate/nitrite is currently not monitored at 891COLWEL and 891COLGAL). 891COLGAL, which comprises all groundwater discharged from the French Drain, contained no detectable VOCs or selenium concentrations above Tier II action levels during 1998. Uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels but below background M2SD levels in all locations except well 11092 (no detections above Tier II action levels), thus the values are not considered to be reportable.

As shown in Figures 2-19 through 2-25, trend plots of representative above Tier II action level contaminants were constructed for wells 10592 and 10792 (selenium), 10992 (selenium and nitrate/nitrite), and 891COLWEL (TCE, PCE, and selenium). Selenium concentrations are historically highest in 891COLWEL located in the center of the 881 Hillside plume. Concentrations in this well rose from about 200 µg/L in 1992 to over 800 µg/L in late 1995 and early 1996, and have steadily fallen back to about 500 µg/L in 1998. When viewed over the long-term, selenium trends in 891COLWEL have remained relatively flat or have slightly increased. Similar trends for TCE and PCE are observed in 891COLWEL, though peak concentrations were attained about one year earlier than for selenium. The selenium trend in well 10592 has steadily declined since concentrations peaked in late 1995 or early 1996, but, over the long term, has returned to concentration levels initially measured in 1993. Selenium trends in well 10992 show a similar decline, while the trend in well 10792 is essentially flat. Nitrate/nitrite in well 10992 also shows a flat to declining trend. Considered collectively, the downgradient well data indicate that contaminants associated with the 881 Hillside plume are not migrating downgradient of the French Drain, and are, therefore, not reportable.

Ryan's Pit

One well, 07391, is designated as a Ryan's Pit plume Performance monitoring well. This well contains some of the highest VOC concentrations ever detected in groundwater at RFETS. TCE is the primary

VOC contaminant, with concentrations attaining a maximum value of 160,000 µg/L during 1998. Other VOCs detected above Tier II action level concentrations include PCE, 1,1,1-trichloroethane, chloroform, and methylene chloride; the latter two contaminants having a questionable presence because both were consistently detected in laboratory blank samples ("B" qualifier). Nitrate/nitrite was detected once above Tier II action levels and background M2SD concentrations, but below historic M2SD concentrations. It is, therefore, not considered to be a reportable occurrence. U-233/234, U-235, and U-238 were all detected at least once above Tier II action levels, with U-238 occurring above background M2SD and historic M2SD activity-concentrations.

Figures 2-26 and 2-27 show that high TCE and PCE concentration conditions persisted throughout 1998. The single instances of above historic M2SD levels reported for each contaminant in the third quarter 1998 are apparently seasonal peaks that are related to major recharge events. In general, TCE and PCE trends do not appear to be increasing, although further monitoring will be required to confirm the presence or absence of an upward trend, especially for PCE. Consequently, the values are not considered to be reportable at this time. In comparison, U-238 activity-concentrations consistently increased during 1998 forming a distinct upward trend above historic M2SD concentrations (Figure 2-28). The combination of abnormally high U-238 activity-concentrations and an upward trend direction represents a reportable occurrence for this analyte. An evaluation to assess the extent of the problem will be initiated during FY2000.

Building 881 Footing Drain Sump

Potential contamination associated with the Building 881 footing drain sump is monitored directly at SW13494 and indirectly by wells 00797 and 5387 (a Plume Extent well). During 1998, organic contamination at SW13494 was distinguished by PCE concentrations that consistently exceeded Tier II action levels, and by a single, suspect methylene chloride value ("B" qualified). VOCs were not detected at downgradient well 00797; however, sulfate was detected above Tier II action levels and background M2SD. Uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels but below background M2SD levels at both locations, thus the values are not considered to be reportable.

Figure 2-29 indicates that PCE concentrations may be increasing at SW13494, although additional data will be required to confirm the upward trend. The significance of this apparent increase will be assessed in future quarterly reports for data collected during 1999. Sulfate in well 00797 was detected at the same concentration (440 mg/L) as last year, but with a sulfate data record consisting of only two values, a trend plot was not constructed for this analyte.

2.3.2.4 Plume Definition Wells

Seventeen Plume Definition wells were monitored during 1998 for the 903 Pad/Ryan's Pit, PU&D Yard, 881 Hillside, IHSS 118.1, and Industrial Area groundwater plumes (Plate 10). As reported in Table 2-8, fifteen of these wells contained at least one or more contaminants that exceeded Tier II action levels, but only well 22896 contained values exceeding Tier I action levels (Tier II ratio greater than or equal to 100). Well 22896 was reclassified as a Plume Definition well in 1998 after unexpectedly high TCE concentrations associated with the Industrial Area VOC plume were detected in 1996 and 1997. This discovery led to an evaluation, presented in Section 4.1 of this report, of potential impacts to surface water along the northern boundary of the IA VOC plume. TCE concentrations in well 22896 (Figure 2-30) constitute reportable values and prompted an evaluation because this is a new well with no historic baseline.

2.3.2.5 Plume Extent Wells

East Trenches Plume

The East Trenches Plume is monitored by nine Plume Extent wells, including wells 03991, 04091, 04591, 04991, 05091, 06091, 08091, 10194, and 23296. A tenth well, 75992, is located near South Walnut Creek between the known boundaries of the East Trenches and Mound plumes, and is employed to monitor contamination that may originate from either plume. As shown in Plate 10, these wells are located along the outermost edge of the East Trenches plume to monitor plume movement and spreading away from potential source areas, such as Trench T-3, Trench T-4, and the northeast lobe of the 903 Pad VOC plume. VOCs represent the primary constituents of the East Trenches plume.

In previous years, above Tier II action level concentrations of TCE in well 23296 and carbon tetrachloride in well 06091 have triggered monthly confirmation sampling investigations that have verified the presence and concentration of above Tier II contamination in both of these wells. The Site initiated further hydrogeologic and surface water evaluations (DOE, 1998) in 1997 at both locations resulting in the design and installation of a groundwater intercept and treatment system along the upper B-series ponds (Section 6.3 of this report). VOC contamination above Tier II action level concentrations was not detected in any of the three new monitoring wells (02697, 02797, and 02897) installed in the paleochannel downgradient of well 06091, and routine monitoring was resumed at this location (DOE, 1998).

VOC concentrations exceeding Tier II action levels were detected in wells 03991 (carbon tetrachloride, PCE, and TCE); 04991 (methylene chloride and TCE); 06091 (carbon tetrachloride and methylene

chloride); 23296 (TCE, cis-1,2-dichloroethene, PCE, and carbon tetrachloride); and 75992 (methylene chloride). Non-radioactive inorganic constituents were not generally detected above Tier II action level concentrations in the East Trenches Plume Extent wells, although isolated instances of nitrate/nitrite in well 06091, selenium in well 10994, and manganese in well 23296 were reported during the year. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels but below background levels in all three wells, thus the values are not considered to be reportable. Likewise, strontium-89/90 was detected in well 75992 above the Tier II action level, but below background M2SD activity-concentrations, and is therefore not a reportable value.

Trend plots for carbon tetrachloride (Figure 2-31), PCE (Figure 2-32), and TCE (Figure 2-33) in well 03991 indicate step-like increases in concentration that are probably triggered by major recharge events. For carbon tetrachloride and PCE, concentrations peaked above historic M2SD levels immediately following the spring of 1998 and declined to below historic M2SD concentrations in subsequent sample periods. The net upward trend of these contaminants, as shown by successively higher "steps" in concentration, infer that the East Trenches plume is slowly moving eastward along the buried paleochannel away from source areas. Plume advancement may also be evident at well 04991 (Figure 2-34), located near the southeast boundary of the East Trenches plume, which experienced a sharp rise in TCE concentration (5 µg/L) to the Tier II action level and above historic M2SD concentrations. Conversely, the upward trend in carbon tetrachloride concentration at nearby well 06091, observed during 1996 and 1997, has since leveled off to within the 5 to 6 µg/L range, indicating that plume concentrations in this part of the paleochannel have, at least temporarily, reached an equilibrium condition. Methylene chloride in well 04991 (Figure 2-35) rose above the Tier II action level in 1998, but did not exceed historic M2SD concentrations and is considered to be reportable. In well 06091, monthly confirmation monitoring for methylene chloride (Figure 2-36), together with PCE (Figure 2-37), was initiated in 1999. Monthly confirmation sampling was also initiated in 1999 for nitrate/nitrite (Figure 2-38) in well 06091 and manganese (Figure 2-39) in well 23296. The exceedance values for these wells have been reported in previous quarterly reports.

Wells 03991 and 06091 are located approximately 600 and 200 feet, respectively, from an unnamed, deeply incised gully that receives alluvial seep flow at the terminus of the paleochannel. Groundwater sampling at 04091 in 1998 and 02697 in 1997 failed to detect VOC contamination, thus suggesting that the leading edge of the plume is limited to the vicinity of wells 03991 and 06091. The significance of the Tier II action level TCE detections at well 04991 will be assessed after more data is collected in 1999.

Solar Evaporation Ponds

Plume Extent wells 1386, 1786, 3386, 3586, B208289, B208789, P218389, and P219489 are utilized for monitoring groundwater contamination associated with the Solar Ponds Plume (SPP). The wells are located at the edge of the SPP nitrate plume, which primarily extends north from the Solar Ponds to North Walnut Creek, with additional minor pathways to the east and south toward South Walnut Creek (Plate 7). Nitrate and uranium are the principal contaminants associated with the SPP.

VOCs concentrations exceeding Tier II action levels were detected in wells 1786 (TCE), 3586 (vinyl chloride), and P219489 (methylene chloride). Above Tier II action level concentrations of nitrate/nitrite were found in wells 1786, B208289, P218389, and P219489, all located to the north and east of the Solar Ponds. Metal concentrations above Tier II action levels were detected in wells 1386 (nickel), 1786 (selenium), 3586 (manganese), B208289 (selenium), and B208789 (manganese). The uranium isotopes U-233/234, U-235, and U-238 were detected at above Tier II action levels in various wells, but below background M2SD levels at all locations, and are thus not considered to be reportable.

TCE concentrations at well 1786, shown in Figure 2-40, have historically fluctuated at or below the Tier II action level of 5 µg/L. Based on previous fluctuations, it is suspected that the 6 µg/L TCE detection listed in Table 2-8 represents a temporary condition rather than an significant upward trend in concentration. Routine monitoring for VOCs will continue at this well during 1999 unless further increases in TCE concentration require the initiation of monthly confirmation sampling. Vinyl chloride concentrations at well 3586 (Figure 2-41) have fallen considerably since peaking at over 900 µg/L in 1989. The source of vinyl chloride in well 3586 is attributable to the Mound plume; SPP contaminants such as nitrate and uranium do not appear to be problematical in this well. In 1998, vinyl chloride continued a downward trend, thus eliminating it as a reportable contaminant. Methylene chloride was detected only once above the Tier II action level in well P219489 (Figure 2-42). The "B" qualifier associated with this value indicates that it is potentially caused by a laboratory artifact rather than an actual increase in groundwater contamination at this location.

The concentration of nitrate/nitrite in wells 1786 (Figure 2-43), B208289 (Figure 2-44), P218389 (Figure 2-45), and P219489 (Figure 2-46) has generally remained within their respective historic M2SD ranges. None of the 1998 nitrate/nitrite concentrations in these wells exceeded the historic M2SD concentrations and are, therefore, not reportable.

Nickel concentrations in well 1386 (Figure 2-47) detected during 1998, including values reported for the monthly confirmation samples, remained well above Tier II action level and historic M2SD levels. According to the IMP, an evaluation of surface water impacts is required at this stage of the process,

although the reason for a nickel exceedance at this well has not been ascertained. At these concentrations, nickel is not known to be a widespread SPP contaminant, as distinguished by the historical absence of high nickel values in other SPP wells, especially those wells located within the main body of the SPP. The lack of characteristic SPP contaminants, especially nitrate, further clouds the issue. The localized nature of nickel at well 1386, like that found at wells 6486 and 6586, suggests that the high nickel concentrations measured in this well may be caused by sampling artifacts related to the stainless steel composition of the well casing, changes in sampling procedures, and the well geochemical environment.

In FY2000, an evaluation of nickel concentrations at well 1386 will be undertaken, including a reexamination of sampling procedures and a downhole television camera survey of well casing and screen conditions to check for corrosion. In addition, a paired PVC Geoprobe well will be installed next to well 1386 and sampled for metals to confirm the presence or absence of nickel in groundwater at these locations. Reproduceable nickel detections above the Tier II action level and historic M2SD concentration at the proposed new well point will then cause the initiation of a surface water impact evaluation developed to investigate the extent of nickel contamination and determine whether nickel represents a potential threat to the surface water quality of North Walnut Creek.

Selenium is a minor component of the SPP that is often associated with elevated nitrate/nitrite concentrations. The selenium concentrations in well 1786 (Figure 2-48) have trended gradually upward until dropping below historic M2SD concentrations in 1998. Selenium in Well B208289 was detected above the Tier II action level and background M2SD. Because of an insufficient number of values, the historic M2SD contamination is not known, and it was not possible to prepare a trend plot for selenium for this well. Routine monitoring for selenium will continue in this well until a trend direction can be established and evaluated. While selenium has exceeded Tier II action level and historic M2SD concentrations in previous years, it is currently not a reportable contaminant for these two wells based on the concentration levels detected in 1998.

In 1998, manganese concentrations detected in well 3586 (Figure 2-49) were below the historic M2SD and are not considered to be reportable. The manganese concentrations in well B208789 (Figure 2-50) were above the Tier II action level, and reached the historic M2SD concentration of 624 µg/L in the fourth quarter, 1998. Monthly confirmation sampling at this well was started in November 1998 and continued through January 1999. The well B208789 manganese trend plot shows a pronounced steady increase in concentration through 1998, after which the concentration drops to below the Tier II action level concentration in the confirmation samples. The reason for this response is unclear, but does not appear to be related to sampling technique. Routine monitoring will be continued at both wells.

Industrial Area VOC Plume (including IHSS 118.1)

Thirteen Plume Extent wells - 1986, 2186, 6186, 7086, P313589, P314289, P416689, 43392, 10994, 22596, 22696, 22796 and 00197 – are utilized for monitoring groundwater contamination associated with the Industrial Area VOC plume, including IHSS 118.1, a distinctive source of IA VOC contamination. Wells 7086 and 10994 also monitor potential groundwater contamination originating from the Old Landfill located on the hillside below the 400 area building complex north of Woman Creek. As shown on Plate 10, the IA VOC plume spans the middle of the IA in a north-northeast orientation that migrates toward both Woman and North Walnut Creeks. TCE, PCE, and carbon tetrachloride are the primary VOC contaminants; the distribution of which tend to be source-specific and non-uniform. There are no known inorganic or radiological groundwater plumes that coincide with VOC contaminated areas within the IA VOC plume.

Monitoring wells located along the south and east perimeter of the IA VOC plume include 6186, 7086, P313589, P314289, P416689, 43392, 10994, and 00197. No VOCs or water quality parameters above Tier II action levels were detected in any of these wells during 1998. Metals detections above Tier II action levels in these wells consisted of manganese (wells 7086 and P314289), nickel (well P314289), and selenium (well 10994). The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels in wells 7086, and 10994, but below background M2SD levels at all locations, and are thus not considered to be reportable.

Monitoring wells located along the north perimeter of the IA VOC plume include 1986, 2186, 22596, 22696, and 22796. VOC detections above Tier II action levels in these wells consisted entirely of TCE in wells 1986, 22696, and 22796. Wells 1986 and 22796 also contained consistently high manganese detections, including a single value above the historic M2SD concentration in well 1986. Selenium above the Tier II action level and background M2SD was found in well 10994, but not above historic M2SD concentrations. No water quality parameters were detected above Tier II action levels in any of the north IA Plume Extent wells. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels in wells 1986, 2186, and 22796, but below background M2SD levels at all locations, and are thus not considered to be reportable.

The TCE value reported for well 1986 appears to be a spurious result based on the recent below Tier II action level history of this compound presented in Figure 2-51. Considering the fact that previous TCE values in this well have exceeded the upper historic M2SD concentration, the well was kept on a routine monitoring schedule for VOCs rather than initiating a monthly sampling program (RMRS, 1999b). TCE concentrations in wells 22696 and 22796 are presented in Figures 2-52 and 2-53. The TCE concentrations in well 22696, after rising sharply above the Tier II action level in the third quarter of

1998, have fallen to the Tier II action level in a subsequent sample. A declining trend in TCE concentrations is apparent in well 22796. Manganese concentrations in wells 1986, 7086, P314289, and 22796, except for a single value in well 1986 (second quarter of 1998), were below historic M2SD concentrations, and are not considered to be reportable values. Trend plots of manganese concentrations for wells 1986, 7086, and 22796 (Figures 2-54 through 2-56) confirm that the 1998 detections, including the above historic M2SD value in well 1986, do not represent significant increases in concentration over previous monitoring periods. In the case of well P314289, an insufficient number of data points (three) precluded the construction of a manganese trend plot. The same situation exists for nickel at well P314289. Selenium concentrations presented in well 10994 (Figure 2-57) tend to fluctuate about the mean and show no evidence of an increasing trend.

903 Pad/Ryan's Pit VOC Plume

Migration of the 903 Pad/Ryan's Pit VOC plume toward Woman Creek is monitored by Plume Extent wells 23096 and 23196. Plate 10 illustrates the location of these wells in relationship to the distal end of the plume and creek. The plume is mainly composed carbon tetrachloride from the 903 Pad area and TCE from Ryan's Pit. A more complete listing of individual 903 Pad and Ryan's Pit plume contaminants is provided in the discussion of Performance Monitoring and Plume Definition wells presented above.

No VOC or metals contaminants above Tier II action levels were detected in wells 23096 and 23196 during 1998. Nitrate/nitrite was detected once above the Tier II action level and background M2SD in well 23196. No other water quality parameters were detected above Tier II action levels in these wells. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels in well 23096, but below background M2SD levels, and thus do not qualify as reportable values.

Nitrate/nitrite in well 23196 was detected just above the Tier II action level at 10.2 µg/L. Monthly confirmation sampling was initiated in September 1998 and completed in November 1998, with the well being dry during the latter two months. The September 1998 nitrate/nitrite concentration was detected below the Tier II action level. This contaminant was absent above the Tier II action level in all 903 Pad/Ryan's Pit Plume Definition wells, including upgradient well 00491. Nitrate/nitrite was detected once above the Tier II action level in Performance monitoring well 07391, but the crossgradient position of this well relative to well 23196 and the absence of VOC contamination in well 23196 makes it highly unlikely that any hydrologic relationship exists between the two wells. Well 23196 was returned to a routine sampling schedule following the conclusion of monthly sampling.

PU&D Yard Plume

Plume Extent wells P114389, 76992, 00397, and 02197 are utilized for monitoring VOC contamination associated with the PU&D Yard, which forms an elongate plume south of the Present Sanitary Landfill that extends from the PU&D Yard on the west to well 02197 on the east. The primary plume contaminants consist of PCE, TCE, and 1,1,1-trichloroethane. Further discussion of PU&D Yard plume contamination is provided in Section 4.2 of this report.

The only constituent found above Tier II action levels in these wells during 1998 was manganese in well P114389. This constituent had exceeded the historic M2SD concentration in 1997 resulting in a round of monthly confirmation sampling from June through August 1998. As shown in Figure 2-58, manganese concentrations in 1998 initially dropped below the historic M2SD value and have since risen above this benchmark continuing an upward trend begun in 1995. The significance of increasing manganese concentrations at well P114389 is unknown, but does not appear to be related to VOC contamination at the PU&D Yard. Manganese is not a PU&D Yard plume contaminant, nor is the well located downgradient of any IHSS or known contaminant source area. The well was returned to a routine sampling schedule based on the results of monthly sampling (2 out of 3 monthly values were below the historic M2SD) (RMRS, 1998b).

881 Hillside Plume

Wells 4787 and 4887 monitor the extent of the 881 Hillside plume. Well 4787 was dry during both semiannual monitoring visits in 1998. Well 4887 was sampled once in 1998, but only a partial sample suite (VOCs and nitrate/nitrite) was collected because of insufficient water conditions. There were no detections of these constituents above Tier II action levels in this well.

Mound Plume

The Mound Plume is monitored by Plume Extent wells 3586 and 75992. Discussion of above Tier II action level concentrations in these wells is contained above within the Solar Evaporation Pond and East Trenches plume extent subsections of this Section. In summary, vinyl chloride (well 3586), methylene chloride (well 75992), manganese (well 3586), uranium-233/234 and uranium-238 (wells 3586 and 75992), and strontium-89/90 were detected above Tier II action levels in 1998, but below background M2SD or historic M2SD concentrations. These detections do not qualify as reportable values under the data quality objective criteria for Plume Extent wells specified in the IMP.

Building 881 Footing Drain Sump

One Plume Extent well, 5387, monitors discharges associated with the Building 881 Footing Drain Sump (SW13494). According to sample results presented for SW13494 (Table 2-8), PCE is the main

contaminant of concern in sump water at this locality. PCE was not detected at well 5387 during the 1998 sample visits; however, methylene chloride was detected once above the Tier II action level and historic M2SD benchmark (Figure 2-59). This constitutes a reportable value, but is considered to be suspect because of methylene chloride's reputation as a common laboratory contaminant. The uranium isotopes U-233/234 and U-238 were detected at above Tier II action levels, but below background M2SD levels, and thus do not qualify as reportable values. No metals or water quality constituents were detected above Tier II action levels.

2.3.3 Upgradient Versus Downgradient Well Comparisons

This section contains a discussion and evaluation of RCRA monitoring wells only. D&D monitoring well results are presented by building number in Section 5.0.

RCRA Wells

The Present Sanitary Landfill at RFETS currently operates under CDPHE and EPA guidelines for solid waste disposal sites and facilities. The current groundwater monitoring program was instituted in accordance with the Rocky Flats Cleanup Agreement (RFCA, 1996), and further defined for RCRA units in the IMP. RCRA groundwater monitoring is conducted to detect potential excursions of contamination beyond an established point of compliance based on comparisons of upgradient to downgradient groundwater quality. Under the IMP, if significant impacts to groundwater quality are detected in downgradient RCRA wells and contaminant concentrations are observed to increase with time, then the results are reported to EPA and CDPHE and an investigation into possible causes is initiated. Special attention is given to groundwater contaminants listed in the Action Levels and Standards Framework for Surface Water, Ground Water, and Soils document (RFCA, 1996, Attachment 5), which if exceeded, trigger an evaluation, remedial action, and/or management action. Non-ALF constituents, such as the major cation metals sodium, potassium, calcium, and magnesium, are not reportable under RFCA, and are, therefore, not emphasized in this section. Plate 1 illustrates the location of existing RCRA wells used for monitoring groundwater quality at the Present Sanitary Landfill.

Recent changes to the site groundwater monitoring program are outlined in the IMP (K-H, 1998a). This plan specifies the monitoring and reporting requirements for the Present Sanitary Landfill, including well identification, sampling frequency, analytical requirements, and reporting. Operating procedures are used to specify techniques for sample collection, preservation, shipment, and chain-of-custody control.

For the reporting period, upgradient wells 5887, 70193, 70393, and 70493, and downgradient wells 4087, 52894, and B206989, were sampled on a quarterly basis (January-March, April-June, July-September, and October-December) to determine compliance with RFCA, as set forth in the IMP. Table 2-10 summarizes sampling activities and shows the hydrostratigraphic unit monitored and material screened for all wells sampled in and near the Present Sanitary Landfill in 1998. The limited number and position of these wells makes it infeasible to construct potentiometric surface maps and concentration isopleth maps, thus current and future reports will only assess impacts to or from the landfill at the upgradient and downgradient landfill boundaries.

Groundwater elevations for active wells were measured quarterly as directed in the IMP (K-H, 1998a). Quarterly groundwater samples were analyzed in accordance with Appendix E-2 of the IMP. The absence of complete analyte suites in most quarters for the downgradient wells listed in Table 2-10 is caused by sample volume limitations imposed by slow recharge and/or thin saturation conditions. The alluvium and weathered bedrock at these localities are frequently dry or thinly saturated partly because the dam for the East Landfill Pond acts as a barrier to alluvial groundwater flow from the west, and partly because evapotranspiration demands consume much of the available shallow groundwater in the gulch during the summer months. For this reason, it is normally not possible to collect complete sample sets for each quarterly sampling period.

The assessment of groundwater chemistry at the Present Sanitary Landfill includes an evaluation of the spatial distribution of groundwater constituents in and around the landfill, and a statistical evaluation of the chemistry of downgradient groundwater with respect to upgradient groundwater, as specified in the IMP. Statistical comparisons between downgradient and upgradient groundwater data were made using the methodology described in the *1995 Annual RCRA Groundwater Monitoring Report* (DOE, 1996a).

Compared to the 1997 well data set, the majority of analytes had sufficient data to perform statistical analyses for 1998 largely resulting from a change from semi-annual to quarterly sampling. The quarterly reports contain the analytical results for groundwater samples collected during 1998 (RMRS, 1998a, 1998b, 1999a, and 1999b).

2.3.3.1 Spatial Distribution of Groundwater Constituents

Upgradient Wells

Currently, four wells (5887, 70193, 70393, and 70493) monitor groundwater chemistry in the UHSU immediately upgradient of the Present Sanitary Landfill. Wells 5887 and 70393 are completed in UHSU

Table 2-10
Well Completion Information and Sampling Summary for Present Sanitary Landfill Wells

Well	Hydro-Stratigraphic Unit	Screened Material	Quarterly Sampling Summary			
			Q1	Q2	Q3	Q4
Upgradient Wells						
5887	UPPER	ALLUVIUM	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U
70193	UPPER	BEDROCK	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U
70393	UPPER	ALLUVIUM	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U
70493	UPPER	BEDROCK	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U	V,W,N,M,T,U
Downgradient Wells						
4087	UPPER	ALLUVIUM	V,W,N,M,T,U	V,W,N,M,T,U	V	Dry
52894	UPPER	ALLUVIUM	Dry	V,N,M,T,U	V,W,N,M,T,U	Dry
B206989	UPPER	BEDROCK	V,N,M,T	V,N,T,U	V,N,T	V,M

V = Volatile organic compounds
W = Water quality parameters
N = Nitrate/Nitrite
M = Metals
T = Tritium
U = Uranium isotopes

alluvial materials and wells 70193 and 70493 are completed in UHSU bedrock. All four wells yielded complete quarterly sample sets for a total of 16 upgradient samples per analyte. The fourth quarter VOC results for wells 5887 and 70393 have been flagged with an "R" data validation qualifier indicating that these results have been rejected and are not reliable.

Concentrations of water quality parameters fall within 0.07 to 0.92 milligrams per liter (mg/L) for fluoride, 0.05 to 5.8 mg/L for nitrate/nitrite, 13 to 48.4 mg/L for sulfate, and 120 to 230 mg/L for TDS. These concentrations occur within the range of background concentrations reported for these analytes in the 1993 *Background Geochemical Characterization Report* (DOE, 1993b). A similar situation exists for all of the metal and radionuclide analytes detected in these wells. Except for the major cations (calcium, magnesium, sodium, potassium, and strontium), the concentrations of most metal analytes are reported below the detection limit or as a detectable contaminant in laboratory blank samples ("B" qualified data). Tritium was not detected in any of the upgradient samples, and the uranium isotopes U-233/234, U-235, and U-238, were essentially detected in only two wells (70393 and 70493).

Alluvial well 70393 yielded consistent detections of five chlorinated VOCs, including TCE (24 µg/L maximum), PCE (8 µg/L maximum), carbon tetrachloride (4 µg/L maximum), 1,1,1-TCA (38 µg/L maximum), and 1,1-DCE (20 µg/L maximum), and single detections of methylene chloride (3 µg/L) and cis-1,2-DCE (0.5 µg/L). Weathered bedrock well 70493, paired with well 70393, contained generally lower concentrations and less consistent detections of the type of VOCs found in the overlying alluvium. VOCs found in this well included methylene chloride (7 µg/L maximum), TCE (1 µg/L maximum), PCE (4 µg/L maximum), 1,1,1-TCA (0.8 µg/L maximum), and a single detection of 1,1,1,2-tetrachloroethane (4 µg/L). Alluvial well 5887 contained single detections of methylene chloride (6 µg/L) and TCE (0.7 µg/L) while weathered bedrock well 70193 contained methylene chloride (19 µg/L maximum) and a single detection of PCE (0.6 µg/L). These results are generally consistent with the results of previous monitoring (DOE, 1998b), which determined that the Property Utilization and Disposal (PU&D) Yard was the source of this contamination. Results for all other VOC constituents monitored in upgradient wells were below detection.

Downgradient Wells

Three wells located east of the East Landfill Pond embankment are used to monitor the chemistry of downgradient groundwater in the UHSU (wells 4087, 52894, and B206989). Well B206989 monitors groundwater in the UHSU bedrock and wells 4087 and 52894 monitor the quality of alluvial groundwater. All of the well locations are consistent with 6 CCR 1007-2, which allows alternate

placement of monitoring wells downgradient of an interim-status facility where existing physical obstacles prevent installation of wells at the boundary.

Downgradient groundwater quality monitored at wells 4087, 52894, and B206989 appear to show that concentrations of fluoride, nitrate/nitrite, sulfate, total dissolved solids, arsenic, cadmium, chromium, lithium, manganese, selenium, strontium, and zinc exceed upgradient concentrations reported for upgradient wells 5887, 70193, 70393, and 70493. Elevated concentrations of the non-hazardous metals sodium, potassium, calcium, and magnesium were also detected in downgradient wells, but have no ALF groundwater action levels and, consequently, are not discussed. Aluminum, cobalt, molybdenum and nickel were found to have no statistically significant differences (at the 1-percent significance level) in upgradient versus downgradient groundwater quality. The uranium isotopes U-233/234, U-235, and U-238 also appear to have elevated activity-concentrations in downgradient wells compared to upgradient wells. Tritium was reported as being undetected in all upgradient and downgradient wells. All other ALF groundwater constituents in downgradient groundwater, including VOCs, were detected at or below upgradient concentration levels.


Trend plots of analytes in downgradient wells that exceed upgradient concentrations are presented in Figures 2-60 through 2-75 per the requirements of the IMP. Concentration trends for analytes with three or more data points tend to be somewhat erratic, but are generally flat or declining, and therefore indicate that landfill groundwater is not currently migrating eastward at increased concentrations past the East Landfill dam. Data sets consisting of one or two data points for some analytes are insufficient for discerning trends and can not be interpreted without additional data. These trends will be reevaluated as more data becomes available from the groundwater monitoring program.

Assuming that groundwater seepage past the dam is appreciable enough to influence downgradient groundwater quality, the elevated concentrations of inorganic analytes in downgradient groundwater can be explained by the evaporative concentration of solutes in pond water in combination with other factors, such as mineral build-up in soils resulting from seasonal desaturation of valley-fill alluvial materials and contributions of more highly mineralized groundwater from the underlying LHSU. Analysis of analyte trends showing concentration increases must account for these conditions in order to differentiate between natural and anthropogenic influences. On the other hand, groundwater VOC contributions to pond water will tend to be lost by volatilization before reaching the downgradient wells.


The elevated concentrations of certain inorganic constituents, specifically nitrate/nitrite (NO_3/NO_2), lithium (Li), and selenium (Se) in well B206989, probably indicate the presence of a non-landfill

Figures 2-60 through 2-75
Trend Plots for Selected Analytes-
Downgradient Wells at the Present Sanitary Landfill


2-60



2-61




2-62




Figures 2-60 through 2-75
Trend Plots for Selected Analytes-
Downgradient Wells at the Present Sanitary Landfill


2-63



2-64




2-65




Figures 2-60 through 2-75
Trend Plots for Selected Analytes-
Downgradient Wells at the Present Sanitary Landfill


2-66



2-67




2-68




104

Figures 2-60 through 2-75
Trend Plots for Selected Analytes-
Downgradient Wells at the Present Sanitary Landfill


2-69



2-70




2-71




Figures 2-60 through 2-75
Trend Plots for Selected Analytes-
Downgradient Wells at the Present Sanitary Landfill


2-72



2-73




2-74



Figures 2-60 through 2-75
Trend Plots for Selected Analytes-
Downgradient Wells at the Present Sanitary Landfill

2-75



contaminant source area that influences downgradient groundwater quality below the landfill pond. This interpretation is supported by the historically low concentration of these analytes in landfill leachate (SW097; mean values = 0.3 mg/L NO₃/NO₂, 40 µg/L Li, and 2 µg/L Se) and landfill pond water (SW098; mean values = 0.093 mg/L NO₃/NO₂ and 77 µg/L Li) (DOE, 1996a, Tables 2-2 and 2-3), and elevated concentration of nitrate/nitrite (mean=143.5 mg/L), lithium (199 µg/L) and selenium (504 µg/L) in samples from UHSU bedrock well B206889, located to the south and upgradient of well B206989. Potential source areas for these contaminants are currently unknown. Regardless of the source of these contaminants, their absence at high concentrations in landfill groundwater and surface water indicate the presence of potential non-landfill interferences in interpreting downgradient weathered bedrock groundwater quality.

2.3.3.2 Statistical Evaluation of Groundwater Constituents

Where possible, analytical data for groundwater monitored upgradient of the Present Sanitary Landfill were compared statistically to analytical data for groundwater sampled from compliance-boundary wells located downgradient of the Present Sanitary Landfill. Results of these comparisons were used to evaluate potential contaminant releases from the regulated unit into the uppermost "aquifer". The comparisons between upgradient and downgradient groundwater quality were made using the statistical methodology discussed in the 1995 Annual RCRA Report (DOE, 1996a). Table 2-11 presents a sampling and detection summary for each groundwater analyte monitored during 1998. Statistical comparisons were not performed for analytes with less than 50-percent quantifiable results or for analytes with less than two quantifiable results. For analytes involving nonparametric analysis, the minimum sample volume requirement of at least two quantifiable results per group was increased to four as recommended by EPA guidance (EPA, 1992b). A sufficient number of samples were collected from upgradient and downgradient well groups to perform statistical comparisons for all analytes with more than 50-percent quantifiable results, except sulfate and total dissolved solids (3 downgradient samples each). Data for volatile organic compounds (except methylene chloride), nine trace metals (arsenic, beryllium, cobalt, lead, mercury, silver, thallium, tin, and vanadium), tritium, and uranium-235 met the sample volume criteria, but non-detections exceeded 50 percent of the data sets, so it was necessary to exclude these compounds from statistical evaluation. Conclusions concerning these analytes are described following the discussion of statistical comparisons.

Table 2-11 Groundwater Sample and Detection Summary for Present Sanitary Landfill Wells

Parameter	Number of Samples			Number of Detections			Percent Detections			Percent Non-Detects
	Upgradient	Down-gradient	Total	Upgradient	Down-gradient	Total	Upgradient	Down-gradient	Total	
Water Quality (mg/L)										
Fluoride	16	3	19	16	3	19	100.0	100.0	100.0	0.0
Nitrate/Nitrite	16	6	22	15	5	20	93.8	83.3	90.9	9.1
Sulfate	16	3	19	16	3	19	100.0	100.0	100.0	0.0
Total Dissolved Solids	16	3	19	16	3	19	100.0	100.0	100.0	0.0
Metals (ug/L)										
Aluminum	16	6	22	15	5	20	93.8	83.3	90.9	9.1
Antimony	16	6	22	9	3	12	56.3	50.0	54.5	45.5
Arsenic	16	6	22	1	4	5	6.3	66.7	22.7	77.3
Barium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Beryllium	16	6	22	2	1	3	12.5	16.7	13.6	86.4
Cadmium	16	6	22	8	5	13	50.0	83.3	59.1	40.9
Calcium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Chromium	16	6	22	12	3	15	75.0	50.0	68.2	31.8
Cobalt	16	6	22	2	3	5	12.5	50.0	22.7	77.3
Copper	16	6	22	13	6	19	81.3	100.0	86.4	13.6
Iron	16	6	22	9	3	12	56.3	50.0	54.5	45.5
Lead	16	6	22	6	2	8	37.5	33.3	36.4	63.6
Lithium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Magnesium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Manganese	16	6	22	15	4	19	93.8	66.7	86.4	13.6
Mercury	16	6	22	1	0	1	6.3	0.0	4.5	95.5
Molybdenum	16	6	22	8	6	14	50.0	100.0	63.6	36.4
Nickel	16	6	22	12	6	18	75.0	100.0	81.8	18.2
Potassium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Selenium	16	6	22	9	6	15	56.3	100.0	68.2	31.8
Silver	16	6	22	4	1	5	25.0	16.7	22.7	77.3
Sodium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Strontium	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Thallium	16	6	22	6	2	8	37.5	33.3	36.4	63.6
Tin	16	6	22	1	2	3	6.3	33.3	13.6	86.4
Vanadium	16	6	22	4	2	6	25.0	33.3	27.3	72.7
Zinc	16	6	22	16	6	22	100.0	100.0	100.0	0.0
Radionuclides (pCi/L)										
Tritium	16	7	23	4	2	6	25.0	28.6	26.1	73.9
U-233/234	16	5	21	7	5	12	43.8	100.0	57.1	42.9
U-235	16	5	21	3	5	8	18.8	100.0	38.1	61.9
U-238	16	5	21	8	5	13	50.0	100.0	61.9	38.1
Volatile Organic Compounds (ug/L)										
1,1,1,2-Tetrachloroethane	16	9	25	1	0	1	6.3	0.0	4.0	96.0
1,1,1-Trichloroethane	16	9	25	6	0	6	37.5	0.0	24.0	76.0
1,1,2,2-Tetrachloroethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,1,2-Trichloroethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,1-Dichloroethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,1-Dichloroethene	16	9	25	4	0	4	25.0	0.0	16.0	84.0
1,1-Dichloropropene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2,3-Trichlorobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2,3-Trichloropropane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2,4-Trichlorobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2,4-Trimethylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0

Table 2-11 Groundwater Sample and Detection Summary for Present Sanitary Landfill Wells

Parameter	Number of Samples			Number of Detections			Percent Detections			Percent Non-Detects
	Upgradient	Down-gradient	Total	Upgradient	Down-gradient	Total	Upgradient	Down-gradient	Total	
1,2-Dibromo-3-chloropropane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2-Dibromoethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2-Dichlorobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2-Dichloroethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,2-Dichloropropane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,3,5-Trimethylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,3-Dichlorobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,3-Dichloropropane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
1,4-Dichlorobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
2,2-Dichloropropane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Benzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Bromobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Bromochloromethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Bromodichloromethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Bromoform	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Bromomethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Carbon Tetrachloride	16	9	25	4	0	4	25.0	0.0	16.0	84.0
Chlorobenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Chloroethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Chloroform	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Chloromethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
cis-1,2-Dichloroethene	16	9	25	1	0	1	6.3	0.0	4.0	96.0
cis-1,3-Dichloropropene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Dibromochloromethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Dibromomethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Dichlorodifluoromethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Ethylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Hexachlorobutadiene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Isopropylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
m/p-Xylene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Methylene Chloride	16	9	25	9	5	14	56.3	55.6	56.0	44.0
Naphthalene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
n-Butylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
n-Propylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
o-Chlorotoluene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
o-Xylene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
p-Chlorotoluene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
p-Isopropyltoluene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
sec-Butylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Styrene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
tert-Butylbenzene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Tetrachloroethene	16	9	25	7	0	7	43.8	0.0	28.0	72.0
Toluene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
trans-1,2-Dichloroethene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
trans-1,3-Dichloropropene	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Trichloroethene	16	9	25	7	0	7	43.8	0.0	28.0	72.0
Trichlorofluoromethane	16	9	25	0	0	0	0.0	0.0	0.0	100.0
Vinyl Chloride	16	9	25	0	0	0	0.0	0.0	0.0	100.0

For analytes with greater than 50-percent quantifiable results, parametric ANOVA or nonparametric Wilcoxon Rank-Sum testing was performed, depending on the percentage of non-detections present in the sample groups and sample distribution characteristics. All UHSU results (alluvial and bedrock) were grouped by analyte into upgradient and downgradient data sets to simplify analyses and provide adequate data to perform statistical testing. This approach is justifiable because all downgradient wells are closely located in a well-defined, narrow drainage way that defines the sole groundwater flow path leading from the landfill. The Wilcoxon Rank-Sum test (also known as the Mann-Whitney U test) was selected to perform nonparametric comparisons in place of the Kruskal-Wallis test based on EPA guidance for statistical evaluations involving two data groups (EPA, 1992b).

Table 2-12 summarizes the results of statistical comparisons for the upgradient and downgradient data groups. Statistically significant differences (at the 1-percent significance level) in upgradient versus downgradient groundwater quality were found for fluoride, cadmium, calcium, lithium, magnesium, molybdenum, potassium, sodium, strontium, U-233/234, and U-238. With the exception of cadmium and molybdenum, these results are similar those reported in previous RCRA reports.

Of the nine trace metals reported with non-detections exceeding 50 percent sample set, only arsenic in well B206989 appears to be elevated above upgradient groundwater concentrations. The elevated concentration of this analyte in well B206989, as also observed for nitrate/nitrite, lithium, and selenium in this well, may signify an association with a contaminant source other than the landfill. The elevated activity-concentration of U-235 in this well compared to the other downgradient wells and upgradient wells could result from either natural sources present within the bedrock, as it occurs within the background range for this isotope (DOE, 1993b; Table D-9), or alternatively, from the unknown source tentatively implicated to explain the elevated concentrations for nitrate/nitrite, lithium, and selenium.

2.4 Discussion of Groundwater Plumes

Plume maps have been updated using 1998 data for composite VOCs (TCE, PCE, vinyl chloride, and carbon tetrachloride) and dissolved nitrate. Groundwater chemistry data extracted from the SWD were used in constructing these maps. All monitoring wells with analytical results for the years 1991 through 1998, regardless of the number of samples collected during that time, were used to produce the plume maps. The maps consist of data compiled from approximately 600 wells. Chemical data were prepared using the methods specified in Section 2.1. The mean concentration of each analyte for each well from 1991 through 1998 was calculated and plotted. Results below the CRDL were identified in the data as

**Table 2-12 Comparative Statistics for Groundwater Analytes with <50 Percent Sample Non-Detections
Present Sanitary Landfill**

Parameter	Percent Non-Defects	Shapiro-Wilk Normality Test			Levene Test			Parametric ANOVA (Single Factor)			Wilcoxon Rank-Sum Test		
		W_s	W_{adj}	$W_{0.05}$	Distribution Type	F_2	F_{L2}	F_{05}	F_{L5}	Significant Difference?	W	Z	Significant Difference?
Water Quality													
Fluoride	0	0.766	0.964	0.901	Log Normal		3.549	4.451	18.841	Yes	N/A	N/A	N/A
Nitrate/Nitrite	9.1	0.488	0.859	0.911	Unknown						35.5	-0.962	No
Sulfate	0	0.455	0.751	0.901	Unknown						*	*	*
TDS	0	0.522	0.693	0.901	Unknown						*	*	*
Metals													
Aluminum	9	0.934	0.884	0.911	Normal	1.377		4.351	2.033	No	N/A	N/A	N/A
Antimony	45.5	N/A	N/A	N/A	Unknown						45	-0.261	No
Barium	0	0.920	0.812	0.911	Normal	11.386		4.351	4.351	N/A	23.5	-1.844	No
Cadmium	40.9	N/A	N/A	N/A	Unknown						80	2.337	Yes
Calcium	0	0.462	0.714	0.911	Unknown						96	3.504	Yes
Chromium	31.8	N/A	N/A	N/A	Unknown						56.5	0.591	No
Copper	13.6	0.818	0.916	0.911	Log Normal		8.103	4.351	N/A	N/A	75	1.957	No
Iron	45.5	N/A	N/A	N/A	Unknown						51.5	0.223	No
Lithium	0	0.501	0.895	0.911	Unknown						96	3.502	Yes
Magnesium	0	0.467	0.742	0.911	Unknown						96	3.503	Yes
Manganese	13.6	0.418	0.818	0.911	Unknown						50	0.111	No
Molybdenum	36.4	N/A	N/A	N/A	Unknown						96	3.525	Yes
Nickel	18.2	N/A	N/A	N/A	Unknown						80	2.325	No
Potassium	0	0.433	0.800	0.911	Unknown						96	3.503	Yes
Selenium	31.8	N/A	N/A	N/A	Unknown						70.5	1.625	No
Sodium	0	0.576	0.750	0.911	Unknown						96	3.502	Yes
Strontium	0	0.453	0.775	0.911	Unknown						96	3.504	Yes
Zinc	0	0.733	0.902	0.911	Unknown						62	0.996	No
Radionuclides													
U-233/234	42.8	N/A	N/A	N/A	Unknown						80	3.262	Yes
U-238	38.1	N/A	N/A	N/A	Unknown						80	3.263	Yes
VOCs													
Methylene Chloride	44.0	N/A	N/A	N/A	Unknown						60	-0.720	No

* Insufficient number of downgradient sample results to perform analysis

N/A = not applicable

¹ Significant difference in downgradient to upgradient sample groups shown in bold typeface

“U” qualified. U-qualified data were given values of one-half the reported CRDL. VOCs have action levels low enough that the variation in CRDLs from one laboratory to another has caused some averages from wells with predominantly non-detect results to be above the Tier II action levels. The CRDLs exhibited the greatest variation for VOCs as a result of sample dilution reruns. For VOCs only, any CRDLs above 1 microgram per liter ($\mu\text{g/L}$) was adjusted to 1 $\mu\text{g/L}$, and the average was calculated using one-half the adjusted CRDL.

It should be noted that the term “plume map” is used here to delineate potential areas of elevated contaminant concentrations derived from each data set. In fact the map for a particular analyte may not show a plume at all, but rather just the distribution of the historical average chemical data results for that analyte. Because of assumptions made during data reduction, it is expected that these maps may contain a limited number of false values above Tier II action levels. Plume boundaries, where drawn, represent the best estimates of the spatial distribution of concentrations of selected chemicals of concern in groundwater at RFETS.

2.4.1 Volatile Organic Compound Plumes

Plate 10 presents a composite of four common VOC contaminants – TCE, PCE, vinyl chloride and carbon tetrachloride – which typify the type of VOC contamination found in general at RFETS. The map shows the estimated extent of Tier I (200 $\mu\text{g/L}$ for vinyl chloride and 500 $\mu\text{g/L}$ for TCE, PCE, and carbon tetrachloride) and Tier II (2 $\mu\text{g/L}$ for vinyl chloride and 5 $\mu\text{g/L}$ for TCE, PCE, and carbon tetrachloride) groundwater VOC contamination based on data collected during the period 1991 to 1998. Individual plume maps for these VOC contaminants were presented in the 1997 Annual RFCA Groundwater Monitoring Report (DOE, 1998), and should be consulted when examining VOC associations with specific source areas.

The VOC plume map has been updated from those published in previous Annual RFCA Groundwater Monitoring Reports (RMRS, 1997b and 1998) to reflect new data collected in 1998. The main area of change involved extending the Tier I and Tier II boundaries from the IA plume westward toward the unnamed drainage that separates the 700 area from Building 371/374. This change incorporates new VOC data collected from well points installed in 1998 for the northern IA plume evaluation (see Section 4.1). The Mound plume boundary was also broadened slightly to account for above Tier I action level TCE concentrations detected at well 00897. Refinements to the Tier II boundary were made at the leading edge of the 903 Pad/Ryan’s Pit plume near the South Interceptor Ditch at Pond C-1, and along the east boundary of the IA plume near Building 779. The 903 Pad/Ryan’s Pit plume boundary was redrawn

to more accurately reflect the extent of VOCs found in the 1998 well points, which resulted in a retraction away from wells 2987 and 23196. The absence of VOCs above Tier II action levels in the Building 779 D&D wells (02297, 02397, and 02497) caused the IA Tier II boundary to be redrawn west of Building 779, thus resulting in a minor retraction of the boundary at Buildings 707 and 777. A small area of Tier II VOC contamination centered around D&D monitoring well 10498, located downgradient of Building 123, was also added to the map.

In 1999, an evaluation of the eastern boundary of the IA VOC plume was implemented to better define the extent of VOC contamination east of the Eighth Street utility corridor and upgradient of Buildings 707, 776, 778, 883, and 865. The proposed field investigation involves the installation and sampling of 15 small diameter wells along Eighth Street between Building 881 on the south and Building 771 on the north. Details of this investigation are specified in RMRS (1999c). The results of this investigation will be reported in the 1999 Annual RFCA Groundwater Monitoring Report.

2.4.2 Nitrate Plumes

The nitrate plume map has been updated slightly from those published in previous Annual RFCA Groundwater Monitoring Reports (RMRS, 1997b and 1998) to reflect new data collected in 1998. Plate 7 shows the estimated extent of Tier I (1,000 mg/L) and Tier II (10 mg/L) groundwater nitrate contamination based on data collected from the period 1991 to 1998. For reference, the background concentration for nitrate in groundwater at RFETS is 4.7 mg/L (DOE, 1993b).

Plate 7 illustrates one major nitrate plume (Solar Ponds Plume) and four minor areas. The Solar Ponds Plume (SPP) is located in the northeast portion of the PA and extends from the Solar Evaporation Ponds to the northeast towards North Walnut Creek. All values of nitrate over the Tier I action level are associated with this plume. The four minor areas of nitrate concentration above the Tier II action level are associated with the Old Landfill, the 903 and 904 Pads, IHSS 119.1 on the 881 Hillside, and an area west of the Present Sanitary Landfill Pond. Scattered occurrences of nitrate above the Tier II action level are also found at well 08391 (444 mg/L), located approximately 1200 feet east of the IA; wells 3386 (12.4 mg/L) and 22896 (12.1 mg/L) in the PA; well 00597 (10.1 mg/L) at the south perimeter of the Present Sanitary Landfill; and well 10498 (26 mg/L) downgradient of Building 123. The only significant change in nitrate plume extent involved extending the SPP Tier II boundary westward to encompass Buildings 774 and 779, and the eastern one third of Building 777. This change is based on consideration of historical nitrate data from building foundation drains available for PA Buildings 707, 771, 774, and 779 (DOE, 1994a) and new nitrate data from North IA well points installed in 1998 (see Section 4.1).

3.0 GROUNDWATER FLOW CONDITIONS DURING 1998

Groundwater level data collected throughout calendar year 1998 were reviewed to determine whether significant changes in groundwater flow direction, flow velocity, and quantity have occurred to the upper hydrostratigraphic unit since 1996 and previous years. This review included evaluations of semiannual potentiometric surface maps, quarterly well pair linear flow velocity calculations, selected well hydrographs, and water level change maps. Comparison of the 1998 data to historical potentiometric surface maps (from previous annual reports) and historical water level trends presented in the individual well hydrographs provide a framework for identifying the type of potentiometric configurations, seasonal fluctuations, and long-term trends typically associated with pre-1996 plant operations. The 1996 data set, because it is the last year before the commencement of D&D activities (and to some extent the 1997 data set) comprises a sitewide baseline that will be used for assessing annual changes to the groundwater flow system during the remaining years of plant closure and post-closure monitoring.

3.1 Potentiometric Surface Maps

Groundwater potentiometric surface maps (Plates 2 and 3) were constructed from water level data collected during the second and fourth quarters (April and October data, respectively) of 1998 for the unconsolidated surficial deposits and selected weathered bedrock components comprising the UHSU. These maps provide information on groundwater flow direction and saturated extent that were used in the selection of well pairs for velocity calculations and definition of plume extent and movement. For map construction, it was assumed that well construction details, borehole logs, and water level measurements were accurate. When the measured depth to water was below the bottom of the well screen, the well was assumed to be dry.

Maps constructed for the UHSU were based entirely on data from fully penetrating wells screened in surficial deposits thought to be representative of regional shallow groundwater flow conditions. For this reason, wells completed in perched alluvial groundwater zones, such as wells 50494 and 51594 located west of the IA, were not utilized for construction of potentiometric contours. Information on unsaturated areas from previous UHSU potentiometric maps, particularly the 1993 maps, were used in the construction of the second and fourth quarter 1998 maps. Areas previously labeled as unsaturated were evaluated and reconfigured utilizing new monitoring well coverage (i.e., IA IM/IRA, D&D wells) and recent water level data. Shaded, non-contoured areas of the maps indicate areas where well coverage is absent. Conceptual potentiometric contour refinements were made in areas with new well coverage such as the north Industrial Area.

The configuration of the potentiometric surfaces for the second and fourth quarters of 1998 generally matches the configurations depicted for earlier quarterly maps.

Plant operations have potentially impacted groundwater flow patterns in areas where potentiometric contours appear to deviate from topographic or bedrock topographic configurations. For example, a prominent and persistent eastward distention of the 6,000 through 6,040-foot contour lines in the west IA deviates significantly from the pattern expected from the surface topography. The coincidence of this broad, mound-like feature within an industrialized portion of the Site suggests that a greater amount of recharge is occurring in this area compared to background areas with similar geologic conditions situated to the north and south. Likewise, the convergence and/or redirection of potentiometric contour lines in the immediate vicinity of Buildings 371, 771, 881, 865, and 997 suggest that foundation drains have localized impacts on groundwater flow in the IA. Unsaturated areas shown on the 1998 maps were generally less extensive than drawn on the 1996 maps (which were a reflection of the 1993 maps). This condition probably reflects the effects of higher than average precipitation at the site for the period of 1995 through 1997, in addition to improved sitewide well coverage.

3.2 Average Linear Flow Velocities

Average linear groundwater flow velocities (seepage velocities) were calculated for 24 UHSU well pairs within the Industrial Area and perimeter based on flow direction considerations derived from the 1998 potentiometric surface maps. The Darcy equation was used to calculate the seepage velocity (v):

$$v = \frac{K}{n} (dh / dl)$$

where:

K = hydraulic conductivity

n = effective porosity

dh/dl = hydraulic gradient

Values for hydraulic gradient were calculated from quarterly water level measurements made between well pairs located along a groundwater pathway. These well pairs were chosen on the basis of their perpendicular orientation to potentiometric contour lines. The data is not complete based on the fact that both well pairs are not necessarily visited for a water level measurement each quarter. Hydraulic conductivity values used for velocity calculations were derived from the geometric mean values reported

for the Rocky Flats Alluvium, colluvium, and Arapahoe Formation sandstone (No. 1 Sandstone) presented in Table G-2 of EG&G (1995b). For each well pair, the K value chosen for the calculation was based on the predominant lithologic unit comprising the flow path between the wells. In the absence of measured values of n, a conservative value of 0.1 is assumed based on its predominant usage in previous velocity calculations performed at RFETS.

Groundwater flow velocities can be used as estimates of the migration rates for conservative (i.e., non-reactive) groundwater chemical constituents. Because they do not consider the effects of dispersion and chemical reactions (e.g., volatilization, biodegradation, dissolution/precipitation, and adsorption) on the concentrations of constituents along a flow path, seepage velocities approximate only the unattenuated rate of migration for dissolved constituents in groundwater. Attenuated, volatile, biodegradable, or redox-sensitive species will likely exhibit migration rates slower than the average linear velocity of groundwater flow.

Large-scale changes in the hydraulic gradient distribution caused by reconfiguration of the groundwater recharge and discharge regime during plant closure have the potential to impact groundwater flow directions and velocities which, in turn, can affect plume concentration, configuration, and movement. Although actual linear flow velocities at any given well pair are not known with certainty, changes in relative flow velocities, combined with potentiometric mapping and hydrograph analysis, can provide some insight into plume dynamics and movement. Linear flow velocity calculations are sensitive only to the magnitude and direction of the hydraulic gradient, assuming that the assigned values of K and n are kept constant. Temporal analysis of relative linear flow velocities using 1996 as a baseline year is expected to compliment the other available assessment tools (potentiometric and water level change maps, hydrographs, plume extent maps, etc.) in monitoring contaminant plume migration toward surface water.

As shown in Table 3-1, the calculated 1998 groundwater flow velocities ranged from approximately 16 feet per year (ft/yr) between well pair P419689/P416889, located in the IA, to approximately 475 ft/yr. between well pair 3687/60295, located in the East Trenches area. Linear flow velocities below 80 ft/yr tend to be associated with the Rocky Flats Alluvium while linear flow velocities above 80 ft/yr tend to be associated with colluvial (hillslope) material. The high value of 477 ft/yr, calculated for the fourth quarter of 1998 for well pair 3687/60296, is associated with the Arapahoe No. 1 Sandstone, which discharges to the hillside above South Walnut Creek.

“U” qualified. U-qualified data were given values of one-half the reported CRDL. VOCs have action levels low enough that the variation in CRDLs from one laboratory to another has caused some averages from wells with predominantly non-detect results to be above the Tier II action levels. The CRDLs exhibited the greatest variation for VOCs as a result of sample dilution reruns. For VOCs only, any CRDLs above 1 microgram per liter ($\mu\text{g/L}$) was adjusted to 1 $\mu\text{g/L}$, and the average was calculated using one-half the adjusted CRDL.

It should be noted that the term “plume map” is used here to delineate potential areas of elevated contaminant concentrations derived from each data set. In fact the map for a particular analyte may not show a plume at all, but rather just the distribution of the historical average chemical data results for that analyte. Because of assumptions made during data reduction, it is expected that these maps may contain a limited number of false values above Tier II action levels. Plume boundaries, where drawn, represent the best estimates of the spatial distribution of concentrations of selected chemicals of concern in groundwater at RFETS.

2.4.1 Volatile Organic Compound Plumes

Plate 10 presents a composite of four common VOC contaminants – TCE, PCE, vinyl chloride and carbon tetrachloride – which typify the type of VOC contamination found in general at RFETS. The map shows the estimated extent of Tier I (200 $\mu\text{g/L}$ for vinyl chloride and 500 $\mu\text{g/L}$ for TCE, PCE, and carbon tetrachloride) and Tier II (2 $\mu\text{g/L}$ for vinyl chloride and 5 $\mu\text{g/L}$ for TCE, PCE, and carbon tetrachloride) groundwater VOC contamination based on data collected during the period 1991 to 1998. Individual plume maps for these VOC contaminants were presented in the 1997 Annual RFCA Groundwater Monitoring Report (DOE, 1998), and should be consulted when examining VOC associations with specific source areas.

The VOC plume map has been updated from those published in previous Annual RFCA Groundwater Monitoring Reports (RMRS, 1997b and 1998) to reflect new data collected in 1998. The main area of change involved extending the Tier I and Tier II boundaries from the IA plume westward toward the unnamed drainage that separates the 700 area from Building 371/374. This change incorporates new VOC data collected from well points installed in 1998 for the northern IA plume evaluation (see Section 4.1). The Mound plume boundary was also broadened slightly to account for above Tier I action level TCE concentrations detected at well 00897. Refinements to the Tier II boundary were made at the leading edge of the 903 Pad/Ryan’s Pit plume near the South Interceptor Ditch at Pond C-1, and along the east boundary of the IA plume near Building 779. The 903 Pad/Ryan’s Pit plume boundary was redrawn

to more accurately reflect the extent of VOCs found in the 1998 well points, which resulted in a retraction away from wells 2987 and 23196. The absence of VOCs above Tier II action levels in the Building 779 D&D wells (02297, 02397, and 02497) caused the IA Tier II boundary to be redrawn west of Building 779, thus resulting in a minor retraction of the boundary at Buildings 707 and 777. A small area of Tier II VOC contamination centered around D&D monitoring well 10498, located downgradient of Building 123, was also added to the map.

In 1999, an evaluation of the eastern boundary of the IA VOC plume was implemented to better define the extent of VOC contamination east of the Eighth Street utility corridor and upgradient of Buildings 707, 776, 778, 883, and 865. The proposed field investigation involves the installation and sampling of 15 small diameter wells along Eighth Street between Building 881 on the south and Building 771 on the north. Details of this investigation are specified in RMRS (1999c). The results of this investigation will be reported in the 1999 Annual RFCA Groundwater Monitoring Report .

2.4.2 Nitrate Plumes

The nitrate plume map has been updated slightly from those published in previous Annual RFCA Groundwater Monitoring Reports (RMRS, 1997b and 1998) to reflect new data collected in 1998. Plate 7 shows the estimated extent of Tier I (1,000 mg/L) and Tier II (10 mg/L) groundwater nitrate contamination based on data collected from the period 1991 to 1998. For reference, the background concentration for nitrate in groundwater at RFETS is 4.7 mg/L (DOE, 1993b).

Plate 7 illustrates one major nitrate plume (Solar Ponds Plume) and four minor areas. The Solar Ponds Plume (SPP) is located in the northeast portion of the PA and extends from the Solar Evaporation Ponds to the northeast towards North Walnut Creek. All values of nitrate over the Tier I action level are associated with this plume. The four minor areas of nitrate concentration above the Tier II action level are associated with the Old Landfill, the 903 and 904 Pads, IHSS 119.1 on the 881 Hillside, and an area west of the Present Sanitary Landfill Pond. Scattered occurrences of nitrate above the Tier II action level are also found at well 08391 (444 mg/L), located approximately 1200 feet east of the IA; wells 3386 (12.4 mg/L) and 22896 (12.1 mg/L) in the PA; well 00597 (10.1 mg/L) at the south perimeter of the Present Sanitary Landfill; and well 10498 (26 mg/L) downgradient of Building 123. The only significant change in nitrate plume extent involved extending the SPP Tier II boundary westward to encompass Buildings 774 and 779, and the eastern one third of Building 777. This change is based on consideration of historical nitrate data from building foundation drains available for PA Buildings 707, 771, 774, and 779 (DOE, 1994a) and new nitrate data from North IA well points installed in 1998 (see Section 4.1).

3.0 GROUNDWATER FLOW CONDITIONS DURING 1998

Groundwater level data collected throughout calendar year 1998 were reviewed to determine whether significant changes in groundwater flow direction, flow velocity, and quantity have occurred to the upper hydrostratigraphic unit since 1996 and previous years. This review included evaluations of semiannual potentiometric surface maps, quarterly well pair linear flow velocity calculations, selected well hydrographs, and water level change maps. Comparison of the 1998 data to historical potentiometric surface maps (from previous annual reports) and historical water level trends presented in the individual well hydrographs provide a framework for identifying the type of potentiometric configurations, seasonal fluctuations, and long-term trends typically associated with pre-1996 plant operations. The 1996 data set, because it is the last year before the commencement of D&D activities (and to some extent the 1997 data set) comprises a sitewide baseline that will be used for assessing annual changes to the groundwater flow system during the remaining years of plant closure and post-closure monitoring.

3.1 Potentiometric Surface Maps

Groundwater potentiometric surface maps (Plates 2 and 3) were constructed from water level data collected during the second and fourth quarters (April and October data, respectively) of 1998 for the unconsolidated surficial deposits and selected weathered bedrock components comprising the UHSU. These maps provide information on groundwater flow direction and saturated extent that were used in the selection of well pairs for velocity calculations and definition of plume extent and movement. For map construction, it was assumed that well construction details, borehole logs, and water level measurements were accurate. When the measured depth to water was below the bottom of the well screen, the well was assumed to be dry.

Maps constructed for the UHSU were based entirely on data from fully penetrating wells screened in surficial deposits thought to be representative of regional shallow groundwater flow conditions. For this reason, wells completed in perched alluvial groundwater zones, such as wells 50494 and 51594 located west of the IA, were not utilized for construction of potentiometric contours. Information on unsaturated areas from previous UHSU potentiometric maps, particularly the 1993 maps, were used in the construction of the second and fourth quarter 1998 maps. Areas previously labeled as unsaturated were evaluated and reconfigured utilizing new monitoring well coverage (i.e., IA IM/IRA, D&D wells) and recent water level data. Shaded, non-contoured areas of the maps indicate areas where well coverage is absent. Conceptual potentiometric contour refinements were made in areas with new well coverage such as the north Industrial Area.

The configuration of the potentiometric surfaces for the second and fourth quarters of 1998 generally matches the configurations depicted for earlier quarterly maps.

Plant operations have potentially impacted groundwater flow patterns in areas where potentiometric contours appear to deviate from topographic or bedrock topographic configurations. For example, a prominent and persistent eastward distention of the 6,000 through 6,040-foot contour lines in the west IA deviates significantly from the pattern expected from the surface topography. The coincidence of this broad, mound-like feature within an industrialized portion of the Site suggests that a greater amount of recharge is occurring in this area compared to background areas with similar geologic conditions situated to the north and south. Likewise, the convergence and/or redirection of potentiometric contour lines in the immediate vicinity of Buildings 371, 771, 881, 865, and 997 suggest that foundation drains have localized impacts on groundwater flow in the IA. Unsaturated areas shown on the 1998 maps were generally less extensive than drawn on the 1996 maps (which were a reflection of the 1993 maps). This condition probably reflects the effects of higher than average precipitation at the site for the period of 1995 through 1997, in addition to improved sitewide well coverage.

3.2 Average Linear Flow Velocities

Average linear groundwater flow velocities (seepage velocities) were calculated for 24 UHSU well pairs within the Industrial Area and perimeter based on flow direction considerations derived from the 1998 potentiometric surface maps. The Darcy equation was used to calculate the seepage velocity (v):

$$v = \frac{K}{n} (dh / dl)$$

where:

K = hydraulic conductivity

n = effective porosity

dh/dl = hydraulic gradient

Values for hydraulic gradient were calculated from quarterly water level measurements made between well pairs located along a groundwater pathway. These well pairs were chosen on the basis of their perpendicular orientation to potentiometric contour lines. The data is not complete based on the fact that both well pairs are not necessarily visited for a water level measurement each quarter. Hydraulic conductivity values used for velocity calculations were derived from the geometric mean values reported

for the Rocky Flats Alluvium, colluvium, and Arapahoe Formation sandstone (No. 1 Sandstone) presented in Table G-2 of EG&G (1995b). For each well pair, the K value chosen for the calculation was based on the predominant lithologic unit comprising the flow path between the wells. In the absence of measured values of n, a conservative value of 0.1 is assumed based on its predominant usage in previous velocity calculations performed at RFETS.

Groundwater flow velocities can be used as estimates of the migration rates for conservative (i.e., non-reactive) groundwater chemical constituents. Because they do not consider the effects of dispersion and chemical reactions (e.g., volatilization, biodegradation, dissolution/precipitation, and adsorption) on the concentrations of constituents along a flow path, seepage velocities approximate only the unattenuated rate of migration for dissolved constituents in groundwater. Attenuated, volatile, biodegradable, or redox-sensitive species will likely exhibit migration rates slower than the average linear velocity of groundwater flow.

Large-scale changes in the hydraulic gradient distribution caused by reconfiguration of the groundwater recharge and discharge regime during plant closure have the potential to impact groundwater flow directions and velocities which, in turn, can affect plume concentration, configuration, and movement. Although actual linear flow velocities at any given well pair are not known with certainty, changes in relative flow velocities, combined with potentiometric mapping and hydrograph analysis, can provide some insight into plume dynamics and movement. Linear flow velocity calculations are sensitive only to the magnitude and direction of the hydraulic gradient, assuming that the assigned values of K and n are kept constant. Temporal analysis of relative linear flow velocities using 1996 as a baseline year is expected to compliment the other available assessment tools (potentiometric and water level change maps, hydrographs, plume extent maps, etc.) in monitoring contaminant plume migration toward surface water.

As shown in Table 3-1, the calculated 1998 groundwater flow velocities ranged from approximately 16 feet per year (ft/yr) between well pair P419689/P416889, located in the IA, to approximately 475 ft/yr. between well pair 3687/60295, located in the East Trenches area. Linear flow velocities below 80 ft/yr tend to be associated with the Rocky Flats Alluvium while linear flow velocities above 80 ft/yr tend to be associated with colluvial (hillslope) material. The high value of 477 ft/yr, calculated for the fourth quarter of 1998 for well pair 3687/60296, is associated with the Arapahoe No. 1 Sandstone, which discharges to the hillside above South Walnut Creek.

Table 3-1
Average Linear Flow Velocities for the Industrial Area and Vicinity

WELL PAIR	AREA	1998 QTR	dh/dl (gradient)	K (cm/sec)	n_e	v (cm/sec)	v (ft/yr)
P416289 / P416689	Industrial Area	1	0.0322	2.10E-04	0.1	6.76E-05	69.96
		2	0.0175	2.10E-04	0.1	3.68E-05	38.02
		3	N/D	2.10E-04	0.1	N/D	N/D
		4	0.0287	2.10E-04	0.1	6.03E-05	62.36
P419689 / P416889	Industrial Area	1	0.0077	2.10E-04	0.1	1.62E-05	16.73
		2	0.0124	2.10E-04	0.1	2.60E-05	26.94
		3	0.0072	2.10E-04	0.1	1.51E-05	15.64
		4	N/D	2.10E-04	0.1	N/D	N/D
P314289 / 10492	Industrial Area / S. Buffer	1	0.1261	9.33E-05	0.1	1.18E-04	121.73
		2	N/D	9.33E-05	0.1	N/D	N/D
		3	N/D	9.33E-05	0.1	N/D	N/D
		4	N/D	9.33E-05	0.1	N/D	N/D
5387 / 00797	881 Hillside	1	0.1920	9.33E-05	0.1	1.79E-04	185.34
		2	0.2121	9.33E-05	0.1	1.98E-04	204.75
		3	0.1610	9.33E-05	0.1	1.50E-04	155.42
		4	0.1709	9.33E-05	0.1	1.59E-04	164.97
34791 / 6386	SE Buffer	1	0.1915	9.33E-05	0.1	1.79E-04	184.86
		2	0.1950	9.33E-05	0.1	1.82E-04	188.24
		3	N/D	9.33E-05	0.1	N/D	N/D
		4	0.1868	9.33E-05	0.1	1.74E-04	180.32
07291 / 07391	903 Pad	1	0.0758	2.10E-04	0.1	1.59E-04	164.69
		2	0.0836	2.10E-04	0.1	1.76E-04	181.64
		3	0.0780	2.10E-04	0.1	1.64E-04	169.48
		4	N/D	2.10E-04	0.1	N/D	N/D
00491 / 23196	SE Buffer	1	0.1623	9.33E-05	0.1	1.51E-04	156.67
		2	0.1686	9.33E-05	0.1	1.57E-04	162.75
		3	0.1662	9.33E-05	0.1	1.55E-04	160.44
		4	N/D	9.33E-05	0.1	N/D	N/D
04591 / 10194	903 Pad	1	0.0124	2.10E-04	0.1	2.60E-05	26.94
		2	0.0117	2.10E-04	0.1	2.46E-05	25.42
		3	0.0088	2.10E-04	0.1	1.85E-05	19.12
		4	N/D	2.10E-04	0.1	N/D	N/D
05291 / 05091	East Trenches	1	0.0221	2.10E-04	0.1	4.64E-05	48.02
		2	0.0219	2.10E-04	0.1	4.60E-05	47.58
		3	N/D	2.10E-04	0.1	N/D	N/D
		4	N/D	2.10E-04	0.1	N/D	N/D
05391/06091	East Trenches	1	0.0175	2.10E-04	0.1	3.68E-05	38.02
		2	0.0180	2.10E-04	0.1	3.78E-05	39.11
		3	0.0161	2.10E-04	0.1	3.38E-05	34.98
		4	0.0142	2.10E-04	0.1	2.98E-05	30.85
4286/20291	East Trenches	1	0.0146	2.10E-04	0.1	3.07E-05	31.72
		2	0.0246	2.10E-04	0.1	5.17E-05	53.45
		3	0.0219	2.10E-04	0.1	4.60E-05	47.58
		4	0.0206	2.10E-04	0.1	4.33E-05	44.76
3687/60295	East Trenches	1	0.0573	7.88E-04	0.1	4.52E-04	467.17
		2	0.0527	7.88E-04	0.1	4.15E-04	429.66
		3	N/D	7.88E-04	0.1	N/D	N/D
		4	0.0585	7.88E-04	0.1	4.61E-04	476.95
00191/13491	903 Pad	1	0.0172	2.10E-04	0.1	3.61E-05	37.37
		2	0.0312	2.10E-04	0.1	6.55E-05	67.79
		3	N/D	2.10E-04	0.1	N/D	N/D

Table 3-1
Average Linear Flow Velocities for the Industrial Area and Vicinity

WELL PAIR	AREA	1998 QTR	dh/dl (gradient)	K (cm/sec)	n _e	v (cm/sec)	v (ft/yr)
1987/3586	Mound	4	N/D	2.10E-04	0.1	N/D	N/D
		1	0.1003	9.33E-05	0.1	9.36E-05	96.82
		2	0.1030	9.33E-05	0.1	9.61E-05	99.43
		3	0.0981	9.33E-05	0.1	9.15E-05	94.70
05293 / 3386	Solar Pond	4	N/D	9.33E-05	0.1	N/D	N/D
		1	0.0546	2.10E-04	0.1	1.15E-04	118.63
		2	0.0527	2.10E-04	0.1	1.11E-04	114.50
		3	0.0521	2.10E-04	0.1	1.09E-04	113.20
P218389 / B208089	Solar Pond	4	N/D	2.10E-04	0.1	N/D	N/D
		1	0.0509	9.33E-05	0.1	4.75E-05	49.14
		2	0.0532	9.33E-05	0.1	4.96E-05	51.36
		3	0.0528	9.33E-05	0.1	4.93E-05	50.97
2286 / 45793	Solar Pond	4	0.0507	9.33E-05	0.1	4.73E-05	48.94
		1	Dry	2.10E-04	0.1	N/D	N/D
		2	0.0622	2.10E-04	0.1	1.31E-04	135.15
		3	N/D	2.10E-04	0.1	N/D	N/D
1986 / 77492	Solar Pond	4	Dry	2.10E-04	0.1	N/D	N/D
		1	0.0261	9.33E-05	0.1	2.44E-05	25.19
		2	0.0250	9.33E-05	0.1	2.33E-05	24.13
		3	0.0203	9.33E-05	0.1	1.89E-05	19.60
P114689 / 22896	Industrial Area / PA	4	N/D	9.33E-05	0.1	N/D	N/D
		1	0.0267	2.10E-04	0.1	5.61E-05	58.01
		2	0.0225	2.10E-04	0.1	4.73E-05	48.89
		3	N/D	2.10E-04	0.1	N/D	N/D
P215789 / P218089	Industrial Area / PA	4	0.0221	2.10E-04	0.1	4.64E-05	48.02
		1	0.0166	2.10E-04	0.1	3.49E-05	36.07
		2	0.0080	2.10E-04	0.1	1.68E-05	17.38
		3	N/D	2.10E-04	0.1	N/D	N/D
P313489 / 6186	Industrial Area	4	0.0073	2.10E-04	0.1	1.53E-05	15.86
		1	0.0119	2.10E-04	0.1	2.50E-05	25.86
		2	0.0152	2.10E-04	0.1	3.19E-05	33.03
		3	N/D	2.10E-04	0.1	N/D	N/D
4486 / P115689	Industrial Area	4	0.0098	2.10E-04	0.1	2.06E-05	21.29
		1	0.0196	2.10E-04	0.1	4.12E-05	42.59
		2	0.0162	2.10E-04	0.1	3.40E-05	35.20
		3	N/D	2.10E-04	0.1	N/D	N/D
P415989 / P115489	Industrial Area	4	0.0227	2.10E-04	0.1	4.77E-05	49.32
		1	0.0209	2.10E-04	0.1	4.39E-05	45.41
		2	0.0212	2.10E-04	0.1	4.45E-05	46.06
		3	N/D	2.10E-04	0.1	N/D	N/D
P115089 / P119389	Industrial Area / PA	4	N/D	2.10E-04	0.1	N/D	N/D
		1	0.0229	2.10E-04	0.1	4.81E-05	49.76
		2	0.0292	2.10E-04	0.1	6.13E-05	63.44
		3	0.0225	2.10E-04	0.1	4.73E-05	48.89
		4	N/D	2.10E-04	0.1	N/D	N/D

Notes: DRY indicates at least one well was dry for the quarter.

N/D indicates no data for at least one well for the quarter.

Linear flow velocity data from 1998 are more comprehensive than for 1996. Generally, water level data were collected for more quarters per well pair in 1998 compared to 1996. Water level data for many well pairs were reported for only one quarter in 1996. For well pairs that had more than one quarter of data for both years, the velocities generally are less consistent (more variant) from quarter to quarter during 1998 than for 1996. This is a response to moderate change in hydraulic gradient from quarter to quarter, and may be a result of the amount and distribution of precipitation with respect to time.

In general, velocities for the 24 well pairs vary by less than 25 percent when comparing the same quarters from 1996 to 1998. The following exceptions occurred. At well pair 04591/10194, in the vicinity of the 903 Pad, first quarter data reveals an increase in linear flow velocity of approximately 60 percent from 1996 to 1998, and third quarter data reveals a decrease in flow velocity of approximately 50 percent from 1996 to 1998. The other exceptions were for well pairs where only one quarter of water level data was available for 1996, or only one quarter out of four showed a variance of greater than 25 percent. One such exception is well pair P314289/10492, located in the IA/south Buffer Zone, where the first quarter in 1998 showed an approximately 50 percent increase in linear flow velocity from the same quarter in 1996. Another is at well pair P419689/P416889, located in the IA, where the second quarter in 1998 showed an approximately 60 percent increase in flow velocity from the same quarter in 1996. This indicates that the hydraulic gradient was steeper between these well pairs, for these quarters, in 1998. At well pair P416289/P416689, located in the IA, second quarter 1998 data revealed an approximately 50 percent decrease in flow velocity from 1996 to 1998. At well pair P313489/6186, located in the IA, fourth quarter data revealed an approximately 50 percent decrease in flow velocity from 1996 to 1998. This indicates that the hydraulic gradient was steeper between these well pairs, for these quarters, in 1996. It is interesting to note that the major changes in flow velocities between 1996 and 1998 took place in well pairs located in the IA. This might be expected in the IA versus the Buffer Zone because of all the artificial features associated with the IA (building drains, pavement, piping and utility corridors, etc.). Velocities reported for 1996 through 1998 are generally higher than velocities reported in pre-1996 annual RCRA groundwater monitoring reports largely because sitewide mean K values are now employed in the calculations instead of individual operable unit mean K values.

3.3 Well Hydrographs and Water Level Change Maps

Hydrograph plots for many RFCA water quality wells have been constructed in order to observe changes in water table elevation with time (see Appendix B). In addition to illustrating seasonal fluctuations in water table elevation, hydrographs are useful for evaluating long-term trends that might result from either artificial activities (plant closure) or natural causes (climatic change). For example, a comparison of IA

well hydrograph data to background well hydrograph data may suggest whether any of the observed trends are natural or artificially induced. Assuming that groundwater levels within the Site have reached a quasi-steady state condition since the cessation of production operations in 1989, it is conceivable that plant closure activities could cause local water levels to rise or fall, depending on the closure action. These changes in water level elevations will be evaluated in future years using annual and life-of-closure water level change maps that will be based on water levels collected during the 1996 baseline year.

Water levels measured during 1998 were, for the most part, observed to fluctuate within normal limits. Some wells, including recharge-sensitive wells such as 20691, 4286, 12191, B200889, and P416689 exhibited very high recharge peaks during the spring season. In general, for all site wells, water levels were higher during the first half of 1998 compared to the second half. Only B-series wells generally displayed higher water levels during the second half of 1998. Overall, water levels were higher in 1998 than in 1996. Water levels in 1996, which were higher than average, were thought to reflect the residual influence of the record high water levels experienced in 1995. Sitewide precipitation data from 1993 through 1998 indicates that precipitation was very high in 1995, 1996 produced near average precipitation, 1997 produced well above average precipitation, and 1998 produced near average precipitation. The continuing higher than average water levels may be based as much on recurrent high precipitation (ample recharge) since 1995 as they are on the residual effects of 1995 and 1997. The sitewide scale of this trend, also observed in background wells, implies that climate is the dominant cause of water level changes during 1998.

Water level change maps (Plates 8 and 9) utilizing 1998 and 1996 water level data, are presented here for the second time in an annual report. These data are used to compare the 1998 water levels for the second (April data) and fourth (October data) quarters to the second and fourth quarter water level data for 1996. Data plotted on these water level change maps indicate areas of the site where changes in saturated thickness, either positive or negative, have taken place between the two given years. It is important to keep in mind that wells that have been purged for sample collection, and have a slow recharge rate, can be responsible for a large discrepancy in water level change from 1996 to the year of the current RFCA Annual Report.

The water level change map for the spring quarters of 1996 and 1998 (Plate 8) generally shows that almost all changes are positive compared to 1996; there was generally a higher spring water table in 1998 than in 1996. The central and southern PA has virtually no change from 1996 to 1998. Along the eastern PA boundary there is a steep positive gradient of up to 6 feet, then a grading back eastward to almost no change by Pond B-2. The northern edge of the PA shows a zero to one-foot positive change from 1996 to

1998. The west central and western IA generally shows positive water level change (1-3 feet) out to the west spray fields where there is virtually no change. Water level changes become positive again to the west, up to 3-4 feet, just east of Highway 93 and west of the gravel pits. The northwest portion of the IA exhibits positive water level changes of up to 5 feet, and a localized area just west of building 371 (well P114589) exhibits positive changes of up to 30-plus feet. Another area of high positive water level changes is immediately south and southwest of Building 440, with changes up to 13 feet from 1996 to 1998. Upgradient of the Present Landfill is an area of 6-8 feet of positive change in the water table elevation from 1996 to 1998. Approximately 2500 feet south of the Trailer 130 complex is an area of 2 to 5-plus feet of positive water level change. Additional bullseyes identified on Plate 8 indicate areas of significant change, from 1996 to 1998, in water levels for the spring quarter.

The water level change map for the fall quarters of 1996 and 1998 (Plate 9) shows that, in general, there is a greater mix of positive and negative water table elevation change throughout the site than presented on the spring quarters of 1996 to 1998 water level change map. West of the IA there are only positive changes, and east of the IA there are almost all positive changes except for a few isolated areas of negative change. The west central IA shows an area of 1-3 feet of negative water level change from 1996 to 1998. This area of negative change is surrounded by zero change areas from the western PA trending southwest through the southwest portion of the IA, and from the western SEP trending south/southwest through the central IA. The eastern third of the IA exhibits an area, from west to east, of 2 feet of positive to 2 feet of negative water level change from 1996 to 1998. An area to note is in the vicinity of Cactus and First Street where there is a steep gradient, from west to east, from a positive 2 feet to a negative 3 feet of water level change within a linear distance of approximately 250 feet. In addition, immediately west of Building 371 is an isolated area (well P114589) of approximately 30 feet of positive water level change from 1996 to 1998. Approximately 2500 feet south of the Trailer 130 complex is an area of 2 to almost 6 feet of positive water level change. Additional bullseyes on Plate 9 indicate areas of significant change, from 1996 to 1998, in water levels for the fall quarter.

In summary, groundwater flow conditions for 1998 appear to generally resemble flow conditions described for recent years with slight variations depending on the location within RFETS. This situation is not unexpected because only minor plant closure activities have been undertaken to date. The variations in water levels and linear flow velocities are probably in response to the timing of water level measurements with respect to natural recharge (precipitation), artificial recharge, or artificial dewatering events. Artificial events may involve recharge or dewatering related to construction, demolition, onsite industrial processes, monitoring well sampling, and building perimeter drain activity or inactivity. The

1996 data set (and to some extent the 1997 data set) will represent the baseline for future annual evaluations.

4.0 GROUNDWATER EVALUATIONS

4.1 Industrial Area Plume

4.1.1 Introduction

The major groundwater evaluation activity in 1998 consisted of an evaluation of four wells in the groundwater program that had VOC concentrations that were above action levels. Wells 22696, 22796 and 22896 were installed in 1996. They were part of the original Industrial Area IM/IRA monitoring program to serve as monitoring points for possible groundwater contamination emanating from the 700 building complex during D&D activities. At the time of installation, it was not anticipated that these wells would discover pre-existing groundwater contamination. Well P219189 was installed in 1989 and is located north of Building 774 near Bowman's Pond. Figure 4-1 shows the location of these wells.

Data from well 22696 has shown Trichloroethene (TCE) concentrations above Tier II action levels. Table 4-1 shows the latest 1998 data for this well. The TCE concentration, although low, is in an area that has not been investigated for possible groundwater contamination. Well 22796 shows concentrations of TCE above Tier II action levels. This well is also in an area that has not been investigated for groundwater contamination. Well 22896 was installed near Building 559. This well shows TCE concentrations above Tier I action levels. Well P209189 has historically shown 1,1 dichloroethene (1,1, DCE) above Tier II action levels. Carbon tetrachloride (carbon tet) is also seen in this well. This well is one of the few wells on Site that contains anomalous concentrations of 1,1-DCE.

The location of these wells near flowing streams suggested that a potential impact to surface water may be possible. Wells 22796 and P219189 are near the Walnut Creek drainage, though the stream has been re-routed through culverts in the general area. Wells 22696 and 22896 are upgradient of a small tributary stream that flows north to Walnut Creek on the east side of Building 371. This stream is fed by a number of pipes and culverts along its path and therefore does not depend upon groundwater influx as it's only source of recharge. Well 1986 is a routine monitoring well located near this stream which showed TCE above action levels (28 µg/L) for the first time in ten years (see Figure 4-1). Because of this, the previous sample result was used pending confirmation of the October sample.

To investigate potential impacts to surface water, a line of temporary wells were installed between the anomalous wells and the streams. Twenty-three wells were installed that were spaced approximately one

hundred feet apart. The RFETS Geoprobe unit was used to install the one inch diameter wells, which were completed below ground surface and protected by a flush mounted metal cap. The wells were installed in or on the side of two existing paved roads, to allow for sampling access. Ten wells were installed in an east-west direction to cover the potential groundwater pathways from wells P219189 and 22796. The rest of the wells were installed on a southwest-northwest line that would define groundwater pathways downgradient of wells 22696 and 22896. The wells were sampled for VOCs as these are the only compounds that exceed action levels. The wells were installed in the third quarter, and sampled during the fourth quarter of 1998. Table 4-1 shows the results of the fourth quarter sampling for the temporary wells, which are numbered 20098-22298. Also in support of the evaluation effort, in the first quarter of 1999, well 77492 was sampled and a stream sample was taken near well 1986.

4.1.2 Hydrogeology

The line of temporary wells is located in an area that was originally composed of hillslope colluvium where it interfingers with valley fill alluvium materials near Walnut Creek and the small tributary stream. Cut and fill activities during construction of the 700 building complex have resulted in areas of fill which are composed dominantly of colluvial material. As such, the dominant lithology in the wells is sandy clay and clayey sand which is interbedded with one half to three foot intervals of clayey to sandy gravel. These gravel intervals are thought to be the edge of the valley fill alluvium which probably does not extend much farther upslope of the Geoprobe line. For this reason these coarser intervals were not factored into the flux calculations discussed in a later section. The Geoprobe holes were taken down to the bedrock contact and the wells were screened so as to include the contact in the screened interval. Wells 21998, 22098 and 22198 did not intersect bedrock due to refusal problems. Bedrock lithology in this area is typically a moderately weathered claystone. Figure 4-1 contains the potentiometric surface for the north IA based on water levels taken in the fourth quarter of 1998. In general the potentiometric surface mimics the topography, and suggests that groundwater flow from the 700 building complex can head northwest, north and northeast.

4.1.3 Evaluation of Sampling Results

The results of the VOC sampling from the temporary wells have been summarized in Table 4-1. Only those VOC compounds for which significant concentrations were detected are listed. In addition, data from other wells in the area is included in Table 4-1 for the purposes of assessing the possible nature and extent of the groundwater contamination. The concentrations of TCE, carbon tet, chloroform, 1,1-DCE and vinyl chloride are presented in Figures 4-2 through 4-6, respectively. It can be seen that the groundwater contamination seen in the area can be related based on the dominant VOCs detected.

Table 4-1
Volatile Organic Compounds in Groundwater North IA Plume

Well	Sample Type	Fall Wate	Sample Date	Concentration in ug/L								Total VOCs
				cis/trans 1,2 Dichloro- ethene	1,1 Dichloro- ethane	Vinyl Chloride	Carbon Tetra- chloride	Trichloro- ethene	1,1 Dichloro- ethene	Tetra- chloro- ethene	Chloroform	
22098	Geoprobe well	5989.5	9/17/98	U	U	U	U	U	U	U	U	0
21998	Geoprobe well	5985.7	9/15/98	U	U	U	U	U	U	U	U	0
21898	Geoprobe well	5970.0	9/23/98	4	1	U	U	10	1	7	U	23
21798	Geoprobe well	5966.4	9/15/98	10	7	12	U	8	2	U	U	39
21698	Geoprobe well	5957.4	3/29/99	8	U	U	U	29	U	7	U	44
21598	Geoprobe well	5963.7	9/23/98	6	U	U	4	86	3	U	U	99
21498	Geoprobe well	5955.3	9/22/98	U	U	U	4	2	U	U	2	8
21398	Geoprobe well		Dry									0
21298	Geoprobe well	5946.9	9/22/98	U	U	U	8	U	U	U	4	12
21198	Geoprobe well	5945.7	9/22/98	U	U	U	7	U	U	U	5	12
21098	Geoprobe well	5946.0	9/24/98	U	U	U	1800	U	U	U	410	2210
20998	Geoprobe well	5944.9	9/23/98	U	U	U	42	U	U	U	130	172
20898	Geoprobe well	5938.8	9/21/98	U	U	U	96	U	U	4	95	195
20798	Geoprobe well	5927.7	9/21/98	1.6	3	U	U	U	U	U	U	4.6
20698	Geoprobe well	5923.2	9/28/98	10	2	3	U	16	U	U	U	31
20598	Geoprobe well	5940.3	9/28/98	4	4	8	U	U	20	U	U	36
20498	Geoprobe well	5927.8	9/23/98	3	9	7	U	U	110	U	U	129
20398	Geoprobe well	5926.9	9/23/98	1	5	1	U	U	4	U	U	11
20298	Geoprobe well	5925.9	9/24/98	U	2	U	U	U	U	U	U	2
20198	Geoprobe well	5932.0	9/23/98	U	U	U	U	U	U	U	U	0
20098	Geoprobe well	5922.0	9/16/98	15	U	U	U	U	U	U	U	15
22198	Geoprobe well	5920.6	9/22/98	U	U	U	U	U	U	U	U	0
22298	Geoprobe well	5916.7	9/24/98	U	U	U	U	U	U	U	U	0
1986	Well	5940.3	6/17/98	U	U	U	U	U	U	U	U	0
2286	Well		7/12/95	U	U	U	180	180	U	U	38	
5687	Well		7/12/95	13	10	2	U	68	5	4	6	
P210189	Well		4/14/98a	68	U	U	5200	3100	U	U	340	8708
P209189	Well		4/14/98a	2	U	U	1	5	U	U	U	8
P209289	Well	5968.67	4/14/98a	U	U	U	49	U	U	U	46	95
P219189	Well	5931.15	6/16/98	U	29	U	7	U	30	U	2	68
P209489	Well	5950.84	5/13/98	11	0.4	U	52	63	1	3	20	150.4
P209389	Well	5964.43	2/23/99	U	1	U	1.6	U	36.1	2	2.8	
77492	Well		3/26/99	U	U	U	U	U	U	U	U	
42393	Well		4/14/98a	U	U	U	U	U	U	U	U	0
41993	Well		12/15/97	U	U	U	U	0.5	U	0.5	U	1
45693	Well		12/8/97	U	U	U	U	2	U	0.5	1	3.5
45893	Well		12/15/97	8	1	U	74	64	1	6	16	170
30595	Well		12/17/97	U	U	U	1	6	U	1	2	10
22696	Well	5964.03	8/31/98	U	U	U	U	10	2	U	U	12
22796	Well	5929.62	6/16/98	11	U	U	U	29	U	U	U	40
22896	Well	5980.5	9/1/98	3	U	U	U	2400	U	U	U	2403
02497	Well	5970.11	11/3/98	U	U	U	U	3	U	U	1	
18199	Well		3/26/99	U	U	U	15400	3	37.6	1.6	2200	17642.2
18299	Well		3/26/99	U	U	U	3280	1.1	U	U	1600	4881.1
18399	Well		3/26/99	U	U	U	23000	U	U	U	3430	26430
18499	Well		3/26/99	U	1.4	U	57800	3.4	150	2.3	8750	66707.1
18599	Well		3/26/99	U	2.4	U	31900	1	27.9	3.5	4300000	4331934.8
18699	Well		3/26/99	U	1.5	U	5	U	U	1.2	U	7.7
18799	Well		3/26/99	U	U	U	927	U	5.8	6.8	511	1450.6
771FDOUT #2	Pipe		3/26/99	U	U	U	12	U	1	U	23	36
771Manhole #3	Pipe		3/26/99	U	U	U	U	U	U	U	U	0
MW771 Manhole	Pipe		3/26/99	U	U	U	U	U	U	U	U	0
1986 Stream	Stream		3/26/99	U	U	U	U	U	U	U	U	
Action Level	ug/L			70	1000	2	5	5	7	5	100	1194

132

The following is a breakdown of the data with respect to nature and extent of contamination: Wells 21599, 21699, 21799 and 21899 are dominated by TCE with attendant PCE and vinyl chloride concentrations above Tier II action levels. The VOC signature in these wells is similar to VOCs found in wells 22698 and 22898. Recent plume concentration maps generated as part of the 1997 Annual Groundwater Monitoring Report (DOE, 1998) have associated well 22896 with the northern extent of the IA VOC plume, and the high concentration of TCE suggests a nearby source. With the addition of the temporary well data, it now appears that the northern IA plume extends farther north than originally thought and is in a position to have contact with the stream in this area. Figure 4-2 shows the spatial relation of TCE detections to the north IA.

Wells 20898, 20998, 21098, 21198, and 21298 are dominated by carbon tet with attendant chloroform above Tier II action levels. There is no TCE or PCE in these wells, which suggests a different source for the groundwater contamination in this area. Figures 4-3 and 4-4 show the concentration of carbon tet and chloroform in the north IA. Table 4-1 includes the recent data collected from the natural attenuation project for IHSS 118.1 (RMRS, 1999d). IHSS 118.1 is a former carbon tet tank location which experienced numerous historic spills and/or leaks. The tank has since been removed. A drilling and sampling program was designed at IHSS 118.1 to collect the data necessary for decision making with respect to natural attenuation. Eight wells were installed in a pattern so as to have two wells upgradient of the DNAPL source, and three wells along an east-west line where two wells were in the source, and one well was located cross gradient to the source (see Figure 4-9). The remaining three wells were installed in a line approximately 60 to 70 feet downgradient from the source. The wells were installed in February 1999 and the first round of sampling was completed by the end of March. In addition, VOC samples were taken of two manholes and one pipe outfall, that are thought to be associated with the Building 771 footing drain system, which lies on the south side of Building 771. Building 771 is approximately 120 feet due north of the IHSS 118.1 source and the footing drain is thought to be intercepting a portion of the VOC plume. Figure 4-1 shows the location of the wells and other sampling locations.

The VOC signature from the IHSS 118.1 wells matches the VOC signature from the temporary wells listed above. Because chloroform is a breakdown product of carbon tet, it is predictable that these two compounds would occur together. Carbon tet was also found above Tier II action levels in sample 771FDOUT #2 which is from an outfall pipeline thought to be related to the 771 footing drain system (see Figure 4-3). Based on the information at hand, it appears that carbon tet plume from IHSS 118.1 is migrating westward towards the stream in concentrations that could impact surface water. In addition, there is evidence that the plume is being captured in part by the 771 footing drain system. Wells 1986 and 77492 lie due west and northwest of the carbon tet plume as seen in the temporary wells. Groundwater

sample data from these wells, and a stream sample taken near well 1986 showed no detections for VOCs. If a pathway to surface water exists here, it must be between these two locations.

Given the evidence for a groundwater pathway to the west of IHSS 118.1, existing data was evaluated to determine if additional pathways may exist to the north and east of the latter. Wells 20198, 20098, 22198, and 22298 were installed to determine if a pathway from the carbon tet plume to surface water existed in this area. Data from these temporary wells shows no detections for VOCs. Table 4-1 and Figures 4-2 through 4-6 also show data from existing wells located to the east of IHSS 118.1. Well P209289 is east of IHSS 118.1 and shows the same VOC signature as other wells associated with the carbon tet plume. Wells P210189, P209489, 2286 and 45893 show carbon tet and chloroform above Tier II action levels, but also contain TCE above Tier II action levels. In fact both TCE and carbon tet have historically been above Tier I action levels in well P210189. Well 5687, which is located to the south of well P210189 has high TCE and very low concentrations of carbon tet. The data suggest that wells in this cluster are possibly being affected by multiple sources; a TCE source and a carbon tet source. It is possible that IHSS 118.1 is contributing the carbon tet that is found in this area.

Well 45893 is north of the possible TCE source and northwest of IHSS 118.1. This is the farthest well to the north that shows both TCE and carbon tet. Well 30595 is farther north outside the PA, near the Walnut Creek drainage and does show TCE above Tier II action levels. It is possible that a pathway exists in the area of these two wells. Given that the Solar Evaporation Ponds (SEPs) groundwater collection and treatment system is being installed in this area, this pathway may no longer require additional investigation. Well P219189 is north of IHSS 118.1 and does show carbon tet above Tier II action levels. However, temporary wells to the north of this well do not show any carbon tet.

The third area of groundwater contamination is located due north of Building 771 and involves temporary wells 20498, 20598 and 20698. These three wells show detections of vinyl chloride above Tier II action levels. Well 20498 also shows TCE above Tier II action levels and well 20698 shows 1,1-DCE above Tier II action levels. The VOC signature for well 20698 closely matches existing well 22796 in that both wells show TCE concentrations. Well 20498 is similar to well P219189 in that they both contain 1,1-DCE above action levels. However, the two wells differ in that well 20498 contains TCE as opposed to P219189, which contains carbon tet above Tier II action levels.

4.1.4 Plume Flux Calculations

Plume flux estimates were made to establish the potential impact to surface water from the three contaminant plume areas referenced above and identified from the Geoprobe drilling project. Table 4-1

was used to derive the total concentration of VOCs detected in each well. Table 4-2 presents the results of calculations to determine the flux of contaminated groundwater to the stream.

Saturated thickness was determined by estimating the feet of water column between the water table elevation and the bottom of the screen. Since all wells are screened primarily in alluvial materials, the bedrock portion of the borehole is typically only a foot or less in thickness.

Transmissivity was calculated by using the saturated thicknesses derived from both fall and spring water levels and using estimates of hydraulic conductivity for colluvial materials from the 1995 Hydrogeologic Characterization Report (EG&G, 1995b). Transmissivities were calculated using the minimum, maximum and geometric mean hydraulic conductivities found in Table G-2 of the Hydrogeologic Report (EG&G, 1995b). Colluvial materials at RFETS are variable in composition both in the vertical dimension in the borehole, but also in the horizontal dimension. Therefore, no attempt was made to make adjustments to hydraulic conductivity based on lithologic changes seen in the colluvium.

The estimated discharge was calculated on a per well basis using the mean transmissivity values for fall and spring periods. The hydraulic gradient was estimated using the difference between water levels in wells 22896 and the elevation of the stream near Geoprobe well 21598. This gradient was used for all wells due to the paucity of upgradient wells available in the area and the complications caused by buildings and associated alterations to the topography. The length perpendicular to flow was set at 100 feet, which is the distance between the temporary wells. Total discharge for the three contaminant plumes is seen at the bottom of Table 4-2.

Using the calculated discharge, and the total VOC concentration data in Table 4-1, an estimate of contaminant load was calculated in Table 4-2. Loads were calculated using both spring and fall data and the total load for each plume occurs at the bottom of the table. Using the load and discharge estimates, a total flux of VOC contaminants is calculated. The wells involved in each plume are labelled and outlined with a dark line in Table 4-2. The flux for the TCE plume is 0.001 Kg/day, 0.015 Kg/day for the carbon tet plume, and 0.001 Kg/day for the vinyl chloride plume.

4.1.5 Conclusions and Recommendations

The results of this investigation suggest that groundwater contamination above groundwater action levels exists in the general area of the unnamed tributary drainage to Walnut Creek in the IA. Well 1986, located in the drainage itself, does not show VOC concentrations above action levels, nor did a surface water sample collected in the stream adjacent to well 1986. Well 77492 also shows no VOC detections,

Table 4-2
Plume Flux Calculations
No. 1A Plume

Well	Casing Elevation	Sep-98 Water Level	Mar-98 Water Level	Creek Elevation	Bottom of Screen Elevation	Fail Saturated Thickness	Spring Saturated Thickness	Fail Water Level Data	Spring Water Level Data	Transmissivity	Discharge Q'	Discharge Q'	Fall Load	Spring Load	Fail GW Flux	Spring GW Flux
		Level	Level			Thickness	Thickness	Minimum	Maximum	Mean	Fail gal/min	Spring gal/min	gram/day/ft	gram/day/ft	kg/day	kg/day
22098	5999.60	10.10	10.19	6000	5975.11	14.50	14.41	0.16443	38.229975	3.8229975	0.1634094	0.101880401	0	0	0	0
21998	5994.60	8.94	8.80	6000	5975.11	10.66	10.80	0.1208844	28.105623	2.8105623	0.122472	0.07489966	0	0	0	0
21898	5988.60	18.61	18.14	5980	5967	2.99	3.46	0.0339066	7.8832845	0.78832845	0.0392364	0.021008441	0.000513	0.0005942	5.1E-05	5.94E-05
21798	5981.50	15.06	14.66	5975	5958	8.44	8.84	0.0957096	22.252482	2.2252482	0.1002456	0.05930142	0.002458	0.00257422	0.00025	0.000257
21698	5973.90	16.53	15.85	5970	5957.5	0.00	0.00	0	0	0	0	0	0	0	0	0
21598	5969.70	5.96	4.79	5960	5955	8.74	9.91	0.0991116	23.043447	2.3043447	0.1123794	0.06140929	0.006461	0.00732551	0.00065	0.000733
21498	5964.60	9.34	3.10	5960	5954	1.26	7.50	0.0142884	3.322053	0.3322053	0.08505	0.008853066	0.006461	0.00732551	0.00065	0.000733
21398	5966.70	DRY	14.23	5955	5952	0.00	0.00	0	0	0	0	0	0	0	0	0
21298	5958.70	11.82	10.14	5950	5939	7.88	9.56	0.0893592	20.776014	2.0776014	0.1084104	0.053366728	0.000706	0.00085658	7.1E-05	8.57E-05
21198	5957.50	11.85	10.38	5945	5928	17.65	19.12	0.200151	46.5351075	4.65351075	0.2168208	0.12401304	0.001581	0.00171316	0.00016	0.000171
21098	5959.00	13.00	11.37	5940	5939	7.00	8.63	0.07938	18.45585	1.845585	0.0978642	0.049183642	0.11551	0.14240733	0.01155	0.014241
20998	5954.90	10.03	10.19	5940	5943	1.87	1.71	0.0212058	4.9303485	0.49303485	0.0193914	0.013139059	0.002402	0.00219611	0.00024	0.00022
20898	5945.50	6.71	6.75	5940	5930	8.79	8.75	0.0996786	23.1752745	2.31752745	0.099225	0.061760602	0.012798	0.01274007	0.00128	0.001274
20798	5943.40	15.75	16.63	5935	5917	10.65	9.77	0.120771	28.0792575	2.80792575	0.1107918	0.074829398	0.000366	0.00033557	Vinyl Chloride Plume	
20698	5942.70	19.55	19.51	5935	5921	2.15	2.19	0.024381	5.6685825	0.56685825	0.0248346	0.015106404	0.000498	0.00050691	5E-05	5.07E-05
20598	5940.30	12.81	12.81	5930	5926	0.00	1.49	0	0	0	0.0168966	0.014690889	0	0.00040051	0	4.01E-05
20498	5939.47	11.70	11.85	5925	5918	9.77	9.62	0.1107918	25.7590935	2.57590935	0.1090908	0.068646312	0.009411	0.00926604	0.00094	0.000927
20398	5937.50	10.65	10.74	5925	5915	11.85	11.76	0.134379	31.2431175	3.12431175	0.133584	0.083260879	0.000973	0.00096589		
20298	5935.58	9.68	8.01	5920	5925	0.90	2.57	0.010206	2.372895	0.2372895	0.0291438	0.006323611	0.018057423	1.34E-05	3.8379E-05	
20198	5934.37	2.42	2.21	5915	5925	6.95	7.16	0.078813	18.3240225	1.83240225	0.0811944	0.04883233	0.050307839	0	0	
20098	5932.55	10.51	7.95	5915	5911	11.04	13.60	0.1251936	29.107512	2.9107512	0.154224	0.077569629	0.001236	0.00152321	0	
22198	5931.60	10.96	10.35	5910	5915	5.64	6.25	0.0639576	14.870142	1.4870142	0.070875	0.039627963	0.043913966	0	0	
22298	5930.60	13.88	11.13	5910	5915	1.72	4.47	0.0195048	4.534666	0.4534666	0.0506898	0.012085123	0	0	0	
NP = the well did not penetrate bedrock																
T = is the product of the saturated thickness for individual wells and the hydraulic conductivity																
Q =	TL(dh/dl)	Using average in-plume Transmissivity (T) values above:														
X =	T(dh/dl)/C	Contaminant load equals transmissivity times hydraulic gradient times concentration														
Unit conversion: T(sq.ft/day) x dh/dl (unitless) x C (ug/L) x 28.32 L/cu.ft x 10-6 g/ug = TC (g/day/ft)																
C _i is taken as the Total VOC concentration from Table 4-1																
F =	XL	Contaminant Flux equals Contaminant Load times Length. L = 100 feet for each well														
Hydraulic Conductivity																
for Colluvium																
In cm/sec	Min	Max Geometric Mean														
	4.0E-06	9.3E-04 9.3E-05														
DH: measured water elevation between well 22896 and creek elevation below 21598																
In feet	22896	Creek elevation														
	5960.52	5960														
DL: measured distance between well 22896 and creek below 21598																
In feet		20.52 feet														
		DL														
		400 feet														
DH/DL =	0.0513															

but the well is located in an area of artificial fill and where the stream is in a culvert, so the well may not be representative of natural hydrologic conditions. This small tributary stream receives influent from a number of pipes and culverts which may serve to dilute the effects of any groundwater recharge to the stream.

The line of Geoprobe wells appears to have adequately characterized the nature and extent of groundwater contamination in the area of the tributary drainage. Additional evaluation may be necessary to establish pathways for the carbon tet plume to the east and north of IHSS 118.1. There is evidence that a portion of the carbon tet plume has moved eastward from the source and possibly intermingled with another VOC plume north of Building 779. Also, well P219189 has carbon tet above action levels which may suggest a pathway from the carbon tet plume to the north. The current well installation program for the D&D monitoring of Building 771 may add information on the extent of the carbon tet plume. In addition, a well installation program is also planned for Building 776/777 D&D monitoring in FY00 which should help define potential pathways for groundwater contamination.

The cumulative contaminant flux to surface water from the three groundwater plume areas defined amounts to approximately 14 grams per day. Given the low flow from the outfall pipe that did show detections for VOCs it can be assumed that this pathway provides little added impact to surface water if the pipe is not being used. Efforts will be made to ascertain whether this outfall has been abandoned and whether it is capable of higher flow rates at certain times of the year.

4.2 PU&D Yard Plume Investigations

In 1997, the Site conducted a field investigation into the nature and extent of VOC groundwater contamination found in upgradient monitoring wells at the Present Sanitary Landfill. This investigation resulted in the identification of the PU&D Yard as the probable source area and implicated the landfill groundwater intercept and diversion system as an important factor in contributing to longitudinal plume spreading (Figure 4-7). The results of this evaluation were summarized in the 1997 Annual RFCA Groundwater Monitoring Report (DOE, 1998). Further investigation into the function of the groundwater intercept and diversion system and its possible role in collecting and discharging PU&D Yard plume contaminants downgradient of the landfill were undertaken in 1998. This section summarizes the results of the 1998 investigation, including field observations of drain valving, flow, and analytical results of samples collected at the drain outfalls in 1998 and 1999.

Figure 4-8 illustrates the layout of the groundwater intercept and diversion system. Information presented in the *Phase I RFI/RI Work Plan for Operable Unit No. 7 - Present Sanitary Landfill* (DOE, 1991) and other Operable Unit 7 documentation contain engineering design specifications and a hydrologic analysis of system effectiveness, but contain little information on system operation, such as valving configurations and discharge data. Discharge at drain outfalls SW099 and SW100 located below the landfill pond dam is usually minimal or absent despite evidence, such as an abundance of valley head-cut seeps in pre-landfill aerial photographs, that suggest flow should be greater than currently observed assuming proper drain function. Explanations for the lack of appreciable discharge at these outfalls involve at least four scenarios: 1) discharge is currently routed toward the landfill pond by valving and piping shown in design drawings, 2) the lines have been broken or breached during normal landfill operations resulting in subsurface releases of drain water to refuse materials, 3) the drain system was never properly functional because of leakage caused by geological irregularities, design or installation flaws, or other potential shortcomings, and 4) groundwater levels at the perimeter of the landfill drop below the elevation of the groundwater diversion system drainpipe during extended periods during the year.

For these reasons, a preliminary investigation into drain operation was undertaken to gain additional information on the fate of groundwater collected by the system. This investigation consisted of a records search to uncover additional documentation on the historical operation and valve configuration; a field search to locate valves, drain line locations, and drain outfall locations at the landfill pond; and a monitoring program for sampling groundwater flow issuing from SW099 and SW100.

A records search resulted in the disclosure of no new information relevant to drain operation beyond that contained within DOE (1991). The field survey, however, was more successful resulting in the location of valving for both the north and south intercept lines, the location of apparent pond line locations indicated by subtle changes in topography and vegetation leading from the valves, and location of the south pond drain outfall during a period of low pond stage (May 1999). Significantly, no discharge was observed at this outfall during a time when SW099 and SW100 were both flowing.

Observation of drain outfalls SW099 and SW100, located on Figure 4-8, was conducted at roughly monthly intervals during the Fall and Winter of 1998, and Spring of 1999. In December 1998, a sufficient amount of flow was observed at SW099 (0.007 gallons per minute [gpm] on 12/18/98) to justify sampling for VOCs. The SW100 outfall was dry during all site visits prior to April 1999, except for incident precipitation which had built up inside the weir box. On April 29, 1999, flows from both outfalls were observed and a complete sample set was collected for VOCs, metals, radionuclides (Pu-239/240, Am-241, uranium isotopes, and tritium), and water quality parameters (total dissolved solids, sulfate,

fluoride, and nitrate/nitrite). Discharges of 0.5 gpm at SW099 and 1.3 gpm at SW100 were measured prior to sampling.

Table 4-3 presents the analytical results of the 1998 and 1999 sampling events at SW099 and SW100. VOCs characteristic of PU&D Yard groundwater contamination were not detected in samples collected at either outfall. Dissolved metals, water quality constituents, Pu-239/240, Am-241, and tritium were all found below Tier II action levels. The uranium isotope U-233/234 was detected above the Tier II action level at 1.2991 pCi/L in SW100, but below the Tier II action level at SW099 (0.9358 pCi/L). U-235 was detected below the Tier II action level and U-238 was detected above the Tier II action level at both locations. In all cases, the reported uranium isotope activities were well below their respective background M2SD activities and, as such, are not reportable values. The information collected thus far indicates that the PU&D Yard VOC plume does not contribute significant concentrations of contaminants to the landfill groundwater intercept and diversion system. Monitoring of the drain outfalls will be continued in 1999 to further investigate the potential impact of PU&D Yard contamination on groundwater and surface water quality downgradient of the landfill.

4.3 Carbon Tetrachloride Plume

This section summarizes the progress on the IHSS 118.1 carbon tetrachloride plume natural attenuation study, which was initiated in FY99. The object of this report is to provide sample results for the suite of analytes that were sampled in the first sampling round and determine whether the suite should be modified given the results obtained. The overall goal of the project is to characterize the potential for natural attenuation as a significant factor in the remediation strategy for the IHSS 118.1 Dense Non-Aqueous Phase Liquid (DNAPL) source. Carbon tet is the main contaminant of concern at IHSS 118.1 and is the result of spills related to a carbon tet storage tank, which has been subsequently removed. Characterization work was initiated in 1997 to identify the extent of the DNAPL source and determine the feasibility of extracting the DNAPL through pumping or excavation. Source removal was postponed because it is presently unfeasible to excavate the source due to the number of active process pipes that run through the source area. The decision was then made to evaluate the potential for the carbon tet plume to be effected by natural attenuation processes.

**Table 4-3 Groundwater Intercept System Analytical Data
Present Sanitary Landfill/PU&D Yard**

Location	Sample Date	Sample #	Analyte	Result	Units	Lab Qualifier	Detection Limit	Validation Qualifier
SW099	4/29/99	GW06353TE	FLUORIDE	0.4	MG/L		0.05	
SW099	4/29/99	GW06353TE	NITRATE/NITRITE	0.19	MG/L		0.05	
SW099	4/29/99	GW06353TE	SULFATE	40	MG/L		1	
SW099	4/29/99	GW06353TE	TOTAL DISSOLVED SOLIDS	380	MG/L		10	
SW100	4/29/99	GW06354TE	FLUORIDE	0.41	MG/L		0.05	
SW100	4/29/99	GW06354TE	NITRATE/NITRITE	0.05	MG/L	U	0.05	
SW100	4/29/99	GW06354TE	SULFATE	58	MG/L		1	
SW100	4/29/99	GW06354TE	TOTAL DISSOLVED SOLIDS	260	MG/L		10	
SW099	12/30/98	GW06198TE	1,1,1,2-TETRACHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,1,1-TRICHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,1,2,2-TETRACHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,1,2-TRICHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,1-DICHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,1-DICHLOROETHENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,1-DICHLOROPROPENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2,3-TRICHLOROBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2,3-TRICHLOROPROPANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2,4-TRICHLOROBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2-DIBROMOETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2-DICHLOROBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2-DICHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,2-DICHLOROPROPANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,3-DICHLOROBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,3-DICHLOROPROPANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	1,4-DICHLOROBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	2,2-DICHLOROPROPANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	4-ISOPROPYLTOLUENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BENZENE, 1,2,4-TRIMETHYL	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BENZENE, 1,3,5-TRIMETHYL-	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BROMOBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BROMOCHLOROMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BROMODICHLOROMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BROMOFORM	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	BROMOMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	CARBON TETRACHLORIDE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	CHLOROBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	CHLOROETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	CHLOROFORM	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	CHLOROMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	cis-1,2-DICHLOROETHENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	cis-1,3-DICHLOROPROPENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	DIBROMOCHLOROMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	DIBROMOMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	DICHLORODIFLUOROMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	ETHYLBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	HEXACHLOROBUTADIENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	ISOPROPYLBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	METHYLENE CHLORIDE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	NAPHTHALENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	n-BUTYLBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	n-PROPYLBENZENE	1	UG/L	U	1	

**Table 4-3 Groundwater Intercept System Analytical Data
Present Sanitary Landfill/PU&D Yard**

Location	Sample Date	Sample #	Analyte	Result	Units	Lab Qualifier	Detection Limit	Validation Qualifier
SW099	12/30/98	GW06198TE	o-CHLOROTOLUENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	p-CHLOROTOLUENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	PROPANE, 1,2-DIBROMO-3-CHLORO-	1	UG/L	U	1	R1
SW099	12/30/98	GW06198TE	sec-BUTYLBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	STYRENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	tert-BUTYLBENZENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	TETRACHLOROETHENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	TOLUENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	TOTAL XYLENES	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	trans-1,2-DICHLOROETHENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	trans-1,3-DICHLOROPROPENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	TRICHLOROETHENE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	TRICHLOROFLUOROMETHANE	1	UG/L	U	1	
SW099	12/30/98	GW06198TE	VINYL CHLORIDE	1	UG/L	U	1	
SW099	4/29/99	GW06353TE	1,1,1,2-TETRACHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,1,1-TRICHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,1,2,2-TETRACHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,1,2-TRICHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,1-DICHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,1-DICHLOROETHENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,1-DICHLOROPROPENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,2,3-TRICHLOROBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	1,2,3-TRICHLOROPROPANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,2,4-TRICHLOROBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	1,2-DIBROMOETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,2-DICHLOROBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	1,2-DICHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,2-DICHLOROPROPANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,3-DICHLOROBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	1,3-DICHLOROPROPANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	1,4-DICHLOROBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	2,2-DICHLOROPROPANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	4-ISOPROPYLTOLUENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	BENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	BENZENE, 1,2,4-TRIMETHYL	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	BENZENE, 1,3,5-TRIMETHYL-	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	BROMOBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	BROMOCHLOROMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	BROMODICHLOROMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	BROMOFORM	0.1	UG/L	J	1	V1
SW099	4/29/99	GW06353TE	BROMOMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	CARBON TETRACHLORIDE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	CHLOROBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	CHLOROETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	CHLOROFORM	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	CHLOROMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	cis-1,2-DICHLOROETHENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	cis-1,3-DICHLOROPROPENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	DIBROMOCHLOROMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	DIBROMOMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	DICHLORODIFLUOROMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	ETHYLBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	HEXACHLOROBUTADIENE	1	UG/L	U	1	V1

**Table 4-3 Groundwater Intercept System Analytical Data
Present Sanitary Landfill/PU&D Yard**

Location	Sample Date	Sample #	Analyte	Result	Units	Lab Qualifier	Detection Limit	Validation Qualifier
SW099	4/29/99	GW06353TE	ISOPROPYLBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	METHYLENE CHLORIDE	0.09	UG/L	BJ	1	JB1
SW099	4/29/99	GW06353TE	NAPHTHALENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	n-BUTYLBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	n-PROPYLBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	o-CHLOROTOLUENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	p-CHLOROTOLUENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	PROPANE, 1,2-DIBROMO-3-CHLORO-	1	UG/L	U	1	R1
SW099	4/29/99	GW06353TE	sec-BUTYLBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	STYRENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	tert-BUTYLBENZENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	TETRACHLOROETHENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	TOLUENE	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	TOTAL XYLENES	1	UG/L	U	1	UJ1
SW099	4/29/99	GW06353TE	trans-1,2-DICHLOROETHENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	trans-1,3-DICHLOROPROPENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	TRICHLOROETHENE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	TRICHLOROFLUOROMETHANE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	VINYL CHLORIDE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1,1,2-TETRACHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1,1-TRICHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1,2,2-TETRACHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1,2-TRICHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1-DICHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1-DICHLOROETHENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,1-DICHLOROPROPENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,2,3-TRICHLOROBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	1,2,3-TRICHLOROPROPANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,2,4-TRICHLOROBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	1,2-DIBROMOETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,2-DICHLOROBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	1,2-DICHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,2-DICHLOROPROPANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,3-DICHLOROBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	1,3-DICHLOROPROPANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	1,4-DICHLOROBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	2,2-DICHLOROPROPANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	4-ISOPROPYLTOLUENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	BENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	BENZENE, 1,2,4-TRIMETHYL	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	BENZENE, 1,3,5-TRIMETHYL-	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	BROMOBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	BROMOCHLOROMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	BROMODICHLOROMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	BROMOFORM	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	BROMOMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	CARBON TETRACHLORIDE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	CHLOROBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	CHLOROETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	CHLOROFORM	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	CHLOROMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	cis-1,2-DICHLOROETHENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	cis-1,3-DICHLOROPROPENE	1	UG/L	U	1	V1

**Table 4-3 Groundwater Intercept System Analytical Data
Present Sanitary Landfill/PU&D Yard**

Location	Sample Date	Sample #	Analyte	Result	Units	Lab Qualifier	Detection Limit	Validation Qualifier
SW100	4/29/99	GW06354TE	DIBROMOCHLOROMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	DIBROMOMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	DICHLORODIFLUOROMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	ETHYLBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	HEXACHLOROBUTADIENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	ISOPROPYLBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06353TE	METHYLENE CHLORIDE	0.1	UG/L	JB	1	JB1
SW100	4/29/99	GW06354TE	NAPHTHALENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	n-BUTYLBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	n-PROPYLBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	o-CHLOROTOLUENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	p-CHLOROTOLUENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	PROPANE, 1,2-DIBROMO-3-CHLORO-	1	UG/L	U	1	R1
SW100	4/29/99	GW06354TE	sec-BUTYLBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	STYRENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	tert-BUTYLBENZENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	TETRACHLOROETHENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	TOLUENE	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	TOTAL XYLENES	1	UG/L	U	1	UJ1
SW100	4/29/99	GW06354TE	trans-1,2-DICHLOROETHENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	trans-1,3-DICHLOROPROPENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	TRICHLOROETHENE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	TRICHLOROFLUOROMETHANE	1	UG/L	U	1	V1
SW100	4/29/99	GW06354TE	VINYL CHLORIDE	1	UG/L	U	1	V1
SW099	4/29/99	GW06353TE	Aluminum	8.1	UG/L	B	5	
SW099	4/29/99	GW06353TE	Antimony	0.98	UG/L	B	0.48	
SW099	4/29/99	GW06353TE	Arsenic	0.58	UG/L	U	0.58	
SW099	4/29/99	GW06353TE	Barium	166	UG/L		0.05	
SW099	4/29/99	GW06353TE	Beryllium	0.02	UG/L	U	0.02	
SW099	4/29/99	GW06353TE	Cadmium	0.08	UG/L	U	0.08	
SW099	4/29/99	GW06353TE	Calcium	87000	UG/L		4.1	
SW099	4/29/99	GW06353TE	Chromium	0.3	UG/L	B	0.15	
SW099	4/29/99	GW06353TE	Cobalt	0.18	UG/L	U	0.18	
SW099	4/29/99	GW06353TE	Copper	2.1	UG/L	B	0.25	
SW099	4/29/99	GW06353TE	Iron	15.2	UG/L	B	4.8	
SW099	4/29/99	GW06353TE	Lead	0.72	UG/L	U	0.72	
SW099	4/29/99	GW06353TE	Lithium	4	UG/L	B	0.05	
SW099	4/29/99	GW06353TE	Magnesium	11800	UG/L		0.7	
SW099	4/29/99	GW06353TE	Manganese	1.1	UG/L	B	0.05	
SW099	4/29/99	GW06353TE	Mercury	0.1	UG/L	U	0.1	
SW099	4/29/99	GW06353TE	Molybdenum	0.88	UG/L	B	0.3	
SW099	4/29/99	GW06353TE	Nickel	1.5	UG/L	B	0.3	
SW099	4/29/99	GW06353TE	Potassium	869	UG/L	B	7	
SW099	4/29/99	GW06353TE	Selenium	1.2	UG/L	U	1.2	
SW099	4/29/99	GW06353TE	Silver	0.35	UG/L	U	0.35	
SW099	4/29/99	GW06353TE	Sodium	18000	UG/L		10.5	
SW099	4/29/99	GW06353TE	Strontium	464	UG/L		0.02	
SW099	4/29/99	GW06353TE	Thallium	0.88	UG/L	U	0.88	
SW099	4/29/99	GW06353TE	Tin	0.68	UG/L	U	0.68	
SW099	4/29/99	GW06353TE	Vanadium	1.6	UG/L	B	0.2	
SW099	4/29/99	GW06353TE	Zinc	4.8	UG/L	B	0.12	
SW100	4/29/99	GW06354TE	Aluminum	155	UG/L		5	

**Table 4-3 Groundwater Intercept System Analytical Data
Present Sanitary Landfill/PU&D Yard**

Location	Sample Date	Sample #	Analyte	Result	Units	Lab Qualifier	Detection Limit	Validation Qualifier
SW100	4/29/99	GW06354TE	Antimony	0.48	UG/L	U	0.48	
SW100	4/29/99	GW06354TE	Arsenic	0.65	UG/L	B	0.58	
SW100	4/29/99	GW06354TE	Barium	63.8	UG/L	B	0.05	
SW100	4/29/99	GW06354TE	Beryllium	0.02	UG/L	U	0.02	
SW100	4/29/99	GW06354TE	Cadmium	0.08	UG/L	U	0.08	
SW100	4/29/99	GW06354TE	Calcium	50500	UG/L		4.1	
SW100	4/29/99	GW06354TE	Chromium	0.42	UG/L	B	0.15	
SW100	4/29/99	GW06354TE	Cobalt	0.18	UG/L	U	0.18	
SW100	4/29/99	GW06354TE	Copper	2.9	UG/L	B	0.25	
SW100	4/29/99	GW06354TE	Iron	104	UG/L		4.8	
SW100	4/29/99	GW06354TE	Lead	0.72	UG/L	U	0.72	
SW100	4/29/99	GW06354TE	Lithium	3.6	UG/L	B	0.05	
SW100	4/29/99	GW06354TE	Magnesium	9120	UG/L		0.7	
SW100	4/29/99	GW06354TE	Manganese	2.3	UG/L	B	0.05	
SW100	4/29/99	GW06354TE	Mercury	0.1	UG/L	U	0.1	
SW100	4/29/99	GW06354TE	Molybdenum	0.91	UG/L	B	0.3	
SW100	4/29/99	GW06354TE	Nickel	1.4	UG/L	B	0.3	
SW100	4/29/99	GW06354TE	Potassium	3070	UG/L	B	7	
SW100	4/29/99	GW06354TE	Selenium	10.9	UG/L		1.2	
SW100	4/29/99	GW06354TE	Silver	0.35	UG/L	U	0.35	
SW100	4/29/99	GW06354TE	Sodium	19900	UG/L		10.5	
SW100	4/29/99	GW06354TE	Strontium	309	UG/L		0.02	
SW100	4/29/99	GW06354TE	Thallium	0.88	UG/L	U	0.88	
SW100	4/29/99	GW06354TE	Tin	0.68	UG/L	U	0.68	
SW100	4/29/99	GW06354TE	Vanadium	1.1	UG/L	B	0.2	
SW100	4/29/99	GW06354TE	Zinc	10.8	UG/L	B	0.12	
SW099	4/29/99	GW06353TE	Americium-241	0.0179	PCI/L	J	0.0144	V1
SW099	4/29/99	GW06353TE	Plutonium-239/240	0.0065	PCI/L	U	0.0185	V1
SW099	4/29/99	GW06353TE	Uranium-233/234	1.2991	PCI/L		0.1595	
SW099	4/29/99	GW06353TE	Uranium-235	0.1085	PCI/L	U	0.1421	
SW099	4/29/99	GW06353TE	Uranium-238	1.143	PCI/L		0.1195	
SW100	4/29/99	GW06354TE	Americium-241	0.0106	PCI/L	J	0.0057	V1
SW100	4/29/99	GW06354TE	Plutonium-239/240	0.0107	PCI/L	J	0.0058	V1
SW100	4/29/99	GW06354TE	Uranium-233/234	0.9358	PCI/L	J	0.0528	
SW100	4/29/99	GW06354TE	Uranium-235	0.0203	PCI/L	U	0.1418	
SW100	4/29/99	GW06354TE	Uranium-238	0.7751	PCI/L	J	0.0973	

A drilling and sampling program was designed to collect the data necessary for decision making with respect to natural attenuation. Eight wells were installed in a pattern so as to have two wells upgradient of the DNAPL source (18799, 18899), three wells along an east-west line where two wells were in the source, and one well located cross gradient to the source (18499, 18599, and 18699). The remaining three wells were installed in a line approximately 60 –70 feet downgradient from the source (18199, 18299, 18399). The wells were installed in February 1999 and the first round of sampling was completed by the end of March. In addition, VOC samples were collected from DNAPL in well 05497. Figure 4-9 shows the location of the wells and sampling locations.

The wells were installed with bladder pumps so that samples could be collected with aeration of the sample kept at a minimum. This is important when collecting VOC samples and when measuring dissolved oxygen (DO) and oxidation reduction potential (redox) parameters. A flow-through cell containing the field parameter probes was used for collection of temperature, DO, redox, alkalinity, specific conductance and pH. A HACH spectrophotometer was used to measure ferrous iron. All other samples were sent to off-site laboratories for analysis. Full suites were obtained from seven of the eight wells. Upgradient well 18899 was dry and could not be sampled. Table 4.4 lists the analyses performed for the IHSS 118.1 study as listed in the IHSS 118.1 Sampling and Analysis Plan (RMRS, 1998). Water levels were obtained for all wells in the project. After additional sampling rounds are completed, the data will be presented in a Data Summary Report.

4.3.1.1 Footing Drain Outfall Samples

Two outfall pathways were sampled that are associated with the Building 771 footing drain system. Building 771 is located approximately 120 feet due north of IHSS 118.1 and has a footing drain system that collects groundwater from the south side of the building. Because the footing drain system is downgradient of the carbon tet groundwater plume, it was important to sample the outfalls from this system to determine if significant concentrations of VOCs were present. Figure 4-9 shows the location of the sample locations. One outfall is located to the west of Building 771 and flows to a small stream which enters North Walnut Creek to the north. This outfall could be sampled directly at it's terminus on the hillside, and has a location name of 771-FDOUT2. The other outfall is believed to be located under the North Perimeter road and probably enters North Walnut Creek. The pipeline to this outfall extends out from the northwest corner of Building 771 and has two manholes that were available for sampling. Sample location 771-Manhole3 is a manhole accessing the outfall pipeline outside Building 771. The second location (NW771-Manhole) is located at the confluence of drain pipes near the north perimeter road.

Table 4- 4. Sample Types/Analytical Methods

Line Item Code	Analytes	Analytical Method	Media Type	Container	Preservative	Comments/Holding Time
SS01B005	Volatile Organic Compounds	SW-846 Method 8260	Water	2 x 40 ml VOA vials - Teflon lined septa lids	Cool, 4° C, HCl	Zero head space 14 day hold time
SS01B006	Volatile Organic Compounds	SW-846 Method 8260	Soil, Waste	60-ml wide mouth glass jar with Teflon lined lid	Cool, 4° C,	Zero head space 14 day hold time
SS02B006	Semivolatiles	SW-846 Method 8270B	Water	3-liter glass jar	Cool, 4° C	7 day hold time
SS02B006	Semivolatiles	SW-846 Method 8270B	Soil	250-ml wide mouth glass jar with Teflon lined lid	Cool, 4° C	14 days to extraction, 40 days from extraction to analysis
RC01B0003	Americium, Plutonium & Uranium	ASD SOW for Isotopics RC01	Soil	125-g wide mouth glass jar	Cool, 4° C	
OS01A002	Gross Alpha/Beta	ASD SOW for Isotopics RC01 Module OS01A	Water	1 liter plastic bottle	Cool, 4° C	
OS01A003	Gross Alpha/Beta	ASD SOW for Isotopics RC01 Module OS01A	Soil	60-g wide mouth glass jar	Cool, 4° C	
SS06B037	Sulfates	SW-846, 9035, 9036	Water	1 liter plastic bottle	Cool, 4° C	Sulfates, Sulfites and Alkalinity come from same bottle 28 day hold time
SS06B039	Sulfides	SW-846 9030A	Water	1 liter plastic bottle	Cool, 4° C	Sulfates, Sulfites and Alkalinity come from same bottle 7 day hold time
SS06B002	Alkalinity	SW-846 310.1, 320.2	Water	1 Liter plastic bottle	Cool, 4° C	Sulfates, Sulfites and Alkalinity come from same bottle 14 day hold time
SS06B020	Nitrates	SW-846 , 300.0	Water	1 liter plastic bottle	Cool, 4° C	48 day hold time
SS06B025	Total Organic Carbon	SW-846 415.1	Water	1 liter plastic bottle	Cool, 4° C pH<2 w/HCl	28 day hold time
SS06B024	Dissolved Organic Carbon	SW-846 415.1	Water	1 liter plastic bottle	Cool, 4° C	28 day hold time
SS06B010	Chlorides	E300.0	Water	100 ml. plastic bottle	None	28 day hold time
Field	pH	SW9040	Water			
Field	Dissolved Oxygen	E360.1	Water			
Field	Oxidation-Reduction Potential	ASTM D1498	Water			
Field	Temperature	E170.1	Water			
Field	Conductivity	SW9050	Water			

For purposes of this preliminary evaluation, three of the seven wells were chosen for discussion. Well 18799 is the only upgradient well that had water, so it is used for background comparison. Well 18499 is in a line due north of 18799 and is in the DNAPL source. Samples were collected above the DNAPL in the well. Well 18199 is a downgradient well due north of well 18499. These wells comprise a representative cross section of groundwater quality across the IHSS 118.1 site. In most cases, data from the other wells conform to those found in this subset. Charts were derived to show the relative changes in water quality across the IHSS. Reference Appendix A from document RF/RMRS-98-420.UN, *Status Report for Monitoring of Natural Attenuation at IHSS 118.1*, for the analytical results obtained from the wells. Evaluation of the various parameters used for the natural attenuation project leads to a number of conclusions with regard to whether the parameters are necessary for the continued tracking of VOC degradation.

4.3.1.2 Natural Attenuation

Natural attenuation is defined as the observed reduction in contaminant concentrations as contaminants migrate from the source in environmental media. This reduction in concentration can be due to a number of fate and transport processes in groundwater including, dilution, dispersion, sorption, volatilization and biotic and abiotic transformations. Biodegradation or bioremediation is used to describe the portion of natural attenuation that is brought about by biological degradation mechanisms. Biological degradation typically involves bacteria that occur naturally in the soil and groundwater. Under the right conditions these bacteria can break down certain fuel hydrocarbons and certain chlorinated organic compounds.

The main mechanism for the biological breakdown of chlorinated organics is through reductive dechlorination reactions. Under reductive dechlorination, a chlorinated organic compound such as carbon tet is used as an electron acceptor, which causes the compound to gain a hydrogen atom at the expense of a chlorine atom. The dechlorination of carbon tet would cause chloroform, methylene chloride and chloromethane to sequentially form as chlorine is progressively removed from the original carbon tet compound.

For biodegradation to occur there must be an electron acceptor, a source of carbon to serve as an electron donor and a favorable environment in the aquifer for the metabolic reactions to take place. The IHSS 118.1 sampling program was designed to provide evidence that these processes are taking place. Wiedemeier et al (1996) have developed a simple system for determining whether biodegradation is occurring at a site based on applying scores to the chemical parameters discussed in this report. The criteria used is summarized in Table 4.5. A score of 0 to 5 points is suggestive of inadequate

Table 4-5

27

evidence of biodegradation. A score of 6 to 14 suggests limited evidence of biodegradation, a score of 15 to 20 shows adequate evidence and scores above 20 show strong evidence of biodegradation.

4.3.2 Electron Donors

The process of natural attenuation that would degrade chlorinated organic compounds like carbon tet is reductive dechlorination. Reductive dechlorination is the substitution of hydrogen for chlorine atoms within the chlorinated organic compound, which causes it to progressively break down into daughter products. This process requires that there be a source of electron donors, which is typically organic carbon. Carbon can be utilized either as natural carbon in the aquifer, or can be acquired from the breakdown of petroleum hydrocarbons. The following analyses were performed to determine available electron donor activity at IHSS 118.1.


4.3.2.1 Semivolatile Organic Suite

The semivolatile organic suite was collected because of a perception that there had been a diesel spill in the area of IHSS 118.1. Diesel by-products could supply the electron donors that are necessary for reductive dechlorination of the carbon tet and breakdown products. Diesel fuel is composed of such indicator compounds as naphthalene, phenanthrene, anthracene, chrysene etc., as opposed to the BTEX compounds (benzene, toluene, ethylbenzene and xylenes) which are common in gasoline. Based on the data collected, there is no evidence of either diesel or gasoline indicator compounds in the vicinity of IHSS 118.1. Therefore, it may be prudent to discontinue the semivolatile analyte suite after one more round of sampling.

4.3.2.2 Total Organic Carbon and Dissolved Organic Carbon

Total organic carbon (TOC) and dissolved organic carbon (DOC) were collected to ascertain the availability of carbon in the environment to serve as an energy source for reductive dechlorination. Figure 4-10 shows that both DOC and TOC are within the 3-4 mg/L range. Wiedemeier et al (1996), suggest that DOC above 20 mg/L assures that enough carbon is present to drive dechlorination. Therefore the limited amount of carbon in groundwater may be retarding the rate of reductive dechlorination at IHSS 118.1. With respect to further sampling, the Wiedemeier paper uses DOC as an indicator parameter, but does not discuss TOC. Given the similarity in concentration, it is suggested that only DOC be sampled after one more sample round.

Figure 4-10
Nitrate, DOC, TOC, Sulfide, Ferrous Iron and DO Concentrations at
IHSS 118.1



158

4.3.3 Electron Acceptors

In order to effect reductive dechlorination of chlorinated organic solvents, the solvents must be able to be electron acceptors. This process occurs when there are sufficient electron donor sources present, the proper chemical environment exists, and a lack of other electron acceptors that would compete with the solvent compounds as electron acceptors.

4.3.3.1 Carbon Tetrachloride

Carbon tetrachloride is the dominant organic compound found in IHSS 118.1. If biodegradation is occurring by reductive dechlorination, carbon tet would breakdown progressively to chloroform, dichloromethane, chloromethane, and ultimately to carbon dioxide and water. If reductive dechlorination was occurring, carbon tet would be seen to progressively decrease in concentration with time as the breakdown products increased in concentration. Downgradient wells would also reflect an increase in breakdown products relative to carbon tet. Figures 4-11 and 4-12 show the trends in carbon tet and daughter species. The sample from the pipe outfall near 771 is also included. In Figure 4-11 carbon tet can be seen to decrease in concentration from the source to downgradient well 18199. This would be expected if biodegradation was occurring. However the trends in chloroform and chloromethane do not increase in downgradient well 18199. Methylene chloride exhibits a similar behavior, but must be viewed with caution because it is a common lab contaminant and some was reported in the lab blank. The data suggest that there are daughter products from reductive dechlorination of carbon tet in the source area, but increased breakdown downgradient of the source is not readily apparent. By looking at the ratio of daughter products to carbon tet with time, a better indication of in-source biodegradation would be obtained. Therefore, it is suggested that sampling for these compounds continue for a sufficient time period to establish a rate of breakdown at the source. The Building 771 outfall locations described above were also sampled for the VOC suite. Location 771-FDOUT2 shows a carbon tet concentration of 12 ug/L and a chloroform concentration of 23 ug/L. The outfall has a very low flow, which suggests that it may be shut off. Because carbon tet and chloroform are the dominant components of the carbon tet plume, it appears that some of the plume is being collected in the footing drain system. The other two sample locations showed no significant VOC detections.

Figure 4-11
Carbon Tetrachloride and Chloroform Concentrations at IHSS 118.1





Figure 4-12
Methylene Chloride, Chloromethane and Methane Concentrations at IHSS 118.1



4.3.3.2 Dissolved Oxygen

Dissolved oxygen is the favored electron acceptor used by bacteria for the biodegradation process. Anaerobic bacteria cannot function at DO concentrations above .5 mg/L and hence, reductive dechlorination cannot occur (Wiedemeier, et al, 1999). Figure 4-10 shows that upgradient DO concentration at well 18799 is at 5.4 mg/L and decreases to .06 mg/L in source well 18499. DO concentration rises again in downgradient well 18199. Taking the data at face value, it would appear that DO levels are detrimental for anaerobic degradation of organic compounds except at the source. DO was measured using a DO probe inside a flow-through cell at the well head. It could be that this method, though far superior to those obtained from bailed water, may allow for some oxygenation of the groundwater. Because DO is one of the most crucial measurements for determining the effects of biodegradation, downhole probes have been acquired to ensure that a representative measurement is obtained in future sample events.


4.3.3.3 Nitrate and Sulfate

Nitrate and sulfate were sampled because they, along with dissolved oxygen, can compete with chlorinated solvents as electron acceptors. If high levels of nitrate and/or sulfate were to exist in the groundwater in the vicinity of IHSS 118.1, the amount of reductive dechlorination of carbon tet and its by products could be retarded. The graph on Figure 4-10 shows the values for nitrate along the three well cross section at IHSS 118.1. The nitrate concentration in upgradient well 18799 is 2 mg/L which is near the RFETS background mean of 1.4 mg/L for Rocky Flats Alluvium (DOE, 1993b). In Figure 4-10, nitrate concentration is seen to decrease at the source and then increase again in concentration away from the source. This trend would be expected if biodegradation was occurring in the source area.

Wiedemeier et al, 1996 have a scoring system for determining the potential for biodegradation. They suggest that a concentration of nitrate above 1 mg/L may impact biodegradation of chlorinated organics. Given the low concentration of nitrate in the vicinity of the IHSS (.05 mg/L at source well 18499), it would seem that nitrate is being removed from the process locally, but that nitrate concentration is perhaps impacting the biodegradation process away from the source. Because nitrate is a key indicator of the efficacy of biodegradation on chlorinated solvents, continued sampling is advised.

The sulfate concentration in upgradient well 18799 is 46 mg/L, which is above the RFETS background mean of 22 mg/L (DOE, 1993b). Figure 4-13 shows the concentration of sulfate dropping near source well 18499, and then increasing in downgradient wells. This trend would be expected if biodegradation

Figure 4-13
Chloride and Sulfate Concentrations at IHSS 118.1



was occurring in the source area. Wiedemeier et al (1996) suggest that sulfate above 20 mg/L could compete with the chlorinated solvents as an electron acceptor and thus retard the biodegradation process of the latter. Given that sulfate was found at 22 mg/L in the source area and at higher levels away from the source, it can be deduced that sulfate may be retarding the amount of biodegradation of carbon tet occurring at IHSS 118.1. Because sulfate is a key indicator of the efficacy of biodegradation on chlorinated solvents, continued sampling is advised.

4.3.4 Metabolic By-Products

The measurement of the metabolic by-products of biodegradation are valuable to determine the predominant microbial and chemical processes that are occurring at IHSS 118.1. The following samples were taken to help determine whether actual biodegradation is occurring.

4.3.4.1 Ferrous Iron

Ferric iron (Fe III) is reduced to ferrous iron (FeII) during anaerobic biodegradation of organic hydrocarbons. Therefore an increase in ferrous iron concentration in the source area can suggest the amount of biodegradation that is occurring. Figure 4-10 shows that ferrous iron increases from 0.01 mg/L in background well 18799 to 1.6 mg/L in source well 18499, then decreases to 0.10 mg/L in downgradient well 18199. Wiedemeier et al (1996) believe that ferrous iron above 1 mg/L would allow reductive dechlorination to take place. Therefore it appears that some reductive dechlorination is occurring at the source. Because ferrous iron is a key indicator of the efficacy of biodegradation on chlorinated solvents, continued sampling is advised.

4.3.4.2 Sulfide

The production of hydrogen sulfide occurs during sulfate reduction and verifies that sulfate is acting as an electron acceptor during biodegradation. Figure 4-10 shows that sulfide is 0.02 mg/L in background well 18799 and does not change in concentration in the source and downgradient wells. Wiedemeier et al (1996) believe that sulfide above 1 mg/L would allow reductive dechlorination to take place. These results suggest that though sulfate is decreasing in concentration in the source area, the amount of hydrogen sulfide generated is minimal. Because of the conflicting evidence for biodegradation given by sulfate/sulfide analyses, and because sulfide is a key indicator of the efficacy of biodegradation on chlorinated solvents, continued sampling is advised.

4.3.4.3 Methane

The presence of methane in groundwater is indicative of strongly reducing conditions. Methane is produced through the biodegradation of petroleum hydrocarbons, and where present in groundwater containing chlorinated solvents, suggests that the chemistry of the groundwater is favorable for reductive dechlorination. Figure 4-12 shows that methane increases from 0.003 mg/L to 0.20 mg/L in the source area, then decreasing to 0.007 in downgradient well 18199. Wiedemeier et al (1996) believe that methane above 0.1 mg/L would allow reductive dechlorination to take place. Methane values are fairly low suggesting that there is little if any petroleum hydrocarbons present at IHSS 118.1. However, the increase in methane production in the source relative to background suggests that some reductive dechlorination is occurring. Because methane is a key indicator of the efficacy of biodegradation on chlorinated solvents, continued sampling is advised.

4.3.4.4 Chloride

The presence of elevated concentrations of chloride in groundwater relative to background suggests that biodegradation of organic solvents is taking place. This is because the replacement of hydrogen for chlorine in the chemical structure of the chlorinated organic compound during reductive dechlorination releases chlorine in the process. Figure 4-12 shows the concentrations of chloride seen in the vicinity of IHSS 118.1. Chloride concentration is in the 65 mg/L range and does not change appreciably in the three wells plotted, although side gradient well 18699 does show twice the concentration of chloride relative to the other wells. The RFETS background mean concentrations for chloride in alluvial materials is 8 to 18 mg/L (DOE, 1993b). The Groundwater Geochemistry Report for RFETS (EG&G, 1995c) shows that chloride concentration increases from west to east at RFETS and that chloride concentrations in the Industrial Area range from 25 to 100 mg/L. Given the lack of dramatic change in chloride concentration at IHSS 118.1 relative to both upgradient and downgradient wells and the surrounding Industrial Area, it may be that only limited reductive dechlorination is occurring at the IHSS. Because chloride is a key indicator of the efficacy of biodegradation on chlorinated solvents, and given the equivocal nature of results, continued sampling is advised.

4.3.5 Conclusions and Recommendations

Based on the preliminary results, a number of conclusions can be made. There is evidence of biodegradation at the IHSS 118.1 source. If the assumption is made that the breakdown products found at IHSS 118.1 are not part of the original free product composition, then based on the scoring system

discussed in Wiedemeier et al (1996), the source area rates a score of 18 (see Table 4-5). The upgradient and downgradient wells rate a score of 3, which suggests that the environment of the aquifer away from the source may be hostile to biodegradation. These scores are derived using data from the three wells used for the cross section discussed above. Given the downgradient score with respect to biodegradation, the decrease in composition of organic solvents away from the source must be partly attributed to physical processes such as dilution and dispersion rather than strictly to biodegradation. These preliminary results suggest that a significant reduction in carbon tet is occurring at the source. Additional monitoring will help determine the rate at which biodegradation is occurring.

One of the footing drain outfalls shows low levels of carbon tet and chloroform that is probably attributable to inflow of carbon tet plume groundwater into the footing drain system. Given the low concentration of VOCs in outfall sample 771-FDOUT2, and the very low flow from the outfall, there does not appear to be a major contribution of VOCs to surface water.

The results of the follow-on sampling at IHSS 118.1 will be used to validate these preliminary findings and can also be used to assess possible remedial strategies. The Groundwater program will be evaluating the downgradient extent of VOC plumes in the Industrial Area in the future to determine potential impacts to surface water. This information will be incorporated with data from IHSS 118.1 and other projects to provide an integrated approach to groundwater management for the Site.

4.3.5.1 Sampling Recommendations

Based on the results obtained to date the following recommendations can be made with respect to future sampling:

1. The present sampling suite should be maintained for the second round of sampling, to confirm the results obtained in the first sampling event. After that point, it may be prudent to eliminate the semivolatile organic suite and TOC sample. The semivolatile organic suite was collected to determine whether there is evidence of fuel hydrocarbons that would aid in the breakdown of carbon tet. If these compounds are not encountered in the second sampling round, the analyses can be discontinued. TOC can be eliminated because only DOC is used in the scoring system for determining the degree of biodegradation.
2. Efforts will be increased to assure the collection of representative DO measurements because it is a critical parameter for determining whether biodegradation can succeed. Down-hole parameter probes will be used for collecting DO in the next sample round.
3. The two Building 771 outfall locations should also be sampled again to confirm the initial results obtained in the first round of sampling. In addition, a check will be made to see if the outfall with detectable concentrations of VOCs is active or has been abandoned.

5.0 BUILDING D&D

The DOE decontamination and decommissioning (D&D) process is the sequence of events that occurs in the disposition of surplus DOE facilities. D&D is primarily concerned with decontamination, dismantling, removal, or entombment of the surplus facilities. The primary tasks associated with D&D are:

- Surveillance and Maintenance
- Assessment and Characterization
- Environmental Review
- Close Out

Activities associated with these tasks involve the removal of fixed materials (including residual constituents of concern), equipment, piping, tanks, ducts, ceilings and other internal building structures, and the buildings themselves. In general, it is planned that D&D will be done in phases, allowing alternative interim use of most buildings before the final decommissioning of the buildings (DOE 1994b).

Building specific D&D activities involve three major steps:

- Deactivation of Building Processes
- Demolition of Building Structures
- Remediation of Building Foundations and Surroundings

The IM/IRA for the IA outlines monitoring activities established to ensure that building D&D activities do not inadvertently impact surface water by degrading groundwater beneath or in contact with the base of the demolished buildings. The proposed groundwater monitoring will provide the data necessary to determine if the precautions and actions taken during D&D have prevented or allowed migration of contaminants to groundwater. If existing information regarding a proposed D&D activity indicates the potential to contaminate groundwater, generally through a knowledge of historical building activity and use, then a pre-D&D groundwater baseline will be established for that building. Exceedances are defined as concentrations detected greater than the mean + 2 standard deviations above the baseline (K-H 1998b). Monitoring will be accomplished by the installation of D&D monitoring wells immediately adjacent to the specific building. These wells in conjunction with appropriately located existing wells will provide the baseline data, and also be utilized for future D&D monitoring of the building specific impacts, if any, on downgradient groundwater quality.

This is a new section to the Annual RFCA Groundwater Monitoring Report. It will be expanded during each successive year to include the D&D activities, as they pertain to groundwater, for that calendar year. The following subsections discuss D&D activities during 1998 for Building 123; Buildings 444, 771, and 886; and Building 779.

5.1 Building 123

Building 123, used as a laboratory for bioassay, dosimetry, and water quality parameter analyses, was located on Central Avenue between Third and Fourth Streets at RFETS. The building underwent D&D activities, and was ultimately demolished in 1998. Subsequent to demolition, six monitoring wells (10098-10598) were installed with a Geoprobe rig immediately adjacent to the building foundation. The purpose of these wells was twofold. First, to assess the potential impact of D&D activities on local groundwater quality and, second, to prepare an IHSS ranking for prioritizing the Building 123 site on the ER ranking list. This report is only concerned with the potential impact of Building 123 D&D activities on downgradient groundwater quality. Figure 5-1 presents the location of Building 123 and associated D&D monitoring wells.

It has been determined, based on the IMP, that four sampling events are required to collect a data set to be used for determination of a unique baseline for each building which will undergo D&D groundwater monitoring. Unfortunately, the schedule for Building 123 D&D became accelerated and it was not possible to collect the required amount of pre-demolition data to derive baseline values for the site. In addition, there are not an appropriate number or distribution of existing monitoring wells in the vicinity of Building 123 to sample for collection of baseline data (utilizing the previous three years sampling data) as the IM/IRA suggests. Only one sampling round, post demolition, was accomplished at the Building 123 D&D monitoring wells during 1998. Depending on groundwater flow conditions at a specific building, it may be possible to create a baseline even though the building has previously been demolished. If linear flow velocities in the immediate vicinity of the building are relatively low, then contaminants potentially mobilized by D&D may take a year or two to reach the D&D monitoring wells.

The results of the one sampling round completed at Building 123 during 1998 indicate that metals analyses exhibited no results above Tier II action levels. There were no Tier I exceedances for VOCs and radionuclide species. A few slight Tier II exceedances occurred for both VOCs and radionuclides. The Tier II exceedances are listed below. Future interpretations will compare upgradient to downgradient water quality instead of Tier levels.

VOCs:

- Monitoring well 10498, sampled on 8/12/98, PCE result of 15 µg/L

Radionuclides:

- Monitoring well 10098, sampled on 8/10/98, uranium 233/234 result of 1.13 pCi/L and uranium 238 result of 1.08 pCi/L
- Monitoring well 10298, sampled on 8/11/98, uranium 233/234 result of 1.08 pCi/L and uranium 238 result of 1.10 pCi/L
- Monitoring well 10498, sampled on 8/12/98, uranium 233/234 result of 1.41 pCi/L and uranium 238 result of 1.22 pCi/L

During 1999, it is anticipated that enough additional analytical data will be available to construct a groundwater chemistry baseline for Building 123.

5.2 Buildings 444, 771, and 886

The Sampling and Analysis Plan for the D&D monitoring of Buildings 444, 771, and 886 was initiated during late 1998. It is anticipated that the SAP will be completed and approved by the State by July 1999, and that the D&D monitoring wells associated with each building will be installed before the end of 1999. Building 444 is currently scheduled for demolition in 2002. Building 771, including Buildings 771C and 774, is currently scheduled for demolition in 2003. Building 886 is currently scheduled for demolition in 2000. This will allow adequate time to construct a groundwater chemistry baseline for each building. The 1999 Annual RFCA Groundwater Monitoring Report will include location maps for these buildings with the final locations of the D&D monitoring wells associated with each site.

5.3 Building 779

Building 779, placed into service in 1979, housed minor production and plutonium recovery operations, but was primarily a research and development facility. Some metal parts were assembled in this building and bulk plutonium residues were recovered in the hydride operations (DOE 1992a). The building is located in the PA approximately 200 feet south of the westernmost Solar Pond and is currently scheduled for demolition in 2000. Three monitoring wells, 02297, 02397, and 02497 were installed with a Geoprobe rig in 1997 to facilitate collection of a D&D monitoring baseline at Building 779. Figure 5-2 presents the building location and the associated D&D monitoring wells.

It has been determined, based on the IMP, that four sampling events are required to collect a data set to be used for determination of a unique baseline for each building which will undergo D&D groundwater monitoring. There will be adequate time for collecting the appropriate amount of data and determining the groundwater chemical baseline before the 2004 demolition date. No sampling rounds were completed during 1997 at the Building 779 D&D monitoring wells. Sampling rounds were accomplished with varying success at the Building 779 D&D monitoring wells during 1998. Not all monitoring wells produced the same number of sampling rounds or amount of samples per round because the wells were either dry or did not produce enough groundwater for full sample suites. Monitoring well 02297 produced enough groundwater in June for VOC analyses only. Monitoring well 02397 produced enough water in March for VOCs only, and in November for VOCs, metals and nitrates. Monitoring well 02497 produced enough water in March and June for VOCs and nitrates only; in November for VOCs only.

The results of these 1998 samples indicated that there were no concentrations from any Building 779 D&D monitoring well above Tier I action levels. Wells 02297 and 02497 had no results above Tier II action levels. The only result during 1998 above Tier II action levels was at monitoring well 02397, in November, where nitrates analysis resulted in a concentration of 12 mg/L.

6.0 GROUNDWATER CHARACTERIZATION ACTIVITIES

The following groundwater characterization activities were ongoing or were performed completely during calendar year 1998. The projects were performed jointly between the Groundwater Operations group and other ER groups at RFETS and are discussed here because of their pertinence to groundwater issues. The following sections are condensed discussions of the various groundwater characterization activities performed during 1998. Greater detail regarding each investigation may be obtained by reviewing the referenced reports for each area, which are listed below and in Section 9.0, References.

6.1 Mound Plume/SW059

The Mound Site consists of a former waste burial area where 1,405 drums containing uranium and beryllium contaminated lathe coolant (a mixture of approximately 70% hydraulic oil and 30% carbon tetrachloride), tetrachloroethene (PCE), other VOCs, and low levels of plutonium were stored. The drums, initially stored on the ground, were buried with soil between April 1954 and September 1958. Ten percent of the drums were suspected to have leaked. In 1970, all of the drums were exhumed from the Mound Site along with some radiologically contaminated soil. The Mound Site area has been disturbed often, generally by construction projects, since the initial source removal. Additional radioactive soils were identified during these projects and removed at later dates. Recent investigations have detected VOCs, primarily PCE, in subsurface soils at concentrations above the subsurface soil action levels that require cleanup.

From the Mound Site, the ground surface slopes steeply downward, to the north, towards the incised drainage of South Walnut Creek. The Mound Site groundwater plume is located north of Central Avenue and east of the PA fence. The plume, comprised primarily of VOC contamination, discharges as seeps and subsurface flow into the South Walnut Creek drainage in the vicinity of seep SW059. The VOC contamination is found along a line of monitoring wells downgradient (north) of the Mound Site and between the Mound Site and South Walnut Creek, indicating that the Mound Site is the primary source of the plume. Figure 6-1 presents the location of the Mound Site Plume area.

An accelerated soil removal action was completed during the spring of 1997 to remove VOC contaminated soils above the Tier I action levels from the Mound Site. Low temperature thermal desorption was used to remove VOCs and treated soils were returned to the excavation. As part of this

project, a permanent culvert was installed in the previously unlined Central Avenue Ditch, located immediately upgradient of the source area, which contributed water to the Mound Site Plume.

A pre-remedial groundwater investigation was performed in March and April of 1997 to examine the nature and extent of the Mound Site Plume adjacent to South Walnut Creek. The results of the investigation indicate that the water level, and quantity of groundwater present, generally declines towards the east and west margins of the plume. The most commonly detected VOCs from the source area to the distal end of the plume are PCE and TCE. Other VOCs are present in the plume, mainly towards the distal end, as degradation products of PCE and TCE (DOE, 1997c). The goal of the investigation was to provide the necessary information to support the design of an interception/collection trench and the proper disposal of soil removed during construction of the interception/collection trench.

The Mound Site Plume project employs an innovative technology for the collection and treatment of groundwater contaminated with chlorinated organic compounds and low levels of radionuclides. Work performed during 1998 on this project consisted of the installation of the Mound Site Plume Treatment System (MSPTS). The MSPTS is a passive subsurface groundwater treatment system consisting of treatment cells containing zero valent iron; an impermeable barrier membrane constructed of high density polyethylene (HDPE) to capture and redirect contaminated groundwater; an engineered permeable filter media backfill, consisting of sand and pea gravel, and containing a 4-inch perforated HDPE pipe routed to a central collection sump; and a barrier monitoring system (piezometers). Some of the barrier monitoring system piezometers were installed during 1998; the remainder are scheduled for installation during 1999.

The system is designed to protect surface water by reducing mass loading consistent with RFCA action levels. The zero valent iron, contained in two buried treatment cells, is used to remediate VOC and radionuclide contaminated groundwater. After treatment, the water is discharged back to groundwater on the downgradient side of the treatment system through a French drain (RMRS, 1999e). During construction of the treatment system, a buried drain pipe was discovered that was probably contributing contaminated groundwater to the SW059 seep. The treatment system also collects this water.

Work scheduled for 1999 on this project consists of sampling and analysis of influent, treatment system effluent, and barrier monitoring wells, in order to ascertain the effectiveness of the MSPTS.

6.2 Solar Evaporation Ponds Nitrate/Uranium Plume

The RFCA set a milestone of fiscal year 1999 for the implementation of a remedial action which would control contaminated groundwater emanating from the Solar Evaporation Ponds, and prevent it from

causing North Walnut Creek to have concentrations above its in-stream standards. The Solar Ponds Plume (SPP) is an area of groundwater contamination which extends from the SEPs, located in the northeastern portion of the PA, to the northeast towards North Walnut Creek and to the southeast towards South Walnut Creek. The primary analytes of concern are nitrate/nitrite and various uranium isotopes; however, other inorganic and organic compounds have also been identified at concentrations above the Tier II action levels.

The SPP emanates from the SEPs. VOCs have been detected in monitoring wells located in the western portion of the SEPs and south of the SEPs. The VOCs are thought to have originated from sources to the west and southeast of the SEPs. Several metal analytes have also been detected in SPP monitoring wells at concentrations above groundwater action levels. Figure 6-2 presents the site location.

The Interceptor Trench System (ITS) was constructed in 1971, and expanded in 1981, to dewater the hillside and prevent the SPP from advancing downgradient to North Walnut Creek. The ITS traverses the hillside to the north of the SEPs and collects surface water infiltration as well as alluvial groundwater; however, the ITS does not collect groundwater from the weathered bedrock immediately below the alluvium. Groundwater flowing through weathered bedrock may continue on towards North Walnut Creek. Water collected by the ITS since 1993 has been stored in modular storage tanks prior to treatment at Building 374.

As an initial phase in determining the appropriate remedial action for the SPP, RMRS began a study in 1997 to evaluate alternatives for the management and treatment of the water collected by the ITS. The objective of the study was to determine a permanent remedy for the SPP. Final evaluation of the alternatives required a detailed characterization of the water quality in the alluvium and weathered bedrock in the vicinity and downgradient of the SEPs (McLane Environmental, 1998). The 1998 field activities associated with this study continued to collect the data necessary to complete a SEPs conceptual hydrogeologic model and groundwater flow model, as well as evaluate the remaining feasible remedial alternatives. Groundwater characterization work completed on this project in 1998 included collection and analysis of groundwater samples from approximately ninety wells in the SEPs area including samples outside the SPP from the North and South Walnut Creek areas and upgradient (background) areas. The primary objective of the sampling was to determine the nature and extent of the SPP in the alluvium, weathered bedrock, and competent bedrock during the low flow (late fall/early winter) and high flow (spring) seasons.

The secondary objective was to evaluate the amount and distribution of uranium in the groundwater associated with the SPP, and estimate what portion of it is attributable to past RFETS activities. Initially, low flow samples (November 1997 through February 1998) from a combination of background, Walnut Creek drainage, and SPP wells were analyzed for uranium isotopes by alpha spectroscopy. Seven SPP wells were resampled during the high flow season (April 1998). In addition to analysis by alpha spectroscopy, four low flow samples and five high flow samples were subsequently sent to Las Alamos National Laboratory (LANL) for analysis of uranium isotopes by high resolution, inductively coupled plasma/mass spectroscopy (ICP/MS). The results of these analyses were used to calculate uranium isotope ratios, which can be used to differentiate between naturally occurring and anthropogenic uranium. As a first step in analyzing the source of uranium in the SPP groundwater, the alpha spectroscopy data was converted from isotope activity to isotope mass and the U-235 to U-238 ratios calculated. In naturally occurring uranium the U-235 to U-238 mass ratio is 0.0072. The resulting ratios were very inconsistent, and because the alpha spectroscopy data was determined not to have sufficient resolution for determining uranium isotopic ratios, the samples described above were sent to LANL for analysis by ICP/MS. The results of the ICP/MS analyses indicate that the uranium occurring in all background samples is naturally occurring. In addition, it was determined that groundwater containing anthropogenic uranium has not yet reached groundwater adjacent to North Walnut Creek (RMRS, 1999f). For additional information regarding these analyses reference the *Solar Ponds Plume Decision Document* (RF/RMRS-98-286.UN), (RMRS, 1999f).

In addition to groundwater sampling, four new monitoring wells were installed during 1998 to provide additional groundwater data where needed. One well, 03498, was installed to the north of the SEPs and three wells (03198, 03298, and 03398) were installed to the southeast of the SEPs (Plate 1). Monitoring well 03198 was dry, but the other three wells contained sufficient water for sampling and analyses.

Based on the results of the above described study, undertaken during 1997 and 1998, the *Solar Ponds Plume Decision Document* was prepared. The Decision Document outlines the remediation strategy, treatment goals, applicable regulatory requirements, and implementation schedule to accomplish a long-term and cost effective remedy for the groundwater collection, management, and treatment of the SPP. A reactive barrier, consisting of a funnel system which will direct SPP groundwater to a treatment cell containing zero-valence iron and a carbon source, was selected as the preferred remedial alternative. The other alternatives described in the Decision Document were found to be ineffective in treating the contaminants or did not achieve the long-term goals for the SPP and RFETS.

The SPP is currently being managed and treated according to the IM/IRA (DOE, 1992b; and 1994b). Activities scheduled for 1999 which are associated with the SPP include installation of the above described treatment system. Groundwater activities completed during 1999 will be described in the 1999 RFCA Groundwater Annual Report.

6.3 B-Ponds/East Trenches Plume

The East Trenches Groundwater Plume is located north of Central Avenue and east of the east perimeter road. This groundwater plume contains VOC contamination which is believed to originate from the East Trenches and 903 Pad sites and extends northward to where the plume discharges as seeps and subsurface flow into the South Walnut Creek drainage. Recent exceedances of the Tier II RFCA VOC groundwater action levels in a designated Tier II well near South Walnut Creek, and recent detections of VOCs in the B-ponds indicate that contaminated groundwater is reaching surface water at this location. Figure 6-3 presents the site location.

A large plume of contaminated groundwater is located in the East Trenches area. Most of the groundwater contamination is believed to be derived from the trenches on the north side of the East Access Road, which includes Trenches T-3 and T-4 (RMRS, 1996c). Upgradient monitoring wells indicate that a component of the contaminated groundwater in this area is derived from VOC contamination emanating from the 903 Pad. However, the VOC concentrations in groundwater increase by more than two orders of magnitude after the groundwater passes through Trenches T-3 and T-4, which reflects previous release from the trenches.

Trenches T-3 and T-4 were used between 1964 and 1967 for disposal of sanitary sewage sludge contaminated with low levels of uranium and plutonium, VOCs, crushed drums, and miscellaneous waste (DOE 1992b). In 1996 these trenches were excavated as part of an accelerated source removal action. Trench T-3, located approximately 300 feet north of the East Access Road and immediately west of Trench T-4, was approximately 134 feet long, 20 feet wide, and 10 feet deep. Trench T-4 was approximately 110 feet long, 15 feet wide, and 10 feet deep. The removed soil and debris were thermally treated to remove the VOCs, which consisted primarily of carbon tetrachloride, TCE, and PCE. The remediated soil, below Tier II action levels, was returned to the trench excavation and the area was revegetated. The component of the East Trenches plume derived from the VOC contamination at the 903 Pad and Lip areas is associated with drums containing plutonium and uranium contaminated soils and

solvents which were stored in the area from the summer of 1958 to January 1967 (RMRS, 1996d; 1997).

Pre-remedial investigations were conducted in the fall of 1997 and the spring of 1998 to determine the extent and configuration of the distal end of the East Trenches plume near South Walnut Creek. Additional characterization work was conducted in the spring of 1998 to collect sufficient data to design a remedial action for the plume. A total of 32 Geoprobe boreholes were advanced with 25 temporary monitoring wells installed. These wells, where they contained sufficient water, were monitored for water table elevation and sampled for radioisotopes and VOCs. Soil samples were collected from several boreholes and analyzed for VOCs and other analytes.

Groundwater flow in the vicinity of the East Trenches plume is to the north and northeast and discharges primarily as seeps, springs, and baseflow to South Walnut Creek. This is particularly apparent where the water bearing strata are incised by the creek. There is a spring and seep complex on the south bank of South Walnut Creek, above ponds B-1 and B-2, where the Arapahoe No.1 Sandstone subcrops.

Concentrations of VOCs above Tier I action levels were detected at this location during 1998. The presence of VOCs in the seep complex indicates that contaminants have reached South Walnut Creek.

The Arapahoe No. 1 Sandstone is present beneath the East Trenches source area and constitutes a preferential groundwater flow pathway towards South Walnut Creek. This unit is continuous in the subsurface from the East Trenches to the distal end of the East Trenches plume and much of the groundwater flow and contaminant flux is through this material. In addition, contaminated groundwater from the East Trenches plume directly discharges into the Valley Fill Alluvium underlying South Walnut Creek. This deposit may also act as a preferential pathway for contaminated groundwater (RMRS, 1999g).

Work to be performed on this project during 1999 will be the installation of a downgradient capture system near South Walnut Creek to intercept contaminated groundwater. A subsurface groundwater collection system coupled with a passive reactive metal treatment system will be utilized to treat VOC contaminated groundwater from the East Trenches plume to below surface water action levels. The downgradient capture system was chosen as the best remediation method, following an evaluation including other more traditional options, because it effectively treats the existing VOCs to below action levels at lower life cycle cost than other treatment options.

An impermeable barrier groundwater collection system will be keyed into the underlying claystone or low permeability colluvium, depending on the elevation of the bedrock surface, and the collected groundwater will be treated in a separate treatment system. A collection sump will be installed at the eastern end of the collection system. The captured groundwater will then gravity flow out of the collection system into a

series of cells containing reactive iron filings, which will remove the VOCs. The treated water is expected to discharge to groundwater through an infiltration gallery, however, for added flexibility the system will be designed to allow discharge directly to South Walnut Creek if necessary.

6.4 903 Pad/Ryan's Pit Plume

The 903 Pad/Ryan's Pit Plume is located directly south of the southeast corner of the PA and between the 903 Pad and Woman Creek at RFETS. Two sources, the 903 Pad and Ryan's Pit, contribute to this plume of contaminated groundwater. The primary analytes comprising the 903 Pad/Ryan's Pit Plume are carbon tetrachloride, TCE, and PCE. The nearest receiving streams for the plume are the South Interceptor Ditch (SID), located approximately 150 feet north of Woman Creek, and Woman Creek. There was an agreed upon 1999 compliance milestone for characterizing 903 Pad/Ryan's Pit Plume groundwater to protect surface water quality in Woman Creek. The Ryan's Pit source removal began in September, 1995, with the removal of contaminated soil. The soil was treated in February, 1996, and the project was completed in August, 1996, with the replacement of treated soil. The 903 Pad source removal is scheduled for 2001. Figure 6-4 presents the location of the 903 Pad/Ryan's Pit Plume area.

The 903 Pad was utilized as a drum storage area from the summer of 1958 to January 1967. The drums contained oils and VOCs contaminated with various radionuclides. Approximately 75 percent of the drums contained plutonium contaminated liquids and most of the remaining drums contained uranium contaminated liquids. Within the drums containing plutonium, the liquid was primarily lathe coolant and carbon tetrachloride in varying amounts. Also stored in drums were hydraulic, vacuum pump, and silicone oils; TCE; PCE; and acetone still bottoms. Leaking drums were observed in 1964 during routine handling operations. The area was fenced to restrict access, and the contents of leaking drums were transferred to new drums. When cleanup of the 903 Pad began in 1967, there were a total of 5,237 drums at the storage site, approximately 420 of which had leaked to some degree. An estimated 50 drums had leaked their entire contents. It was estimated that approximately 5,000 gallons of contaminated liquid, containing about 86 grams of plutonium, had escaped to the subsurface. During 1968 and 1969, some of the radiologically contaminated material was removed, the area regraded, and much of the area capped with asphalt. Dense non-aqueous phase liquids (DNAPLs) are suspected to exist beneath the 903 Pad and high concentrations of VOCs are present in groundwater beneath and downgradient of the site.

Ryan's Pit (previously known as Trench T-2) is located approximately 150 feet south of the 903 Pad and was approximately 20 feet long, 10 feet wide, and 5 feet deep. The 1995 source removal took place between September 5th and 12th. The excavation was 32 feet long, 18 feet wide, and varied in depth from 5.5 to 8 feet. It was originally thought that Ryan's Pit was used for disposal of sludge from the sanitary wastewater treatment plant, as the East Trenches, which were filled from 1954 through 1968. An extensive evaluation of aerial and low angle oblique photography, spanning the years of 1953 through 1971, indicated that Ryan's Pit was not in existence until 1969 (DOE 1996b). Ryan's Pit was used from approximately 1969 to 1971 for the disposal of nonradioactive liquid chemical wastes. The wastes were primarily solvents (PCE, TCE, and carbon tetrachloride), paint thinners, diesel fuel, and other construction related chemicals. However, wells downgradient of Ryan's Pit are anomalous in uranium 233/234 and U238 (DOE 1997 B, Plates 17 and 21). Radiation screening of the wastes was performed and if identified as nonradioactive, the liquids were dumped in the trench. Only liquids were put into the pit; containers were either reused or disposed of in other areas (DOE 1992b).

In 1998, the RFETS program to characterize the 903 Pad/Ryan's Pit plume was approved by the EPA and the CDPHE. A field investigation was performed during 1998 to delineate the extent of groundwater contamination in areas with potential impact to surface water at the distal end of the 903 Pad/Ryan's Pit plume. The investigation included the installation of 26 Geoprobe boreholes with six yielding enough water for VOC sample collection. The results were used to develop preliminary recommendations regarding the need for remedial action(s) to contain and/or treat contaminated groundwater from this plume. The results (Figure 6-4) indicate that the extent of the 903 Pad/Ryan's Pit plume adjacent to Woman Creek is limited, that VOC concentrations within the plume are relatively low, and the ability of the saturated colluvium and weathered claystone within the area of the groundwater plume to transmit significant amounts of groundwater (and therefore a significant flux of contaminants) to the Woman Creek drainage is limited. The contaminated groundwater plume is not affecting surface water quality, and there was evidence of the occurrence of natural attenuation (RMRS, 1999h). Based on the results, it was proposed that the preliminary remedial design consist of natural attenuation, which involves intrinsic biodegradation coupled with physical loss mechanisms, as a groundwater evaluation strategy for the 903 Pad/Ryan's Pit plume.

Work planned for 1999 on this project includes the installation of four permanent downgradient monitoring wells to monitor VOCs. One of these wells will twin 1998 Geoprobe borehole 01298. The other three will be downgradient of the 1998 Geoprobe boreholes and upgradient of the SID. These wells will provide the necessary information to establish a trend in downgradient VOC concentrations. Monitoring will initially be performed quarterly. If at any time the groundwater monitoring data indicates

that the plume may cause surface water concentrations to exceed the established limits, then the remedial design for the 903 Pad/Ryan's Pit plume will have to be reevaluated.

6.5 903 Pad

As stated previously in Section 6.4, the 903 Pad was utilized as a drum storage area from the summer of 1958 to January 1967. The drums contained oils and VOCs contaminated with various radionuclides. Also stored in drums were hydraulic, vacuum pump, and silicone oils. Leaking drums were observed in 1964 during routine handling operations. When cleanup of the 903 Pad began in 1967, there were a total of 5,237 drums at the storage site, approximately 420 of which had leaked to some degree. It was estimated that approximately 5,000 gallons of contaminated liquid, containing about 86 grams of plutonium, had escaped to the subsurface. VOCs have impacted groundwater as a result of the leaking drums. DNAPLs are suspected to exist beneath the 903 Pad and high concentrations of VOCs are present in groundwater beneath and downgradient of the site. Figure 6-5 presents the site location.

A field investigation took place during 1998 (and continued into 1999) at the 903 Pad, 903 Lip Area, and Americium Zone, which are located in the Buffer Zone Operable Unit (OU). The purpose of the investigation was to estimate the volume of soil exceeding the RFCA Action Level Framework (ALF) Tier I soil action levels or other action levels identified as being protective of surface water for radionuclides in surface soils and VOCs in the subsurface (RMRS 1998d). This discussion will focus on the portion of the investigation associated with the 903 Pad and the VOC contamination associated with the 903 Pad. The portion of the investigation which encompasses the 903 Lip Area and the Americium Zone deal with radiological contamination which spread from the 903 Pad to the 903 Lip Area by wind and rain and to the Americium Zone primarily by wind dispersion. This airborne contamination has had little or no impact on groundwater.

Work completed during 1998 on the 903 Pad VOC investigation, that are pertinent to this discussion, consisted of the drilling and sampling of eight soil boreholes. The boreholes, which were advanced with a Geoprobe rig, varied in depth from 16 to 22 feet below ground surface and were sampled as composites. The results of these samples will be available in the RMRS 903 Pad Characterization Report to be released in 1999. No new monitoring wells were installed during the investigation of the 903 Pad.

Two existing monitoring wells, 06691 and 08891, both located on the 903 Pad, were sampled on June 10, 1998, in support of the 903 Pad VOC investigation. The results of these samples indicate that high concentrations of VOCs exist beneath the 903 Pad at both locations. Monitoring well 06691, located in

the west central portion of the 903 Pad, had results of 85,000 and 9,400 µg/L for carbon tetrachloride and PCE, respectively. These concentrations are almost double for carbon tetrachloride and almost four times greater for PCE than from the previous sampling event, which took place on July 20, 1994. The concentration of TCE decreased from 2500 µg/L in 1994 to 180 µg/L during the 1998 sampling round. Methylene chloride had a 1998 result of 29,000 µg/L in monitoring well 06691. The 1998 data has not been validated yet, which may be pertinent in the case of methylene chloride, a common laboratory artifact. Methylene chloride contamination is known at well 06691, with validated concentrations as high as 24,000 µg/L observed in November 1992. Monitoring well 08891, located in the northeast quarter of the 903 Pad, was previously sampled on June 19, 1995. The concentration of carbon tetrachloride decreased from 5500 to 5300 µg/L from 1995 to 1998. The concentration of PCE increased from 16,000 to 27,000 µg/L from 1995 to 1998. Methylene chloride, which had historically been non-detect at monitoring well 08891, exhibited a result (not validated) of 11,000 µg/L in 1998. The concentration of TCE at monitoring well 08891 decreased from 2,100 to 1,300 µg/L from 1995 to 1998.

Methylene chloride is a natural degradation product of carbon tetrachloride. The 903 Pad is situated such that groundwater flow tends to bifurcate from beneath the pad with a component of flow trending northeast and another component trending southeast. It is possible that the methylene chloride observed in 1998 at monitoring well 06691 is spreading northeast (and possibly impacting monitoring well 08891) and southeast.

During 1999, nine additional Geoprobe boreholes will be completed as part of the 903 Pad VOC investigation. Four new monitoring wells will be installed during 1999 on the 903 Pad which will twin existing wells that have Pu/Am detections. This work is associated with the Actinide Migration Project. The Site Characterization Report for the 903 Pad will be completed in 1999.

6.6 T-1 Trench Excavation

The T-1 trench is located approximately 40 feet south of the southeast corner of the PA fence at RFETS. The site is also known as IHSS 108. Before its excavation, the trench was anticipated to be approximately 200 feet long, 15 to 20 feet wide, and 10 feet deep. Figure 6-6 presents the location of the T-1 trench. Historical documentation indicates that depleted uranium metal chips, derived from lathe and machine turnings, and originating from Building 444 were packed in drums with lathe coolant and buried in the west end and possibly the east end of the T-1 trench. It was suspected that as many as 125 drums of this material were buried in the trench. In addition, it was suspected that ten drums of cemented cyanide

and one drum of still bottoms, consisting of recovered waste solvents or evaporated lathe coolant sludge, were buried in the trench along with an unknown amount of assorted debris. Drums buried in the trench were covered with one to two feet of soil. The trench was filled intermittently from November 1954 to December 1962. Weed cutting activities in the fall of 1982 revealed two drums which were no longer adequately backfilled. Samples of the liquids and sludges in the drums yielded low levels of plutonium and uranium (potentially enriched). Since the discovery of the drums, numerous site investigations have been conducted along with historical aerial photograph review, a detailed record search, and employee interviews to evaluate the area and to determine the potential contaminants present, (RMRS, 1998e).

The geology of the area surrounding the T-1 trench consists of Rocky Flats Alluvium overlying weathered, predominantly claystone, bedrock of the Arapahoe Formation. In the trench area proper, one or two feet of fill material overlie anywhere from 8-13 feet of alluvium. The alluvium consists of lenses of poorly sorted clayey and silty sand and gravel interbedded with clay and silt lenses. Groundwater in the vicinity of the T-1 trench seasonally varies in depth from approximately 10 to 22 feet below ground surface. In May 1995, a period with abnormally high precipitation, groundwater was measured within six feet of the ground surface. It is likely that groundwater had, on occasion, reached the base of the trench and possibly come into contact with buried drums.

The T-1 trench excavation was completed from June 10 through August 20, 1998. The actual measurements of the excavation were not recorded. Prior to excavation a large, freestanding, temporary structure was constructed over the trench. This tent allowed for the excavation, inerting, and stockpiling of soil and waste regardless of weather conditions. One hundred seventy one drums or containers were removed from the trench during the excavation activities. Other than drum carcasses very little debris was encountered. Results of the sidewall and excavation floor verification samples indicate that all criteria in the *Final Proposed Action Memorandum for the Source Removal at Trench 1, IHSS 108* were met. For radionuclides and cyanide, subsurface soils were cleaned up to below Tier II action levels; for VOC's, subsurface soils were cleaned up to below Tier I action levels (RMRS, 1999i).

The T-1 trench may have possibly been a contributor to the contaminated groundwater that comprises the Mound Plume. As such, any groundwater contamination resulting from the leaching of the T-1 trench waste would be remediated by the now operating Mound Site Plume Treatment System (see Section 6.1).

Work to be performed on the project during 1999 will consist of removal of the T-1 trench tent structure in March and April, with final site reclamation to be completed by September 1999.

7.0 OTHER GROUNDWATER PROGRAM ACTIVITIES

7.1 Well Control Program

The Well Control Program (WCP) establishes the administrative guidelines for the installation of all new monitoring wells and piezometers at RFETS. The procedures which comprise the WCP will be implemented through the Water Operations Division; more specifically Groundwater Operations. The WCP was integrally designed to assure compliance with the procedures for monitoring well installations at RFETS and the complete documentation of all pertinent data relative to all monitoring wells installed at RFETS. It also assures compliance with the regulations set forth by the State of Colorado, Office of the State Engineer, State Board of Examiners of Water Well Construction and Pump Installation Contractors, in 2 CCR 402-2, *Revised and Amended Rules and Regulations of the Board of Examiners of Water Well Construction and Pump Installation Contractors*. The WCP also provides guidance to the organization or individual responsible for installation of the monitoring well(s) or piezometer(s) regarding the interface between the WCP and applicable RFETS soil disturbance procedures.

A Well Control Program was originally placed in effect by EG&G on June 1, 1995. After one year the original WCP expired and was not reinstated. The new WCP described in this section will be adopted in 1999. The new procedure document number is 1-K92-RFP-94-001, Revision 1.

The WCP has come back into existence because Groundwater Operations has been formally identified as the party ultimately responsible for well installation documentation. The purpose of the WCP program is threefold. First, to protect groundwater at RFETS from improper drilling and well installation procedures, and to ensure that each installation receives a unique well name. Second, to ensure that all permitting activities required by the State of Colorado are complied with. Third, to create a central repository for data collection and management with respect to all data generated from the installation and sampling of new monitoring wells and piezometers.

7.2 Real Time Groundwater Monitoring Network

As a requirement of the RFETS Integrated Monitoring Plan, a real time water level monitoring network was established for the UHSU during 1998. The network consists of twenty-five monitoring wells outfitted with In-Situ Inc., Model SP4000, Troll® data logging systems. The twenty-five monitoring locations were chosen for the program based on surface location, historical groundwater occurrence at each location, stratigraphic completion interval, and well construction details. The network provides for simultaneous measurement of groundwater levels at all locations. The goals of the real time groundwater

monitoring network are to provide ample, concurrent, water level measurements for environmentally or hydrogeologically sensitive areas of RFETS, such as beneath and downgradient of the IA, and along stream channels to the north, south, and east of the IA. This data, when used alone or in conjunction with similarly collected surface water data, will allow a greater understanding of the effects of precipitation and surface water infiltration events on the UHSU.

The Troll is a compact downhole instrument that contains a data logger, temperature sensor, pressure transducer, and battery in a self-contained watertight unit. It measures and records temperature and temperature-corrected water level and allows for unattended long-term monitoring. It is programmed and downloaded with a portable computer. In-Situ Inc.'s Win-Situ[®] software allows the user to communicate with the Trolls in order to program a variety of short-term tests, a long-term monitoring scheme (such as is currently being implemented at RFETS), or to download data.

The real time groundwater monitoring network was activated with the initial twenty five monitoring stations on Wednesday, June 17, 1998. At this time all of the Trolls are programmed to measure the water level in each well every four hours; twelve A.M., four A.M., eight A.M., twelve P.M., four P.M., and eight P.M. As shown on Plate 11 and Figure 7-1, monitoring wells utilized for the real time groundwater monitoring network are located to provide sitewide coverage with concentration in the IA and immediately east of the IA. In addition, locations were chosen to monitor water levels in colluvial, alluvial, and weathered bedrock (pediment surface) deposits within the UHSU. The arrangement of Trolls throughout RFETS will allow observation, simultaneously across the site, of the impact of a precipitation infiltration event on the UHSU. The location of the Trolls within the various sedimentary depositional environments and weathered bedrock which comprise the UHSU will allow for a better understanding of the relationship between groundwater and surface water at various locations around RFETS.

The monitoring wells currently included in the real time groundwater monitoring network are 1086, 3686, 4786, 5586, 6886, 0187, 1487, P114889, P115489, P119389, P209889, P213689, P415889, P416589, B200589, B210489, 03791, 05191, 20691, 20991, 37591, 77492, 05293, 10794, and 51494.

There are certain wells where incomplete or very little data exists from the startup date of approximately June 17, 1998, through the end of calendar year 1998. Monitoring wells 20991 and 4786 had the Trolls initially installed under a water column of greater than 34.5 feet. This exceeded the 15 pounds per square inch (psi) rating of the Trolls. This was remedied by raising the Trolls in the wells so that the water column did not exceed the 15 psi rating. These are the only two wells in the real time groundwater

monitoring system that could be affected by this phenomenon. In addition, there were a few monitoring wells for which data or partial data was inadvertently lost in the field because of operator error while learning to operate the Trolls, or upon downloading the Trolls. Because of these errors, there is no 1998 data for real time groundwater monitoring stations 4786, 51494, and 6886.

Data collected from the real time groundwater-monitoring network has been analyzed for the period of June 17 through December 31, 1998, for presentation in this 1998 Groundwater Monitoring RFCA Annual Report. Plate 11 presents the monitoring locations with a hydrograph of the groundwater level data collected from that station. Superimposed on the hydrograph is precipitation data from the particular surface water station at RFETS that is closest to the individual real time groundwater monitoring station. The hydrographs and precipitation data imply that responses to precipitation events are varied across RFETS. The following are general observations from the first one-half year of real time groundwater monitoring data:

Wells in or immediately adjacent to creek beds generally exhibit an almost immediate response to precipitation events. This includes wells B210489, 3686, and 6886. Well 10794, downstream of the A-Ponds, appears to be the exception. This well appears to only show responses to discharges from Pond A-4.

Wells east and southeast of the IA (1487, 05191, 03791, and 20991) generally exhibit baseflow conditions with little or no response to individual precipitation events. These wells show a relatively smooth decline in water level during the last six months of 1998. Well 20691, located just southeast of the southeast corner of the PA, exhibits this general trend but does have precipitation events superimposed on the baseflow in a subtle manner. This well is screened in a buried paleochannel and that may account for its sensitivity.

Wells in the IA (including the PA), of which there are 11 with Trolls, generally exhibit a response time to precipitation events of approximately a few days to up to ten days. One exception to this is well P114889, located just southeast of the southwest corner of the PA, which exhibits a general decline in baseflow with no precipitation events superimposed on it. It is situated between two wells with Trolls, P119389 and P115489, which exhibit a marked response to precipitation events. Another exception is well P209889, located on the hillside just north of the SEPs, which exhibits a baseflow decline with only very minor precipitation response.

Well 0187, located on the hillside just southwest of Building 881, shows the greatest and most immediate response of any well, other than those in drainages, to a precipitation event.

Well 1086, located immediately upgradient of the Present Landfill, exhibits an approximately one-week response time to precipitation events superimposed on baseflow.

The series of wells trending from the southwest to the northeast in the buffer zone north of the IA is expected to exhibit natural flow conditions along the high pediment surface without the effects of the plant site. These wells include 4786 and B200589, as well as 11494, 1190, and B200889 which will be added to the network during 1999. Wells 51494 and 5586 probably exhibit the same sort of background baseflow to which plant site wells can be compared. This may allow for a better understanding of the plant site's affect on an individual well's response to recharge or dewatering events.

The 1999 Annual RFCA Groundwater Monitoring Report will present one and a half years of groundwater and precipitation data on the hydrographs. More than a full yearly cycle will be displayed allowing for more complete analysis and discussion.

The following monitoring wells are scheduled to have Trolls installed in them and be added to the real time groundwater monitoring network during 1999: 0186, 3986, 1587, 4287, P414189, B200889, 1190, and 11494 (Figure 7-1). In addition, during 1999 all real time groundwater-monitoring stations will be brought into compliance for year 2000.

7.3 Well Abandonment and Installation

Figure 7-2 presents the locations of all 1998 monitoring well installations and abandonments.

During 1998 there were 67 monitoring wells installed at RFETS. Of the 67 wells, 61 were installed for the purpose of plume characterization, and six were installed as part of Building 123 D&D activities. All of these monitoring wells were installed with a Geoprobe to monitor the UHSU. Following is a listing of 1998 monitoring well installations by area:

- Monitoring wells 00198 – 02298 were installed as part of the 903 Pad/Ryan's Pit Plume characterization project.
- Monitoring wells 02398 – 02898, 03598, 03698, and 03998 – 04298 were installed as part of the East Trenches/B-Ponds characterization project.
- Monitoring wells 03198 – 03498 were installed as part of the Solar Ponds Plume study.
- Monitoring wells 10098 – 10598 were installed to monitor Building 123 D&D activities.
- Monitoring wells 20098 – 22298 were installed to monitor the North Industrial Area Plume.

During 1998 there were 35 monitoring wells abandoned at RFETS. The wells were abandoned because they were located in areas where treatment systems were going to be constructed or site remediation was taking place. Following is a list of 1998 well abandonments by area:

- Monitoring wells 10297 – 11297, 11497, 11597, and 11797 were abandoned as part of the construction activities associated with the SW059/Mound Site Plume treatment system.
- Monitoring wells 22597 – 23997, 24197 – 24497, and 25097 were abandoned as part of the construction activities associated with the B-Ponds/East Trenches Plume treatment system.
- Monitoring well 2387 was abandoned because of its proximity to the T-1 Trench excavation.

8.0 CONCLUSIONS AND FUTURE ACTIVITIES

The groundwater program experienced a number of improvements during 1998 and set projects in motion which will be accomplished in 1999. The following conclusions can be made with respect to the groundwater program based on the detailed discussions found elsewhere in the report.

Data collection and data quality for groundwater samples collected in 1998 have improved in the areas of data validation and verification. Much of this information was readily available and could be included in the data quality assessment section. Though the validation and verification percentages are not at the required levels the results show that only a small percentage of the analytical data is rejected. In addition, procedural improvements have been made in 1999 that will help collect more samples from wells that have low recharge. This will be done by timing visits based on an approximate recharge rate rather than a set time period.

The implementation of the real time monitoring network will also improve the understanding of the nature of recharge at RFETS and will potentially shed light on discharge and flow rates.

With respect to groundwater reporting, changes have been made to this years Annual RFCA Groundwater Monitoring Report based on input from the regulatory community. This report tried to focus on data evaluation as opposed to data presentation. Individual wells have been discussed more completely and the results of groundwater evaluations have been expanded. The actual data used in the annual report will be provided in the RFCA Quarterly reports and not reproduced here. The RFCA Quarterly reports have stayed the same except for some changes in the format of the report.

The Building D&D monitoring program was expanded with the addition of the Building 123 monitoring network. D&D monitoring for Bldg. 444, 886 and 771 will be implemented in 1999.

The largest programmatic improvement for groundwater has been in the characterization and quantification of groundwater plume nature and extent. Evaluation of the East Trenches Plume resulted in a remedial strategy involving the construction of a passive VOC treatment system which will be installed in 1999. The Solar Ponds nitrate/uranium plume also received additional characterization and modeling of contaminant fluxes. This has also resulted in a remedial decision to construct a groundwater treatment system in 1999.

Characterization activities were also initiated for the Ryan's Pit/903 Pad Plume with installation of a line of temporary wells and estimation of plume flux to Woman Creek. A natural attenuation project will be

implemented in 1999 to determine whether contaminants are naturally degrading prior to impacting surface water.

Groundwater evaluation of the northern end of the Industrial Area plume has revealed significant contamination that may be reaching surface water from both the IA plume, and the carbon tetrachloride plume, which has IHSS 118.1 as its source. A natural attenuation study was also implemented for the IHSS 118.1 source area. Future groundwater evaluations will involve establishment of the eastern extent of the IA plume and investigating natural attenuation at the PU&D Yard Plume.

Given the large amount of new data with respect to the nature and extent of groundwater contamination at RFETS, a review of the groundwater monitoring network will be done in FY00. It is anticipated that some minor changes will be made to the monitoring based on this evaluation. Specific areas of review would include the north IA, the Present Landfill, and the Ryan's Pit source area which have shown evidence of increased extent or concentrations of contaminants.

9.0 REFERENCES

- DOE, 1991. Phase I RFI/RI Work Plan for Operable Unit No. 7 - Present Sanitary Landfill (IHSS No. 114) and the Inactive Hazardous Waste Storage Area (IHSS No. 203) (Operable Unit No. 7). U.S. Department of Energy, Rocky Flats Plant, Golden, Colorado. August 1991.
- DOE, 1992a. *Final Historical Release Report for the Rocky Flats Plant*, U.S. Department of Energy, Rocky Flats Plant, Golden, Colorado, June.
- DOE, 1992b. *Historical Release Report for the Rocky Flats Plant*, Rocky Flats Plant, Golden, CO, June.
- DOE, 1992b. *Interim Measure/Interim Remedial Action French Drain Performance Monitoring Plan*, U.S. Department of Energy, June.
- DOE, 1993a. *Final Ground Water Assessment Plan*, U.S. Department of Energy, Rocky Flats Plant, Golden, Colorado, February, 24.
- DOE, 1993b. *Background Geochemical Characterization Report*. EG&G Rocky Flats, Inc., Golden, Colorado. September 1993.
- DOE, 1994a. *Technical Memorandum No. 1, Investigations of Foundation Drains and Other Data Compilation, Addendum to the Operable Unit 8 Work Plan*, Rocky Flats Environmental Technology Site, 700 Area, RFP/ERM-TM1-94-00011, Draft Final, November, 1994.
- DOE, 1994b. *Final Interim Measures/Interim Remedial Action Decision Document for the Rocky Flats Industrial Area*, U.S. Department of Energy, Rocky Flats Plant, Golden, Colorado, March.
- DOE, 1996a. *1995 Annual RCRA Groundwater Monitoring Report for Regulated Units at the Rocky Flats Environmental Technology site*, Golden, Colorado, February 29, 1996.
- DOE, 1996b. *Annual Update for the Historical Release Report, August 1, 1995 through August 1, 1996*, RF/ER 96-0046, September.
- DOE, 1997a. *Background Comparison for Radionuclides in Groundwater*, Draft, January, 1997.
- DOE, 1997b. *1996 Annual RFCA Groundwater Monitoring Report for Rocky Flats Environmental Technology Site*, RF/RMRS-97-087.UN, November 1997.
- DOE, 1997c. *Final Mound Site Plume Decisions document*, RF RMRS-97-024.UN, September.
- DOE, 1998. *1997 Annual RFCA Groundwater Monitoring Report for Rocky Flats Environmental Technology Site*, RF/RMRS-98-293.UN, November 1998.
- DOE, 1998b. *1997 Groundwater Monitoring at the Present Sanitary Landfill*. Rocky Flats Environmental Technology Site. Golden, Colorado. August 10, 1998.
- EG&G, 1991a. *Final Geologic Characterization Report for the U.S. D.O.E Rocky Flats Plant*.
- EG&G, 1992. *1991 Annual RCRA Groundwater Monitoring Report for Regulated Units at the Rocky Flats Plant*, Golden, Colorado, March.
- EG&G, 1993a. *Background Geochemical Characterization Report*, Rocky Flats Plant, Golden, Colorado, September.

- EG&G, 1993b. Ground-water Recharge Study, Final Interim Report Rocky Flats Plant, Golden, Colorado, October.
- EG&G, 1993c. 1992 Annual RCRA Groundwater Monitoring Report for Regulated Units at the Rocky Flats Plant, Golden, Colorado, March.
- EG&G, 1993d. Groundwater Protection and Monitoring Program Plan for Rocky Flats Plant, Golden, Colorado, October.
- EG&G, 1994a. Well Evaluation Report Final, EG&G Rocky Flats, Inc., Golden, Colorado, April.
- EG&G, 1994b. 1993 Annual RCRA Groundwater Monitoring Report for Regulated Units at the Rocky Flats Plant, February.
- EG&G, 1995a. Geologic Characterization Report for the Rocky Flats Technology Site, Sitewide Geoscience Characterization Study, Vol I, March.
- EG&G, 1995b. Hydrogeologic Characterization Report for the Rocky Flats Technology Site, Sitewide Geoscience Characterization Study Vol II. April.
- EG&G, 1995c. Groundwater Geochemistry Report For the Rocky Flats Environmental Technology Site, Sitewide Geoscience Characterization Study Vol. III, January.
- EG&G, 1995d. 1994 Annual RCRA Report for Regulated Units at the Rocky Flats Environmental Technology Site, March.
- EPA, 1992a. Guidance for Data Usability in Risk Assessment, Final. EPA/9285.7-09.
- EPA, 1992b, Statistical Analysis of Ground-Water Monitoring Data at RCRA Facilities, Draft Addendum to Interim Final Guidance, Washington, D.C., July 1992.
- Fetter, G.W. Jr., 1998. Applied Hydrogeology, 2nd ed., Merrill Publishing Company, Columbus OH.
- Haun, J. D. and H. C. Kent, 1965. Geologic History of the Rocky Mountain Region, Bull. of the American Association of Petroleum Geologists, v 49, no. 11, p. 1781-1800.
- IAG, 1991. State of Colorado, U.S. Environmental Protection Agency, and U.S. Department of Energy, Rocky Flats Interagency Agreement: Federal Facility Agreement and Consent Order, CERCLA-VIII-91-03, RCRA (3008(h))-VIII-91-07, State of Colorado Docket #91-01-22-01, Jan. 22.
- K-H 1998a. Rocky Flats Environmental Technology Site Integrated Monitoring Plan Document.
- K-H 1998b. Rocky Flats Environmental Technology Site Integrated Monitoring Plan Background Document.
- McLane Environmental, L.L.C. 1998, Conceptual Model for Hydrogeologic Evaluation of Remedial Alternatives for the Solar Ponds Plume, March 9, 1998.
- Pearl, R. H., 1980. "Ground-Water Resources of Colorado" in: Colorado Geology, H. C. Kent and K. W. Porter eds.
- RFCA, 1996. Final Rocky Flats Cleanup Agreement, U.S. Department of Energy, Colorado Department of Health and Environment, U.S. Environmental Protection Agency, July, 1996.

- RMRS, 1996a. White Paper - Analysis of Vertical Contaminant Migration Potential, Final Report, RF/ER-96-0040. UN., August 16, 1996.
- RMRS, 1996b. Conceptual Plan for the Management and Remediation of Groundwater at the Rocky Flats Environmental Technology Site, RF/ER-95-0121, Rev. 2, Environmental Restoration Program, Rocky Flats Environmental Technology Site, Golden, Colorado, March.
- RMRS, 1996c, Final Revised Groundwater Conceptual Plan, RF/ER-95-0121.UN, September.
- RMRS, 1996d, Completion Report for the Source Removal at Trenches T-3 and T-4 (IHSSs 110 and 111.1), RF/ER-96-0051, September.
- RMRS, 1997, Sampling and Analysis Plan for the Site Characterization of the 903 Drum Storage Area (IHSS 112), 903 Lip Area (IHSS 155), and Americium Zone, RF/RMRS-97-084, January 1998 Rev.0.
- RMRS, 1998a, 1998 First Quarter RFCA Groundwater Monitoring Report for Rocky Flats Environmental Technology Site, RF/RMRS-98-265.UN, August 1998.
- RMRS, 1998b, 1998 Second Quarter RFCA Groundwater Monitoring Report for Rocky Flats Environmental Technology Site, RF/RMRS-98-292.UN, November 1998.
- RMRS, 1998c. Final Sampling and Analysis Plan for Monitoring of Natural Attenuation at IHSS 118.1, October.
- RMRS 1998d. Final Sampling and Analysis Plan for the Site Characterization of the 903 Drum Storage Area, 903 Lip Area, and Americium Zone, RF/RMRS-97-084, Rev. 1, August.
- RMRS 1998e, Final Proposed Action Memorandum for the Source Removal at Trench 1, IHSS 108, RF/RMRS-97-011, Rev. 5, March.
- RMRS, 1999a, 1998 Third Quarter RFCA Groundwater Monitoring Report for Rocky Flats Environmental Technology Site, RF/RMRS-99-324.UN, February 1999.
- RMRS, 1999b, 1998 Fourth Quarter RFCA Groundwater Monitoring Report for Rocky Flats Environmental Technology Site, RF/RMRS-99-351.UN, May 1999.
- RMRS, 1999c, Sampling and Analysis Plan for Groundwater Investigations Involving Actinide Drilling-Artifact Contamination, the Industrial Area VOC Plume East Boundary, and Solar Ponds Plume Well Installations, RF/RMRS-99-347, July, 1999.
- RMRS, 1999d. Status Report for Monitoring of Natural Attenuation at IHSS 118.1. August
- RMRS, 1999e. Final Mound Site Plume Project Completion Report, RF/RMRS-98-289.UN, May.
- RMRS 1999f, Draft Solar Ponds Plume Decision Document, RF/RMRS-98-286.UN, January.
- RMRS, 1999g, Final Proposed Action Memorandum for the East Trenches Plume, RF/FMRS-98-258.UN, February.
- RMRS 1999h, Final Technical Memorandum, Monitoring of the 903 Pa/Ryan's Pit Plume, Revision 0, RF/RMRS-98-294.UN, May.
- RMRS 1999i, Closeout Report for the Source Removal at the Trench 1 Site IHSS 108.

- RMRS/KH, 1996. 1995 Annual RCRA Report for Regulated Units at Rocky Flats Environmental Technology Site, February.
- Scott, G. R., 1975. Cenozoic Surfaces and Deposits in the Southern Rocky Mountains, In Cenozoic History of the Southern Rocky Mountains, Curtis, B. F., ed., Geological Society of America Memoir 144.
- Shroba, R. R. and P. E. Carrara, 1994. Preliminary Surficial Geologic Map of the Rocky Flats Plant and Vicinity, Jefferson and Boulder Counties, Colorado, U.S. Geological Survey Open-file Report, OFR-94-162.
- Spencer, F. D., 1961. Bedrock Geology of the Louisville Quadrangle, Colorado. USGS. Geological Quadrangle Map GQ-151, lat. 39 52' 30" to 40 long 105 07' 30" to 105 15' scale 1:24000, contour interval 10 feet.
- Wiedemeier, T.H., M. A. Swanson, D. E. Moutoux, J. T. Wilson, D. H. Kampbell, J. E. Hansen, and P. Haas, 1996, Overview of the Technical Protocol for Natural Attenuation of Chlorinated Aliphatic Hydrocarbons in Ground Water Under Development for the U. S. Air Force Center for Environmental Excellence, Proceedings of the Symposium on Natural Attenuation of Chlorinated Organics in Ground Water, Dallas, Texas, September 11-13, 1996, EPA/540/R-97/504.
- Wiedemeier, T. H., Rifai, H. S., Newell, C.J., Wilson, J. T., 1999, Natural Attenuation of Fuels and Chlorinated Solvents in the Subsurface. John Wiley, New York.

TARGET SHEET

Plate 1:

IMP Monitoring Well Location Map

Map ID: FY99, RFCA

September 23, 1999

DOE/RFFO CERCLA Administrative Record: SW-A-003446

TARGET SHEET

Plate 2:

Potentiometric Surface
of Unconsolidated
Surficial Deposits,
Second Quarter 1998

Map ID: 99-0350

September 28, 1999

DOE/RFFO CERCLA Administrative Record: SW-A-003446

TARGET SHEET

Plate 3:

Potentiometric Surface
of Unconsolidated
Surficial Deposits,
Fourth Quarter 1998

Map ID: 99-0350

September 13, 1999

DOE/RFFO CERCLA Administrative Record: SW-A-003446

TARGET SHEET

Plate 4:

Radionuclides in Groundwater RFCA Wells, 1998

Map ID: 99-0352

August 13, 1999

DOE/RFFO CERCLA Administrative Record: SW-A- 003446

TARGET SHEET

Plate 5: VOCs in Groundwater RFCA Wells, 1998

Map ID: 99-0352

September 1, 1999

DOE/RFFO CERCLA Administrative Record: SW-A-003446

TARGET SHEET

Plate 6: Water Quality Parameters in Groundwater RFCA Wells, 1998

Map ID: 99-0331

September 2, 1999

DOE/RFFO CERCLA Administrative Record: SW-A- 003446

TARGET SHEET

Plate 7:

Nitrate Concentration in
Groundwater 1991-1998
(Avg.)

Map ID: RFCA-RPT

September 1, 1999

DOE/RFFO CERCLA Administrative Record: SW-A-003446

TARGET SHEET

Plate 8:

Water Level Change
Map 1996 - 1998
Second Quarter Data

Map ID: 99-0381

September 1, 1999

DOE/RFFO CERCLA Administrative Record: SW-A-003446

TARGET SHEET

Plate 9:

Water Level Change
Map 1996 - 1998
Fourth Quarter Data

Map ID: 99-0381

August 13, 1999

DOE/RFFO CERCLA Administrative Record: SW-A- 003446

TARGET SHEET

Plate 10: VOCs Composite Plume Map

Map ID: FY99 RFCA RPT

November 9, 1999

DOE/RFFO CERCLA Administrative Record: SW-A- 003446

TARGET SHEET

Plate 11:

Real-Time Groundwater Monitoring Location Hydrographs with Precipitation Data

Map ID: 98-0191

September 1, 1999

DOE/RFFO CERCLA Administrative Record: SW-A- 003446

Appendix A

1998 Water Level Data

DRAFT

Appendix A

RF/RMRS-99-433.UN

Location	Date	Water Level from TOC (ft.)	Water Level Elevation (ft.)	Dry or Technically Dry (W.L. below scrm)	Bottom Screen Elevation
00191	1/14/98	18.81	5951.63		5945.44
00191	4/6/98	9.35	5961.09		5945.44
00197	4/7/98	5.81	5921.69		5918.10
00197	5/13/98	6.10	5921.40		5918.10
00197	7/1/98	9.34	5918.16		5918.10
00197	10/6/98	8.78	5918.72		5918.10
00293	1/12/98	25.02	6027.42		6004.44
00293	2/3/98	25.21	6027.23		6004.44
00293	3/2/98	25.24	6027.20		6004.44
00293	4/10/98	24.09	6028.35		6004.44
00293	5/5/98	20.39	6032.05		6004.44
00293	6/1/98	19.49	6032.95		6004.44
00293	7/9/98	20.87	6031.57		6004.44
00293	8/3/98	21.66	6030.78		6004.44
00293	9/3/98	22.15	6030.29		6004.44
00293	10/5/98	22.83	6029.61		6004.44
00293	11/2/98	23.42	6029.02		6004.44
00293	12/7/98	24.34	6028.10		6004.44
00297	1/7/98	11.01	5963.91	X	5966.62
00297	2/5/98	10.98	5963.94	X	5966.62
00297	3/3/98	11.11	5963.81	X	5966.62
00297	4/8/98	10.06	5964.86	X	5966.62
00297	7/7/98	9.65	5965.27	X	5966.62
00297	10/7/98	9.49	5965.43	X	5966.62
00391	1/14/98	4.28	5918.12		5900.60
00391	4/6/98	1.98	5920.42		5900.60
00397	4/7/98	11.00	5927.03	X	5929.03
00397	5/8/98	11.41	5926.62	X	5929.03
00397	7/1/98			DRY	5929.03
00397	10/6/98			DRY	5929.03
00491	1/8/98	12.85	5892.12		5887.47
00491	4/9/98	9.78	5895.19		5887.47
00597	1/7/98	10.92	5973.61		5963.63
00597	4/7/98	5.35	5979.18		5963.63
00597	5/8/98	5.62	5978.91		5963.63
00597	7/1/98	9.97	5974.56		5963.63
00597	10/5/98	12.03	5972.50		5963.63
00697	1/13/98			DRY	5968.04
00697	4/9/98			DRY	5968.04
00697	7/1/98			DRY	5968.04
00697	10/6/98	11.66	5964.38	X	5968.04
00797	1/13/98	23.49	5917.51		5914.20
00797	2/9/98	22.00	5919.00		5914.20
00797	3/2/98	27.72	5913.28	X	5914.20

214 215

00797	4/9/98	24.78	5916.22		5914.20
00797	7/2/98	18.70	5922.30		5914.20
00797	10/8/98	21.87	5919.13		5914.20
00891	1/8/98			DRY	5852.05
00891	2/9/98			DRY	5852.05
00891	3/3/98			DRY	5852.05
00891	4/9/98			DRY	5852.05
00891	5/5/98			DRY	5852.05
00891	6/5/98			DRY	5852.05
00891	7/1/98			DRY	5852.05
00891	8/4/98			DRY	5852.05
00897	4/8/98	16.78	5950.82		5939.10
00897	7/8/98	19.56	5948.04		5939.10
00897	10/5/98	21.87	5945.73		5939.10
00997	1/5/98	5.80	5796.10		5791.50
00997	2/5/98	5.82	5796.08		5791.50
00997	3/3/98	5.82	5796.08		5791.50
00997	4/13/98	5.19	5796.71		5791.50
00997	5/5/98	4.49	5797.41		5791.50
00997	6/2/98	4.87	5797.03		5791.50
00997	7/1/98	5.69	5796.21		5791.50
00997	8/4/98	11.02	5790.88	X	5791.50
00997	9/3/98	6.08	5795.82		5791.50
00997	10/6/98	5.97	5795.93		5791.50
00997	11/4/98	5.92	5795.98		5791.50
00997	12/3/98	5.88	5796.02		5791.50
01097	5/8/98	11.74	6017.26		5989.20
01197	1/16/98	13.24	6002.04		5987.28
01197	5/8/98	6.84	6008.44		5987.28
01291	1/8/98	17.08	5835.77	X	5839.55
01291	4/9/98	17.07	5835.78	X	5839.55
01291	10/6/98	13.70	5839.15	X	5839.55
01297	5/8/98	2.21	6013.89		5982.10
01391	1/7/98	10.72	5964.58		5961.30
01391	2/9/98	10.75	5964.55		5961.30
01391	3/5/98	11.08	5964.22		5961.30
01391	4/1/98	10.51	5964.79		5961.30
01391	5/6/98	9.81	5965.49		5961.30
01391	6/3/98	10.04	5965.26		5961.30
01391	7/1/98	10.39	5964.91		5961.30
01391	8/4/98	10.65	5964.65		5961.30
01391	9/8/98	11.03	5964.27		5961.30
01391	10/5/98	11.39	5963.91		5961.30
01391	11/5/98	11.62	5963.68		5961.30
01391	12/7/98	11.36	5963.94		5961.30
01397	5/8/98	1.31	6005.63		5984.74
01497	5/8/98	3.97	5999.93		5980.80
01597	5/8/98	4.50	6001.86		5976.76
01697	5/8/98	17.11	5981.85		5970.76

2/16/98 2/16

DRAFT

Appendix A

RF/RMRS-99-433.UN

01797	5/8/98	15.71	5981.29		5975.00
0186	1/5/98	9.45	5619.87		5619.12
0186	2/9/98	9.19	5620.13		5619.12
0186	3/3/98	8.99	5620.33		5619.12
0186	4/13/98	8.51	5620.81		5619.12
0186	5/4/98	8.95	5620.37		5619.12
0186	6/4/98	9.71	5619.61		5619.12
0186	7/2/98	10.71	5618.61	X	5619.12
0186	8/4/98	11.96	5617.36	X	5619.12
0186	9/1/98	12.31	5617.01	X	5619.12
0186	10/8/98			DRY	5619.12
0186	11/3/98			DRY	5619.12
0186	12/4/98	9.94	5619.38		5619.12
0187	1/6/98	9.79	5984.29		5982.28
0187	3/12/98	10.71	5983.37		5982.28
0187	4/8/98	6.91	5987.17		5982.28
0187	5/7/98	7.22	5986.86		5982.28
0187	6/3/98	8.56	5985.52		5982.28
0187	6/18/98	9.00	5985.08		5982.28
0187	7/8/98	9.68	5984.40		5982.28
01897	5/8/98	10.06	5980.44		5967.70
0190	1/12/98	36.00	6009.88		6001.38
0190	2/4/98	36.00	6009.88		6001.38
0190	3/4/98	36.64	6009.24		6001.38
0190	4/10/98	31.30	6014.58		6001.38
0190	5/5/98	25.13	6020.75		6001.38
0190	6/1/98	27.88	6018.00		6001.38
0190	7/9/98	32.25	6013.63		6001.38
0190	8/3/98	33.67	6012.21		6001.38
0190	9/3/98	34.64	6011.24		6001.38
0190	10/5/98	35.61	6010.27		6001.38
0190	11/2/98	36.22	6009.66		6001.38
0190	12/2/98	36.77	6009.11		6001.38
01997	5/8/98	7.66	5978.24		5973.90
02097	5/8/98	3.72	5972.03		5963.85
02197	4/7/98	5.34	5955.36		5949.80
02197	5/8/98	6.03	5954.67		5949.80
02197	7/1/98	10.81	5949.89		5949.80
02197	10/6/98	12.82	5947.88	X	5949.80
02297	1/12/98	12.20	5966.45	X	5966.65
02297	2/5/98	12.25	5966.40	X	5966.65
02297	3/3/98	12.37	5966.28	X	5966.65
02297	4/8/98	11.43	5967.22		5966.65
02297	7/7/98	12.22	5966.43	X	5966.65
02297	10/7/98	12.43	5966.22	X	5966.65
02397	1/12/98	10.53	5976.28		5975.81
02397	2/5/98	11.31	5975.50	X	5975.81
02397	3/3/98			DRY	5975.81
02397	4/8/98	9.06	5977.75		5975.81

28
217

02397	7/7/98	11.46	5975.35	X	5975.81
02397	10/7/98	11.42	5975.39	X	5975.81
02497	1/12/98	8.71	5970.71		5968.42
02497	2/5/98	8.85	5970.57		5968.42
02497	3/3/98			DRY	5968.42
02497	4/8/98	5.94	5973.48		5968.42
02497	7/7/98	8.11	5971.31		5968.42
02497	10/7/98	9.31	5970.11		5968.42
02591	1/16/98	43.33	5882.01		5876.24
02591	5/11/98	39.24	5886.10		5876.24
02691	2/19/98	10.33	5926.05		5920.38
02691	3/11/98	10.15	5926.23		5920.38
02691	4/2/98	7.82	5928.56		5920.38
02691	5/6/98	6.71	5929.67		5920.38
02691	6/5/98	7.15	5929.23		5920.38
02697	1/6/98	24.57	5893.33		5891.80
02697	2/9/98	24.59	5893.31		5891.80
02697	3/4/98	24.68	5893.22		5891.80
02697	4/1/98	24.16	5893.74		5891.80
02697	5/7/98	21.72	5896.18		5891.80
02697	7/2/98	21.57	5896.33		5891.80
02697	10/12/98	22.70	5895.20		5891.80
02797	1/6/98	37.62	5893.90		5890.12
02797	2/9/98	37.67	5893.85		5890.12
02797	3/4/98	37.77	5893.75		5890.12
02797	4/1/98	37.81	5893.71		5890.12
02797	5/7/98	35.07	5896.45		5890.12
02797	7/6/98	34.01	5897.51		5890.12
02797	10/12/98	35.47	5896.05		5890.12
02897	1/6/98	36.57	5893.18		5892.95
02897	2/9/98	36.62	5893.13		5892.95
02897	3/4/98	36.73	5893.02		5892.95
02897	4/1/98	36.75	5893.00		5892.95
02897	5/7/98	34.49	5895.26		5892.95
02897	7/6/98	33.49	5896.26		5892.95
02897	10/12/98	34.81	5894.94		5892.95
0290	1/12/98	47.27	6003.38		5993.15
0290	2/4/98	47.22	6003.43		5993.15
0290	3/4/98	47.37	6003.28		5993.15
0290	4/10/98	46.79	6003.86		5993.15
0290	5/5/98	42.80	6007.85		5993.15
0290	6/1/98	41.78	6008.87		5993.15
0290	7/9/98	43.47	6007.18		5993.15
0290	8/3/98	44.34	6006.31		5993.15
0290	9/3/98	45.04	6005.61		5993.15
0290	10/5/98	45.67	6004.98		5993.15
0290	11/2/98	46.03	6004.62		5993.15
0290	12/2/98	46.43	6004.22		5993.15
03191	1/13/98	20.18	5931.84		5930.82

DRAFT

Appendix A

RF/RMRS-99-433.UN

03191	4/1/98	18.36	5933.66		5930.82
03191	5/11/98	16.10	5935.92		5930.82
03191	10/12/98	20.14	5931.88		5930.82
03198	3/3/98	4.50	5925.00		5917.50
03198	4/8/98	0.83	5928.67		5917.50
03198	5/6/98	1.96	5927.54		5917.50
03198	6/5/98	4.40	5925.10		5917.50
03298	3/3/98	18.31	5930.19		5923.50
03298	4/8/98	14.91	5933.59		5923.50
03298	5/6/98	15.38	5933.12		5923.50
03298	6/5/98	16.90	5931.60		5923.50
03398	3/5/98	11.90	5915.60		5908.50
03398	4/8/98	9.34	5918.16		5908.50
03398	5/7/98	10.16	5917.34		5908.50
03398	6/5/98	11.07	5916.43		5908.50
03498	3/4/98			DRY	5878.50
03498	4/9/98			DRY	5878.50
03498	5/7/98	14.75	5879.75		5878.50
03498	6/5/98	13.86	5880.64		5878.50
03591	5/11/98	18.18	5932.62		5920.70
03691	1/13/98	33.46	5900.97		5894.43
03691	5/11/98	34.75	5899.68		5894.43
03791	1/13/98	37.91	5900.33		5890.24
03791	3/11/98	38.47	5899.77		5890.24
03791	4/1/98	38.20	5900.04		5890.24
03791	5/5/98	34.33	5903.91		5890.24
03791	6/4/98	33.69	5904.55		5890.24
03791	6/17/98	34.26	5903.98		5890.24
03791	7/2/98	35.15	5903.09		5890.24
0386	1/5/98	17.11	5660.75		5654.16
0386	2/9/98	17.18	5660.68		5654.16
0386	3/3/98	17.18	5660.68		5654.16
0386	4/13/98	16.41	5661.45		5654.16
0386	5/4/98	15.49	5662.37		5654.16
0386	6/4/98	14.83	5663.03		5654.16
0386	7/2/98	14.85	5663.01		5654.16
0386	8/4/98	15.31	5662.55		5654.16
0386	9/2/98	15.46	5662.40		5654.16
0386	10/8/98	15.72	5662.14		5654.16
0386	11/3/98	15.38	5662.48		5654.16
0386	12/4/98	15.95	5661.91		5654.16
0390	1/8/98	55.98	6023.15		6014.13
0390	2/3/98	56.04	6023.09		6014.13
0390	3/2/98	55.98	6023.15		6014.13
0390	4/10/98	55.95	6023.18		6014.13
0390	5/5/98	54.33	6024.80		6014.13
0390	6/1/98	52.79	6026.34		6014.13
0390	7/8/98	52.50	6026.63		6014.13
0390	8/3/98	52.80	6026.33		6014.13

220
219

DRAFT

Appendix A

RF/RMRS-99-433.UN

0390	9/3/98	52.85	6026.28		6014.13
0390	10/5/98	53.18	6025.95		6014.13
0390	11/2/98	53.28	6025.85		6014.13
0390	12/7/98	53.93	6025.20		6014.13
03991	1/8/98	34.83	5902.04		5899.47
03991	4/1/98	35.50	5901.37		5899.47
03991	5/11/98	28.42	5908.45		5899.47
03991	7/2/98	30.63	5906.24		5899.47
03991	10/12/98	34.46	5902.41		5899.47
04091	1/8/98	37.40	5892.74	X	5894.14
04091	4/1/98	37.52	5892.62	X	5894.14
04091	5/11/98	36.42	5893.72	X	5894.14
04091	10/12/98	37.29	5892.85	X	5894.14
04191	1/14/98	17.89	5939.10	X	5939.89
04191	4/6/98	18.06	5938.93	X	5939.89
04591	1/14/98	44.78	5905.47	X	5906.15
04591	4/6/98	44.87	5905.38	X	5906.15
04591	7/6/98	42.90	5907.35		5906.15
0487	2/9/98	8.08	5903.50		5892.08
0487	3/2/98	8.55	5903.03		5892.08
0487	4/9/98	4.26	5907.32		5892.08
0487	5/5/98	4.40	5907.18		5892.08
0487	6/1/98	5.70	5905.88		5892.08
0487	7/2/98	7.50	5904.08		5892.08
0487	8/4/98	8.98	5902.60		5892.08
0487	9/8/98	10.19	5901.39		5892.08
0487	10/8/98	11.31	5900.27		5892.08
0487	11/3/98	11.78	5899.80		5892.08
0487	12/1/98	11.95	5899.63		5892.08
04991	1/15/98	41.31	5897.32	X	5898.33
04991	4/13/98	41.28	5897.35	X	5898.33
04991	7/2/98	36.09	5902.54		5898.33
04991	10/6/98	37.58	5901.05		5898.33
05091	1/15/98	42.99	5896.25		5895.24
05091	4/13/98	43.02	5896.22		5895.24
05091	7/2/98	37.88	5901.36		5895.24
05091	10/6/98	39.77	5899.47		5895.24
05093	2/10/98	9.84	5955.70		5955.04
05191	6/16/98	38.31	5901.54		5893.85
05191	7/6/98	38.59	5901.26		5893.85
05193	1/6/98	9.71	5960.87		5959.18
05193	2/5/98	8.93	5961.65		5959.18
05193	2/16/98	9.06	5961.52		5959.18
05193	3/3/98	9.23	5961.35		5959.18
05193	4/2/98	7.22	5963.36		5959.18
05193	5/6/98	7.11	5963.47		5959.18
05193	6/2/98	7.86	5962.72		5959.18
05193	7/7/98	9.99	5960.59		5959.18
05193	8/5/98	11.15	5959.43		5959.18

224 220

05193	9/2/98	11.67	5958.91	X	5959.18
05193	10/7/98	12.34	5958.24	X	5959.18
05193	11/2/98	12.60	5957.98	X	5959.18
05193	12/1/98	12.60	5957.98	X	5959.18
05197	1/27/98	7.46	5979.24		5958.70
05291	1/14/98	36.71	5906.29	X	5907.90
05291	4/6/98	36.80	5906.20	X	5907.90
05293	1/12/98	7.68	5975.43		5975.41
05293	2/5/98	7.85	5975.26	X	5975.41
05293	3/3/98	8.18	5974.93	X	5975.41
05293	4/8/98	6.60	5976.51		5975.41
05293	5/6/98	7.11	5976.00		5975.41
05293	6/2/98	8.15	5974.96	X	5975.41
05293	6/17/98	8.23	5974.88	X	5975.41
05293	7/7/98	9.16	5973.95	X	5975.41
05391	1/8/98	34.44	5907.23		5906.57
05391	4/1/98	34.30	5907.37		5906.57
05391	5/11/98	26.34	5915.33		5906.57
05391	7/2/98	31.06	5910.61		5906.57
05391	10/12/98	34.60	5907.07		5906.57
05393	2/11/98	18.91	5950.78		5947.59
05397	1/27/98	8.52	5979.13		5962.85
05497	1/27/98	6.54	5979.36		5963.50
05691	4/1/98	28.37	5920.62		5913.89
05691	5/11/98	13.02	5935.97		5913.89
05691	7/2/98	21.42	5927.57		5913.89
05691	10/12/98	28.12	5920.87		5913.89
05697	1/27/98	6.86	5978.94		5967.00
05897	1/27/98	6.77	5890.78		5875.25
05997	1/27/98	7.40	5979.30		5964.30
06091	1/6/98	36.94	5894.66		5890.90
06091	2/9/98	37.04	5894.56		5890.90
06091	3/4/98	37.18	5894.42		5890.90
06091	4/1/98	37.16	5894.44		5890.90
06091	5/5/98	34.27	5897.33		5890.90
06091	6/4/98	32.61	5898.99		5890.90
06091	7/2/98	32.61	5898.99		5890.90
06091	8/4/98	33.24	5898.36		5890.90
06091	9/1/98	33.63	5897.97		5890.90
06091	10/12/98	34.46	5897.14		5890.90
06091	11/4/98	34.90	5896.70		5890.90
06091	12/7/98	35.52	5896.08		5890.90
06191	1/6/98	33.58	5887.14	X	5888.62
06191	4/1/98	33.85	5886.87	X	5888.62
06191	10/12/98	31.86	5888.86		5888.62
06291	1/6/98	27.66	5871.62		5866.38
06291	2/9/98	26.96	5872.32		5866.38
06291	3/4/98	26.77	5872.51		5866.38
06291	4/1/98	26.85	5872.43		5866.38

DRAFT

Appendix A

RF/RMRS-99-433.UN

06291	5/4/98	26.02	5873.26		5866.38
06291	6/4/98	25.25	5874.03		5866.38
06291	8/4/98	24.14	5875.14		5866.38
06291	9/1/98	24.07	5875.21		5866.38
06291	10/12/98	24.27	5875.01		5866.38
06291	11/4/98	24.34	5874.94		5866.38
06291	12/7/98	24.41	5874.87		5866.38
06391	1/6/98			DRY	5882.57
06491	1/15/98	14.40	5658.85		5657.35
06491	4/13/98	16.76	5656.49	X	5657.35
06491	7/2/98	11.05	5662.20		5657.35
06491	10/8/98	12.53	5660.72		5657.35
06991	1/14/98	18.48	5956.09		5945.57
06991	4/6/98	9.85	5964.72		5945.57
07291	1/14/98	20.68	5958.12	X	5958.20
07291	2/2/98	20.86	5957.94	X	5958.20
07291	3/2/98	21.01	5957.79	X	5958.20
07291	4/6/98	17.12	5961.68		5958.20
07291	5/6/98	15.28	5963.52		5958.20
07291	6/8/98	18.31	5960.49		5958.20
07291	7/6/98	20.16	5958.64		5958.20
07291	8/10/98	20.62	5958.18	X	5958.20
07291	9/8/98	20.79	5958.01	X	5958.20
07291	11/4/98	21.10	5957.70	X	5958.20
07291	12/4/98	21.17	5957.63	X	5958.20
07391	1/8/98	7.65	5942.96		5939.21
07391	4/9/98	5.65	5944.96		5939.21
07391	7/6/98	7.96	5942.65		5939.21
07391	10/6/98	8.90	5941.71		5939.21
08091	1/14/98			DRY	5933.21
08091	4/6/98			DRY	5933.21
08091	7/6/98	15.67	5933.84		5933.21
0990	1/5/98	4.84	6078.64		6048.48
0990	2/4/98	5.16	6078.32		6048.48
0990	3/2/98	6.31	6077.17		6048.48
0990	4/1/98	3.04	6080.44		6048.48
0990	5/4/98	2.10	6081.38		6048.48
0990	6/1/98	2.93	6080.55		6048.48
0990	7/1/98	5.10	6078.38		6048.48
0990	8/3/98	5.64	6077.84		6048.48
0990	9/1/98	6.15	6077.33		6048.48
0990	10/6/98	6.71	6076.77		6048.48
0990	11/3/98	6.75	6076.73		6048.48
0990	12/1/98	6.98	6076.50		6048.48
10092	1/13/98			DRY	5881.67
10098	9/17/98	5.98	6029.52		6026.80
10098	10/5/98	6.34	6029.16		6026.80
10194	1/15/98	38.64	5901.74		5899.58
10194	4/9/98	38.51	5901.87		5899.58

223 222

DRAFT

Appendix A

RF/RMRS-99-433.UN

10194	7/6/98	35.66	5904.72		5899.58
10198	9/17/98	4.57	6030.93		6022.40
10198	10/5/98	4.89	6030.61		6022.40
10292	1/13/98			DRY	5902.76
10294	1/5/98	4.09	5602.11		5591.60
10294	4/13/98	3.01	5603.19		5591.60
10294	7/2/98	3.62	5602.58		5591.60
10294	10/8/98	3.06	5603.14		5591.60
10298	9/17/98	4.71	6024.69		6013.80
10298	10/5/98	5.23	6024.17		6013.80
10392	1/13/98			DRY	5906.85
10394	1/5/98	4.72	5628.41		5624.93
10394	4/13/98	4.65	5628.48		5624.93
10394	7/2/98			DRY	5624.93
10394	10/8/98			DRY	5624.93
10398	9/17/98	5.35	6025.15		6019.40
10398	10/5/98	5.66	6024.84		6019.40
10492	1/13/98	30.37	5902.44		5902.51
10498	9/17/98	5.62	6026.88		6020.60
10498	10/5/98	5.19	6027.31		6020.60
10592	1/13/98	22.60	5915.33		5913.93
10592	4/7/98	17.20	5920.73		5913.93
10592	7/2/98	19.76	5918.17		5913.93
10592	10/8/98	14.80	5923.13		5913.93
10594	1/12/98	8.50	5812.45	X	5813.05
10594	2/19/98	8.53	5812.42	X	5813.05
10594	4/7/98	3.37	5817.58		5813.05
10594	10/6/98	10.53	5810.42	X	5813.05
10598	9/17/98	4.97	6028.43		6025.30
10598	10/5/98	3.77	6029.63		6025.30
10692	1/13/98	4.41	5939.19		5924.20
10692	4/7/98	3.53	5940.07		5924.20
10692	7/2/98	4.69	5938.91		5924.20
10692	10/8/98	6.04	5937.56		5924.20
10694	1/12/98	5.89	5754.34	X	5754.53
10694	2/19/98	5.94	5754.29	X	5754.53
10694	4/7/98	5.12	5755.11		5754.53
10694	10/6/98	6.92	5753.31	X	5754.53
10792	1/13/98	23.74	5893.36	X	5894.70
10792	4/7/98	21.74	5895.36		5894.70
10792	7/2/98	23.04	5894.06	X	5894.70
10792	10/8/98	23.61	5893.49	X	5894.70
10794	1/5/98	6.78	5691.73	X	5694.01
10794	2/5/98	6.76	5691.75	X	5694.01
10794	3/4/98	6.78	5691.73	X	5694.01
10794	4/1/98	5.45	5693.06	X	5694.01
10794	5/5/98	5.82	5692.69	X	5694.01
10794	6/2/98	5.95	5692.56	X	5694.01
10794	6/17/98	6.77	5691.74	X	5694.01

224 223

10794	7/1/98	6.80	5691.71	X	5694.01
1086	1/7/98	9.11	5989.08		5974.39
1086	2/5/98	9.55	5988.64		5974.39
1086	3/5/98	10.78	5987.41		5974.39
1086	4/7/98	2.58	5995.61		5974.39
1086	5/5/98	2.50	5995.69		5974.39
1086	6/2/98	5.06	5993.13		5974.39
1086	6/18/98	6.24	5991.95		5974.39
1086	7/1/98	7.64	5990.55		5974.39
1087	1/16/98			DRY	5971.52
1087	4/9/98			DRY	5971.52
1087	10/6/98			DRY	5971.52
10892	1/13/98			DRY	5905.80
10894	1/5/98	5.70	5663.21		5660.91
10894	4/13/98	4.20	5664.71		5660.91
10894	10/8/98	6.30	5662.61		5660.91
1090	5/8/98	11.53	5975.33		5956.86
10991	1/15/98	44.16	5897.48		5890.64
10992	1/13/98	29.77	5868.79	X	5869.16
10992	4/9/98	26.60	5871.96		5869.16
10992	7/2/98	23.72	5874.84		5869.16
10992	10/8/98	29.93	5868.63	X	5869.16
10994	1/13/98	16.00	5901.48		5900.28
10994	4/9/98	14.95	5902.53		5900.28
10994	5/18/98	15.30	5902.18		5900.28
10994	7/1/98	15.87	5901.61		5900.28
10994	10/6/98	16.52	5900.96		5900.28
11092	1/13/98	22.44	5872.87	X	5876.31
11092	4/9/98	22.42	5872.89	X	5876.31
11092	7/2/98	22.41	5872.90	X	5876.31
11092	10/8/98	21.91	5873.40	X	5876.31
11094	5/14/98	6.76	5905.61		5905.57
11294	1/7/98	20.33	6153.17		6097.30
11294	2/4/98	20.07	6153.43		6097.30
11294	3/2/98	20.30	6153.20		6097.30
11294	4/10/98	19.05	6154.45		6097.30
11294	5/5/98	17.32	6156.18		6097.30
11294	6/1/98	17.19	6156.31		6097.30
11294	7/2/98	18.35	6155.15		6097.30
11294	8/3/98	19.33	6154.17		6097.30
11294	9/2/98	19.90	6153.60		6097.30
11294	10/1/98	20.59	6152.91		6097.30
11294	11/2/98	21.18	6152.32		6097.30
11294	12/7/98	22.01	6151.49		6097.30
11494	1/7/98	19.19	6167.44		6119.63
11494	2/4/98	18.94	6167.69		6119.63
11494	3/2/98	19.39	6167.24		6119.63
11494	4/10/98	17.98	6168.65		6119.63
11494	5/5/98	16.81	6169.82		6119.63

225224

11494	6/1/98	16.65	6169.98		6119.63
11494	7/2/98	17.37	6169.26		6119.63
11494	8/3/98	17.95	6168.68		6119.63
11494	9/2/98	18.43	6168.20		6119.63
11494	10/1/98	18.95	6167.68		6119.63
11494	11/2/98	19.52	6167.11		6119.63
11494	12/7/98	20.20	6166.43		6119.63
11594	1/7/98	59.92	6056.41		6052.73
11594	2/4/98	59.22	6057.11		6052.73
11594	3/2/98	58.98	6057.35		6052.73
11594	4/10/98	59.31	6057.02		6052.73
11594	5/5/98	56.75	6059.58		6052.73
11594	6/1/98	52.31	6064.02		6052.73
11594	7/2/98	54.87	6061.46		6052.73
11594	8/3/98	57.22	6059.11		6052.73
11594	9/2/98	58.29	6058.04		6052.73
11594	10/1/98	58.91	6057.42		6052.73
11594	11/2/98	59.25	6057.08		6052.73
11594	12/7/98	59.59	6056.74		6052.73
11691	1/13/98	33.43	5906.48		5906.41
11691	1/13/98	33.43	5906.48		5906.41
11691	5/11/98	30.76	5909.15		5906.41
1187	1/8/98	18.59	5896.53		5894.82
11891	4/1/98	23.69	5923.75		5919.44
11891	5/11/98	20.42	5927.02		5919.44
11891	7/2/98	23.35	5924.09		5919.44
11891	10/8/98	25.87	5921.57		5919.44
1190	1/12/98	18.56	5982.52		5971.78
1190	2/3/98	18.52	5982.56		5971.78
1190	4/10/98	9.47	5991.61		5971.78
1190	5/8/98	8.03	5993.05		5971.78
1190	6/5/98	13.63	5987.45		5971.78
1190	7/8/98	16.04	5985.04		5971.78
1190	8/3/98	17.01	5984.07		5971.78
1190	9/3/98	17.93	5983.15		5971.78
1190	10/5/98	18.75	5982.33		5971.78
1190	11/2/98	19.23	5981.85		5971.78
1190	12/7/98	19.53	5981.55		5971.78
12094	1/12/98	5.78	5757.29		5753.07
12191	4/1/98	23.50	5934.69		5925.19
12191	7/9/98	19.66	5938.53		5925.19
12391	5/11/98	47.20	5894.50		5873.30
12491	1/13/98	27.61	5920.74		5888.35
12691	1/13/98	31.60	5919.48		5887.98
12691	4/1/98	32.29	5918.79		5887.98
12691	5/11/98	20.76	5930.32		5887.98
12691	7/2/98	24.99	5926.09		5887.98
12691	10/12/98	31.88	5919.20		5887.98
1290	1/12/98	24.76	5990.11		5979.87

224 225

1290	4/10/98	17.17	5997.70		5979.87
1290	5/8/98	12.54	6002.33		5979.87
1290	10/5/98	24.48	5990.39		5979.87
13091	1/14/98	19.77	5955.43		5953.90
13091	4/6/98	13.25	5961.95		5953.90
13391	1/6/98	38.32	5887.03		5886.35
13391	4/13/98	38.12	5887.23		5886.35
13391	5/11/98	37.40	5887.95		5886.35
13391	10/12/98	37.73	5887.62		5886.35
13491	1/8/98	21.23	5942.19		5934.42
13491	4/1/98	19.50	5943.92		5934.42
13491	10/12/98	22.95	5940.47		5934.42
13591	1/14/98			DRY	5951.55
13591	4/6/98	17.16	5950.39	X	5951.55
1386	1/12/98	5.26	5837.33		5833.09
1386	2/5/98	5.31	5837.28		5833.09
1386	3/5/98	5.34	5837.25		5833.09
1386	4/7/98	4.02	5838.57		5833.09
1386	5/5/98	4.18	5838.41		5833.09
1386	6/2/98	5.45	5837.14		5833.09
1386	8/4/98	7.66	5834.93		5833.09
1386	9/1/98	9.31	5833.28		5833.09
1386	10/6/98	6.04	5836.55		5833.09
1386	11/3/98	5.61	5836.98		5833.09
1386	12/3/98	5.48	5837.11		5833.09
1390	1/12/98	28.93	5991.69		5981.62
1390	4/10/98	23.04	5997.58		5981.62
1390	5/8/98	17.57	6003.05		5981.62
1390	10/5/98	28.41	5992.21		5981.62
1486	2/18/98	9.82	5836.89		5791.31
1486	3/11/98	9.93	5836.78		5791.31
1486	4/9/98	10.06	5836.65		5791.31
1486	5/6/98	10.03	5836.68		5791.31
1486	6/5/98	10.26	5836.45		5791.31
1486	7/1/98	6.19	5840.52		5791.31
1487	1/8/98	14.77	5841.79		5832.46
1487	6/18/98	13.24	5843.32		5832.46
1487	7/1/98	13.53	5843.03		5832.46
1490	1/12/98	53.80	6017.48		6011.78
1490	2/4/98	53.61	6017.67		6011.78
1490	3/4/98	53.66	6017.62		6011.78
1490	4/10/98	53.60	6017.68		6011.78
1490	5/5/98	50.19	6021.09		6011.78
1490	6/1/98	48.13	6023.15		6011.78
1490	7/9/98	48.95	6022.33		6011.78
1490	8/3/98	49.69	6021.59		6011.78
1490	9/3/98	50.21	6021.07		6011.78
1490	10/5/98	50.92	6020.36		6011.78
1490	11/2/98	51.36	6019.92		6011.78

227 226

1490	12/2/98	51.92	6019.36		6011.78
1586	1/12/98	6.78	5843.85		5836.23
1586	2/18/98	6.83	5843.80		5836.23
1586	3/11/98	6.74	5843.89		5836.23
1586	4/9/98	4.96	5845.67		5836.23
1586	5/6/98	5.27	5845.36		5836.23
1586	6/5/98	6.37	5844.26		5836.23
1587	1/14/98	20.40	5952.39		5950.69
1587	2/2/98	20.76	5952.03		5950.69
1587	3/2/98	21.47	5951.32		5950.69
1587	4/6/98	14.50	5958.29		5950.69
1587	5/6/98	12.22	5960.57		5950.69
1587	6/8/98	16.29	5956.50		5950.69
1587	7/6/98	18.84	5953.95		5950.69
1587	8/10/98	19.93	5952.86		5950.69
1587	9/8/98	20.97	5951.82		5950.69
1587	11/4/98	22.38	5950.41	X	5950.69
1587	12/4/98	21.83	5950.96		5950.69
1686	2/18/98	5.80	5863.75		5824.45
1786	1/12/98	6.86	5862.71		5855.57
1786	2/5/98	6.72	5862.85		5855.57
1786	3/5/98	3.83	5865.74		5855.57
1786	4/7/98	4.37	5865.20		5855.57
1786	5/5/98	5.34	5864.23		5855.57
1786	6/2/98	6.27	5863.30		5855.57
1786	7/1/98	6.53	5863.04		5855.57
1786	8/4/98	6.35	5863.22		5855.57
1786	9/1/98	6.55	5863.02		5855.57
1786	10/6/98	6.61	5862.96		5855.57
1786	11/3/98	6.45	5863.12		5855.57
1786	12/3/98	6.56	5863.01		5855.57
1886	1/12/98			DRY	5880.47
1886	4/7/98			DRY	5880.47
1886	10/6/98			DRY	5880.47
1986	1/7/98	2.75	5941.11		5931.56
1986	2/5/98	2.81	5941.05		5931.56
1986	3/3/98	2.91	5940.95		5931.56
1986	4/8/98	2.16	5941.70		5931.56
1986	5/6/98	2.35	5941.51		5931.56
1986	6/2/98	3.25	5940.61		5931.56
1986	7/7/98	3.72	5940.14		5931.56
1986	8/5/98	2.92	5940.94		5931.56
1986	9/2/98	3.60	5940.26		5931.56
1986	10/7/98	3.67	5940.19		5931.56
1986	11/2/98	2.98	5940.88		5931.56
1986	12/1/98	3.01	5940.85		5931.56
1987	1/13/98	11.68	5958.23		5958.21
1987	4/8/98	7.04	5962.87		5958.21
1987	10/5/98	12.85	5957.06	X	5958.21

227

20196	4/10/98	40.16	6000.93		5975.79
20196	10/5/98	40.85	6000.24		5975.79
20197	5/14/98	2.73	5936.88		5933.01
20291	1/13/98	27.70	5920.88		5915.58
20291	2/9/98	27.41	5921.17		5915.58
20291	3/4/98	29.07	5919.51		5915.58
20291	4/1/98	28.21	5920.37		5915.58
20291	5/5/98	17.91	5930.67		5915.58
20291	6/4/98	18.40	5930.18		5915.58
20291	7/2/98	21.25	5927.33		5915.58
20291	8/4/98	24.06	5924.52		5915.58
20291	9/1/98	25.75	5922.83		5915.58
20291	10/12/98	27.97	5920.61		5915.58
20291	11/4/98	29.00	5919.58		5915.58
20291	12/7/98	30.13	5918.45		5915.58
20296	4/10/98	31.38	6004.83		5980.81
20296	5/8/98	24.94	6011.27		5980.81
20296	10/5/98	35.99	6000.22		5980.81
20396	4/10/98	26.22	6010.88		5986.40
20396	5/8/98	20.35	6016.75		5986.40
20396	10/5/98	32.63	6004.47		5986.40
20397	5/14/98	3.99	5936.65		5934.04
20496	4/10/98	44.56	6021.32		6001.38
20496	10/5/98	43.75	6022.13		6001.38
20596	4/10/98	55.58	6025.58		6010.06
20596	10/5/98	52.19	6028.97		6010.06
20597	5/14/98	8.04	5936.46		5934.30
20691	1/13/98	19.26	5950.37		5945.13
20691	2/9/98	20.18	5949.45		5945.13
20691	3/5/98	21.24	5948.39		5945.13
20691	4/8/98	10.30	5959.33		5945.13
20691	5/6/98	5.91	5963.72		5945.13
20691	6/3/98	9.96	5959.67		5945.13
20691	6/17/98	11.89	5957.74		5945.13
20691	7/8/98	15.11	5954.52		5945.13
20696	3/12/98	44.04	6011.98		5985.62
20696	4/10/98	41.60	6014.42		5985.62
20696	5/5/98	35.74	6020.28		5985.62
20696	6/1/98	36.19	6019.83		5985.62
20696	7/9/98	39.09	6016.93		5985.62
20696	8/3/98	40.24	6015.78		5985.62
20696	9/3/98	41.11	6014.91		5985.62
20696	10/5/98	41.98	6014.04		5985.62
20696	11/2/98	42.62	6013.40		5985.62
20696	12/2/98	43.21	6012.81		5985.62
20697	5/13/98	4.81	5961.99		5957.00
20796	4/10/98	43.88	6012.22		5976.10
20796	10/5/98	43.57	6012.53		5976.10
20797	5/18/98	3.61	5944.91		5939.92

DRAFT

Appendix A

RF/RMRS-99-433.UN

20991	5/11/98	26.02	5925.37		5888.39
20991	6/17/98	27.79	5923.60		5888.39
20991	7/2/98	29.20	5922.19		5888.39
21097	5/14/98	3.47	5958.51		5953.98
21197	5/8/98	3.72	5933.75		5930.17
21297	5/8/98	1.46	5977.89		5973.45
21397	5/8/98	2.19	5973.11		5969.50
21497	5/8/98	1.18	5969.22		5963.00
21597	5/8/98	3.09	5962.58		5960.57
21697	5/8/98	4.24	5957.30		5952.84
21797	5/8/98	2.80	5954.60		5951.60
2186	1/12/98	31.71	5974.25		5938.76
2186	4/8/98	31.74	5974.22		5938.76
2186	7/7/98	32.17	5973.79		5938.76
2186	10/7/98	32.73	5973.23		5938.76
2187	1/7/98	2.98	5926.71		5919.29
2187	1/13/98	3.10	5926.59		5919.29
2187	4/8/98	2.45	5927.24		5919.29
2187	10/7/98	4.33	5925.36		5919.29
21897	5/8/98	3.43	5949.07		5946.60
21997	5/8/98	5.53	5944.97		5943.10
22097	5/8/98	4.45	5943.05		5940.60
22197	5/8/98	4.97	5939.53		5938.20
22297	5/8/98	1.98	5938.67		5937.65
22397	5/8/98			DRY	5932.80
22497	5/8/98	3.97	5939.03		5937.10
22596	2/5/98			DRY	5982.80
22596	3/3/98			DRY	5982.80
22596	4/8/98	22.71	5987.09		5982.80
22596	5/6/98	22.01	5987.79		5982.80
22596	6/2/98	24.07	5985.73		5982.80
22596	7/7/98			DRY	5982.80
22596	8/5/98	25.65	5984.15		5982.80
22596	9/1/98			DRY	5982.80
22596	10/7/98			DRY	5982.80
22596	11/3/98			DRY	5982.80
22596	12/1/98			DRY	5982.80
22597	1/8/98	17.46	5897.09		5888.55
22597	5/7/98	12.50	5902.05		5888.55
22696	1/6/98	14.83	5967.75		5965.08
22696	1/7/98	14.84	5967.74		5965.08
22696	4/8/98	11.04	5971.54		5965.08
22696	7/7/98	14.72	5967.86		5965.08
22696	10/7/98	18.55	5964.03	X	5965.08
22697	1/8/98	12.18	5895.33		5889.61
22697	5/7/98	8.56	5898.95		5889.61
22796	1/12/98			DRY	5927.50
22796	4/8/98	12.65	5931.85		5927.50
22796	7/7/98	14.24	5930.26		5927.50

270 229

22796	10/7/98	14.88	5929.62		5927.50
22797	1/8/98	7.02	5892.48		5885.90
22797	5/7/98	4.43	5895.07		5885.90
2286	1/5/98	9.35	5970.20		5968.35
2286	2/5/98	9.64	5969.91		5968.35
2286	3/3/98	10.19	5969.36		5968.35
2286	4/8/98	5.26	5974.29		5968.35
2286	5/6/98	6.29	5973.26		5968.35
2286	6/2/98	7.33	5972.22		5968.35
2286	7/7/98	8.71	5970.84		5968.35
2286	8/5/98	7.66	5971.89		5968.35
2286	9/2/98	8.90	5970.65		5968.35
2286	10/7/98			DRY	5968.35
2286	11/3/98			DRY	5968.35
2286	12/2/98			DRY	5968.35
22896	1/6/98	20.84	5980.58		5978.12
22896	4/8/98	15.89	5985.53		5978.12
22896	7/7/98	20.89	5980.53		5978.12
22896	10/7/98	21.15	5980.27		5978.12
22897	1/8/98	13.89	5883.76		5873.55
22897	5/7/98	10.97	5886.68		5873.55
22996	1/6/98	6.60	5981.90		5980.00
22996	2/5/98	7.05	5981.45		5980.00
22996	3/4/98			DRY	5980.00
22996	4/8/98	4.27	5984.23		5980.00
22996	5/6/98	4.91	5983.59		5980.00
22996	6/3/98	5.88	5982.62		5980.00
22996	7/8/98	7.42	5981.08		5980.00
22996	8/4/98			DRY	5980.00
22996	9/8/98			DRY	5980.00
22996	10/6/98			DRY	5980.00
22996	11/5/98			DRY	5980.00
22996	12/7/98			DRY	5980.00
22997	1/8/98	8.85	5882.75		5875.60
22997	5/7/98	5.85	5885.75		5875.60
23096	1/13/98	9.47	5828.33		5823.80
23096	4/7/98	6.85	5830.95		5823.80
23096	6/18/98	12.22	5825.58		5823.80
23096	7/1/98	13.54	5824.26		5823.80
23096	10/6/98	12.91	5824.89		5823.80
23097	1/8/98	8.05	5879.43		5873.88
23097	5/7/98	5.43	5882.05		5873.88
23196	1/16/98	26.00	5790.67	X	5791.67
23196	4/7/98	26.86	5789.81	X	5791.67
23196	7/1/98	27.35	5789.32	X	5791.67
23196	10/6/98	28.01	5788.66	X	5791.67
23197	1/8/98	8.77	5877.09		5871.66
23197	5/7/98	6.50	5879.36		5871.66
23296	1/5/98	5.00	5853.00		5850.00

DRAFT

Appendix A

RF/RMRS-99-433.UN

23296	4/10/98	3.78	5854.22		5850.00
23296	5/12/98	3.42	5854.58		5850.00
23296	7/1/98	4.67	5853.33		5850.00
23296	10/6/98	5.44	5852.56		5850.00
23297	1/8/98	13.31	5868.46	X	5868.67
23297	5/7/98	11.53	5870.24		5868.67
23397	1/8/98	13.19	5866.40		5865.49
23397	5/7/98	10.98	5868.61		5865.49
23497	1/8/98			DRY	5864.26
23497	5/7/98	12.40	5864.06	X	5864.26
23597	1/8/98	13.76	5859.58		5854.14
23597	5/7/98	11.69	5861.65		5854.14
23697	1/8/98			DRY	5860.68
23697	5/7/98			DRY	5860.68
23797	1/8/98	17.40	5850.31		5847.71
23797	5/7/98	16.61	5851.10		5847.71
2386	2/16/98	99.31	5883.15		5865.16
23897	1/8/98	12.07	5850.28		5844.25
23897	5/7/98	11.73	5850.62		5844.25
23997	1/8/98			DRY	5843.73
23997	5/7/98	13.70	5847.93		5843.73
24097	5/7/98	15.17	5844.50		5841.57
24197	5/7/98	13.58	5844.02		5841.60
24297	1/8/98	5.90	5891.82		5888.62
24297	5/7/98	3.34	5894.38		5888.62
24397	1/8/98	9.08	5916.53		5907.31
24397	5/7/98	4.77	5920.84		5907.31
24497	1/8/98	12.30	5905.30		5900.70
24497	5/7/98	9.16	5908.44		5900.70
2486	1/7/98			DRY	5976.06
2486	4/2/98	6.83	5976.73		5976.06
2486	10/7/98			DRY	5976.06
2487	1/13/98	14.88	5944.81	X	5946.09
2487	4/1/98	12.70	5946.99		5946.09
2487	5/12/98	9.56	5950.13		5946.09
2487	10/12/98	15.53	5944.16	X	5946.09
25097	5/7/98	23.34	5911.16		5910.00
2586	1/5/98	17.95	5959.19		5895.14
2586	2/10/98	43.47	5933.67		5895.14
2587	5/12/98	11.76	5949.22		5917.48
2686	1/7/98	11.36	5965.81	X	5966.17
2686	2/10/98	11.58	5965.59	X	5966.17
2686	3/11/98	11.81	5965.36	X	5966.17
2686	4/2/98	9.42	5967.75		5966.17
2686	5/6/98	9.46	5967.71		5966.17
2686	6/5/98	10.70	5966.47		5966.17
2686	10/7/98	12.82	5964.35	X	5966.17
2687	1/14/98			DRY	5942.40
2687	4/6/98			DRY	5942.40

237 231

26995	2/19/98	13.39	5922.81		5914.20
2786	2/10/98	103.49	5860.39		5830.88
28295	2/19/98	5.66	5846.44		5837.10
29395	2/16/98	3.68	5930.92		5922.60
29795	2/19/98	2.55	5844.75		5840.30
2986	1/7/98			DRY	5951.88
2986	4/2/98			DRY	5951.88
2986	10/7/98			DRY	5951.88
2987	1/16/98			DRY	5793.99
2987	4/7/98	12.56	5801.73		5793.99
2987	7/1/98	18.15	5796.14		5793.99
2987	10/6/98			DRY	5793.99
30595	2/19/98	9.10	5901.30		5888.40
30695	2/19/98	9.20	5911.60		5905.80
3086	2/11/98	6.12	5952.27		5943.49
3087	1/16/98	24.82	5786.95		5717.37
3087	4/7/98	29.55	5782.22		5717.37
3087	7/1/98	27.92	5783.85		5717.37
3087	10/6/98	25.07	5786.70		5717.37
308-P-1	5/8/98	23.71	5920.40		5904.11
308-P-2	5/8/98	24.77	5919.25		5904.02
31491	1/13/98			DRY	5886.13
31791	1/13/98			DRY	5868.00
3286	2/11/98	57.50	5910.42		5842.42
3286	3/11/98	53.34	5914.58		5842.42
3286	4/8/98	52.37	5915.55		5842.42
3286	5/6/98	52.12	5915.80		5842.42
3286	6/4/98	51.95	5915.97		5842.42
3287	1/14/98	47.63	5900.34	X	5901.37
3287	4/6/98	47.45	5900.52	X	5901.37
3386	1/5/98	8.10	5944.32	X	5945.12
3386	2/5/98	8.09	5944.33	X	5945.12
3386	3/3/98	8.27	5944.15	X	5945.12
3386	4/8/98	5.95	5946.47		5945.12
3386	5/6/98	6.36	5946.06		5945.12
3386	6/2/98	7.17	5945.25		5945.12
3386	7/7/98	8.19	5944.23	X	5945.12
3386	8/5/98	8.65	5943.77	X	5945.12
3386	9/2/98			DRY	5945.12
3386	10/7/98			DRY	5945.12
3386	11/2/98			DRY	5945.12
3386	12/2/98			DRY	5945.12
3387	1/14/98	20.60	5926.62	X	5927.22
3387	2/10/98	8.11	5939.11		5927.22
3387	4/6/98	20.05	5927.17	X	5927.22
34791	1/8/98	3.94	5949.97		5945.91
34791	4/9/98	1.18	5952.73		5945.91
34791	10/6/98	6.09	5947.82		5945.91
3586	1/13/98	7.70	5905.06		5901.16

232

3586	2/9/98	7.61	5905.15		5901.16
3586	3/5/98	7.61	5905.15		5901.16
3586	4/8/98	4.49	5908.27		5901.16
3586	5/6/98	5.23	5907.53		5901.16
3586	6/3/98	6.97	5905.79		5901.16
3586	7/9/98	7.67	5905.09		5901.16
3586	8/6/98	7.54	5905.22		5901.16
3586	9/8/98	7.67	5905.09		5901.16
3586	10/5/98	7.71	5905.05		5901.16
3586	11/5/98	7.51	5905.25		5901.16
3586	12/7/98	7.88	5904.88		5901.16
3587	5/11/98			DRY	5941.99
3686	1/5/98	6.26	5878.96		5878.72
3686	2/5/98	6.18	5879.04		5878.72
3686	2/9/98	6.20	5879.02		5878.72
3686	3/4/98	6.26	5878.96		5878.72
3686	4/10/98	4.90	5880.32		5878.72
3686	5/5/98	4.00	5881.22		5878.72
3686	6/2/98	6.30	5878.92		5878.72
3686	6/17/98	5.60	5879.62		5878.72
3686	7/1/98	6.19	5879.03		5878.72
3687	1/13/98	34.06	5917.05		5887.71
3687	2/9/98	34.72	5916.39		5887.71
3687	3/4/98	35.23	5915.88		5887.71
3687	4/1/98	34.72	5916.39		5887.71
3687	5/5/98	26.97	5924.14		5887.71
3687	6/4/98	27.05	5924.06		5887.71
3687	7/2/98	29.22	5921.89		5887.71
3687	7/2/98	29.22	5921.89		5887.71
3687	8/4/98	31.57	5919.54		5887.71
3687	9/1/98	32.71	5918.40		5887.71
3687	10/12/98	34.41	5916.70		5887.71
3687	11/4/98	35.33	5915.78		5887.71
3687	12/7/98	35.82	5915.29		5887.71
37191	1/13/98	9.39	5938.90		5927.19
37191	4/9/98	7.41	5940.88		5927.19
37191	10/5/98	9.47	5938.82		5927.19
37591	1/7/98	10.38	5983.07		5980.85
37591	2/5/98	10.58	5982.87		5980.85
37591	3/5/98	10.91	5982.54		5980.85
37591	4/8/98	8.96	5984.49		5980.85
37591	5/6/98	7.71	5985.74		5980.85
37591	6/3/98	8.33	5985.12		5980.85
37591	6/18/98	8.74	5984.71		5980.85
37591	7/8/98	9.30	5984.15		5980.85
37691	1/7/98	18.27	5966.97	X	5968.74
37691	4/9/98	13.72	5971.52		5968.74
37691	10/6/98	18.30	5966.94	X	5968.74
37791	1/6/98	18.91	5985.27		5983.58

DRAFT

Appendix A

RF/RMRS-99-433.UN

37791	4/7/98	19.27	5984.91		5983.58
37791	10/6/98	16.24	5987.94		5983.58
38591	1/5/98	8.32	5858.30	X	5858.92
38591	4/9/98	7.14	5859.48		5858.92
38591	7/1/98	9.34	5857.28	X	5858.92
38591	10/6/98			DRY	5858.92
3986	1/6/98	28.08	5881.33		5877.91
3986	2/9/98	28.22	5881.19		5877.91
3986	3/4/98	28.35	5881.06		5877.91
3986	4/13/98	28.57	5880.84		5877.91
3986	5/4/98	25.47	5883.94		5877.91
3986	6/4/98	23.80	5885.61		5877.91
3986	8/4/98	25.14	5884.27		5877.91
3986	9/1/98	25.54	5883.87		5877.91
3986	10/12/98	25.89	5883.52		5877.91
3986	11/4/98	26.18	5883.23		5877.91
3986	12/7/98	26.83	5882.58		5877.91
3987	2/11/98	103.48	5844.94		5831.32
4087	1/12/98	2.51	5882.10		5878.11
4087	2/5/98	1.80	5882.81		5878.11
4087	3/5/98	2.79	5881.82		5878.11
4087	4/10/98	2.39	5882.22		5878.11
4087	5/5/98	2.39	5882.22		5878.11
4087	6/1/98	4.56	5880.05		5878.11
4087	7/1/98	5.46	5879.15		5878.11
4087	8/4/98	6.82	5877.79	X	5878.11
4087	9/1/98	8.25	5876.36	X	5878.11
4087	10/6/98			DRY	5878.11
4087	11/3/98			DRY	5878.11
4087	12/3/98			DRY	5878.11
41091	1/5/98	9.75	5712.10		5711.85
41091	2/5/98	10.01	5711.84	X	5711.85
41091	3/4/98	8.64	5713.21		5711.85
41091	4/7/98	5.23	5716.62		5711.85
41091	5/5/98	7.79	5714.06		5711.85
41091	6/2/98	7.25	5714.60		5711.85
41091	7/1/98	9.73	5712.12		5711.85
41091	8/4/98	9.24	5712.61		5711.85
41091	9/1/98	5.50	5716.35		5711.85
41091	10/6/98	9.83	5712.02		5711.85
41091	11/4/98	10.14	5711.71	X	5711.85
41091	12/3/98			DRY	5711.85
41193	2/11/98	7.99	5954.53		5954.52
41193	3/11/98	8.11	5954.41	X	5954.52
41193	4/8/98	4.11	5958.41		5954.52
41193	5/6/98	5.22	5957.30		5954.52
41193	6/4/98	7.26	5955.26		5954.52
41591	1/5/98	7.16	5720.11		5716.27
41591	2/9/98	7.69	5719.58		5716.27

234

41591	3/3/98	8.09	5719.18		5716.27
41591	4/13/98	4.37	5722.90		5716.27
41591	5/4/98	4.86	5722.41		5716.27
41591	6/4/98	6.57	5720.70		5716.27
41591	7/2/98	8.35	5718.92		5716.27
41591	8/4/98	8.91	5718.36		5716.27
41591	9/2/98	9.65	5717.62		5716.27
41591	10/8/98			DRY	5716.27
41591	11/3/98			DRY	5716.27
41591	12/4/98			DRY	5716.27
41691	1/5/98	8.68	5637.20		5631.18
41691	2/9/98	9.60	5636.28		5631.18
41691	3/3/98	8.20	5637.68		5631.18
41691	4/1/98	7.32	5638.56		5631.18
41691	5/4/98	7.82	5638.06		5631.18
41691	6/4/98	7.93	5637.95		5631.18
41691	7/2/98	9.83	5636.05		5631.18
41691	8/4/98	10.44	5635.44		5631.18
41691	9/2/98	7.34	5638.54		5631.18
41691	10/8/98	10.19	5635.69		5631.18
41691	11/3/98	10.55	5635.33		5631.18
41691	12/4/98	7.54	5638.34		5631.18
41693	2/11/98	13.50	5961.75		5959.25
41693	3/11/98	13.61	5961.64		5959.25
41693	4/8/98	13.04	5962.21		5959.25
41693	5/6/98	12.74	5962.51		5959.25
41693	6/4/98	12.59	5962.66		5959.25
4186	1/14/98	46.31	5898.05	X	5899.66
4186	2/2/98	46.35	5898.01	X	5899.66
4186	3/2/98	46.39	5897.97	X	5899.66
4186	4/6/98	46.45	5897.91	X	5899.66
4186	5/7/98	45.12	5899.24	X	5899.66
4186	6/8/98	42.20	5902.16		5899.66
4186	7/6/98	41.38	5902.98		5899.66
4186	8/10/98	41.52	5902.84		5899.66
41993	2/16/98	14.45	5963.89		5963.84
42393	2/16/98	14.08	5967.88	X	5968.96
42393	3/11/98	14.68	5967.28	X	5968.96
42393	4/1/98	10.30	5971.66		5968.96
42393	5/6/98	10.29	5971.67		5968.96
42393	6/5/98	10.39	5971.57		5968.96
4286	1/8/98	26.80	5931.07		5928.17
4286	2/9/98	22.03	5935.84		5928.17
4286	3/4/98	22.83	5935.04		5928.17
4286	4/1/98	20.31	5937.56		5928.17
4286	5/5/98	10.11	5947.76		5928.17
4286	6/4/98	11.09	5946.78		5928.17
4286	7/2/98	15.22	5942.65		5928.17
4286	8/4/98	19.19	5938.68		5928.17

234 235

4286	9/3/98	20.87	5937.00		5928.17
4286	10/12/98	22.86	5935.01		5928.17
4286	11/4/98	23.63	5934.24		5928.17
4286	12/7/98	24.77	5933.10		5928.17
42993	2/16/98	12.18	5968.57		5964.75
42993	3/11/98	12.63	5968.12		5964.75
42993	4/8/98	8.89	5971.86		5964.75
42993	5/6/98	8.57	5972.18		5964.75
42993	6/5/98	9.61	5971.14		5964.75
43293	2/11/98			DRY	5944.14
43392	1/13/98	28.18	6015.26		6013.14
43392	4/9/98	24.41	6019.03		6013.14
43392	7/1/98	28.03	6015.41		6013.14
43392	10/6/98	30.15	6013.29		6013.14
43593	2/16/98	8.75	5971.19		5968.94
4386	1/13/98	17.67	5956.79	X	5957.66
4386	2/9/98	18.13	5956.33	X	5957.66
4386	3/5/98			DRY	5957.66
4386	4/9/98	12.50	5961.96		5957.66
4386	5/6/98	11.85	5962.61		5957.66
4386	6/3/98	13.94	5960.52		5957.66
4386	7/8/98	16.48	5957.98		5957.66
4386	8/4/98	17.13	5957.33	X	5957.66
4386	9/8/98	18.11	5956.35	X	5957.66
4386	10/5/98			DRY	5957.66
4386	11/5/98			DRY	5957.66
4386	12/7/98	18.31	5956.15	X	5957.66
4387	1/13/98	9.63	5916.78		5914.11
4387	4/9/98	6.22	5920.19		5914.11
4387	10/5/98	8.78	5917.63		5914.11
43893	2/16/98	12.75	5967.34		5966.09
43995	2/16/98	10.91			
4486	1/6/98	7.48	6014.48		5995.66
4486	4/8/98	5.72	6016.24		5995.66
4486	9/17/98	7.23	6014.73		5995.66
4486	10/6/98	7.35	6014.61		5995.66
4487	1/13/98			DRY	5947.60
44893	1/13/98			DRY	5913.83
44893	2/5/98			DRY	5913.83
44893	3/4/98			DRY	5913.83
44893	4/7/98			DRY	5913.83
44893	5/5/98			DRY	5913.83
44893	6/2/98			DRY	5913.83
44893	7/1/98			DRY	5913.83
44893	8/4/98			DRY	5913.83
44893	9/1/98			DRY	5913.83
44893	10/6/98			DRY	5913.83
44893	11/3/98			DRY	5913.83
44893	12/3/98			DRY	5913.83

DRAFT

Appendix A

RF/RMRS-99-433.UN

45093	2/18/98	11.96	5917.90	X	5918.16
45391	1/13/98			DRY	5876.54
45393	2/18/98	13.26	5912.40		5908.96
45393	3/11/98	13.58	5912.08		5908.96
45393	4/9/98	13.91	5911.75		5908.96
45393	5/6/98	14.27	5911.39		5908.96
45393	6/5/98	14.63	5911.03		5908.96
45693	2/11/98	3.29	5935.52		5933.31
45793	1/12/98			DRY	5949.12
45793	2/11/98			DRY	5949.12
45793	4/8/98	6.84	5946.28	X	5949.12
45793	10/7/98	6.89	5946.23	X	5949.12
45893	2/11/98			DRY	5944.50
45993	2/11/98			DRY	5947.81
46193	2/11/98	3.88	5934.82		5931.70
46292	1/7/98	54.81	6042.43		6006.74
46292	4/10/98	54.61	6042.63		6006.74
46292	10/1/98	51.03	6046.21		6006.74
46293	1/12/98	3.13	5938.46		5933.59
46293	2/5/98	3.45	5938.14		5933.59
46293	2/16/98	3.35	5938.24		5933.59
46293	3/3/98	4.23	5937.36		5933.59
46293	4/8/98	0.20	5941.39		5933.59
46293	5/6/98	0.00	5941.59		5933.59
46293	6/2/98	1.93	5939.66		5933.59
46293	7/7/98	4.91	5936.68		5933.59
46293	8/5/98	4.04	5937.55		5933.59
46393	2/19/98	20.83	5881.91		5880.24
46492	1/8/98	24.18	6032.63		6013.61
46492	4/10/98	21.70	6035.11		6013.61
46492	9/17/98	23.96	6032.85		6013.61
46492	10/1/98	24.63	6032.18		6013.61
4686	1/8/98	73.70	6010.29		5923.19
4786	1/8/98	59.08	6024.59		5989.17
4786	2/3/98	59.10	6024.57		5989.17
4786	3/2/98	59.04	6024.63		5989.17
4786	4/10/98	59.01	6024.66		5989.17
4786	5/5/98	57.28	6026.39		5989.17
4786	6/1/98	55.48	6028.19		5989.17
4786	6/16/98	54.93	6028.74		5989.17
4786	7/8/98	55.12	6028.55		5989.17
4786	8/10/98	55.32	6028.35		5989.17
4787	1/13/98			DRY	5877.34
4787	4/9/98	3.93	5880.71		5877.34
4787	7/2/98	8.52	5876.12	X	5877.34
4787	10/8/98			DRY	5877.34
4887	1/13/98	10.36	5901.05	X	5901.31
4887	4/9/98	5.91	5905.50		5901.31
4887	7/2/98	10.24	5901.17	X	5901.31

237

4887	10/8/98			DRY	5901.31
50494	1/7/98			DRY	6072.64
50494	4/10/98			DRY	6072.64
50494	10/1/98	24.61	6069.73	X	6072.64
50694	1/8/98	24.28	6063.22		6060.70
50694	4/10/98	23.81	6063.69		6060.70
50694	10/1/98	20.59	6066.91		6060.70
5087	1/13/98			DRY	5921.28
51094	1/5/98	44.50	6048.75		6035.55
51094	4/10/98	44.22	6049.03		6035.55
51094	10/1/98	40.74	6052.51		6035.55
51194	1/8/98	37.84	6035.47		6023.31
51194	4/10/98	36.80	6036.51		6023.31
51194	10/1/98	34.86	6038.45		6023.31
51294	1/8/98	21.86	6042.82		6029.68
51294	2/4/98	21.58	6043.10		6029.68
51294	3/4/98	21.71	6042.97		6029.68
51294	4/10/98	21.07	6043.61		6029.68
51294	5/5/98	18.47	6046.21		6029.68
51294	6/1/98	17.00	6047.68		6029.68
51294	8/4/98	18.04	6046.64		6029.68
51294	8/6/98	17.90	6046.78		6029.68
51294	9/3/98	18.22	6046.46		6029.68
51294	10/1/98	19.01	6045.67		6029.68
51294	11/2/98	19.82	6044.86		6029.68
51294	12/2/98	20.27	6044.41		6029.68
51494	1/7/98	51.64	6047.62		6030.56
51494	2/3/98	51.60	6047.66		6030.56
51494	3/2/98	51.37	6047.89		6030.56
51494	4/10/98	51.38	6047.88		6030.56
51494	5/5/98	49.86	6049.40		6030.56
51494	6/1/98	48.18	6051.08		6030.56
51494	6/16/98	47.39	6051.87		6030.56
51594	1/7/98	8.92	6090.57		6079.49
51594	2/3/98	8.67	6090.82		6079.49
51594	3/2/98	8.42	6091.07		6079.49
51594	4/10/98	7.58	6091.91		6079.49
51594	5/5/98	6.53	6092.96		6079.49
51594	6/1/98	6.42	6093.07		6079.49
51594	7/9/98	7.56	6091.93		6079.49
51594	8/3/98	8.13	6091.36		6079.49
51594	9/3/98	8.87	6090.62		6079.49
51594	10/1/98	9.60	6089.89		6079.49
51594	11/2/98	10.89	6088.60		6079.49
51594	12/7/98	12.38	6087.11		6079.49
5287	1/6/98	9.86	5959.71		5949.27
5287	2/5/98	9.76	5959.81		5949.27
5287	3/3/98	9.89	5959.68		5949.27
5287	4/7/98	9.11	5960.46		5949.27

DRAFT

Appendix A

RF/RMRS-99-433.UN

5287	5/7/98	9.20	5960.37		5949.27
5287	6/3/98	9.62	5959.95		5949.27
5287	7/8/98	9.77	5959.80		5949.27
5287	8/4/98	9.59	5959.98		5949.27
5287	9/8/98	9.75	5959.82		5949.27
5287	10/5/98	9.92	5959.65		5949.27
5287	11/4/98	9.73	5959.84		5949.27
5287	12/2/98	9.89	5959.68		5949.27
52893	5/13/98			DRY	5934.50
52894	1/12/98	4.48	5866.27	X	5866.75
52894	4/10/98	3.29	5867.46		5866.75
52894	7/1/98	6.15	5864.60	X	5866.75
52894	10/6/98	7.98	5862.77	X	5866.75
52993	5/13/98			DRY	5931.00
52994	1/12/98			DRY	5858.81
52994	4/10/98			DRY	5858.81
52994	7/1/98	18.73	5855.08	X	5858.81
52994	10/6/98			DRY	5858.81
53093	5/13/98			DRY	5935.70
53193	5/13/98			DRY	5938.50
53194	1/12/98	3.65	5835.73		5832.38
53293	5/18/98			DRY	5942.80
53393	5/13/98			DRY	5914.70
53493	5/18/98	5.04	5900.36		5895.40
5387	1/16/98	5.90	5955.91		5952.71
5387	4/9/98	3.16	5958.65		5952.71
5387	7/2/98	7.32	5954.49		5952.71
5387	10/8/98	8.50	5953.31		5952.71
5586	1/5/98	21.90	6096.82		6082.32
5586	2/4/98	21.65	6097.07		6082.32
5586	3/2/98	22.55	6096.17		6082.32
5586	4/1/98	17.82	6100.90		6082.32
5586	5/4/98	10.10	6108.62		6082.32
5586	6/1/98	13.07	6105.65		6082.32
5586	6/16/98	15.61	6103.11		6082.32
5586	7/1/98	17.93	6100.79		6082.32
5587	1/5/98	8.75	5851.34	X	5852.69
5587	2/4/98	8.05	5852.04	X	5852.69
5587	3/2/98	7.80	5852.29	X	5852.69
5587	4/9/98	6.10	5853.99		5852.69
5587	5/4/98			DRY	5852.69
5587	6/1/98	8.07	5852.02	X	5852.69
5587	7/1/98	7.84	5852.25	X	5852.69
5587	8/4/98	8.14	5851.95	X	5852.69
5587	9/2/98	8.62	5851.47	X	5852.69
5587	10/6/98	9.35	5850.74	X	5852.69
5587	11/3/98			DRY	5852.69
5587	12/1/98	8.40	5851.69	X	5852.69
5686	1/13/98	6.82	5982.11		5979.33

240 239

5686	2/9/98	6.54	5982.39		5979.33
5686	3/3/98	6.30	5982.63		5979.33
5686	4/1/98	4.28	5984.65		5979.33
5686	5/4/98	5.50	5983.43		5979.33
5686	6/1/98	6.64	5982.29		5979.33
5686	7/1/98	6.80	5982.13		5979.33
5686	8/6/98	6.84	5982.09		5979.33
5686	9/2/98	6.83	5982.10		5979.33
5686	10/6/98	6.87	5982.06		5979.33
5686	11/3/98	6.82	5982.11		5979.33
5686	12/1/98	6.84	5982.09		5979.33
5687	2/10/98	8.50	5971.27		5970.07
56994	1/16/98	17.30	6004.33		5997.13
56994	4/1/98	16.40	6005.23		5997.13
56994	5/21/98	14.92	6006.71		5997.13
56994	10/6/98	17.09	6004.54		5997.13
57094	1/13/98	33.37	5938.75		5938.12
57094	4/1/98	33.28	5938.84		5938.12
57094	5/13/98	32.73	5939.39		5938.12
57094	10/6/98	34.21	5937.91	X	5938.12
57594	5/13/98	8.10	5940.33		5858.53
57994	5/14/98	4.75	5936.52		5934.27
58094	5/13/98	4.17	5926.74		5919.91
58194	5/13/98	3.58	5927.05		5922.63
58294	5/14/98	7.32	5941.49	X	5943.81
58394	5/21/98	6.48	5993.06	X	5994.14
58494	5/21/98	3.17	5993.21		5986.38
58594	5/13/98	5.31	5914.83		5914.14
58694	5/13/98	5.48	5954.48	X	5954.96
58793	1/13/98	14.50	5999.70		5989.40
58793	4/1/98	12.38	6001.82		5989.40
58793	7/1/98	9.41	6004.79		5989.40
58793	10/6/98	13.86	6000.34		5989.40
58794	5/18/98	5.00	5953.91		5953.91
5887	1/7/98	9.53	5987.24		5974.47
5887	4/7/98	4.41	5992.36		5974.47
5887	5/8/98	4.30	5992.47		5974.47
5887	7/1/98	8.46	5988.31		5974.47
5887	10/5/98	11.85	5984.92		5974.47
59393	1/13/98	7.24	5947.46		5947.20
59394	5/13/98	32.23	5934.73		5879.46
59493	1/15/98	4.52	5987.88		5979.50
59493	4/1/98	4.08	5988.32		5979.50
59493	7/1/98	5.81	5986.59		5979.50
59493	10/6/98	9.63	5982.77		5979.50
59594	1/13/98	28.04	6020.87		6011.31
59594	4/1/98	25.30	6023.61		6011.31
59594	10/6/98	31.26	6017.65		6011.31
59793	5/13/98	8.21	5937.59		5932.10

24 240

DRAFT

Appendix A

RF/RMRS-99-433.UN

59893	1/16/98	4.42	5941.98		5931.80
59893	4/1/98	2.70	5943.70		5931.80
59893	5/18/98	3.72	5942.68		5931.80
59893	10/6/98	9.40	5937.00		5931.80
59993	5/18/98	7.23	5937.07		5928.00
60093	5/13/98	9.90	5935.50	X	5935.60
60193	5/13/98			DRY	5939.20
60195	1/8/98	5.65	5894.35		5889.00
60195	2/5/98	5.98	5894.02		5889.00
60195	3/4/98	6.29	5893.71		5889.00
60195	4/10/98	4.05	5895.95		5889.00
60195	5/5/98	3.11	5896.89		5889.00
60195	6/2/98	3.62	5896.38		5889.00
60195	7/1/98	4.50	5895.50		5889.00
60195	8/6/98	5.29	5894.71		5889.00
60195	9/1/98	6.15	5893.85		5889.00
60195	10/6/98	6.62	5893.38		5889.00
60195	11/4/98	6.78	5893.22		5889.00
60195	12/3/98	6.54	5893.46		5889.00
60294	1/14/98	Well Not found			
60294	4/9/98	2.60	5919.23		
60295	1/8/98	4.57	5892.43		5880.80
60295	4/10/98	3.26	5893.74		5880.80
60295	5/11/98	2.10	5894.90		5880.80
60295	10/6/98	5.46	5891.54		5880.80
60395	1/8/98	5.75	5881.25		5878.70
60395	4/10/98	3.94	5883.06		5878.70
60395	5/11/98	3.28	5883.72		5878.70
60395	10/6/98	6.89	5880.11		5878.70
60693	1/15/98	14.40	6009.30		6005.90
60693	4/1/98			DRY	6005.90
60693	7/1/98	15.90	6007.80		6005.90
60693	10/6/98	16.14	6007.56		6005.90
60695	1/6/98	9.35	5875.65		5871.10
60695	4/13/98	8.49	5876.51		5871.10
60695	5/11/98	6.18	5878.82		5871.10
60695	10/12/98	8.20	5876.80		5871.10
60795	1/16/98			DRY	5833.90
60795	4/13/98			DRY	5833.90
60795	5/11/98	2.00	5840.00		5833.90
60795	10/12/98	8.14	5833.86	X	5833.90
6087	1/7/98	10.60	5975.36		5958.46
6087	4/7/98	4.85	5981.11		5958.46
6087	5/8/98	5.00	5980.96		5958.46
6087	10/6/98	12.12	5973.84		5958.46
60895	5/11/98			DRY	5830.10
60993	5/21/98	3.53	5983.37		5978.90
60994	1/14/98			DRY	5920.77
60994	1/16/98			DRY	5920.77

242 241

60994	4/9/98	3.28	5928.79		5920.77
60994	10/8/98			DRY	5920.77
61093	5/21/98	4.81	5968.79		5960.60
61293	1/15/98	2.10	5984.60		5978.70
61293	4/1/98	2.05	5984.65		5978.70
61293	7/1/98	5.77	5980.93		5978.70
61293	10/6/98	8.75	5977.95	X	5978.70
61295	1/13/98	3.58	5863.42		5856.60
61295	4/13/98	2.62	5864.38		5856.60
61295	10/6/98	4.11	5862.89		5856.60
61495	1/16/98	5.84	5972.16		5965.80
61495	4/10/98	2.91	5975.09		5965.80
61495	5/8/98	3.14	5974.86		5965.80
61495	10/5/98	6.66	5971.34		5965.80
61595	1/16/98	2.84	5970.16		5962.10
61595	4/10/98	0.93	5972.07		5962.10
61595	5/8/98	1.36	5971.64		5962.10
61595	10/5/98	3.72	5969.28		5962.10
61695	1/16/98	3.33	5984.67		5973.60
61695	4/10/98	1.61	5986.39		5973.60
61695	5/8/98	1.59	5986.41		5973.60
61695	10/5/98	4.30	5983.70		5973.60
61793	5/14/98	4.50	5914.20		5912.80
6186	1/6/98	10.31	5990.29		5988.60
6186	4/7/98	7.25	5993.35		5988.60
6186	7/8/98	10.18	5990.42		5988.60
6186	10/6/98	9.98	5990.62		5988.60
61893	5/14/98	0.00	5946.20		5937.40
61993	5/14/98	5.96	5929.54		5929.50
62395	1/6/98			DRY	
62395	2/9/98			DRY	
62395	3/4/98			DRY	
62395	4/8/98	2.12			
62395	5/4/98	7.55			
62395	6/4/98	8.48			
62395	8/4/98	9.02			
62395	9/1/98	9.35			
62395	10/12/98	9.31			
62395	11/4/98	9.21			
62395	12/7/98	9.26			
62593	1/15/98	4.40	6043.40		6039.40
62593	2/9/98	2.97	6044.83		6039.40
62593	3/3/98	3.53	6044.27		6039.40
62593	4/1/98	0.56	6047.24		6039.40
62593	5/4/98	0.56	6047.24		6039.40
62593	6/2/98	2.79	6045.01		6039.40
62593	7/1/98	4.21	6043.59		6039.40
62593	8/10/98	5.71	6042.09		6039.40
62593	9/2/98	6.75	6041.05		6039.40

243 242

DRAFT

Appendix A

RF/RMRS-99-433.UN

62593	10/6/98	7.33	6040.47		6039.40
62593	11/3/98	7.35	6040.45		6039.40
62593	12/1/98	6.40	6041.40		6039.40
62693	1/15/98	1.84	6039.96		6033.20
62693	2/9/98	1.34	6040.46		6033.20
62693	3/3/98	1.93	6039.87		6033.20
62693	4/1/98	0.00	6041.80		6033.20
62693	5/4/98	0.00	6041.80		6033.20
62693	6/2/98	2.97	6038.83		6033.20
62693	7/1/98	4.43	6037.37		6033.20
62693	8/10/98	6.11	6035.69		6033.20
62693	9/2/98	7.60	6034.20		6033.20
62693	10/6/98	7.94	6033.86		6033.20
62693	11/3/98	7.70	6034.10		6033.20
62693	12/1/98	4.96	6036.84		6033.20
62793	5/14/98			DRY	5927.70
6286	1/8/98	29.31	5873.87		5867.98
6286	4/9/98	29.13	5874.05		5867.98
6286	7/2/98	27.61	5875.57		5867.98
6286	10/8/98	27.25	5875.93		5867.98
62893	1/15/98	0.75	5994.45		5980.40
62893	4/1/98	0.00	5995.20		5980.40
62893	5/18/98	0.70	5994.50		5980.40
62893	10/6/98	1.80	5993.40		5980.40
63193	5/13/98			DRY	5948.90
63395	1/5/98	7.16	5892.84		5892.00
63395	4/10/98	6.72	5893.28		5892.00
63395	5/12/98	4.57	5895.43		5892.00
63395	10/6/98	7.18	5892.82		5892.00
63495	1/16/98	2.86	6008.14		6003.20
63495	4/13/98	2.10	6008.90		6003.20
63495	5/8/98	2.10	6008.90		6003.20
63495	10/5/98	3.51	6007.49		6003.20
63795	1/12/98	4.90			
63795	2/3/98	5.50			
63795	3/4/98	4.99			
63795	4/10/98	3.44			
63795	5/5/98	4.10			
63795	6/1/98	4.91			
63795	7/8/98	6.44			
63795	8/3/98	7.61			
63795	9/3/98	9.96			
63795	10/5/98	9.68			
63795	11/2/98	9.35			
63795	12/7/98	8.96			
6386	1/8/98	15.22	5886.79		5886.71
6386	4/9/98	13.63	5888.38		5886.71
6386	7/2/98	9.65	5892.36		5886.71
6386	10/8/98	15.84	5886.17	X	5886.71

244 243

63895	1/12/98	5.60			
63895	2/3/98	5.57			
63895	3/4/98	5.60			
63895	4/10/98	4.12			
63895	5/5/98	4.15			
63895	6/1/98	4.44			
63895	7/8/98	4.80			
63895	8/3/98	4.85			
63895	9/3/98	5.21			
63895	10/5/98	5.27			
63895	11/2/98	5.33			
63895	12/7/98	5.60			
64595	1/16/98			DRY	5787.80
64595	2/9/98			DRY	5787.80
64595	3/4/98			DRY	5787.80
64595	4/7/98			DRY	5787.80
64595	5/4/98			DRY	5787.80
6486	1/13/98	7.08	5833.97		5832.05
6486	2/4/98	7.04	5834.01		5832.05
6486	3/2/98	7.22	5833.83		5832.05
6486	4/7/98	6.47	5834.58		5832.05
6486	5/4/98	7.82	5833.23		5832.05
6486	6/1/98	7.53	5833.52		5832.05
6486	7/1/98	8.42	5832.63		5832.05
6486	8/4/98			DRY	5832.05
6486	9/2/98	11.21	5829.84	X	5832.05
6486	10/6/98			DRY	5832.05
6486	11/3/98			DRY	5832.05
6486	12/1/98	10.82	5830.23	X	5832.05
6586	1/16/98			DRY	5780.27
6586	3/2/98			DRY	5780.27
6586	4/7/98	7.81	5780.46		5780.27
6586	5/5/98	6.00	5782.27		5780.27
6586	6/1/98			DRY	5780.27
6586	7/1/98			DRY	5780.27
6586	8/4/98			DRY	5780.27
6586	9/2/98			DRY	5780.27
6586	10/6/98			DRY	5780.27
6586	11/3/98	6.15	5782.12		5780.27
6586	12/1/98	6.01	5782.26		5780.27
6587	2/4/98	8.05	5976.94		5960.99
6686	1/5/98	4.45	5689.75		5687.70
6686	2/4/98	4.37	5689.83		5687.70
6686	3/3/98	4.64	5689.56		5687.70
6686	4/13/98	4.72	5689.48		5687.70
6686	5/4/98	4.88	5689.32		5687.70
6686	6/4/98	5.14	5689.06		5687.70
6686	7/2/98	6.62	5687.58	X	5687.70
6686	8/4/98	7.32	5686.88	X	5687.70

245 244

Appendix A

6686	9/1/98	7.53	5686.67	X	5687.70
6686	10/8/98	8.13	5686.07	X	5687.70
6686	11/3/98	4.49	5689.71		5687.70
6686	12/4/98	4.86	5689.34		5687.70
6774	5/8/98	2.64	6047.50		5993.14
6786	1/16/98			DRY	5789.17
6786	4/7/98			DRY	5789.17
6786	10/8/98	15.99	5787.98	X	5789.17
68194	9/17/98	6.64	6020.46		6009.10
68494	1/16/98	6.50	6017.87		6009.17
68494	9/17/98	6.18	6018.19		6009.17
6886	1/16/98	3.50	5886.99		5886.99
6886	3/12/98	3.49	5887.00		5886.99
6886	4/9/98	3.29	5887.20		5886.99
6886	5/4/98	3.55	5886.94	X	5886.99
6886	6/1/98	3.81	5886.68	X	5886.99
6886	6/18/98	3.82	5886.67	X	5886.99
6886	7/1/98	4.01	5886.48	X	5886.99
70093	1/7/98	12.50	5980.40		5970.90
70093	5/8/98	4.55	5988.35		5970.90
70193	1/7/98	12.12	5979.88		5954.70
70193	4/7/98	5.21	5986.79		5954.70
70193	7/1/98	10.18	5981.82		5954.70
70193	10/6/98	12.76	5979.24		5954.70
70393	1/7/98	9.71	5990.39		5977.30
70393	1/7/98	9.71	5990.39		5977.30
70393	4/7/98	3.81	5996.29		5977.30
70393	5/8/98	3.05	5997.05		5977.30
70393	7/1/98	8.05	5992.05		5977.30
70393	10/5/98	12.03	5988.07		5977.30
70493	1/7/98	9.70	5990.30		5956.00
70493	4/7/98	5.48	5994.52		5956.00
70493	7/1/98	10.16	5989.84		5956.00
70493	10/5/98	11.16	5988.84		5956.00
70593	1/7/98	30.99	5969.01		5864.00
70693	1/7/98	16.08	5976.62		5964.30
70693	4/7/98	6.67	5986.03		5964.30
70693	5/8/98	7.36	5985.34		5964.30
70693	10/5/98	17.62	5975.08		5964.30
7086	1/16/98	3.13	5936.26		5931.49
7086	4/7/98	2.66	5936.73		5931.49
7086	5/13/98	3.21	5936.18		5931.49
7086	7/1/98	4.65	5934.74		5931.49
7086	10/6/98	4.48	5934.91		5931.49
7187	1/7/98	6.90	5958.59		5951.99
7187	4/7/98	4.26	5961.23		5951.99
7187	10/6/98	8.61	5956.88		5951.99
75292	1/5/98	6.42	5750.48		5749.30
75292	2/5/98	5.64	5751.26		5749.30

244 245

75292	2/19/98	6.96	5749.94		5749.30
75292	3/4/98	7.24	5749.66		5749.30
75292	4/7/98	4.15	5752.75		5749.30
75292	5/5/98	4.51	5752.39		5749.30
75292	6/2/98	4.61	5752.29		5749.30
75292	7/1/98	8.66	5748.24	X	5749.30
75292	8/4/98	8.02	5748.88	X	5749.30
75292	9/1/98	8.91	5747.99	X	5749.30
75292	10/6/98	8.16	5748.74	X	5749.30
75292	11/4/98	5.57	5751.33		5749.30
75292	12/3/98	6.45	5750.45		5749.30
75992	1/5/98	7.80	5891.30		5889.10
75992	1/5/98	7.80	5891.30		5889.10
75992	4/13/98	5.78	5893.32		5889.10
75992	5/11/98	5.82	5893.28		5889.10
75992	7/1/98	7.76	5891.34		5889.10
75992	10/6/98	8.79	5890.31		5889.10
76292	1/7/98	18.55	5940.75		5940.10
76292	2/11/98	19.16	5940.14		5940.10
76292	3/11/98	19.57	5939.73	X	5940.10
76292	4/8/98	10.21	5949.09		5940.10
76292	5/6/98	9.09	5950.21		5940.10
76292	6/4/98	12.37	5946.93		5940.10
76792	1/12/98	6.93	5938.57	X	5940.00
76792	4/7/98	2.22	5943.28		5940.00
76792	5/8/98	2.50	5943.00		5940.00
76792	10/6/98	7.19	5938.31	X	5940.00
76992	1/12/98	9.87	5948.13	X	5948.60
76992	4/7/98	6.11	5951.89		5948.60
76992	5/8/98	7.30	5950.70		5948.60
76992	7/1/98	10.01	5947.99	X	5948.60
76992	10/6/98	12.06	5945.94	X	5948.60
77192	5/8/98	2.32	5913.58		5910.00
77392	1/12/98			DRY	5958.60
77392	4/7/98	5.22	5960.28		5958.60
77392	5/8/98	4.19	5961.31		5958.60
77392	7/1/98	8.51	5956.99	X	5958.60
77392	10/6/98	10.13	5955.37	X	5958.60
77492	1/6/98	13.82	5930.68		5922.40
77492	2/5/98	13.90	5930.60		5922.40
77492	3/3/98	14.03	5930.47		5922.40
77492	4/2/98	12.80	5931.70		5922.40
77492	5/6/98	11.94	5932.56		5922.40
77492	6/2/98	12.24	5932.26		5922.40
77492	6/17/98	12.16	5932.34		5922.40
77492	7/7/98	12.49	5932.01		5922.40
B102289	1/12/98	2.88	5977.18		5967.56
B102289	4/10/98	2.95	5977.11		5967.56
B102289	10/5/98	3.02	5977.04		5967.56

247 246

B102389	1/12/98	4.76	5936.42		5930.28
B102389	4/10/98	3.73	5937.45		5930.28
B102389	10/5/98	7.29	5933.89		5930.28
B110889	1/8/98	35.82	6041.95		6012.97
B110889	4/10/98	35.29	6042.48		6012.97
B110889	10/1/98	32.68	6045.09		6012.97
B110989	1/8/98	47.98	6036.38		6018.76
B110989	2/3/98	48.11	6036.25		6018.76
B110989	3/2/98	47.98	6036.38		6018.76
B110989	4/10/98	47.74	6036.62		6018.76
B110989	5/5/98	45.39	6038.97		6018.76
B110989	6/1/98	43.68	6040.68		6018.76
B110989	7/9/98	43.68	6040.68		6018.76
B110989	8/3/98	44.09	6040.27		6018.76
B110989	9/3/98	44.24	6040.12		6018.76
B110989	10/1/98	44.77	6039.59		6018.76
B110989	11/2/98	45.25	6039.11		6018.76
B110989	12/7/98	46.10	6038.26		6018.76
B111189	1/7/98	59.00	6048.52		6034.92
B111189	2/3/98	59.04	6048.48		6034.92
B111189	3/2/98	58.85	6048.67		6034.92
B111189	4/10/98	58.95	6048.57		6034.92
B111189	5/5/98	58.38	6049.14		6034.92
B111189	6/1/98	57.78	6049.74		6034.92
B111189	7/1/98	57.25	6050.27		6034.92
B111189	8/3/98	56.96	6050.56		6034.92
B111189	9/3/98	56.43	6051.09		6034.92
B111189	10/1/98	56.34	6051.18		6034.92
B111189	11/2/98	56.08	6051.44		6034.92
B111189	12/7/98	56.29	6051.23		6034.92
B200589	1/12/98	21.18	5948.99		5938.57
B200589	2/3/98	21.24	5948.93		5938.57
B200589	2/3/98	19.24	5950.93		5938.57
B200589	3/4/98	21.32	5948.85		5938.57
B200589	4/10/98	17.13	5953.04		5938.57
B200589	5/8/98	13.28	5956.89		5938.57
B200589	6/5/98	16.71	5953.46		5938.57
B200589	6/16/98	17.50	5952.67		5938.57
B200589	7/8/98	18.86	5951.31		5938.57
B200889	1/12/98	19.16	5918.92		5914.98
B200889	3/4/98	19.35	5918.73		5914.98
B200889	4/13/98	13.50	5924.58		5914.98
B200889	5/8/98	8.03	5930.05		5914.98
B200889	6/5/98	10.79	5927.29		5914.98
B200889	7/8/98	13.44	5924.64		5914.98
B200889	8/3/98	15.07	5923.01		5914.98
B200889	9/3/98	16.07	5922.01		5914.98
B200889	10/5/98	17.17	5920.91		5914.98
B200889	11/2/98	17.83	5920.25		5914.98

28 247

B200889	11/2/98	17.83	5920.25		5914.98
B200889	12/7/98	18.68	5919.40		5914.98
B202589	1/15/98	3.37	5722.08		5713.85
B206989	1/12/98	21.24	5863.08		5863.02
B206989	4/10/98	22.43	5861.89	X	5863.02
B206989	7/1/98	23.07	5861.25	X	5863.02
B206989	10/6/98	22.57	5861.75	X	5863.02
B208089	1/13/98	12.93	5924.14	X	5924.17
B208089	2/5/98	13.06	5924.01	X	5924.17
B208089	3/4/98	13.40	5923.67	X	5924.17
B208089	4/13/98	8.00	5929.07		5924.17
B208089	5/5/98	8.29	5928.78		5924.17
B208089	6/2/98	11.16	5925.91		5924.17
B208089	7/1/98	11.98	5925.09		5924.17
B208089	8/4/98	12.61	5924.46		5924.17
B208089	9/1/98	12.70	5924.37		5924.17
B208089	10/6/98	13.15	5923.92	X	5924.17
B208089	11/3/98	13.48	5923.59	X	5924.17
B208089	12/3/98	13.61	5923.46	X	5924.17
B208189	1/13/98	13.93	5923.53		5911.16
B208289	1/12/98	17.04	5835.91	X	5837.55
B208289	4/7/98	17.11	5835.84	X	5837.55
B208289	7/1/98	17.27	5835.68	X	5837.55
B208289	10/6/98	16.65	5836.30	X	5837.55
B208589	1/12/98	4.00	5854.35		5854.35
B208589	2/18/98	4.05	5854.30	X	5854.35
B208589	3/11/98	4.02	5854.33	X	5854.35
B208589	4/9/98	2.87	5855.48		5854.35
B208589	5/7/98	3.21	5855.14		5854.35
B208589	6/5/98	4.45	5853.90	X	5854.35
B208689	1/12/98	18.27	5851.33		5847.80
B208689	2/18/98	15.75	5853.85		5847.80
B208789	1/13/98	3.14	5905.89		5898.13
B208789	2/19/98	3.33	5905.70		5898.13
B208789	4/7/98	2.60	5906.43		5898.13
B208789	5/8/98	2.52	5906.51		5898.13
B208789	7/1/98	4.65	5904.38		5898.13
B208789	10/6/98	6.37	5902.66		5898.13
B210389	1/12/98	24.75	5850.57	X	5852.22
B210389	2/18/98	23.96	5851.36	X	5852.22
B210389	3/11/98	23.59	5851.73	X	5852.22
B210389	4/9/98	23.08	5852.24		5852.22
B210389	5/6/98	22.67	5852.65		5852.22
B210389	6/5/98	22.11	5853.21		5852.22
B210489	1/12/98	4.13	5854.58		5851.31
B210489	2/18/98	4.17	5854.54		5851.31
B210489	3/11/98	4.15	5854.56		5851.31
B210489	4/7/98	2.80	5855.91		5851.31
B210489	5/5/98	2.83	5855.88		5851.31

B210489	6/2/98	4.93	5853.78		5851.31
B210489	6/17/98	5.07	5853.64		5851.31
B210489	7/1/98	5.76	5852.95		5851.31
B213789	5/11/98	8.56	5911.45	X	5913.11
B400389	1/5/98	23.07	6100.93		6075.00
B400389	2/4/98	23.74	6100.26		6075.00
B400389	3/2/98	25.28	6098.72		6075.00
B400389	4/1/98	21.85	6102.15		6075.00
B400389	5/4/98	16.37	6107.63		6075.00
B400389	6/1/98	16.75	6107.25		6075.00
B400389	7/1/98	20.05	6103.95		6075.00
B400389	8/3/98	20.23	6103.77		6075.00
B400389	9/1/98	21.22	6102.78		6075.00
B400389	10/5/98	22.41	6101.59		6075.00
B400389	11/3/98	23.33	6100.67		6075.00
B400389	12/1/98	23.89	6100.11		6075.00
B402689	1/5/98	4.16	6042.91	X	6043.77
B402689	2/4/98	3.81	6043.26	X	6043.77
B402689	3/2/98	4.45	6042.62	X	6043.77
B402689	4/1/98	2.90	6044.17		6043.77
B402689	4/7/98	2.98	6044.09		6043.77
B402689	5/4/98	3.11	6043.96		6043.77
B402689	6/1/98	3.90	6043.17	X	6043.77
B402689	7/1/98	5.65	6041.42	X	6043.77
B402689	8/3/98	5.63	6041.44	X	6043.77
B402689	9/1/98	6.24	6040.83	X	6043.77
B402689	10/5/98	6.24	6040.83	X	6043.77
B402689	11/3/98	5.37	6041.70	X	6043.77
B402689	12/1/98	4.27	6042.80	X	6043.77
B410589	1/5/98	54.27	6059.53		6053.80
B410589	2/3/98	54.26	6059.54		6053.80
B410589	3/2/98	54.02	6059.78		6053.80
B410589	4/10/98	54.03	6059.77		6053.80
B410589	5/5/98	52.66	6061.14		6053.80
B410589	6/1/98	51.47	6062.33		6053.80
B410589	7/2/98	50.57	6063.23		6053.80
B410589	8/3/98	51.08	6062.72		6053.80
B410589	9/1/98	50.96	6062.84		6053.80
B410589	10/1/98	51.07	6062.73		6053.80
B410589	11/2/98	51.16	6062.64		6053.80
B410589	12/7/98	51.74	6062.06		6053.80
B410689	1/5/98	44.00	6049.71		6043.61
B410689	4/10/98	43.66	6050.05		6043.61
B410689	10/1/98	40.18	6053.53		6043.61
B410789	1/8/98	37.52	6046.14		6038.66
B410789	4/10/98	37.12	6046.54		6038.66
B410789	10/1/98	34.05	6049.61		6038.66
B411289	1/7/98	63.92	6063.38		6058.90
B411289	2/4/98	63.66	6063.64		6058.90

B411289	3/2/98	63.66	6063.64		6058.90
B411289	4/10/98	63.59	6063.71		6058.90
B411289	5/5/98	63.16	6064.14		6058.90
B411289	6/1/98	62.73	6064.57		6058.90
B411289	7/1/98	62.13	6065.17		6058.90
B411289	8/3/98	61.65	6065.65		6058.90
B411289	9/3/98	60.95	6066.35		6058.90
B411289	10/1/98	60.81	6066.49		6058.90
B411289	11/2/98	60.43	6066.87		6058.90
B411289	12/7/98	60.35	6066.95		6058.90
B411389	2/3/98	55.63	6055.43		6047.56
P114389	1/6/98	6.88	5986.29		5978.67
P114389	2/5/98	6.75	5986.42		5978.67
P114389	3/5/98	7.30	5985.87		5978.67
P114389	4/7/98	5.96	5987.21		5978.67
P114389	5/5/98	6.00	5987.17		5978.67
P114389	6/3/98	6.67	5986.50		5978.67
P114389	7/1/98	7.28	5985.89		5978.67
P114389	8/4/98	7.22	5985.95		5978.67
P114389	9/8/98	7.60	5985.57		5978.67
P114389	10/5/98	7.78	5985.39		5978.67
P114389	11/5/98	7.33	5985.84		5978.67
P114389	12/2/98	7.51	5985.66		5978.67
P114489	1/13/98	12.73	6022.70		5986.63
P114489	4/8/98	8.35	6027.08		5986.63
P114489	10/5/98	14.03	6021.40		5986.63
P114589	1/13/98	5.06	6020.84		5989.40
P114589	4/8/98	2.62	6023.28		5989.40
P114589	10/5/98	7.20	6018.70		5989.40
P114689	1/7/98	10.51	5995.25		5983.56
P114689	4/8/98	7.88	5997.88		5983.56
P114689	9/17/98	12.53	5993.23		5983.56
P114689	10/5/98	13.34	5992.42		5983.56
P114789	1/7/98	9.66	6002.74		5986.20
P114789	4/8/98	7.91	6004.49		5986.20
P114789	9/17/98	10.08	6002.32		5986.20
P114789	10/5/98	10.22	6002.18		5986.20
P114889	1/7/98	7.10	6011.16		6003.96
P114889	3/11/98	7.14	6011.12		6003.96
P114889	4/8/98	6.42	6011.84		6003.96
P114889	5/5/98	6.15	6012.11		6003.96
P114889	6/3/98	4.78	6013.48		6003.96
P114889	6/18/98	4.78	6013.48		6003.96
P114889	7/8/98	4.93	6013.33		6003.96
P114889	9/17/98	5.33	6012.93		6003.96
P114989	1/6/98	13.36	6018.48		5993.84
P114989	4/8/98	14.47	6017.37		5993.84
P114989	9/17/98	12.50	6019.34		5993.84
P114989	10/5/98	12.53	6019.31		5993.84

P115089	1/6/98	13.95	6026.15		5999.40
P115089	2/5/98	13.90	6026.20		5999.40
P115089	3/2/98	14.80	6025.30		5999.40
P115089	4/8/98	9.94	6030.16		5999.40
P115089	5/5/98	8.63	6031.47		5999.40
P115089	6/3/98	10.63	6029.47		5999.40
P115089	7/8/98	12.73	6027.37		5999.40
P115089	8/4/98	13.36	6026.74		5999.40
P115089	9/8/98	14.24	6025.86		5999.40
P115089	9/17/98	14.68	6025.42		5999.40
P115089	10/5/98	15.32	6024.78		5999.40
P115089	11/5/98	16.31	6023.79		5999.40
P115089	12/2/98	16.12	6023.98		5999.40
P115489	1/16/98	9.49	6015.61		5998.60
P115489	3/11/98	10.35	6014.75		5998.60
P115489	4/8/98	7.15	6017.95		5998.60
P115489	5/5/98	6.62	6018.48		5998.60
P115489	6/3/98	7.59	6017.51		5998.60
P115489	6/18/98	7.98	6017.12		5998.60
P115489	7/8/98	8.74	6016.36		5998.60
P115489	9/17/98	10.10	6015.00		5998.60
P115489	9/17/98	10.10	6015.00		5998.60
P115589	1/7/98	6.48	6009.29		5986.27
P115589	4/8/98	4.20	6011.57		5986.27
P115589	9/17/98	7.67	6008.10		5986.27
P115589	10/5/98	8.21	6007.56		5986.27
P115689	1/7/98	10.40	5998.31		5988.51
P115689	4/8/98	5.82	6002.89		5988.51
P115689	9/17/98	12.56	5996.15		5988.51
P115689	10/5/98	12.80	5995.91		5988.51
P119389	1/7/98	4.24	6008.94		5996.28
P119389	2/5/98	4.50	6008.68		5996.28
P119389	3/3/98	4.99	6008.19		5996.28
P119389	4/2/98	4.95	6008.23		5996.28
P119389	5/6/98	5.64	6007.54		5996.28
P119389	6/2/98	4.81	6008.37		5996.28
P119389	6/17/98	4.04	6009.14		5996.28
P119389	7/7/98	4.91	6008.27		5996.28
P207389	1/12/98	6.76	5976.01		5967.57
P207689	1/7/98	8.03	5959.85		5954.78
P207689	4/2/98	5.80	5962.08		5954.78
P207689	10/7/98	10.62	5957.26		5954.78
P207789	1/7/98	25.71	5942.04		5940.45
P207889	1/6/98	6.12	5958.78		5957.20
P207889	2/11/98	5.97	5958.93		5957.20
P207889	4/2/98	3.93	5960.97		5957.20
P207889	10/7/98	10.11	5954.79	X	5957.20
P207989	1/6/98	20.64	5944.53	X	5944.67
P207989	2/10/98	25.34	5939.83	X	5944.67

P207989	2/11/98	18.85	5946.32		5944.67
P208889	2/11/98	93.08	5856.17		5852.35
P208989	2/11/98	17.41	5947.15		5939.76
P208989	3/11/98	17.52	5947.04		5939.76
P208989	4/8/98	13.00	5951.56		5939.76
P208989	5/6/98	12.00	5952.56		5939.76
P208989	6/4/98	14.34	5950.22		5939.76
P209089	2/11/98	24.55	5949.70		5948.25
P209189	2/16/98	13.51	5968.70		5947.21
P209289	1/6/98	14.73	5968.69	X	5970.72
P209289	4/2/98	13.63	5969.79	X	5970.72
P209289	7/7/98	15.04	5968.38	X	5970.72
P209289	10/7/98	14.75	5968.67	X	5970.72
P209389	1/12/98	19.07	5964.32		5954.59
P209389	4/2/98	16.88	5966.51		5954.59
P209389	7/7/98	18.46	5964.93		5954.59
P209389	10/7/98	18.96	5964.43		5954.59
P209489	2/16/98	29.27	5950.83		5945.10
P209489	4/8/98	27.05	5953.05		5945.10
P209489	7/7/98	28.73	5951.37		5945.10
P209489	10/7/98	29.26	5950.84		5945.10
P209589	2/11/98	20.17	5929.87	X	5931.54
P209689	1/7/98	24.68	5939.75		5937.73
P209789	1/7/98	8.72	5956.22		5952.44
P209789	2/10/98	8.81	5956.13		5952.44
P209789	4/2/98	4.34	5960.60		5952.44
P209789	10/7/98	11.81	5953.13		5952.44
P209889	2/11/98	5.65	5936.75		5924.10
P209889	6/17/98	4.93	5937.47		5924.10
P209889	7/7/98	5.39	5937.01		5924.10
P209889	7/7/98	5.39	5937.01		5924.10
P210089	1/13/98	20.40	5880.00		5878.90
P210089	2/19/98	19.23	5881.17		5878.90
P210089	3/11/98	18.90	5881.50		5878.90
P210089	4/9/98	15.81	5884.59		5878.90
P210089	5/6/98	11.91	5888.49		5878.90
P210089	6/5/98	18.51	5881.89		5878.90
P210189	2/16/98	14.50	5967.98		5946.38
P213689	1/13/98	9.42	5986.62		5982.54
P213689	3/11/98	9.78	5986.26		5982.54
P213689	4/8/98	8.69	5987.35		5982.54
P213689	5/7/98	8.17	5987.87		5982.54
P213689	6/3/98	7.66	5988.38		5982.54
P213689	6/18/98	8.08	5987.96		5982.54
P213689	7/8/98	8.73	5987.31		5982.54
P213989	1/13/98			DRY	5949.48
P215789	1/13/98	9.23	5994.43		5985.16
P215789	4/8/98	14.23	5989.43		5985.16
P215789	10/5/98	16.46	5987.20		5985.16

P218089	1/7/98	5.55	5982.00		5980.15
P218089	4/2/98	4.12	5983.43		5980.15
P218089	10/7/98	5.85	5981.70		5980.15
P218289	1/6/98	9.42	6008.78		5994.70
P218289	4/8/98	4.98	6013.22		5994.70
P218289	9/17/98	9.92	6008.28		5994.70
P218289	10/6/98	10.46	6007.74		5994.70
P218389	1/7/98	14.44	5944.01	X	5945.95
P218389	2/5/98	14.75	5943.70	X	5945.95
P218389	2/16/98	14.80	5943.65	X	5945.95
P218389	3/3/98	14.80	5943.65	X	5945.95
P218389	3/11/98	14.84	5943.61	X	5945.95
P218389	4/2/98	8.65	5949.80		5945.95
P218389	5/6/98	7.24	5951.21		5945.95
P218389	6/4/98	10.17	5948.28		5945.95
P218389	7/7/98	12.77	5945.68	X	5945.95
P218389	8/5/98	10.18	5948.27		5945.95
P218389	9/2/98	14.32	5944.13	X	5945.95
P218389	10/7/98	14.77	5943.68	X	5945.95
P218389	11/2/98	14.84	5943.61	X	5945.95
P218389	12/1/98			DRY	5945.95
P219189	1/5/98	12.40	5930.75	X	5931.65
P219189	2/5/98	13.45	5929.70	X	5931.65
P219189	3/3/98	13.14	5930.01	X	5931.65
P219189	4/8/98	12.66	5930.49	X	5931.65
P219189	5/6/98	11.87	5931.28	X	5931.65
P219189	6/2/98	11.41	5931.74		5931.65
P219189	7/7/98	13.47	5929.68	X	5931.65
P219189	8/5/98	13.04	5930.11	X	5931.65
P219189	9/2/98	12.58	5930.57	X	5931.65
P219189	10/7/98	12.01	5931.14	X	5931.65
P219189	11/2/98	12.00	5931.15	X	5931.65
P219189	12/1/98	13.42	5929.73	X	5931.65
P219489	1/6/98	23.35	5937.80	X	5938.25
P219489	4/2/98	23.74	5937.41	X	5938.25
P219489	7/7/98	24.42	5936.73	X	5938.25
P219489	10/7/98	22.93	5938.22	X	5938.25
P219589	2/16/98	27.43	5938.27	X	5940.00
P219589	3/11/98	27.28	5938.42	X	5940.00
P219589	4/8/98	27.00	5938.70	X	5940.00
P219589	5/6/98	26.64	5939.06	X	5940.00
P219589	6/5/98	26.28	5939.42	X	5940.00
P313489	1/6/98	14.69	5998.89		5992.48
P313489	4/8/98	9.26	6004.32		5992.48
P313489	9/17/98	15.53	5998.05		5992.48
P313489	10/6/98	15.89	5997.69		5992.48
P313589	1/6/98	9.39	6000.72		5997.61
P313589	2/5/98	9.55	6000.56		5997.61
P313589	3/5/98	10.15	5999.96		5997.61

P313589	4/2/98	7.14	6002.97		5997.61
P313589	5/5/98	7.52	6002.59		5997.61
P313589	6/3/98	8.04	6002.07		5997.61
P313589	7/8/98	8.45	6001.66		5997.61
P313589	8/4/98	8.08	6002.03		5997.61
P313589	9/8/98	8.55	6001.56		5997.61
P313589	10/6/98	8.94	6001.17		5997.61
P313589	11/5/98	9.34	6000.77		5997.61
P313589	12/1/98	9.41	6000.70		5997.61
P314289	1/6/98	13.45	5998.32		5998.27
P314289	2/5/98	13.89	5997.88	X	5998.27
P314289	3/5/98	16.41	5995.36	X	5998.27
P314289	4/2/98	15.03	5996.74	X	5998.27
P314289	5/5/98	13.19	5998.58		5998.27
P314289	6/3/98	12.69	5999.08		5998.27
P314289	7/8/98	12.95	5998.82		5998.27
P314289	8/4/98	14.29	5997.48	X	5998.27
P314289	9/8/98	12.77	5999.00		5998.27
P314289	9/17/98	12.81	5998.96		5998.27
P314289	10/6/98	12.86	5998.91		5998.27
P314289	11/4/98	13.43	5998.34		5998.27
P314289	12/1/98	13.78	5997.99	X	5998.27
P317989	1/7/98	6.42	5986.42		5985.34
P317989	4/7/98	3.62	5989.22		5985.34
P317989	10/6/98	7.84	5985.00	X	5985.34
P320089	1/6/98	14.41	5997.46		5993.07
P320089	4/8/98	9.99	6001.88		5993.07
P320089	9/17/98	15.20	5996.67		5993.07
P320089	10/5/98	15.50	5996.37		5993.07
P414189	1/6/98	8.81	6003.37		5993.68
P414189	4/8/98	5.09	6007.09		5993.68
P414189	9/17/98	11.09	6001.09		5993.68
P414189	10/6/98	12.15	6000.03		5993.68
P415889	1/6/98	13.23	6039.37		6009.40
P415889	2/5/98	13.33	6039.27		6009.40
P415889	3/5/98	15.15	6037.45		6009.40
P415889	4/8/98	10.63	6041.97		6009.40
P415889	5/5/98	9.64	6042.96		6009.40
P415889	6/3/98	10.90	6041.70		6009.40
P415889	6/16/98	11.21	6041.39		6009.40
P415889	7/8/98	13.09	6039.51		6009.40
P415889	9/17/98	15.56	6037.04		6009.40
P415989	1/6/98	5.56	6041.15		6020.01
P415989	4/8/98	2.94	6043.77		6020.01
P415989	9/17/98	8.45	6038.26		6020.01
P415989	10/5/98	9.61	6037.10		6020.01
P416089	1/6/98	6.48	6047.47		6019.95
P416089	2/5/98	3.60	6050.35		6019.95
P416089	3/5/98	10.23	6043.72		6019.95

255254

P416089	4/8/98	3.84	6050.11		6019.95
P416089	5/5/98	3.86	6050.09		6019.95
P416089	6/3/98	5.45	6048.50		6019.95
P416089	7/8/98	8.86	6045.09		6019.95
P416089	8/4/98	7.76	6046.19		6019.95
P416089	9/8/98	10.73	6043.22		6019.95
P416089	9/17/98	11.53	6042.42		6019.95
P416089	10/5/98	12.42	6041.53		6019.95
P416089	11/4/98	14.03	6039.92		6019.95
P416089	12/1/98	11.88	6042.07		6019.95
P416189	1/6/98	7.90	6040.05		6018.25
P416189	4/8/98	5.22	6042.73		6018.25
P416189	9/17/98	11.66	6036.29		6018.25
P416189	10/5/98	13.18	6034.77		6018.25
P416289	1/6/98	13.44	6026.78		6016.72
P416289	4/2/98	11.64	6028.58		6016.72
P416289	9/17/98	15.07	6025.15		6016.72
P416289	10/5/98	15.98	6024.24		6016.72
P416389	1/6/98	13.23	6043.91		6027.04
P416389	4/8/98	5.15	6051.99		6027.04
P416389	9/17/98	16.67	6040.47		6027.04
P416389	10/5/98	18.00	6039.14		6027.04
P416489	1/6/98	14.57	6035.58		6024.45
P416489	2/5/98	14.82	6035.33		6024.45
P416489	3/5/98	17.54	6032.61		6024.45
P416489	4/8/98	9.22	6040.93		6024.45
P416489	5/5/98	8.52	6041.63		6024.45
P416489	6/3/98	11.91	6038.24		6024.45
P416489	7/8/98	16.60	6033.55		6024.45
P416489	8/4/98	17.65	6032.50		6024.45
P416489	9/3/98	18.41	6031.74		6024.45
P416489	9/17/98	19.37	6030.78		6024.45
P416489	10/5/98	20.44	6029.71		6024.45
P416489	11/4/98	22.10	6028.05		6024.45
P416489	12/1/98	20.20	6029.95		6024.45
P416589	1/6/98	26.04	6016.77		6011.81
P416589	3/12/98	27.46	6015.35		6011.81
P416589	4/2/98	24.92	6017.89		6011.81
P416589	5/5/98	21.50	6021.31		6011.81
P416589	6/3/98	23.80	6019.01		6011.81
P416589	6/16/98	24.64	6018.17		6011.81
P416589	7/8/98	26.40	6016.41		6011.81
P416589	9/17/98	27.53	6015.28		6011.81
P416689	1/6/98	29.06	6007.49		6004.05
P416689	2/5/98	29.16	6007.39		6004.05
P416689	3/5/98	29.57	6006.98		6004.05
P416689	4/2/98	18.44	6018.11		6004.05
P416689	5/5/98	27.87	6008.68		6004.05
P416689	6/3/98	28.06	6008.49		6004.05

P416689	7/8/98	29.03	6007.52		6004.05
P416689	8/4/98	29.12	6007.43		6004.05
P416689	9/3/98	29.18	6007.37		6004.05
P416689	9/17/98	29.36	6007.19		6004.05
P416689	10/5/98	29.52	6007.03		6004.05
P416689	11/4/98	32.86	6003.69	X	6004.05
P416689	12/1/98	30.31	6006.24		6004.05
P416789	1/6/98	27.07	6002.20	X	6002.37
P416789	2/5/98	27.21	6002.06	X	6002.37
P416789	3/5/98	27.62	6001.65	X	6002.37
P416789	4/2/98	23.54	6005.73		6002.37
P416789	5/5/98	23.43	6005.84		6002.37
P416789	6/3/98	25.56	6003.71		6002.37
P416789	7/8/98	26.91	6002.36	X	6002.37
P416789	8/4/98	26.65	6002.62		6002.37
P416789	9/8/98	27.36	6001.91	X	6002.37
P416789	9/17/98	27.51	6001.76	X	6002.37
P416789	10/5/98	27.69	6001.58	X	6002.37
P416789	11/4/98	29.67	5999.60	X	6002.37
P416789	12/1/98	27.21	6002.06	X	6002.37
P416889	1/6/98	17.86	6000.93		5998.49
P416889	2/5/98	18.00	6000.79		5998.49
P416889	3/5/98	18.47	6000.32		5998.49
P416889	4/2/98	14.60	6004.19		5998.49
P416889	5/5/98	14.12	6004.67		5998.49
P416889	6/3/98	16.48	6002.31		5998.49
P416889	7/8/98	17.76	6001.03		5998.49
P416889	8/4/98	17.46	6001.33		5998.49
P416889	9/8/98	18.35	6000.44		5998.49
P416889	10/5/98	18.62	6000.17		5998.49
P416889	11/4/98	18.66	6000.13		5998.49
P416889	12/1/98	18.11	6000.68		5998.49
P416989	1/7/98	39.39	6008.16		5891.95
P416989	4/8/98	39.11	6008.44		5891.95
P416989	10/5/98	39.15	6008.40		5891.95
P419689	1/6/98	19.20	6004.22		5999.92
P419689	4/8/98	13.89	6009.53		5999.92
P419689	9/17/98	19.65	6003.77		5999.92
P419689	10/5/98	20.14	6003.28		5999.92
TH19	1/12/98	39.79	6006.78		5967.57
TH19	2/4/98	39.90	6006.67		5967.57
TH19	3/4/98	40.40	6006.17		5967.57
TH21	1/12/98	35.77	6003.59		5960.36
TH21	2/4/98	35.95	6003.41		5960.36
TH21	3/4/98	36.35	6003.01		5960.36
TH-21	5/8/98	25.36	6014.00		5960.36


257 256




Appendix B

Well Hydrographs


Hydrograph 00293




Hydrograph 00491




Hydrograph 0190




Hydrograph 0290




Hydrograph 0386




Hydrograph 0390



Hydrograph 03991




Hydrograph 04091




206 265


Hydrograph 04591



Hydrograph 0487




Hydrograph 04991




265 218


Hydrograph 05091



Hydrograph 05391




Hydrograph 05691




272 291

Hydrograph 06091




Hydrograph 06491




274-273

Hydrograph 07391




Hydrograph 08091




276275

Hydrograph 0990




Hydrograph 10194




278 277

Hydrograph 10394




274-278


Hydrograph 10592




Hydrograph 10692




Hydrograph 10792




Hydrograph 10994




Hydrograph 11092




Hydrograph 11294



Hydrograph 11494




Hydrograph 11594




287 280

Hydrograph 11891




288 287


Hydrograph 1190



Hydrograph 12191




Hydrograph 12691




294 290

Hydrograph 1290




168 291

Hydrograph 1386




283 292


Hydrograph 1490



Hydrograph 1786




Hydrograph 1986




286295


Hydrograph 2186




Hydrograph 22596



Hydrograph 22696




Hydrograph 22796




22796


Hydrograph 22896




Hydrograph 22996




Hydrograph 23096




Hydrograph 23196



Hydrograph 23296




Hydrograph 2987




206 305


Hydrograph 3087




Hydrograph 3386




Hydrograph 3586




Hydrograph 3687




Hydrograph 38591




Hydrograph 4087




Hydrograph 41591




Hydrograph 41691




Hydrograph 43392




Hydrograph 46292



Hydrograph 4786




Hydrograph 4787




317


Hydrograph 4887




Hydrograph 50494




Hydrograph 51094




Hydrograph 51494




Hydrograph 51594




Hydrograph 52894




Hydrograph 52994




Hydrograph 5387




Hydrograph 5586




Hydrograph 5587




Hydrograph 5686




Hydrograph 5887



Hydrograph 6186




Hydrograph 62593




331
332


Hydrograph 6286




Hydrograph 6386




Hydrograph 6486




Hydrograph 6586




Hydrograph 6786




Hydrograph 70193




Hydrograph 70393




Hydrograph 70493



Hydrograph 7086




Hydrograph 75992




341
242


Hydrograph 77392




Hydrograph 76992



Hydrograph B102289




Hydrograph B102389




345
346

Hydrograph B110989




Hydrograph B111189




347
348

Hydrograph B200589




Hydrograph B200889




349
320


Hydrograph B206989




Hydrograph B208289




Hydrograph B208789



Hydrograph B400389




Hydrograph B402689




354
357

Hydrograph B410589




355
357

Hydrograph B410689




356
2875

Hydrograph B411289




357
 158
 260


Hydrograph P114389




Hydrograph P209289



Hydrograph P209389




Hydrograph P209489




361
364


Hydrograph P218389




Hydrograph P219189




Hydrograph P219489



Hydrograph P313589




Hydrograph P314289



248
L08

Hydrograph P416689





Appendix C.1

1998 Borehole Logs

321 368

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 00198
 Location - North: _____ East: _____
 Date: 3/17/96
 Geologist: Jim Cox / EAM Tota
 Drilling Equip.: Geoprobe - continuous

Surface Elevation: _____
 Area: 905 PAD / RYAN'S PIT
 Total Depth: 12.0
 Company: IT CORP Project No.: _____
 Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____ DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 10/2 0.0 - 12.0	0							0		0-0.35' CLAYEY SILT W/ SAND Y. DK. GRAY (10 YR 3/1) SOME GRANITIC PEBBLES MOIST, W/ GRASS, ROOTS, WORM
								1		0.35'-0.5' GRAVEL GRANITIC PEBBLES SUBROUNDED, W/ CLAYEY SILT W/SAND AS ABOVE. MOIST
								2		0.5-2.0 CLAYEY SILT, Y. DK. GRAYISH BROWN (10 YR 3/2) SOME SAND AND GRANITIC PEBBLES, SUBANGULAR TO SUB ROUNDED, MOIST, SOFT
								3		
								4		2.0' to 4.0' NO RECOVERY CORE STUCK IN BARREL
								5		
								6		4.0' to 5.0' NO RECOVERY CORE STUCK IN BARREL.
								7		(POSSIBLE CONTACT IN THIS INTERVAL CLAYEY SILT AT 8.3-8.6 IS POSSIBLY SLOUGH) (SL)
								8		8.0-8.3' SLOUGH.
								9		8.3-9.0' CLAYEY SILT, Y. DK. BROWN (10 YR 2/2) SOME V. F. SAND, GRANITIC PEBBLES, SUBANGULAR, MOIST, SOFT
										8.6-10.3 - CALICHE LENS AT CONTACT W/ BROWN TOP OF BEDROCK - SILTY CLAYEY SILT, BROWNISH YELLOW (10 YR 6/6) Y. MOTTLED, W/ CALICHE, DRY, HARD

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: CO198
 Location - North: _____ East: _____
 Date: 3/12/98
 Geologist: Jim Cox / Z. Tutu
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT
 Total Depth: 18.0'
 Company: IT CORP Project No.: 774115
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 101	RUN #3 11.0	2.9' 100%	SAMPLE 14.2-14.5					10		10.0-10.5 SILTY SANDS, L. GRAY (10 YR 7/2). FINE SUBROUND TO ROUND. Y. POORLY CEMENTED. NO VCL.
	RUN #4 12.0	0.7' 70%						11		10.5-10.9 - SILTSTONE, YELLOWISH BROWN (10 YR 5/6) W/ CLASTS, LIMONITIC AND HANGENITIC STAINING. NO VCL.
	RUN #5 12.0	4.0' 133%						12		11.0-11.3 SLOUGH 12.11-12.6 SILTSTONE, YELLOWISH BROWN (10 YR 5/6)
Box 2012	RUN #6 15.0	3.0' 133%	SAMPLE 14.2-14.5 RUN 98A1633					13		12.0-14.5 SANDSTONE (ARAPAHO) PALE BROWN (10 YR 4/3) FINE, SUBROUND TO ROUND, SILTY NOT WELL CEMENTED. SOME LIMONITIC STAINING, FINE- MED. GRAIN. UPWARD.
	RUN #7 15.0	3.0' 133%						14		14.5-14.6 FINE-MED. GRAVEL. 14.6-15.3 - MED GRAVEL LENS IMBEDDED IN SILTSTONE W/ CLAY, BROWNISH YELLOW (10 YR 4/6) SOME SAND, FINE GRAINED, MASSIVE.
	RUN #8 15.0	3.0' 133%						15		15.3-15.4 MED GRAVEL LENS IMBEDDED IN SILTSTONE MATRIX. 15.4 - SILTSTONE AS ABOVE.
Box 2012	RUN #9 18.0	3.0' 133%						16		15 - 18 - NO RECOVERY CORE STUCK IN BARREL.
	RUN #10 18.0	3.0' 133%						17		IN THE SILTSTONE WE ARE GETTING MORE THAN 100% RECOVERY.
	RUN #11 18.0	3.0' 133%						18		TD = 18.0'
	RUN #12 18.0	3.0' 133%								SOIL SAMPLE RUN # EVENT # 98H1433 001 - SAMPLE # - 001 25 - 002 VCL - 003 152
	RUN #13 18.0	3.0' 133%								NOT COMPLETED AS A WELL. *

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: CO198A
 Location - North: _____ East: _____
 Date: 3/12/95
 Geologist: J. Lox / J. Tuta
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT
 Total Depth: 16.0
 Company: IT CORP Project No.: 774115
 Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
0	0.0							0	10	0.0 - 3.4 CLAYEY SILT, v. dark gray (10 YR 3/1) med. pebbles, subrounded at 0.3', w/roots to 0.5', med. pebble, subrounded at 2.9; moist
Bot 1 of 3	Run #1	4.0 (100%)						2		
								3		3.4 - 4.0 CLAYEY SILT, (less clay), grayish brown (10 YR 5/2), some caliche, less moist than above.
	4.0							4		4.0 - 4.3 Slough
	Run #2	2.4 (120%)						5		4.3 - 6.4 CLAYEY SILT, grayish brown (2.5 Y 5/2); some sand, fine gr., subrounded; some caliche with caliche increasing from 6.0 - 6.4'
Bot 2 of 3	6.0							6		6.0 - 6.2 Slough
	Run #3	2.7 (135%)						7		6.2 - 8.8 CLAYEY SILT (as above) grayish brown (2.5 Y 5/2) some sand, fine grained subrounded, some caliche, DRY.
	8.0							8		8.0 - 8.2 Slough
	Run #4	3.3 (165%)						9		8.2 - 9.8 CLAYEY SILT (As above) 9.0 9.1
8								9.8		9.8 11.2 TOP OF BEDROCK
								10		9.8 - 11.2 CLAYSTONE, darkish yellow brown (10 YR 4/6), w/ dark clasts, limonitic staining, MOIST

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 00198A
 Location - North: _____ East: _____
 Date: 3/17/98
 Geologist: Jim Cox / Jim Turner
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 903 PAD / RYAN'S 271
 Total Depth: 16.4
 Company: IT CLP Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 20/3	RUN #5	2.0' 100%						10.0 - 10.2	slough	
								10.2 - 11.2	claystone as above.	
								11.2 - 11.8	H. PEBBLE COATED W/ SILT & V. FINE SAND SUBROUNDED	
								11.8 - 12.0	SANDSTONE (ARAPAHOE)	
								12.0 - 12.2	Pale Brown (10YR 6/3) V. FINE, SUBROUNDED TO ROUND, SILTY, NOT CEMENTED, SOME LIMONITIC STAINING	
Box 30/3	RUN #6	2.5' (125%)						12.2 - 14.4	SLUGH	
								12.2 - 14.4	SANDSTONE AS ABOVE.	
								14.4		
								14.4 - 14.8	SANDY SILTSTONE, dark yellowish brown (10YR 4/6) fine gr. sand, rounded.	
								15.2 - 16.0	CLAYSTONE, grayish brown (10YR 5/2) w/ LIMONITIC and magenetic staining, HARD, DRY	
Box 4	TD	16.4								
										TD = 16.4
										NO SOIL SAMPLE COLLECTED SAMPLE COLLECT FROM BORING 00198
										* NO sample collected from this borehole - use sample from borehole #00198.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

375 372

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 0298
 Location - North: _____ East: _____
 Date: 3/25/99
 Geologist: Jim Cox
 Drilling Equip.: SLMOM

Surface Elevation: _____
 Area: 903 PAD / RHINO PIT PLUMB
 Total Depth: 12.5
 Company: IT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDINGS ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	0.0	1.8	RIN# 98A1433 / 005-D13 / 005-D14 SAMPLE 7.4-7.9				CL	1	0.0-0.5 CLAYEY SILT, dk. br. (7.5 YR 3 1/2) root hairs abundant, f. form. pebbles subrounded, v. moist, soft.	
	2.0	90%		2	0.5-1.8 CLAYEY SILT, dk. yellowish br. (10YR 4/6) some calcite, v. moist, soft.					
	4.0	135%		3	2.0-2.6 CLAYEY SILT, grayish br. (2.5 Y 5 1/2) abundant calcite, moist. soft. v. weathered.					
	6.0	110%		4	2.6-4.0 TOP OF WEATHERED BR. SILTY CLAYSTONE, brownish yellow (10YR 4/6) mottled w/gray. v. moistless v. moist, soft.					
Box 2 of 2	8.0	110%	7.9					5	4.0-4.6 same 4.6-4.7 Heavy calcite layer 4.7-6.0 SILTY CLAYSTONE, gray (10YR 5/1) less moist, soft, w/ calcite, v. weathered.	
	10.0							6	6.0-6.4 CLAYSTONE, yellowish br. (10YR 5/4) mottled, w/ iron nodules.	
								7	6.4-8.0 CLAYSTONE, gray (10YR 5/1) v. weathered, abundant calcite	
								8	8.0-8.6 CLAYSTONE AS ABOVE, v. weathered w/ several slip faces w/ slickensides.	
								9	8.6-10.0 CLAYSTONE, yellowish br. (10YR 5/4) abundant calcite, v. weathered.	
								10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 00298
 Location - North: _____ East: _____
 Date: 4/15/99
 Geologist: Jim Cox
 Drilling Equip.: geoproc

Surface Elevation: _____
 Area: G03 PAD/KYAN'S PIT PLUMB.
 Total Depth: 12.5
 Company: IT Project No.: _____
 Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL IN FIELD MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BE DIPS ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SQU LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2	Run #6	2.8						10	--	10.0-12.5 CLAYSTONE, yellowish br. (10 Y 12 5/4) v. weathered, some calcite abundant smooth fracture faces (30°) w/ slickensides, manganese staining on the surfaces, well developed calcite at 11.1
								11	--	
								12	--	
	12.5	12.2%								
TD=12.5										TD at 12.5

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

- (1) Badly broken core, accurate footage measurements not possible.
- (2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 00398
 Location - North: _____ East: _____
 Date: 5/23/98
 Geologist: Jim Cox
 Drilling Equip.: GEO probe

Surface Elevation: _____
 Area: _____
 Total Depth: 16.2
 Company: IT Project No.: _____
 Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	RUN # 1	3.7						1	0.0 - 0.8	SILTY CLAY, dk. yellowish br. (10YR 3/4), some f. g. sand, w/ gravel 0.1 to 0.5, med. to coarse pebbles, subangular to angular. moist
								2	0.8 - 1.9	SILTY CLAY, dk. yellowish br. (10YR 4/6), w/ well developed caliche, MOIST, soft.
	4.0	92%						3	1.9 - 3.7	SILTY CLAY, dk. yellowish br. (10YR 3/4) v. weathered, abundant caliche w/ few root hairs at 2.5. MOIST
								4	4.0 - 5.8	Same, w/out caliche small cobble at 5.4.
	5.0	90%						5		
								6	6.0 - 7.3	Same
	7.0							7	6.8 - 7.1	fine pebble, quartz, subang/subround
								8	7.1 - 7.7	fine pebble, mafic, subang/subround and root hair.
	8.0	100%						9	7.7 - 8.0	sm. to med. little fractured by core process, above SANDY SILT, yellowish red (5YR 4/1) w. coarse pebble subrounded
								10	8.0 - 9.2	SILTY CLAY, dk. yellowish br. (10YR 3/4) v. weathered, some caliche st. moist
Box 2 of 2	RUN # 4	2.4						11	8.5 - 9.2	Same small pebbles - mafic & quartz.
								12	9.2 - 9.8	TOP OF WEATHERED BR. SILTY CLAYSTONE, dk. y. (10YR 4/1), less weathered, some caliche, moist
								13	9.8 - 10.0	Same more weathered

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: CC398
 Location - North: _____ East: _____
 Date: 3/23/98
 Geologist: Jim Cox
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: _____
 Total Depth: 16.2
 Company: IT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2 9.9-16.2	12 Run #5	2.0	10.6					10		10.0 - 11.8 SILTY CLAYSTONE, y. pale brown (10YR 7/2) v. weathered, w/ caliche moist soft.
	12 Run #6	4.0	11.4					11		11.6-12.0
			14.8					12		11.8-12.9 CLAYSTONE, dk gr. (10YR 4/1) less weathered, sil moist.
								13		12.9-13.7 CLAYSTONE, yellowish br (10YR 5/6) less weathered, thin caliche layer at 13.3 y. sil. moist. HARD
								14		13.7-15.6 CLAYSTONE, dk gr. (10YR 4/1) not weathered heavily, no caliche, massive, some smooth fracture surfaces, MOIST.
								15		15.6-16.2 SANDY SILTSTONE, yellowish red (5YR 4/6) w/f. pebbles, subang/subround, w/f. to c. sand, subrounded to rounded, caliche as nodules.
TD=16.2		95%	14.8					16		TD=16.2
			SAMPLE 10.6-11.4 RUN # 98A1453 + 148							SAMPLE = USED CLAYSTONE FROM 14.8 as a cap over rest of sand for seal - the capped glass jar w/ lid.

NOTES. General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 00498

Surface Elevation: _____

Location - North: _____ East: _____

Area: 903 PAD EXAM'S DIT/ALOMADate: 3/25/95Total Depth: 14.0Geologist: Jim CoxCompany: ITC-27 Project No.: _____Drilling Equip.: GeoprobeSample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	RUN #1	1.8					MH-ML	1		0.0-0.4 CLAYEY SILT, dk br (7.5R 3/2) abundant fine roots v. moist
	20	90%						2		0.4-1.8 - CLAYEY SILT, dk yellowish br. (7.5 R 5/4) roots less abundant, some fine pebbles subround. v. moist.
										1.8-2.0 NO RECOVERY
	#2	1.8					MH-ML	3		2.0-3.0 CLAYEY SILT - dk yellowish br. (10YR 4/4) massive, occasional root (2.4) occasional f. to m. pebbles, subround, calcareous begins at 3.2, some fine sand moist to v. moist.
	4.0	90%						4		3.0-4.0 NO RECOVERY
							ML	5		4.0-5.1 SANDY SILT, yellowish red (5YR 2.4/6) weathered, some v. fine pebbles fine to med. pebble (max) at 4.9. v. moist
Box 2 of 2	#3	2.2						6		5.1-6.0 SILTY CLAY, yellowish brown (10YR 5/3) abundant calcareous, weathered, sl. moist w/ f. pebble layer at 5.5 (subround).
	6.0	110%						7		6.0-8.0 SILTY CLAY, grayish br (2.5YR 5/2) caliche nodules abundant. w/ med. pebbles (max) at 6.3 and 7.3 and w/ calcareous hard, only v. sl. moist. w/ f. sand.
	#4	2.3					CH	8		8.0-9.7 some w/ slickens, dss at 8.4 8.9.6. some f. pebbles at 9.5.
	8.0	115%						9		9.7-10.0 TOP OF WEATHERED BR. CLAYSTONE dk yellowish br (10YR 4/4) w/ darker clasts no sand, no pebbles, harder. DRY.
	#5	2.0						10		
Box 2 of 2	10.0	100%								

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 00498
 Location - North: _____ East: _____
 Date: 3/25/98
 Geologist: JIM LUY
 Drilling Equip.: GLOPWIN

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT
 Total Depth: 14.0
 Company: ITC LOP Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2	#6	22	11.0					10		10.0-10.3 same
										10.3-10.5 same w/ abundant caliche, med pebble, fresh fracture, likely not in place.
	12.0	110%	11.6					11		10.5-11.5 CLAYSTONE as above. less caliche w/ limonitic staining.
	#7	27						12		11.5-12.0 same w/ abundant caliche getting more
										12.0-12.8 same
								13		12.8-13.3 same w/ less caliche and abundant iron staining
										13.3-13.7 same w/ caliche
14.0	14.0	135%						14		13.7-13.9 CLAYSTONE, dk yellowish br. (10 YR 2.5/4) Y. DRK
TD=14.0										13.9-14.0 CLAYSTONE, grayish br. (10 YR 5/2) w/ limonitic staining.
SAMPLE 11.0-11.6 RWD 98A1433										TD 14.0
Soil Sample 11.6-11.6 Rin # 98A1433 006-016 -017										

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 00598

Surface Elevation: _____

Location - North: _____ East: _____

Area: 903 PAD / RYAN < PIR PLANTSDate: 3/24/98Total Depth: 20.0Geologist: Jim CoxCompany: IT CORP

Project No.: _____

Drilling Equip.: 5000Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 3	Rm #1	0.4					CH OH			0.0-0.9 SILTY CLAY, dark yellowish br. (10YR 3/4) w/ f. to m. gr. sand, subrounded to rounded, w/ common roots (fine) to 0.3. v. moist
	2.0	45%					X	1	X	0.9-2.0 - NO RECOVERY
							X	2	X	2.0-3.5 SILTY CLAY, dk. yellowish br. (10YR 4/6) w/ some m. to c. pebbles subangular to sub rounded, cyanitic. moist.
	#2	2.2					CH	3		3.5-3.8 small cobble, quartzite, w/ fresh angular fractures from freeze.
	4.0	110%								3.8-4.0 SILTY CLAY, dk yellowish br. (10YR 4/6), w/ m to c. gr. sand, w/ pebbles, f. to c., subangular to subround, MOIST
							CH	4		4.0-5.4 CLAY, dk grayish br. (2.5Y 4/2), massive, mottled w/ limonitic staining w/ calcite nodules, occasional f. to c. subangular. MOIST.
	#5	2.2					CL	5		5.4-6.0 FEET OF WEATHERED BEDROCK CLAYSTONE, grayish brown (10YR 5/2) mottled, limonitic staining heavy calcite layer at 5.4. MOIST. CALCITE LAYER APPEARS v. WEATHERED.
	6.0	110%						6		6.0-8.0 same, w/ calcite zones at 6.2 and 6.8, limonitic staining minimal from 7.0-7.5, massive. MOIST.
	#4	2.4						7		- at 8.0' med. cobble, fresh frag. strong
	8.0	120%						8		8.0-10.0 - SANDY SILTSTONE, dk reddish br. (5YR 3/4) w/ silt massive, MOIST fresh cobble fraction at 7.5 uncertain if in place.
Box 2 of 3	#5	2.0						9		
	10.0	100%						10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 00598
 Location - North: _____ East: _____
 Date: 3/24/98
 Geologist: JML
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 703 PHD BURNS PIT PLANT
 Total Depth: 20.0
 Company: ITL 2 P Project No.: _____
 Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL FIELD MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 3	#6	2.2	004-010 Rad Ser. -011 VOC.					11		10.0-12.0 Same, w/ small cobbles at 11.3 fresh fracture MOIST.
	12.0	135%						12		12.0-14.0 Same moist
	#7	2.5						13		
	14.0	125%						14		14.0-15.9 Same, sample N.O.-14.6
Box 3 of 3	#8	2.9	SAMPLE 14.0-14.6 R.N. #98A1433					15		
	16.0	145%						16		TOP OF WEATHERED BEDROCK 15.9-16.0 SILTY CLAYSTONE, dk gray sh br (2.5 Y 4/2) w catiche, moist.
	#9	2.7						17		16.0-18.0 same w/ abundant catiche from 17.5-18.0 MOIST.
	18.0	135%						18		18.0-19.0 Same ^{SL} MOIST.
	#10	2.8						19		19.0-20.0 gradual change to CLAYSTONE yellowish br (10 YR 5/6) changing to reddish br (5 YR 4/4) at 19.5 DRY.
20.0	20.0	140%						20.0		REFUSAL AT 20.0. from sandy silty stone

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 00698
 Location - North: _____ East: _____
 Date: 3/23/98
 Geologist: Jim Cox
 Drilling Equip.: Hydro

Surface Elevation: _____
 Area: 903 PAD/RYAN'S PIT PLUME
 Total Depth: 19.2
 Company: IT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SONU LITHOLOGIC LOG	SAMPLE DESCRIPTION
	0.0									0.2' Rock gamma in core tip except for rock / no recovery.
	Run #1	0.2'						1		
	2.0							2		2.0-2.3 - SILTY CLAY, dark yellowish brown (10YR 4/4), some sand, f. gr.; some yf. to med. pebbles, some calcite nodules. w/ roots
	Run #2	2.0'						3		2.3-2.9 - SILTY CLAY, dk, yellowish br. (10YR 4/6), minor sand, some pebbles, med. subrounded. w/ roots to 2.4. moist.
	4.0							4		2.9-4.0 - SANDY SILT - yellowish brown (10YR 5/4) sl. cemented, calcite, some fine pebbles. sl. moist.
	Run #3	2.0						5		4.0-5.4 some more massive, w/ some med. pebbles subrounded and iron staining.
	6.0							6		5.4-6.0 silty clay, brown (10YR 4/3), w/ less calcite and siltstone (from drilling?) w/ coarse lobe at 5.7 crushed during drilling (angular).
	Run #4							7		6.0-7.7 silt clay, brown (10YR 4/3) w/ v.f. to coarse pebbles, some crushed in extraction. moist
	8.0							8		7.7-8.0 - SILTY CLAY, dk grayish br. (2.5Y 4/2) w/ occasional f. pebble subrounded. moist
	Run #5							9		8.0-10.0 - silt, clay dk grayish br. (2.5Y 4/2) moist, mottled, w occasional f. pebble and iron staining.
	10.0							10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

TOP W. BE at 10.0

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 00698
 Location - North: _____ East: _____
 Date: 3/23/98
 Geologist: Jim Cox
 Drilling Equip.: geoprobe

Surface Elevation: _____
 Area: 9.03 PAD/RVAD'S PIT PLUTUM
 Total Depth: 18.2
 Company: IT Project No.: _____
 Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2 10.0 - 18.2								10.0		TOP OF WEATHERED BEDROCK
	Run #6	2.3	003-067 Rad Sor. - DCC VDC.					11		10.0-12.0 SILTY CLAYSTONE, D. grayish br. (2.5 Y 4/2), mottled, some limonitic staining, some caliche, w/ magnetic staining on slickensides at 10.1, moist.
	12.0	15%						12		12.0-13.5 Same
	Run #7	2.0						13		
	14.0	100%	13.8					14		13.5-13.8 grading into SANDY SILTSTONE v. f. sand, well rounded, v. sl. moist. sand increasing w/ depth
	Run #8		SAMPLE #7					14		14.0-14.6 - SANDY SILTSTONE, yellow (10 YR 7/8) v. fine sand, well rounded
	16.0							15		14.6-14.9 SILTY CLAYSTONE, yellowish br. (10 YR 5/2) mottled, limonitic staining. 14.9-15.2 same w/ abundant iron staining 15.2-16.0 same w/ abundant caliche
	Run #9		RIN# 98A1433					16		16.0-18.2 - SANDY SILTSTONE, gray (10 YR 5/1) v. f. gr. sand, caliche throughout. DRY.
	18.2							18		
TD=18.2										TD=18.2

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 00798
 Location - North: _____ East: _____
 Date: 3/24/98
 Geologist: Jim Lov
 Drilling Equip.: Geo Probe

Surface Elevation: _____
 Area: 903 PADIRYAN'S PIT PLUME
 Total Depth: 14.1
 Company: ITC 028 Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
0.0	Run #1	1.8	90%				OH/ CH	0.0	1	0.0-0.8 - CLAY LOAM, v. dk grayish br. (10YR 3/2), abundant roots, occasional med. pebble - v. moist.
							SM	0.8	1	0.8-1.8 - SANDY CLAY LOAM, dk. yellowish br. (10YR 3/6), occasional root, occasional fine pebble, moist.
							NO RECOVERY	2	2	2.0-3.1 - SANDY CLAY, dk yellowish br. (10YR 3/6), occasional culiche, moist.
	#2	1.9					CH	3	3	3.1-3.9 sandy clay loam, dk yellowish br. (10YR 3/6) occasional fine pebble surrounded. moist
	4.0	95%					CH	4	4	NO RECOVERY
							CL	5	5	4.0-5.0 - SILTY CLAY, dk yellowish br. (10YR 3/6) occasional fine pebble surrounded to subangular some minor culiche.
	#3	2.9								at 5.0 thin culiche layer.
	6.0	15%						6	6	5.0-6.0. TOP WEATHERED BR. SILTY CLAYSTONE, dk grayish br. (2.5 Y 4/2) mottled, limonitic staining occasional f. pebble not in place. minor culiche, moist
	#4	2.4						7	7	6.0-8.0 - Same.
	8.0	20%						8	8	8.0-8.3 same
										8.3-10.0 same v. weathered w/ abundant culiche soft.
9.8	Box 2	115%								
10.0										

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 0079R
 Location - North: _____ East: _____
 Date: 3/26/98
 Geologist: JML
 Drilling Equip.: GEOPROBE

Surface Elevation: _____
 Area: GIESPAD/RVHIN & PTI PLUME
 Total Depth: 14.1
 Company: ITLORP Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN/OUT	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL FIELD MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2								10		SANDY CLAYSTONE
								10.0-10.3		SILTY SANDSTONE, light olive br. (2.5Y 5/6) v. f. gr. sand moist.
		2.6						10.3-10.3		SILTY CLAYSTONE, d. grayish brown (2.5Y 4/2), mottled, limonitic staining, sl. moist.
	12.0							10.3-12.0		CLAYSTONE, gray (10YR 5/1) w/ iron staining, v. dry, blocky.
		2.6						12.0-13.8		same
14.1	14.1							13.8-14.1		SILTY SANDSTONE, light brownish gray (10YR 4/2), bedding planes, v. fine gr. to fine gr. sand, dry.
TD = 14.1										
TD = 14.1										
Soil SAMPLE										
Rin #										
Event #										
Sample #										
98A1433 007 - 019 RS.										
- 020 VOL										
- 021 ISO										

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

387 384

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1

Borehole Number: 00598
 Location - North: _____ East: _____
 Date: 3-27-78
 Geologist: D. GRAVENS
 Drilling Equip.: GEOPROBE

Surface Elevation: _____
 Area: 903 PAR RYAN'S PIT
 Total Depth: 16.1 FT GARDNER
 Company: IT CORP Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BLODDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	0915	0-2 FT	RECOVERY 1.5 FT					1		SOIL HORIZON SILTY CLAY, dk BROWN (7.5 YR 3/2) GRADING TO (7.5 YR 4/4) WITH 1.5-2' DEPTH, SOME ROCK FRAGS, V. ANGLULAR, POOR RECOVERY DUE TO LOGS, DRY.
	0943	2-4 FT	RECOVERY 0.9 FT					2		
	0947	4-6 FT	RECOVERY 1.5 FT					3		
	0939	6-8 FT	RECOVERY 2.05 FT					4		CLAYSTONE, LIGHT OLIVE BROWN (2.5 Y 5/4) MOTTLED W/ WHITE CALCAREOUS ZONES, V. DENSE, DRY
	0945	8-10 FT	RECOVERY 2.3 FT					5		5.5-6.0 - NO RECOVERY
								6		SAME AS ABOVE
								7		
								8		SAME AS ABOVE WITH A COARSE ORANGE YELLOWISH BROWN (10 YR 5/4) FROM ~ 8.6' - 9.0' BACK TO LT OLIVE BROWN (2.5 Y 5/4)
								9		
								10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 00548
 Location - North: _____ East: _____
 Date: 3-27-98
 Geologist: D. GRAVES
 Drilling Equip.: HURRICANE 600

Surface Elevation: _____
 Area: 403 RAD/RYS PIT
 Total Depth: 16.1 FT GRADE
 Company: IT Corp Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	INCLINING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2	10-12	Recovery 3.0 FT						11	+	10-11 SAME AS ABOVE WITH SANDSTONE
	12-14	Recovery 2.5 FT	Run 50R -022 YOC.					12	+	11-12 V. FINE SAND, SOME SILT light yellowish brown (104R 6/4) well sorted, si micst.
	14-16	Recovery 3.0 FT	Run 98A1433					13	+	SAME AS ABOVE
	16.0	TD=16.0						14	+	SAME AS ABOVE
								15	+	
								16	+	15.8-16 CLAYSTONE yellowish brown (104R 5/4), irregular bedding planes si micst. TD=16.0
										Soil Sample Run # 98A1433 EVENT 008 - 022 RADST. Sample # - 023 YOC

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 0096
 Location - North: _____ East: _____
 Date: 11/1/93
 Geologist: J. M. ...
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT
 Total Depth: 12.1
 Company: ... Project No.: _____
 Sample Type: grab

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	REDDISH ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 10/2										0.0-0.6 - SILTY CLAY, LIGHT, V. DK gray (10YR 3/1) w/many roots & fine grains v. wet
		1.7						1		0.6-1.7 - SILTY CLAY, w/sand and small rounded fine grains Sub ang. to sub round.
	2.0							2		1.7-4.6 SILTY CLAY, dark grayish brown (2.5Y 4/2) massive, occasional fine to med pubble subangular to subround some catclaw as nodules. TOP OF WBL
		2.5						3		4.6-5.3 SILTY CLAYSTONE gray, (10YR 5/1) blocky, slight sand content increasing w/depth v. fine sand. TOP OF WEATHERED BEDROCK. MOIST.
	4.0							4		INTERBEDDED W/ 5.3-6.0 - SILTY SANDSTONE SANDSTONE CLAYSTONE V. FINE GR. SAND ROUNDED iron nodules.
		2.3						5		w/some clay. moist.
	6.0							6		6.0-7.0 SANDY CLAYSTONE BLOCKY/DARK gray (10YR 4/1) V. FINE GR. SAND
		2.3						7		7.0-7.2 TRANSITION ZONE SAND % increasing.
	8.0							8		7.2-7.8 SILTY SANDSTONE, light yellowish brown (10YR 6/4) not blocky, not well cemented v. f. sand.
	8.4							9		8.0-10.0 INTERBEDDED SILTY SANDSTONE AND SANDY CLAYSTONE AS ABOVE WITH CLAYSTONE IRON STAINING INCREASING W/DEPTH
Box 20/2		2.3						10		

NOTES. General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2


Borehole Number: 00992
 Location - North: _____ East: _____
 Date: 3/1/95
 Geologist: Jim Cox
 Drilling Equip.: McCormick

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT / DOME
 Total Depth: 12.1
 Company: IT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box # 12.1	#6 12.0	3.0 1563						10		10.0 - 12.0 - SILTY CLAYSTONE, Y. DK. GRAYISH BROWN (2.5Y 3/2) ABUNDANT IRON STAINING, BLOCKY, DRY. MINOR V. FINE SAND.
	ID = 12.1							12.1		TD = 12.1 BACKFILL TO 12.1 BY CENTER IS CHIP

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 01098
 Location - North: _____ East: _____
 Date: 4-10-88
 Geologist: D. G. Anderson
 Drilling Equip.: Geo Probe

Surface Elevation: _____
 Area: 903 Pad 14th St
 Total Depth: 12.0
 Company: IT Corp Project No.: 77415
 Sample Type: Root Columns

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
	0	0.112								SURFACE SAMPLE SILTY CLAY REDISH BROWN (5 YR 4/4) LCLY GRAVEL MINOR DIAMETER 0.1 FT ROOT / PLANT FRAGS, SOFT TO MED DENSITY, SL MOIST.
	2	2.15' 6" X RECOVERY	0919					1		
		2.2 FEET RECOVERY						2		SLIM CLAY REDISH BROWN (5 YR 4/3) SOME SAND & GRAVEL 5% ROUNDED TO SUB ANGULAR, FINE FRAGS, SL MOIST.
	4	2.0 FT RECOVERY	0920					3		
		2.0 FT RECOVERY						4		SAME AS ABOVE INCREASE SAND CONTENT 40% LITTLE NO CLAY WHITE CARBON STAINING, DRY.
	6	2.0 FT RECOVERY	0934					5		5.4' LATE GRAVEL
		2.0 FT RECOVERY						6		6-8 SAME AS ABOVE FINE SAND SILT, 7.5 YR 4/6 STRONG BROWN, WHITE / BUT CARBON STAINING. GRAVEL / COBBLES ROUNDED SUB ROUNDED.
	8	2.2 FT RECOVERY	0940					7		
								8		8.8 - ROCK FRAGMENTS MIXED WITH CLAY / SILT. DARK YELLOWISH BROWN (10 YR 4/6) V. DENSE, DRY - SL MOIST SOME SUB ROUNDED GRAVEL 1/2 MIN. 1/2.
12.0	10							9		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

PAGE 2 OF 2

Surface Elevation: _____
Area: 403 1st AND RYAN'S PT
Total Depth: _____
Company: IT CORP Project No.: 774115
Sample Type: CONTINUOUS PILE

APPROVAL

DATE _____

[illegible]

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 1145
 Location - North: _____ East: _____
 Date: 4/9/95
 Geologist: Jim Cox
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 903 PAD/ RYAN'S PIT PLUMB
 Total Depth: 20.5
 Company: IT COLT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL	FIELD MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOLU LITHOLOGIC LOG	SAMPLE DESCRIPTION
											0.0-0.5 SEVERAL LARGE COBBLES REMOVED BY HAND NOT PUSHED.
0.5	0.5							OH			0.5-0.9 SILTY CLAY LOAM, dk. br. (7.5YR 3/4) abundant root hairs, V. MOIST
	Run: 1.5								1		0.9-2.0 SILTY CLAY, dk yellowish br. (10YR 3/4) massive
	2.5	100%						CH	2		2.0-3.6 same silty & moist. MOIST
	4.2	2.3							3		
	4.0	115%							4		3.6-4.0 CLAYEY SILT. dk yellowish br. (10YR 4/6) BLOCKY w/ calcareous inclusions
	4.3	2.1							5		4.0-4.8 same w/ greater pebbles (fine - med subang. - some fresh fractures from push at 5.2', 5.4', 5.9' root at 5.9'. DRY
	6.0	115%						CL/HL	6		6.0-8.0 CLAYEY SILT TO SILTY CLAY strong br. (7.5YR 4/6), w/ calcareous hairs w/sm. to med. pebbles some parting some medium. DRY w/sand
	4.4	2.3							7		
	8.0	115%							8		8.0-10.0 same w/ greater sand content and f.-m. pebbles subang/subround. Some calciche, heaviest 9.8-10.0. DRY
	4.5	1.9							9		
	10.0										

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 01198
 Location - North: _____ East: _____
 Date: 7/9/98
 Geologist: Jim Cox
 Drilling Equip.: Geo Probe

Surface Elevation: _____
 Area: 903 PAD/RYAN'S PIT PLUMES
 Total Depth: 20.5
 Company: FT Project No.: _____
 Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	DIP/SLIP ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
								10		10.0-12.0 same w/out pebbles, only minor catiches except at
	11.0	2.0						11		v.s. moist 11.0-11.4 same, heavy catiche zone 11.4-11.6 same, some catiche 11.9 - catiche layer v.s. moist
	12.0	12.0%						12		12.0-13.7 CLAYEY SILT, strong br. (7.5YR 4/6) w/sand, some catiche, v. coarse med. c. pebble at 12.5 subang/subround. DRY
	13.7	2.5						13		13.7-14.0 same w/ heavy catiche
	14.0	12.5%						14		14.0-16.0 same, w/ heavy catiche zones at 14.6 to 15.0 and from 15.5 to 16.0
	16.0	16.0						16		16.0-16.1 same heavy catiche
								17		16.1-16.7 gravel, f.-c. pebbles moved in clayey to sandy silt; fresh frags, otherwise subang/subround. abundant catiche DRY.
	17.0	2.1					OL	17		16.7-17.4 clay, olive br. (2.5Y 4/2) mottled, 1/2 in. mottled staining. no coarse v. sl. moist to dry. 17.4-18.0 catiche layer at 17.9 - then no above - f. to m. pebbles - trace silts in tip.
	18.0	17.8					HL	18		18.0-18.4 SANDY SILTSTONE, strong br. (7.5YR 4/6) w/ clay, v. fine gr. sand DRY
							CL	18		18.4-18.8 SILTY CLAY, l. olive br. (2.5YR 3/4) w/ several f. pebbles, some catiche v. sl. moist
	20.5	2.9						19		18.8-19.1 TOP WEATHERED BR. CLAYSTONE, l. olive br. (2.5Y 5/4) catiche layer at 18.8 - No sand or pebbles v. sl. moist, w/ 1/2 in. mottled staining. 19.1-20.5 CLAYSTONE, olive br. (2.5Y 4/2) v. mottled, blocky v. DRY.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

TD = 20.5

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 01298
 Location - North: _____ East: _____
 Date: 11-17-69
 Geologist: _____
 Drilling Equip.: Geopline

Surface Elevation: _____
 Area: 903 PAD/RYANS PIT PLUME
 Total Depth: 18.3
 Company: ITC 02P Project No.: _____
 Sample Type: Long Intervals

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	REDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 3	Run H, 1	1.3						0	0.0-0.4 SILTY CLAY, v. dk. br (10YR 2/2) with abundant root hairs, some f. pebbles, wet to v. moist.	
	2.0	65%						1	0.4-1.3 - SILTY CLAY, dk. br. (7.5 YR 3/4) massive, occasional root hairs, occasional f. pebble.	
	H4	2.2						2	2.0-2.4 SILTY CLAY br (7.5 YR 4/4) few root hairs, moist	
	4.0	110%						3	2.4-3.2 SILTY CLAY, strong br (7.5 YR 4/6) w/ minor f. sand & caliche increasing w/ depth. sl. moist 3.2-4.0 DRY SAME DAY.	
Box 1 of 3	H3	2.2					CH	4	4.0-6.0 SILTY CLAY, dk yellowish br. (10YR 4/6), some mafic pebbles fine to med. sub ang. to sub round (4.8 to 5.0) sl. moist.	
	6.0	110%						5		
	H4	2.4						6	6.0-8.0 SILTY CLAY, strong br. (7.5 YR 4/4) w/ some f. sand (7Y) and some caliche nodules (6.1, 6.8) soft mafic pebble, sub round at 6.7, sl. moist.	
	8.0	120%						7		
8.4								8	8.0-9.0 SILTY CLAY as above w/ f. mafic pebble at 8.3, some v. f. sand. sl. moist to v. sl. moist - sand w/ depth	
Box 2 of 2	H5	2.1						9	9.0-10.0 SANDY CLAY, dk yellowish br. (10YR 7) v. f. sand w/ abundant caliche 9.4-10.0	
	10.0	105%					CL	10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 01298
Location - North: _____ East: _____
Date: 4/8/98
Geologist: Jim Cox
Drilling Equip.: gyroprobe

Surface Elevation: _____
Area: 903 PAD / RYAN'S PIT PLUMB
Total Depth: 18.3
Company: IT Project No.: _____
Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG
SAMPLE DESCRIPTION									
CLAYEY SILT									
Box 2 of 3	#6		OCC - DCU Rader. - DSS YOC.					10	10.0-12.0 - SLTY CLAY, dk yellowish br, (10YR 4/6) v. silty, some f. gr. sand sl. moist; sm. mafic pebbles at 11.2 w/calcite abundant at 11.5. Sl. moist.
	#2	3.6						11	
		18.0	13.3					17	12.0 - 13.0 sl. moist. Same Caliche from SILTY CLAY TO SANDY SILT strong br (7.5YR 2/ 13.0-14.0 / Silty clay w/ f. gr. sand and f. mafic pebbles. coarsening downward. w/calcite 13-14 Sl. moist.
		14.0						13	
	#2	1.9	RN TBA1600					14	14.0-14.6 - STIFF SANDY SILT, st. br. (5YR 4/6) sand content higher than above.
Box 3 of 3	#9	2.8						15	14.6-15.8 gravel - f. pebbles to to v. coarse pebbles Subang/subround w/ fresh frags from pushing, granitic, quartz Some mafic near top. DRY.
								16	15.8-16.0 - CLAY, yellowish brown (10YR 5/4) heavy calcite, mottled w/ gravel from above. DRY
								17	16.0-16.3 - Same dry
								18	16.3 TOP OF WEATHERED BR. SILTY CLAYSTONE, yellowish br. (10YR 5/4), mottled, limonitic staining, no sand or pebbles observed, limonitic staining, iron staining, calcite. Calcite layer right at 16.3.
		18.3 = TD							

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1Borehole Number: 01398

Surface Elevation: _____

Location - North: _____ East: _____

Area: 903 PAD / RYAN'S PT PLUMEDate: 4/1/98Total Depth: 10.1Geologist: Jim CoxCompany: IT Project No.: _____Drilling Equip.: Geo probeSample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1012 6.0 - 9.3	Ru #1	1.9	010-026 RS 010-029 YOC 011-031 DOP VDC					0		0.0-0.8 - SANDY CLAY LOAM, v. dark grayish brown (10YR 3/2) w/ many roots, occasional caliche nodule at 0.8, Y. MOIST
	2.0	90%						1		0.8-1.8 CLAY LOAM, dark yellowish brown (10YR 4/6) w/ several caliche nodules, medium pebble at 1.2, wet subrounded, moist. some roots.
	#2	1.7	98A1433					2		2.0-3.2 same w/ coarse pebble at 3.2, subrounded and gravel layer (med to coarse pebbles) from 3.6 to 3.7 fresh fractures. sub ang. to subround moist.
	4.0	85%	RN #98A1433					3		4.0-5.2 low recovery direct to gravel. possibly all slush. - gravel is same as above as is clay loam matrix. Dry
	#3	1.2	010-028, 010-029					4		RIN # 98A1433
	6.0	45%	010-028, 010-031					5		6.0-6.4 - gravel (10YR 4/6) clay loam, some caliche, med-coarse pebbles sub angular to subround - mostly quartzite fresh fractures.
	#4	2.3	6					6		6.4-8.0 Top of weathered bedrock, SILTY CLAYSTONE, grayish brown (10YR 5/2) mottled, iron staining, no sand or pebbles some caliche - heavy iron staining
	8.5	115%	44-6.5					7		7.9-8.0 weathered, moist.
	#5							8		8.0-8.9 SILTY CLAYSTONE grayish brown (10YR 5/2) very little iron staining. some caliche, v. weathered & moist.
Box 2012 10.0								9		8.9-10.1 - same heavy iron staining. caliche sl. moist.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

TD = 10.1 NOTE!

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1

Borehole Number: 21498
 Location - North: _____ East: _____
 Date: 4/1/98
 Geologist: Jim Cox
 Drilling Equip.: GeoProbe

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT PLUME
 Total Depth: 10.2
 Company: IT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1012 0.0-9.0	RUN #1	1.8	001 - 001 RAD SCR - 002 YOC					1		0.0-1.8 SANDY CLAY LOAM - v. dk. grayish br. (10YR 3/2) w/ many roots, occasional f. to m. pebble, subrounded. V. MOIST
	3.0	90%						2		2.0-3.7 SILTY CLAY, Brown (10YR 5/3) mottled w/ grayish br. (10YR 5/2) weathered w/ caliche, pebble (coarse) at 2.3 not in place. MOIST, w/ limonitic & iron staining
	RUN #2	1.7						3		
	4.0							4		4.0-6.0 SILTY CLAY, grayish br. (2.5Y 5/2) v. weathered, abundant caliche, coarse pebble at 4.4 not in place. MOIST
	RUN #3	2.3						5		
	6.0	115%						6		6.0-6.4 same 6.4 - caliche layer 6.4-7.5 TOP OF WEATHERED BR.
	RUN #4	2.3						7		SILTY CLAYSTONE, grayish br. (2.5Y 5/2) mottled, limonitic staining, Silt content less than above, massive, w/ crystal structure at 7.4 appears calcareous MOIST.
	8.0	115%						8		7.5-8.0 SILTY CLAYSTONE, grayish br. (2.5Y 5/2) iron staining & blocky less moist than above
	RUN #5							9		8.0-8.5 same, only v. sl. moist.
	10.2							10.2		8.5-10.2 - CLAYSTONE - grayish br. (2.5YR 5/2) some iron staining, v. blocky DRY.
Box 2012 9.0-10.2			RUN # 98A/600							TD = 10.2

10.2 NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

NOTE

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: C15-98
 Location - North: _____ East: _____
 Date: 04/17/98
 Geologist: Eane Tuta
 Drilling Equip.: geoprobe-continuous

Surface Elevation: _____
 Area: 903 Pond/Ryan's P. + Plume
 Total Depth: 10.2
 Company: IT Corp. Project No.: _____
 Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2 0 to 8.4 ft	#1	1.5				ml		0.0 - 1.2		SILTY CLAY, dk grayish brown (10YR 4/2), soft, moist, with trace sand. Rootlets.
	#2	2.0				ml		1.2 - 3.0		SILTY CLAY, brown (10YR 5/3) mottled with yellowish brown (10YR 5/6), soft, moist, with some sand.
	#3	2.5				sm		3.0 - 3.5		SILTY SAND, brown (10YR 5/3) mottled with yellowish brown (10YR 5/6), soft, moist, fine, subround.
	#4	2.4				ml		3.5 - 7.0		SANDY SILT, grayish brown (10YR 5/2) mottled with brownish yellow (10YR 6/3) and abundant grayish white caliche (10YR 8/1), SLIGHTLY moist.
	#5	2.3						7.0 - 10.2		CLAYEY SILTSTONE, dark grayish brown (10YR 4/2), mottled w/ yellowish brown (10YR 5/6), orange limonitic stain coating fractures. Limonitic Fossil leaf fragment at 9.5. Highly weathered, poor horz. bedding laminae faintly visible. SLIGHTLY moist.
Box 2 of 2 8.4 to 10.2 ft			RN 98A1600							

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 2 OF 2

Surface Elevation: _____
Area: 903 P.O./Ryan's P.T. Plume
Total Depth: 10.2
Company: IT Corp. Project No.: _____
Sample Type: Contaminant

APPROVAL _____ DATE _____

[illegible]

(2) Core breaks cannot be matched, accurate footage measurements not possible

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 01698
 Location - North: _____ East: _____
 Date: 4/2/68
 Geologist: Jim Cox
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: 903PAD RYAN'S PIT PLANT
 Total Depth: 16.2
 Company: il Project No.: _____
 Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL FIELD MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOLID LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	Ran #1	1.2						1		0.0-0.5 - SILTY CLAY LOAM v. dk. br. (10YR 2/2) w/ gravel and abundant root hairs. s. moist.
	2.0	10%						2		0.5-1.2 - SILTY CLAY, dk. yellowish br. (10YR 4/4) some root hairs.
	#2	2.1						3		2.0-3.0 SILTY CLAY w/ sand, light yellowish br. (2.5Y 6/4) w/ v. f. gr. Sand. DAMP. w/ calc. line
	4.0	105%						4		3.0-4.0 SILTY CLAY, l. yellowish br. (2.5Y 6/4) sand decreasing to none. w/ calc. line. DAMP.
	#3	2.1						5		4.0-6.0 CLAYEY SAND TO SANDY CLAY l. yellowish br. (2.5Y 6/4). v. f. gr. Sand, some calc. line, DRY.
	6.0	105%						6		6.0-8.0 Sand DRY
	#4	2.1						7		
	8.0	105%						8		8.0-10.0 becoming SILTY SAND w/ clay l. yellowish br. (2.5Y 6/4) DAMP
	9.0	2.2						9		
	Box 2 of 2	10.0						10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 01698
 Location - North: _____ East: _____
 Date: 4/21/98
 Geologist: Jim Cox
 Drilling Equip.: gypro

Surface Elevation: _____
 Area: 903 PAD RYAN'S PIT PLUMB
 Total Depth: 16.2
 Company: IT Project No.: _____
 Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 201 2 9.0-16.2	#6	2.2	0104-025 009-024 YCC					10		10-12 SILTY SANDSTONE, light yellowish brown. (2.5 Y 6/2), well sorted some bedding planes, v.f.g. sand clay content clay content ↑ from 11.4 to 11.8 DAMPER
		110%						11		
	#7	2.4						12		12-13 same DAMP
		120%						13		13-13.6 SILTY SANDSTONE w/CLAY light yellowish brown (2.5 Y 6/2) DAMP
	#8	2.5						14		13.6-14. SAME CLAY CONTENT ↑ DAMP. w/some iron staining
16.2	#4	125%	14.2 15.5					15		14.0-14.9 same TOP OF W. BR.
TD								16		14.9-16.2 SILTY CLAYSTONE light olive br. (2.5 Y 5/4) w/ sand, v.f.g. bedding planes w/ iron staining and concretions, w/ quartz pebbles, coarse at 14.9 DRY
										16.2 TD

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 1 OF 1

Surface Elevation: _____
Area: 903 PAD / Ryan's 7.1 Home
Total Depth: 8.0
Company: IT Project No.: _____
Sample Type: CONTINUOUS

APPROVAL

DATE _____

[illegible]

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1

Borehole Number: 01898
 Location - North: _____ East: _____
 Date: 7/22/98
 Geologist: Jim Cox
 Drilling Equip.: GLC 00000

Surface Elevation: _____
 Area: 903 PAD/RYAN'S DIRT PLUME
 Total Depth: 8.2
 Company: IT Project No.: _____
 Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	INTERVAL OF FEET OF CORE IN INTERVAL MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
2A	0.5	011-031 VOL DUP					1		0.0-0.3 - VOL SILTY CLAY, v. dk. grayish br. (10 YR 5/2) abundant root hairs coarse matrix pebbles subrounded. MOIST.
1	25%						2		0.3-0.5 - SILTY CLAY, yellowish br. (10 YR 5/6) to light brownish gray (10 YR 4/2) mottled, w/ caliche, some root hairs weathered. MOIST. (5Y 4/4)
2	2.4						3		2.0-3.2 SILTY CLAY, olive brown, (2.5 Y 4/4) some f. g. same. Abundant caliche very weathered MOIST TO SL. MOIST mottled
	120%	4.5					4		3.2-4.0 TOP OF WEATHERED BEDROCK SILTY CLAYSTONE, light olive brown (2.5 Y 5/6) w/ caliche in layers and nodules, iron nodules, MOIST. MASSIVE
3	2.1						5		4.0-4.3 - SILTY CLAYSTONE, olive gray (5Y 4/2) w/ caliche as crystals and in veins. MOIST AT 4.0 v. SL. MOIST AT 4.3. BLOCKY.
	105%						6		4.3-5.9 SILTY CLAYSTONE, dk grayish br. (2.5 Y 4/2) w/ iron staining, minor caliche, v. sl. moist.
Run 44	2.2	SAMPLE 001-001 RS 001-002 VOL					7		5.9-6.0 - SILTY CLAYSTONE, dk, grayish br. (2.5 Y 4/2) BLOCKY, v. DRY.
8.2	100%						8		6.0-8.2 - Same
		Run 98A1806							8.2 = TD

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1

Borehole Number: 0194B
 Location - North: _____ East: _____
 Date: 4/23/98
 Geologist: Jim Cox
 Drilling Equip.: S200-022

Surface Elevation: _____
 Area: 903 PAD RYAN'S DTI PLUMB
 Total Depth: 8
 Company: IT Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Run #1	1.0									0.0 - 0.7 - SILTY CLAY LOAM, dk br. (7.5 YR 3/2) occasional f to M gravel pebbles, subang/subround abundant roots. v. moist.
										0.7 - 1.0 - SILTY CLAY, yellowish br. (10YR 5/6) occasional f. pebble subround, occas. roots. MOIST
2.0	50%	2.0						2		2.0 - 2.4 - SILTY CLAY, dk yellowish br (10YR 4/6) some root hairs, under v. f. pebbles to v. coarse sand well rounded. Moist
#2	1.7									2.4 - 3.2 - TOP WEATHERED DR. CLAYSTONE, 1 foot of m. br. (2.5Y 5/4) mass. calc. nodules, limonitic staining, mottled massive st. moist.
4.0	85%							4		4.0 - 4.4 CLAYSTONE AS ABOVE. v. SL. MOIST
#3	2.5									4.4 - 6.0 - CLAYSTONE - grayish br. (2.5Y 5/2). DRY TO Y. DRY, DRYER w/DEPTH - BLOCKY.
6.0	95%							6		6 - 8.0 same. v. DRY.
#	2.3							7		
8.0								8		
										TD = 8

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core. accurate footage measurements not possible.

(2) Core breaks cannot be matched. accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1Borehole Number: 02095

Surface Elevation: _____

Location - North: _____ East: _____

Area: 903 PAD/RYAN'S PIT PILEDate: 4/22/95Total Depth: 6.1Geologist: JIM COXCompany: IT Project No.: _____Drilling Equip.: 40006Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
	<u>Rw</u>	<u>1.7</u>						<u>1</u>		<u>0.0-0.5 - SILTY CLAY, v. dk br. (10YR 2/2), abundant roots, moist. soil horizon.</u>
	<u>2.0</u>	<u>85%</u>						<u>2</u>		<u>0.5-1.7 - SILTY CLAY, brown, (10YR 5/4) w/ sand f.s.s. w/ some pebbles, fine to med. subang. sm. round, med. v. coarse pebble subround, occas. caliche nodules, sl. moist.</u>
	<u>4.0</u>	<u>80%</u>						<u>3</u>		<u>2.0-3.0 - SILTY CLAY br. (10YR 5/4) w/ f.s.s. sand plas. caliche as nodules, massive, sl. moist.</u>
	<u>4.0</u>	<u>80%</u>						<u>4</u>		<u>3.0-3.6 - SILTY CLAY, olive br. (2.5Y 5/4) occas. caliche nodules, limonite staining mottled, massive, sl. moist.</u>
	<u>4.0</u>	<u>80%</u>						<u>5</u>		<u>4.0-4.3 same.</u>
	<u>6.1</u>	<u>150%</u>						<u>6</u>		<u>4.3-6.1 - SILTY CLAYSTONE TO CLAYSTONE grayish br. (10YR 5/2) occasional iron concretions, minor limonite staining blocky, becoming drier w/ depth 4.3 v. sl. moist to at 4.9-6.1 v. dry.</u>
										<u>TD = 6.1</u>

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 52198
 Location - North: _____ East: _____
 Date: 4/13/98 SK
 Geologist: Jim Cox
 Drilling Equip.: 4000000

Surface Elevation: _____
 Area: 903 PAD/RXNRY PIT PLUMB
 Total Depth: 12.0
 Company: IT CORP Project No.: _____
 Sample Type: Continuous

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL MEASUREMENT	SAMPLE NUMBER	FRACTURE ANGL	BT DIPS ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	Run 1.6 #1	2.0 80%	Run #98A1600 007-019 25 007-020 VOC					0		0.0-0.7 SILTY CLAY, dk yellowish br. (10YR 3/4) Moist w/ root hairs, some fine pebbles from 0.0-0.2. Moist.
								1		0.7-1.6 SILTY CLAY, dk yellowish br. (10YR 4/2) Moist some root hairs to grayish br. (2.5Y 5/2) mottled, limonitic staining w/ calcite nodules in nodules & layers. Soft, moist.
								2	X	2.0-3.2 SILTY CLAY, dk grayish br. (2.5Y 4/2) to dk yellowish br. (10YR 4/3) w/ calcite w/ root hairs - no observed pebbles. Soft. Moist.
	#2 2.2							3		3.2-4.0 SILTY CLAY, dk gray (10YR 4/1) becoming drier still sl. moist, less soft. Transition to 1
	4.0 110%							4		4.0-4.5 as above SILTY CLAY w/ some blocky clay clasts. Y. sl. moist.
										4.5 well developed calcite layer. TOP W. BR 3.9
	#3 1.9							5		4.5-6.0 SILTY CLAYSTONE, yellowish br. (10YR 5/4) w/ abundant calcite. Y. HARD, Y. DRY. calcite nodules at 5.9.
	6.0 95%							6	X	6.0-8.0 SILTY CLAYSTONE, dk grayish br. (2.5Y 4/2), mottled, limonitic staining some calcite (abundant at 7.3) DRY, MASSIVE
	#4 2.1							7		
	8.0 105%							8		8.0-10.0 same w/ iron staining (abundant at 8.9). DRY. PLASTIC. MASSIVE.
95 Box 2 of 2	#5 2.1							9		
	10.0							10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

- (1) Badly broken core, accurate footage measurements not possible.
- (2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 02148
Location - North: _____ East: _____
Date: 4/12/98
Geologist: Jim Cox
Drilling Equip.: Seagor

Surface Elevation: _____
Area: 903 PND 21/10/2017 PIT PLUMME
Total Depth: 12.0
Company: IT Project No.: _____
Sample Type: continuous

EG&G LOGGING SUPERVISOR

APPROVAL

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BLEEDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2	#6	ZS								10.0-12.0 CLAYSTONE, olive brown. (2.5Y 4/4) HARD, DRY w/ IRON STAINING, ABUNDANT IRON STAINING FROM 11.0-12.0 CONCRETION AT 11.5.
TD = 12.0								12		TD = 12.0 Refusal
										Backfill to 8.0 w/ Sand.

NOTES. General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 1

Borehole Number: 02298
 Location - North: _____ East: _____
 Date: 4/10/68
 Geologist: Jim Cox
 Drilling Equip.: Sloprom

Surface Elevation: _____
 Area: 903 PAD / RYAN'S PIT PLUME
 Total Depth: 8.3
 Company: ITC LP Project No.: _____
 Sample Type: CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 1	2.0 ±	2.0	005 - 016 RAD 500					1		0.0-0.7 ^{9.5} CLAY LOAM, y. dk. gr. br. (10YR 3/2) w/ root hairs, some fine pebbles subang/ subround, moist, v. soft.
	2.0	100%	006 - 017 VOL.					2		0.7-2.0 - SILTY CLAY, dk. yellowish br (10YR 4/4) w/ some iron staining, occasional root hair, w/ rare f. pebble. moist, soft.
	#2 2.0		006 - 016 RAD 500					3		2.0-4.0 - SILTY CLAY, dk. gr. br (2.5Y 4/2) occasional fine pebble, subang/ subround. some catiches, some iron staining. sl. moist, sl. soft.
	4.0	100%	006 - 016 RAD 500					4		4.0-4.6 same, drier/harder.
Box 2 of 1	#3 2.0		006 - 016 RAD 500					5		4.6 Top weathered BR. SILTY CLAYSTONE, dk. gr. br (2.5Y 4/2) w/ limonitic staining (some). w/ catiches, no pebbles, DRY, HARD.
	6.0	100%	006 - 016 RAD 500					6		6.0-7.8 CLAYSTONE, dk. gr. br (2.5Y 4/2) w/ clasts and sheer planes w/ slickensides iron concretions at 6.8. BLOCKY, DRY, HARD
	#4		006 - 016 RAD 500					7		7.8-8.0 CLAYSTONE, dk. gr. br (2.5Y 4/2) mottled, limonitic staining w/ sheer planes w/ slickensides MASSIVE, DRY.
	8.0		006 - 016 RAD 500					8		
	TD 8.3							9		TD = 8.3 REFUSAL.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 03198
 Location - North: _____ East: _____
 Date: 2/12/98 6-2-98
 Geologist: T. Lovseth (Rig) F. Grigsby (Log)
 Drilling Equip.: Stratoprobe

Surface Elevation: _____
 Area: SE of Solar Ponds
 Total Depth: 12.0'
 Company: Terra Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 2	Box 1 of 2	Rec 3.7'					CL	0		0-0.5' Gravelly Clay. some silt & sand. Dusky Brown (5YR 2/2). S. Damp. Gravel quartzite. Some feldspar. Broken fragments. Low plasticity. Top soil. Some root fragments.
							CL	1		0.5 - 1.3' Gravelly silt & sand. Matrix Dark yellowish brown (10YR 4/2) Gravel med well graded. Fred. Quartzite. Int. damp. Damp.
							CL	2		1.3 - 3.7' Sandy Clay - Dark yellowish brown (10YR 4/2) Damp. Estimated med fine grained. Sd. fine grained. Poorly graded. Int. appears non-fermentable.
							GC	4		3.7' - 4.0' No Recovery
							GC	5		4.0 - 4.4' Clayey Gravel - Matrix Dark yellowish brown (10YR 4/2). Fragments of feldspar and quartzite at top of interval core damp.
							GC	6		4.4 - 5.2' Sandy Gravel - some clay. Matrix pale yellowish brown (10YR 4/2) to very pale orange (10YR 8/2) Overall interval appears very permeable. (Still in lexon sleeve -) Core damp.
								7		5.2 - 6.7' Clayey gravel - Matrix pale yellowish brown (10YR 4/2) - Gravel med. quartzite. Well graded, sub angular - SI. Damp.
								8		6.7 - 12.0' TOP of bedrock - Claystone - Dark yellowish
Box 2 of 2	Box 2 of 2	Rec 4' +						9		
								10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Core stored in lexon sleeves -
Moisture retained.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2Borehole Number: 03198

Surface Elevation: _____

Location - North: _____ East: _____

Area: S.E. of Solar PondsDate: 2/12/98 & 6/12/98Total Depth: 12'Geologist: T. Lovsett (Reg.) & E. Griggs (Log)Company: Terra Project No.: _____Drilling Equip.: StrataprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOL/LITHOLOGIC LOG	SAMPLE DESCRIPTION
<u>Box 2 of 2</u>	<u>Run No. 3</u>	<u>8.0' - 12.0'</u>						<u>10</u>		<u>6.7-12.0' Continued</u> <u>Brown (10YR 4/2) gradings</u> <u>to Brownish Gray (5YR 4/1)</u> <u>Core varies from sl. phos.</u> <u>(upper part - sl. damp) to</u> <u>dry & indurated. Some</u> <u>reworked section below</u> <u>contact.</u> <u>Note: Top 0.4' of Core</u> <u>from Run No. 3 is stuff</u> <u>from above -</u>
								<u>11</u>		
								<u>12</u>		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 03298

Surface Elevation: _____

Location - North: _____ East: _____

Area: ESE. of Solar PondDate: 02/12/98 & 6-3-98Total Depth: 25'Geologist: T. Lovsøth (Rtg) F. Griggs (Log)Company: Terra

Project No.: _____

Drilling Equip.: StratoprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
BOX 1 of 3	Run No. 1 0'-4'	Rec. 3.3'					SM	0		0-0.6' Gravelly Silt, some clay & gd. - Grayish Brown (5yr. 3 1/2) - Estimated low plasticity. - Core dry - Roots & plant debris. - Topsoil zone.
							CI	1		
							CL	2		0.6' - 1.5' Silty clay - some sd. - fr. gravel. Pale Yellowish Brown (10yr 6 1/2) with Grayish Brown (5yr 3 1/2) inclusions. - Med plasticity - Estimated - sl. damp. sl. phabla.
	Run No. 2 4' - 8'	Rec. 3.8'					CL	3	shown zone	1.5' - 1.6' broken cobbles.
							CC	4		1.6' - 1.8' Silty clay - same as 0.6' - 1.5' (based on small sample).
								5		1.8' - 2.8' - sandy clay - some silt fr. gravel. Pale Yellowish Brown (10yr 6 1/2) to Grayish Orange (10yr 7 1/4) (Estimated) - Estimated med. plasticity. - Non-permeable. - wx interval. Core sl. damp.
	Run No. 3 8' - 12'	Rec. 4.0'						6		2.8' - 3.3' - shear zone - top 0.2' of interval is pale Yellowish Brown (10yr 6 1/2) with Grayish Orange (10yr 7 1/4) Fe staining against it. Silty clay against Dark Reddish Brown (10yr. 3 1/4) sandy clay - L - approx. 45°
								7		Lower shear is of moderate Brown (5yr 3 1/4) Silty clay against a clayey gravel.
								8		Matrix Pale Yellowish Brown (10yr 6 1/2) - L = 60° white coating over lower interval
								9		3.3' - 8.3' see next page

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Core stored in lexon tubes - retained some moisture.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 03298

Surface Elevation: _____

Location - North: _____ East: _____

Area: E. S.E. of Solar PondsDate: 2/13/98 & 6/13/98Total Depth: 25'Geologist: T. Lovett (R) F. Griggs (Log) Company: TerraLog Project No.: _____Drilling Equip.: StrataprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 343	Run No. 3 8.0' - 12.0'	Rec: 4.0'						10		3.3' - 4.3' Clayey gravel - some silt - Moderate Brown (5YR 3/4) at top of interval - grading to Pale Yellowish Brown (10YR 6/6) at bottom of interval - Core dry- clay mod. indurated. - Some gravel are broken cobbles - Minimum to non permeable because of clay matrix. Top 0.15 of core was compacted from above.
	Run No. 4 12.0' - 16.0'	Rec: 4.0'						11		6.3' - 7.8' Sandy clay - some silt, gravel and caliche in upper 0.3' of interval - intermed. brownish gray (5YR 4/1) and yellowish gray (5Y 8/1) clays, caliche & caliche nodules at 6-8', and caliche rich interval from 7.2 to 7.5' sand to mg., quartz, quartzite & some matrix - intermed. indurated sl. damp. etc. estimated mod. plasticity.
	Run No. 5 16.0' - 19.0'	Rec: 4.0'						12		7.8' - 8.0' No Recovery.
								13		8.0' - 12.8' - Top of bedrock claystone. Pale yellowish Brown (10YR 6/2) at top of interval, grading to brownish Gray (5YR 4/1) below 10' to 17.8' - upper part of core highly reworked - some caliche nodules in upper two feet.
								14		All runs over fractured & packed causing induced horizontal fractures along bedding or parting plane - occasional 45° fractures related to coring - Core sl. damp, moderately indurated, some zones of grayish orange (10YR 7/4) to staining.
								15		
								16		
								17		
								18		
								19		
								20		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3Borehole Number: 03298

Surface Elevation: _____

Location - North: _____ East: _____

Area: E.S.E. of Solar PondDate: 2/13/98 & 6/3/98Total Depth: 25'Geologist: T. Lovett (Rig) F. Griggs (Log)Company: Terra (DGS) Project No.: _____Drilling Equip.: Strata probeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box No. 3 of 3	Run No. 6 19' - 23'	Rec. 4.0'						20	17.8 - 25' - clayey siltstone -	From 17.8 to 19', core grades from claystone to siltstone - clayey siltstone. Below 19.0' recovery was poor on the initial run, and recovered wet sloughs. Pieces of larger diameter core recovered during clean out indicate the bottom of the hole is clayey siltstone.
								21		
								22		
								23		
								24		
	Run No. 7 23.0' - 25.0'	Sloughs at 24.5' Rec. 4.0'						25		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2Borehole Number: 03398

Surface Elevation: _____

Location - North: _____ East: _____

Area: W. of STPDate: 2/7/98 & 6/4/98Total Depth: 19.0'Geologist: T. Lovgren (R.G.) F. Griggs (Log)Company: Tierco (P&E) Project No.: _____Drilling Equip.: ShatrappeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR _____

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 3 0'-9.5'	Run No. 1 0'-4.0'	Rec: 4.0'						0		0'-8.0' - Gravelly clay - some silt & sd. - Fill material - Moderate yellowish brown (10yr 2.5)
							CL	1		To Dark Yellowish Brown (10yr 4/2) varies from very silty to very clayey - Amount of gravel varies throughout interval - general abundant this interval. Core damp.
								2		4.0'-8.6' Silty clay - some gravel - some as above except less gravel - plasticity in both intervals generally med. to high. Core damp. - (Plastic. Fill)
								3		Material.
	Run No. 2 4.0'-8.0'	Rec: 4.0'						4		8.6'-9.6' Silty clay - some sd. - Tr. gravel (small) - Dusky Yellowish Brown (10yr 2.5) Soil Horizon before fill. - Core sl. damp. - Estimated med. plasticity - some calcareous material.
							CL	5		9.6'-13.7' Silty clay - some sd - Tr. gravel. some as above except color ranges from moderate yellowish brown (10yr 2.5) to Dark Yellowish brown (10yr 4.5)
								6		Estimated med. plasticity - Core sl. damp - Plastic - occasional med. size Pebbles imbedded in core (center - not pushed down)
	Run No. 3 8.0'-11.0'	Rec: 3.5'						7		
							CL	8		
								9		
								10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2Borehole Number: 03398

Surface Elevation: _____

Location - North: _____ East: _____

Area: W. of STPDate: 2/17/98 & 6/9/98Total Depth: 19.0'Geologist: T. Lovett (Reg) F. Griggs (Log)Company: Terrad (DGE) Project No.: _____Drilling Equip.: StratagradeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box No. 2 of 3 9.5' - 16.5'	Run No. 3 8.0' - 11.0'	Rec: 3.5'						10		13.7' - 15.1' - <u>Silty</u> <u>Claystone</u> with interbedded <u>clay</u> <u>sandstone</u> <u>claystone</u> <u>clay</u> <u>pred. pale yellowish brown</u> <u>(10YR 6/2)</u> <u>(sandy)</u> <u>grayish orange (10YR 7/4)</u> <u>Top of interval grades from</u> <u>pred. claystone to claystone</u> <u>sandy intervals comprised</u> <u>of VFG to F.G. quartzite</u> <u>frains, Range from subrd.</u> <u>to spherical - possible</u> <u>reworked H1 sandstone -</u> <u>Entire interval comp is</u> <u>most - weathered - friable.</u>
	Run No. 4 11.0' - 14.0'	Rec: 3.5'					CL	11		
	Run No. 5 14.0' - 16.5'	Rec: 7.0'					CL	12		
Box 3 of 3 16.5' - 19.0'	Run No. 6 16.5' - 19.0'	Rec: 4.0'						13		15.1' - 16.5' - <u>claystone</u> <u>Top of Bedrock - composed</u> <u>of intermixed zones of</u> <u>pale yellowish brown (10YR 6/2)</u> <u>and Pale Brown (5YR 5/2)</u> <u>claystone lens and thin</u> <u>beds - Dark carbonaceous</u> <u>mattered associated with</u> <u>the pale brown intervals.</u> <u>Dark yellowish orange (10YR 6/6)</u> <u>becomes the staining</u> <u>and coating occurs on coating</u> <u>on clay coat or as filling</u> <u>in several micro fractures.</u> 16.5' - 19.0' - <u>Claystone - some</u> <u>interbedded sandstones.</u> <u>claystone - pale yellowish brown (10YR 6/2)</u> <u>sandstone - dark yellowish orange (10YR 6/6)</u> <u>Core highly comp - compressed.</u> <u>Top of claystone (pred. sand) at</u> <u>top. No accurate depths</u> <u>possible - Core damp.</u> <u>highly compressed.</u>
								14		
								15		
								16		
								17		
								18		
								19		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2Borehole Number: 03488

Surface Elevation: _____

Location - North: _____ East: _____

Area: Solar Field Phase 6Date: 2-17-98 & 6-5-98Total Depth: 16'Geologist: T. Lovette (Rg) & Grigsby (log) Company: Terra (DET) Project No.: _____Drilling Equip.: StratoprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/LITHOLOGIC LOG	SAMPLE DESCRIPTION
							CL	0		Tr. sd. 0-0.4' silty clay - (10yr 50%) Waxy brown (5yr 42). Sl. damp - friable, abundant roots -
							CL	1		0.4-1.4' clay - some sd & gravel in bottom 0.4' ft. of interval - moderate yellowish brown (10yr 54) to dark yellowish brown (10yr 42) with some grayish orange (10yr 71A)
							GC	2		grayish orange (10yr 71A) mottling. Good coarse gravel to ± 3/4" in lower 0.4' of interval. Core slightly damp - estimated med. high plasticity - contains roots.
								3		
								4		
							CL	5		1.4'-2.5' clayey gravel matrix moderate brown (5yr 44) other to grayish orange (10yr 71A) at bottom of interval - gravel well graded from cobble size to f. 6 - good quartzite - sub angular - clay matrix - est. med. plasticity.
								6		Int. Wx - Core sl. comp - covered with residual white rock dust (?)
								7		2.5'-4.0' No. Recovering.
								8		4.0'-5.7' clay - some gravel - pred. moderate yellowish brown (10yr 54)
							CL	9		sl. damp - friable, estimated med to med. high plasticity. Scattered large gravel - Int. Wx.
								10		5.7'-10.3' silty clay - some gravel - old soil horizon - abundant dusty brown (5yr 24) in top

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2Borehole Number: 03498

Surface Elevation: _____

Location - North: _____ East: _____

Area: 9000 Pond PlumbDate: 2-18-98 & 6-5-98Total Depth: 16'Geologist: T. L. L. (Rig) F. Griggs (Log)Company: Terra (R&E) Project No.: _____Drilling Equip.: StrataprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 3	Run No. 2	10.0' - 12.0'	Rec: 2.0'				CL	10		5.7-11.0' 10.0-11.0' (Continued) half interval - to clay gravel (5y 4) in lower half of interval. Core damp - med to med high plasticity. gneiss & Carbonaceous material in top half - Plant imprint & roots at approx 6.7'. Core becomes homogeneous below 8.2' (where color change occurs. - 45° fractured at 6.7' - may be induced. Color change to Grayish Orange (6yR 7.5) occurs from 10.0' - 10.3'. May be related to slush from Fl. in top of run. - Scattered gravel from 10.2' - 11.0'.
	Run No. 5	12.0' - 14.0'	Rec: 3.0'				GC	11		
	Run No. 6	14.0' - 16.0'	Rec: 2.0'					12		11.0' - 13.3' - Clayey Gravel - matrix fine yellowish brown (10YR 6.2) Gravel med. well graded to quartzite. well graded from broken cobbles to small. - Approx. 1.0' of slush & clay from above in run from 12.0' - 14.0' - Core dry
								13		13.3' - 16.0' - Top of bedrock. Fine Crystalline. - Dusky brown (5YR 2.5) in upper half of interval grading to pale yellowish brown (10YR 6.2) with abundant Grayish orange (10YR 7.5) limonite stained fracture filled zones in lower half of interval. Entire interval appears reworked and/or brecciated. - Induced horizontal fracture prevalent throughout interval. One large healed fracture (60°) from approx. 14.3' - 14.8' (Fe stained). Other random healed fractures below this interval. Some desiminated calcite occurring in top 0.2' - 0.3' of interval. Core dry.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 10098
 Location - North: _____ East: _____
 Date: 7/30/98 - 7/31/98
 Geologist: J. BOYLAN, T. LUTHERER
 Drilling Equip.: GEO PROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 11.0
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

LOCATION OF TUBE IN BOX	TOP OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENTS)	SAMPLE NUMBER	FRAC. TAIL MARK	BEDDING MARK	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LOG	SAMPLE DESCRIPTION
BOX 1 OF 1: 0.0 - 11.0'	0.0	0.0					SM	0.0		Gravelly, silty sand w/clay - dominantly dark brown (10YR 2/3). Sl. moist to moist.
	1.0	1.2						1.0		NOTE: Entire interval probed first w/solid point; recovered core is disturbed "cleaning run."
	4.0							1.2		NO RECOVERY 1.2 - 4.0
	4.0	4.0						2.0		
	4.0	4.0						3.0		
	4.0	4.0						4.0		
	4.0	4.0						5.0		Same as above 0.0-1.2'. Colors more variable, mottled. Caliche-rich zone near base (~5.1-5.3'). Sl. moist to moist. Caliche zone is clayey, pliable.
	4.0	4.0						5.5		NOTE: coring run followed pre-probe w/solid point.
	4.0	4.0						6.0		Same as above, 5.5 0.0-1.2'. Graded lower contact. Dominant color about brownish yellow (10YR 6/6) to light yellowish brown (10YR 6/4) - very mottled. Clay pods common. Coarser towards base. See NOTE below!
	4.0	4.0						7.0		
BOX 1 OF 1: 0.0 - 11.0'	7.0	7.0					GM	7.0		Bandy gravel w/silt, clay - same as above, 5.5-7.0, but abundant shattered quartzite gravels. Moist.
	8.0	8.0						8.0		See NOTE below!
	8.0	8.0						8.5		SANDY GRAVEL WITH SILT/CLAY - SAME AS ABOVE, ABUNDANT SHATTERED LITHIC GRAVELS, SATURATED.
	8.0	8.0						9.0		NO CORE TAKEN, 8.5-9.0
	8.0	8.0						9.0		
	8.0	8.0						9.5		
	8.0	8.0						10.0		
	8.0	8.0						10.5		
	8.0	8.0						11.0		
	8.0	8.0						11.0		NO RECOVERY - SOLID POINT 9.0-11.0

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

NOTE: ALL CORING RUNS ARE PRECEDED BY A SOLID-POINT RUN, so depths, texture, etc have been disturbed.

PAGE 2 CF 2

Surface Elevation: _____

Area: BLDG. 12.3

Total Depth: 11'

Company: TERRA Project No.: _____

Sample Type: CONTINUOUS COR

APPROVAL

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF HATCH	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FIGURE MARK	BEARING MARK	WIND SIZE DIRECTION	WIND DIRECTION	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
11.0	11.0	11.0						10.0	X	NO CORE TAKEN 110' TD WITH PROBE TD = 11.0'
								11.0		
								12.0		
								13.0		
								14.0		
								15.0		
								16.0		
								17.0		
								18.0		
								19.0		
								20.0		

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 1 OF 2

Surface Elevation: _____
Area: BLDG. 123
Total Depth: 13.3
Company: TIERRA Project No.: _____
Sample Type: CONTINUOUS CORE

APPROVAL

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENTS)	SAMPLE NUMBER	FIVE-TUPLE ANAL.	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL / LITHOLOGICAL UNITS	SAMPLE DESCRIPTION
0.0	0.0	0.0						0.0	Asphalt	
RUN 1:										
0.0-4.0	3.4							0.6	GM/GC	Silty gravel-sand mixture ranging to clayey, silty gravel-sand mixture - dark brown (7.5YR 4/3) below 0.9 very dark grayish brown (2.5Y 3/2) above. Sl. moist. Gravel; mostly shattered, quartzite.
								2.4	CL	Silty clay - red (2.5YR 4/6) to dark red (2.5YR 3/6). Moist. Containing rotting ss clasts or sand rip-up clasts that are very pale brown (10YR 8/4). Fairly sharppebbles lower contacts.
								3.4	GM	Silty, sandy gravel to silty gravel-sand mixture - mottled, but predominantly various shades of brown. Shattered quartzite common. Slightly moist to moist.
								3.4		NO RECOVERY 3.4 @ - 4.0
RUN 2:								4.0		Same as above, 3.1-3.4.
4.0-6.5	3.3 ind. 0.8' slough							5.0		
6.5-6.5								6.5		Same as above, 3.1-6.5'
RUN 3:								7.0		
6.5-9.8	4.0 ind. 0.7' slough							8.0		
								9.0		
9.8-9.8								9.8		same as above 3.1-9.8' (Cont'd next page)

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 10198
 Location - North: _____ East: _____
 Date: 8/10/93
 Geologist: J. BOYLAN
 Drilling Equip.: GEO PROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 13.3
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INDIVIDUAL FEET OF CORE	FEET OF CORE IN INDIVIDUAL FEET OF CORE	SAMPLE NUMBER	FIXTURE AIRLIFT	BLINDERS AIRLIFT	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LOGGING LOGS	SAMPLE DESCRIPTION
	9.3	9.3					GM	10.0		Core very overpacked - top portion is slough, but due to overpacking, distinction between "slough" and "core" is difficult.
	Run 4:	4.0						11.0		
	9.8	ind.						12.0		
	13.2	0.6'						13.0		
	13.2	13.2						13.2		
13.3	Run 5	0						13.3		NO RECOVERY 13.2-13.3 - TIRE REFUSAL
	13.3	13.3						14.0		
								15.0		
								16.0		
								17.0		
								18.0		
								19.0		
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2Borehole Number: 10298

Surface Elevation: _____

Location - North: _____ East: _____

Area: BLDG. 123Date: 8/4/98 - 8/5/98Total Depth: 16.0Geologist: J. BOYLANCompany: TIERRA

Project No.: _____

Drilling Equip.: GEOPROBESample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN LOG	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FINAL TRUE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
0.0	0.0	0.0					SC	0.0		Clayey, gravelly sand - dominantly dark brown (7.5YR 4/4). Pockets of caliche (~1/2", soft) common. Sl. moist to moist. Gravels typically <1" but some shattered fragments present, especially below 2.0' where rock flour is also common. Color below 2.0' mottled. Material below 2.5' less moist than above. Material below 2.5' approaches GC.
	RUN 1:	3.3						1.0		NOTE: Coring run followed solid-point pre-probe run, so core is disturbed, depths very approximate.
	0.0-5.0							2.0		
								3.0		
								3.3		
								4.0		NO RECOVERY 3.3-5.0'
								5.0		
	5.0-5.0						GC	5.0		Clayey, sandy gravel - much like above (0.0-3.3) but coarser. Some lenses more clay-rich. Mottled above ~5.8' (browns, grays); below matrix typically is light olive brown (2.5Y 5/3). Sl. moist to moist. Caliche packet @ 6.6'. Gravels shattered. Rock Flour common.
	RUN 2:	3.2'						6.0		
	5.0-8.0							7.0		NOTE: 5.0-6.0' interval disturbed by solid-point pre-probe run.
								8.0		
	8.0-8.0						GC/SC	8.0		Clayey, sandy gravel to clayey, gravelly sand - same as above, 5.0-8.0 but more fines. Color above is predominantly mottled throughout, w/ variegated browns, red/orange browns, olive grays. Sl. moist to moist.
	RUN 3:	4.0 incl. 1.0' slough						9.0		NOTE: Coring run followed pre-probe run, so core is disturbed.
	8.0-11.0							10.0		
10.0										

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 10298
 Location - North: _____ East: _____
 Date: 8/5/98
 Geologist: J. BOYLAN
 Drilling Equip.: GEO PROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 16.0
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	TIME IN MIN.	BLINDS IN MIN.	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
0.0	see previous page						GC/SC	10.0		See previous page
	11.0 11.0	11.0 11.0						11.0		Same as above, 8.0-11.0. Difficult to differentiate slough. Slough and 11.3-11.8' interval are wet; balance sl. moist to moist.
	11.0	3.6						12.0		Some portions GC, but overall it's a mix, GC/SC. Gravels still dominantly quartzite, shattered.
	14.0	0.4'						13.0		
	14.0	14.0						14.0		Sandy, clayey gravel - same as above 11.0-14.0, but coarser - more gravels (shattered quartzite mainly, but also some fresh pink ls-spars). Predominant color in the sandy clay matrix is pale yellow (2.5Y 7/3) to light gray (2.5Y 7/2). Slough is moist to wet, core is sl. moist to moist.
	14.0	4.0,					GC	15.0		measured TD = 15.8', so slight caving occurred.
	14.0-16.0	2.0' slough						16.0		
Box 2 of 2: 10.0-16.0'								16.0		TD = 16.0'
								17.0		
								18.0		
								19.0		
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 10398

Surface Elevation: _____

Location - North: _____ East: _____

Area: B-123

Date: 8/11/90

Total Depth: 11.3

Geologist: J. Barlan

Company: _____

Project No.: _____

Drilling Equip.: Geoprobe

Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP OF CORE IN BOX	TOP OF CORE IN INTERVAL	FEET OF CORE IN INTERVAL MEASUREMENT	SAMPLE NUMBER	FINAL TIME ASIDE	DEVIATIONS ASIDE	GRIND SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
0.0	0.0	0.0						0.0		ASPHALT
	RUN 1:						GC CU	0.6		Clayey, sandy gravel w/silt - dark brown (6YR 3/1)
	0.0-3.2						CL	1.0		
	4.0							1.4		Gravelly, sandy clay w/silt - mottled & streaked but mainly yellowish red (5YR 4/6). Mottling is shades of ochre & v. dark brown & browns. Sl. moist. Gravels mostly < 0.5" but some shattered fragments of larger clasts also present. Coarsens @ base.
								2.0		
								3.0		
								3.2		
								3.2		NO RECOVERY
								4.0		3.2-4.0
	RUN 2:							4.0		Same as above 1.4-3.2, but slightly coarser to gravelly sand-clay mixture. Some to abundant black flecks/grains = Fe/Mn oxides? To GC @ base. (Short an d to tip - small) (SAB)
	4.0-7.6						SMY GM	5.0		Gravelly silty sand to silty sand gravel mixture dominantly strong brown (7.5 YR 4/6). Shattered gravels (mostly quartzite, traces sandstone, Feldspar). Some to abundant Fe/Mn oxides (black grains & flecks) present @ 4.0-4.5 decreasing below this. Some clay throughout, and clayey gravel lens present below 7.1'. Some portions sandier, some more gravel-rich.
								6.0		NOTE: Resistive material present in offset location (which produced all core below 4.0'), underlain by very soft/void space. Not present in original hole (which produced 0.0-4.0 core).
								7.0		
								7.6		
								8.0		Same as above 4.0-7.6'. Abundant shattered gravels, especially below 9.5'. Clay-rich lenses, as at 8.2', contain light brownish gray (2.5 Y 4/6) clays, usually. These lenses (GC) are common but not dominant. Sl. moist to moist.
								9.0		
								9.6		
								10.0		
								10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2



Borehole Number: 10398
 Location - North: _____ East: _____
 Date: 8/8/98 8/11/98
 Geologist: J. BOYLAN
 Drilling Equip.: GEOPROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 11.3
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP OF CORE OF CORE IN LOG	TOP OF CORE OF INTERVAL	FEET OF CORE IN INTERVAL (MEASURED IN LOG)	SAMPLE NUMBER	FLAC LURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SORT SYMBOL LOG	SAMPLE DESCRIPTION
8.6 Box 2 or 2 8.6 - 11.3	10.0 Run 4: 10.0 - 11.3	2.6, incl. 1.3' slough					GC	10.0		Same as above, 4.0 - 10.0'. Sl. moist to moist. However, has graded to clayey gravel - clayey gravel-sand mixture. So, call it GC.
11.3	11.3	11.3						11.0		← change symbol to GC
								11.3		11.3' = T.D.
								12.0		
								13.0		
								14.0		
								15.0		
								16.0		
								17.0		
								18.0		
								19.0		
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 10498
 Location - North: _____ East: _____
 Date: 8/7/98
 Geologist: J. BOYLAN
 Drilling Equip.: GEOPROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 12.1
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

LOCATION OF CORE IN BOX	TOP POSITION OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENTS)	SAMPLE NUMBER	FLUID TYPE	APPEARANCE	BEDDING APPEARANCE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ROCK LOGS	SAMPLE DESCRIPTION
BOX 1 OF 2	0.0	0.0						SM	0.0		Silty, gravelly sand - Top 0.1' is very chippy, friable asphalt. Bottom 0.1' of recovery is also asphalt. Balance is dry to sl. moist, dark yellowish brown (10YR 4/4), some clay, mostly fine gravels but a few > 1".
	0.0	0.0							1.0		
	0.0	0.0							2.0		
	0.0	0.0							2.2		
	0.0	0.0							3.0		
	0.0	0.0							4.0		
	0.0	0.0							4.2		
	0.0	0.0							5.0		
	0.0	0.0							5.2		
	0.0	0.0							6.0		
BOX 1 OF 2	4.0	4.0						SM	4.0		Looks like artificial fill. Clean coarse sand @ 4.0-4.2', then sand-clay mixture w/ trace gravel to 4.6' then silty sand w/ trace clay (sand coarse) to 5.1, then sand-clay mixture to base of recovery (assumed 5.2, by convention). To 4.0 fine gravel in top core listed. Color predominantly the same as above.
	4.0	4.0							5.0		
	4.0	4.0							5.2		
	4.0	4.0							6.0		
	4.0	4.0							7.0		
	4.0	4.0							8.0		
	4.0	4.0							9.0		
	4.0	4.0							10.0		
	4.0	4.0							11.0		
	4.0	4.0							12.0		
BOX 2 OF 2	8.0	8.0						GM	8.0		Sandy gravels w/ clay and silt - Mottled. Fresh, shattered & pulverized feldspar near base gives basal recovery a pink color, rest is overall strong brown (7.5YR 5/6) w/ same-colored and light gray (2.5Y 7/2) streamers of clay. Gravels fine to > 1" (and therefore shattered), dominantly quartzite. Saturated to moist.
	8.0	8.0							9.0		
	8.0	8.0							10.0		
	8.0	8.0							11.0		
	8.0	8.0							12.0		
	8.0	8.0							13.0		
	8.0	8.0							14.0		
	8.0	8.0							15.0		
	8.0	8.0							16.0		
	8.0	8.0							17.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 10498
 Location - North: _____ East: _____
 Date: 8/2/98
 Geologist: J. BOYUN
 Drilling Equip.: GEO PROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 12.1
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUORESCENCE ANALYSIS	BEDDING ANALYSIS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOGS	SAMPLE DESCRIPTION
Box 1 of 1: 0.0-12.1'	see ↑ previous page	↑						10.0 10.2	see previous page	NO RECOVERY 10.2-12.0'
12.1	12.1	12.1						12.0 12.1	NO RECOVERY, 12.0-12.1- TIP REFUSAL	TD = 12.0' (circled) 12.1'
	RW 4: 12.0- 12.1	0.0						13.0 14.0 15.0 16.0 17.0 18.0 19.0 20.0		TD = 12.1'

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 10598

Surface Elevation: _____

Location - North: _____ East: _____

Area: BLDG. 123Date: 8/6/98Total Depth: 10.8Geologist: J. BOYLANCompany: TIERRA

Project No.: _____


Drilling Equip.: GEO PROBESample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

SAMPLE DESCRIPTION



NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 10598
 Location - North: _____ East: _____
 Date: 8/16/98
 Geologist: J. BOYLAN
 Drilling Equip.: GEOPROBE

Surface Elevation: _____
 Area: BLDG. 123
 Total Depth: 10.8
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/SECTION OF CORE IN BOX	TOP/SECTION OF INTERVAL	FEET OF CORE INTERVAL MEASUREMENT	SAMPLE NUMBER	FLUID TEMP AT GLE	BLENDING AT GLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
SEE PREVIOUS PAGE							GM	10.0		see previous page.
0.0	10.8	10.8						10.8		
								11.0		TD = 10.8'
								12.0		
								13.0		
								14.0		
								15.0		
								16.0		
								17.0		
								18.0		
								19.0		
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 20098
 Location - North: _____ East: _____
 Date: 6-24-88
 Geologist: R. KOEHLER/F. Grigg (Log)
 Drilling Equip.: GEOPROBE/MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 21.0'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

SAMPLE DESCRIPTION

LOCATION OF CORE IN BOX	TOP BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUCTUATION	BEARING	GRADE	QUANTITY DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG
Box No. 1 of 3	0.85 - 9.2	8.35	Rec. No. 1						0.0	0-0.85 - NO sample collection 0-0.6 - Asphalt. 0.6-0.85 - Road Base.
	9.2 - 20.1	10.9	Rec. No. 2						1.0	0.85 - 1.6' - sandy clay - some gravel - sl. damp. Est. med. plasticity. light brownish gray (10YR 4/2)
	20.1 - 21.0	0.9	Rec. No. 3						2.0	1.6' - 2.8' - Gravelly clay. some sand. Red. silty gray (5Y-5/3) - sl. damp & plastic. Est. med. high plasticity. Gravel sized (approx. note) coarsest 8 granitic clast - Abundant black asphaltic material mixed with clay.
									3.0	2.8' - 3.6' - sandy clay - some silt - sl. damp - light brownish gray (5YR 4/2) to moderate brown (5YR 4/4) sl. damp - sl. fine gr. sd. poorly graded - Red. med. gr. - w/
									4.0	3.6 - 3.7' - clayey gravel - matrix clayish yellowish brown (10YR 4/2)
									5.0	3.7 - 4.6' - No Recovery 4.6' - 5.9' - Gravelly clay - some sd. - dark yellowish brown (10YR 4/2) - sl. damp - Est. med plasticity - dense. Non friable. Gravel quartzite some to 0.1' max.
									6.0	5.9' - 7.3' - silty clay - some gravel - To sd. - Top 0.9' - Dusty yellowish brown (10YR 4/2) lower interval more gravelly - color change to grayish brown (5YR 3/2)
									7.0	7.3 - 8.0' - Gravelly clay - some sd. Above (5.9-7.3) calc. ext. slight increase in gravel content.
									8.0	8.0' - 9.3' - silty clay - some gravel - color change to moderate yellowish
									9.0	
									10.0	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 20098
 Location - North: _____ East: _____
 Date: 6-24-98
 Geologist: F. Griggley - R. S. L. L.
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: North PA
 Total Depth: 21.0'
 Company: Terra Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SONO/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 3 9.2' - 15.4'	Run No. 4 10.0' - 12.0'	Rec 3.1' (1.1 sample)					CL	10		8.0 - 9.3 (continued) Brown (10yr. 5/4) sl. damp - non friable. Est. med plasticity.
								11		9.3 - 13.5' silty clay - trace of gravel. Grayish orange (10yr 7.4) in upper foot & internal, grading to moderate yellowish brown (10yr 5/4) in remainder of interval. Some flecks of organic materials on surface. Some core breaks. - Est. med plasticity - med. to non friable - sl. damp - wax.
								12		
								13		13.5 - 15.4 gravelly clay - Zone of dark reddish brown (10yr 3/4) clay from 13.3' to 13.6' underlies very gravelly zone.
							CL	14		13.5 - 15.4 - gravelly clay, some sd.
								15		Dark Reddish Brown (10yr 3/4) in top 0.3' of core, and yellowish gray (5yr 7.4) to moderate brown (5yr 4/4) in remainder of interval. - sl. damp & med. friable - wax.
							GC	16		15.4 - 15.8 - clayey gravel - some sd. (based on one core fragment) - matrix very fine orange (10yr. 8/2) with grayish orange (10yr. 7.4)
								17		Core dry. - Most of core consists of broken quartzite (cobble, 15.8 - 16.0' No Recovery
								18		16.0 - 19.4 - Top of bed rock - actual depth questionable. Clay str. - some silt - Brownish gray (5yr. 4/1) grading
								19		
								20		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3Borehole Number: 20098

Surface Elevation: _____

Location - North: _____ East: _____

Area: North PA.Date: 6-25-98Total Depth: 21.0Geologist: R. KOENIG (R-9) F. Longley (209)Company: Terra Project No.: _____Drilling Equip.: GeoprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN LOG	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRAC. TIME APPROX	BEDDING APPROX	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL TEMPERATURE LOG	SAMPLE DESCRIPTION
20										18.0' - 19.4' Continued - to light olive gray (5Y 6/1) at bottom of interval -
21										to crevice inch of YG - 100 SS. or sand and gravel sand at top of interval. - May account for - Non Recovery from 15.8' to 18.0'. Numerous random fractures (1/8" to 1/4") filled (light brown 5YR 5/6) This interval appears to be reworked to brecciated. From 19.1' to 19.4' core appears to be finely laminated crevice (1/8" cracks) over week-end 19.4' - 21.0' No Recovery

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 20198
 Location - North: _____ East: _____
 Date: 6-29-98 / 6-30-98
 Geologist: R. Bachler (Rtg) F. Graggs (Log)
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: N. RA. Plume
 Total Depth: 16.0'
 Company: Terra Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 2	Run No. 9	10.0' - 13.0'	Run No. 10					10		9.5' - 16.0' Continued
9.0' - 16.0'	Run No. 5	13.0' - 16.0'	Run No. 2.0					11		Claystone. - Some silty intervals - Color grades from grayish orange (5 yr. 4a) at top of interval to pale yellowish brown (5 yr. 4a) and dark yellowish brown (5 yr. 4a) over rest of interval. Harder
								12		Top of interval contains concentration of small fractures - concentration - second concentration of fractures at 15.5' - to 15.8' larger, and core interval has slight color change to moderate brown (5 yr. 4a) at top of interval -
								13		Carbonaceous zone at approx. 13.4' - 13.7' color change to brownish gray (5 yr. 4a) in interval - some
								14		FeO coated minor fractures occurring in lower 1.5' of interval. Core is very sh. dense - H.C. interval to slightly friable. Entire interval interbedded with moderately reworked. Most extensive occurs in upper portion of interval & decreasing with depth.
								15		
								16		
								TO		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 20298
 Location - North: _____ East: _____
 Date: 7/1/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE/MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 13
 Company: TIERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL F. DringDATE 7-2-98

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL OF CORE IN FIELD (MEASUREMENT)	SAMPLE NUMBER	FRacture MARKS	BEARING MARKS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SON/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
							0.0		0.0-0.7 ft asphalt
							0.4		0.4-1.1 Sandy Gravel yellowish brown (SYR 5/4) gravel up to 1.5 cm, rounded, unconsolidated, moist, void fill.
							1.0		1.1-1.5 1.1 woven fiberglass (?) mat
							1.5		1.5-2.6 Gravelly Clay dark grayish brown to light olive brown (2.5Y 4/2 to 2.5Y 5.6/2, 3cm rounded gravel, moist, fractured) 1.5-2.6 Old Asphalt rock at bottom - irregular
							2.0		
							2.6		2.6-4.0 Gravelly Clay, dark grayish brown to light olive brown (2.5Y 4/2 to 2.5Y 5/6, 2.5Y 4/3) rounded gravel up to 2.5 cm, igneous mostly, moist, trace wispy concretions.
							3.0		
							4.0		4.0-6.85 Clay with trace sand and gravel, olive brown (2.5Y 4/4) to olive yellow (R 2.5/5.5/3). Gravel 1-5 mm (one down to 4.5 ft), fine sand, moist.
							5.0		Colors mottled, some 3mm to 5mm ironstone concretions. Yellow parts may contain fine sand.
							6.0		
							7.0		No Recovery 6.85-7.0 ft
							7.0		7.0-8.0 as above 4.0-6.85
							8.0		8.0-9.3 Gravelly Clay, Black to Very Dark Gray (5Y 2.5/1 to 5Y 3/1), rounded to subrounded igneous & metamorphic clasts up to 9.5 cm, trace root hairs, massive, moist.
							9.0		
							9.0		
							10.0		No Recovery 9.3-10.0

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2Borehole Number: 20298

Surface Elevation: _____

Location - North: _____ East: _____

Area: North FA PlumeDate: 7-1-98 / 7-2-98Total Depth: 13'Geologist: R. Koehle-UG) F. Grigeb, (UG)Company: UG Project No.: _____Drilling Equip.: GeoprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

SAMPLE DESCRIPTION

Continued Slough above following interval

10.0 - 11.4 - Clay - some sd. - Fred.
 Olive gray (5) - 41,) some - desiccated
 mid plates & (very small g. and (small)
 5) down - Plate & Lin. - some thin
 clay. (?) seams -

Top of Bedrock - 11.4

Claystone - some sd. - JP. Caliche
 light olive gray (5) - 5/2 -

Not well defined contact. - Bedrock
 removed (some 1/2) some 1/2

stained cores (40% yellowish
 coarse (10412-46) some thin

13 - 10
 Caliche filled fracture.

Core sl. damp non friable -
 non visible.

NOTES. General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 20398
 Location - North: _____ East: _____
 Date: 7/6/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE/MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 23'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL F. DreyerDATE 7-7-98

LOCATION OF CORE BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (IF RECOVERY)	SAMPLE NUMBER	FRACATURE ANGLE	BEDDING ANGLE	GLAUCOSE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
Box 1 of 0.0 - 82.5	Run #1 0.0-4.0 ft. Recovery 3.5 ft.	Recovery 3.5 ft.						0.0		0.0-0.6 Asphalt
								0.6		0.6-1.1 Road base sandy gravel, dk yellowish brown (pyR4/4) rounded gravel to 2 cm, 19 and sedimentary medium sand, poorly graded, moist, 1 ft depth of flash mount, unconsolidated
							CL	1.1		1.1-2.5 Clay (woven cloth mat at 1.1 ft) Gravelly clay, brown (7.5YR4/3) to olive gray (5.5Y4/3) gravel up to 2.5 cm, subangular, granitic, grades to sand (Ck), plastic, moist, unconsolidated
								2.0		2.0-3.5 ft, Asphalt
							CL	3.0		3.5-4.0 ft Gravelly clay, grayish brown (2.5Y5/3) to olive brown (2.5Y4/3) sub. and to angular clasts to 3 cm, rotten granitic, some calcite, fr wood frag (humid?) 2.5 ft med sand at 3.6 ft, moist, plastic, unconsolidated, massive
								4.0		4.0-5.5 Clay, mottled grayish brown (2.5Y5/2) to light yellowish brown (10YR 6/4) some patches brownish yellow (10YR 6/3) trace medium sand (fracture?) 4.4 ft, trace angular gravel at 4.8 ft, possibly some clay clasts, moist, massive, plastic
							CL	5.5		5.5-7.0 Clay, clay clasts gray (10YR 5/1) in light yellowish brown (2.5Y 6/4) to olive yellow (2.5Y 6/8) matrix, possibly a random fracture - two, brecciated, small blocks, calcareous fragments, moist, only slightly plastic
								7.0		7.0-7.9 Clay as above 5.5-7.0 slightly less blocky, fracturing more massive, slightly more plastic, more moist.
							SM	8.0		7.9-8.8 Gravelly Sand; dark yellowish brown (10YR 4/6) fractured quartzite (?) gravel up to 2.5 cm, coarse angular sand, granitic clasts, clayey, moist, massive, unconsolidated.
								8.8-8.9		SL. 8.8-8.9
8.9 8.9	Run #3 7.0-10.0 ft Recovery 2.4 ft. including 0.2 ft slugs.	Recovery 2.4 ft.					CL	9.0		8.9-9.4 Clay as above 5.5-7.0
								9.4		SL. 9.4-9.4
								9.4		9.4-10.0 No Recovery

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 20398
 Location - North: _____ East: _____
 Date: 7/6/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPHOS/MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 23'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL F. DrigleyDATE 7-8-98

TOP/BOTTOM OF CORE INTERVAL	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FINAL TIME AREA	BEDDING AREA	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
	Run #4 10.0-13.0 ft.	Recovery 2.9 ft including 0.2 ft slough.					CL	10.0		10.0-11.1 Sandy Clay, Gray (10YR 5/1) clay clasts in clay-sand matrix (gray to yellowish brown (10YR 5/8)) fine sand poorly graded, massive, moist, plastic although unconsolidated
							CL	11.0		11.1-11.7 Clay as above 5.5-7.0, prominent clasts, more moist than 5.5-7.0
							CL	11.7		11.7-12.8 Clay-Sand Gravel, Clay at top decreases down yellowish browns (10YR 5/4-5/6) with weak red (10R 4/6) mottles, gravel up to 2cm, rounded, granitic, medium to coarsened, poorly graded, unconsolidated, lower sandier part wet
							CL	12.8		12.8-13.0 No Recovery
							CL	13.0		13.0-13.4 Clay Sand Gravel as above 11.7-12.8 - wet
							CL	13.4		13.4-13.9 Clay Sand (from gravel), light olive gray (5Y 4/2) fine sand, massive, wet
							CL	13.9		13.9-15.1 Gravely Clay; darkish gray (5Y 3/2) to black (5Y 2.5/2) Gravel to 2cm, rounded, plastic, moist to wet, root hairs
								15.0		15.1-16.0 No Recovery
							CL	16.0		16.0-16.9 Clay - fine grained - Dark yellowish brown (10YR 4/2) some fine sand in lower part of interval with 10% change to fine Gravelly Clay (10YR 7/4) Large gravel clast at bottom of interval. Core mid length - Plastic - Est med. plasticity
								17.0		16.9-19.0 No Recovery
								18.0		19.0-19.6 Top of Bedrock Claystone. Interbedded with fine yellowish brown (10YR 4/2) fine grained claystone (10YR 7/4) bedded dip. and. differentially horizontal - upper part of core is not of bedrock
								19.0		19.6-22.0 No Recovery
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.


(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE ~~2~~ OF 3

Surface Elevation: _____
Area: NORTH-PA
Total Depth: 23'
Company: TERRA Project No.: _____
Sample Type: PUSH / CONTINUOUS CORE

APPROVAL: E. Z. [Signature]

DATE 7-8-98

TOP-BOTTOM OF CORE IN BOX		TOP-BOTTOM OF INTERVAL		FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ANGLE	BEDDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Ryn #8 220-230	Ran #7 19.0-22.0	Ran 0.8 ft	Recovery							20.0 21.0 22.0 23.0 24.0 25.0 26.0 27.0 28.0 29.0 30.0		<p>22.0-23.0 Clay, dm to dk sm (7.5 YR 4/2) part of strong brown (7.5 YR 5/8), carbonaceous, firm, plastic ^{plastic}, massive, moist. quartz is fractured.</p>

Materials amounts are estimated by % volume instead of % weight.

- (1) Badly broken core, accurate footage measurements not possible.
(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 20498
 Location - North: _____ East: _____
 Date: 7/7/98 7/8/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE/MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 22'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL E. KoeplerDATE 7-9-98

SAMPLE DESCRIPTION

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUID NAME ANALY	BEDDING ANALY	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 1 of 3 0.0 to 10.0 ft	Run #1 0.0 - 4.0 ft. Recovery 4.0 ft (3.4 ft core barrel, dug out 1.2 ft flush mud)							0.0		0.0-0.5 ft Asphalt
								0.5		0.5-1.2 ft Sand and Gravel, yellowish brown (10YR 5/6), rounded gravel to 2 cm, igneous - granitic coarse sand, unconsolidated, moist woven mat 1.2 ft
								1.0		
								1.2		
								1.4		1.2-1.6 Gravel - Sand - Clay, yellowish brown (10YR 5/4) to black (10YR 2/1), rounded gravel to 1.5 cm, moist, plastic, well graded
								1.6		1.6-2.1 Asphalt - crumbled
								2.0		
								2.1		2.1-2.6 Gravel - Sand - Clay As Above 1.2-1.6, Sand med to CRS, gravel granitic,
								2.6		2.6-4.0 Gravelly Clay, mottled (10YR 5/2) grayish brown brownish yellow (10YR 6/8) and dark gray (10YR 4/1), rounded but fractured gravel to 2.5 cm, granitic, unconsolidated rare layer (<0.5 cm) fine sand, clay clasts, moist, plastic to slightly plastic, gravel and sand associated together for the most part.
								3.0		
	Run #2 4.0-7.0 ft. Recovery 2.1 ft. (unseen if top 0.2 is slough)							4.0		4.0-5.7 Clayey Gravel, (top 0.2 is slough) brown (2.5Y 4/3) Clay may be slough, dark yellowish-brown (10YR 3/4), fractured granitic gravel up to 3 cm, slightly moist, slightly plastic, poorly graded,
								5.0		
								5.7		5.7-6.1 Clayey
								6.0		6.0-6.1 Sand, brownish yellow (10YR 6/3), rounded, quartz, medium (USC), moist, massive, unconsolidated,
								6.1		6.1-7.0 No recovery
								7.0		
								8.0		7.0-9.6 Clayey Sand with gravel, brownish yellow (10YR 6/6 to 6/8) some strong brown (7.5YR 5/8). Angular to subangular gravel up to 3 cm, quartzitic part, sand dominantly fine grained but grades up to coarse, crudely bedded (1 zone 0.5 ft from plant to 8 to 8.3 ft), well graded, plastic, moist,
								9.0		
								9.6		9.6-10.0 Clayey Gravelly Clay, black (10YR 2/1), gravel up to 2 cm, massive, moist, plastic, root hairs.
								10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

* - Both intervals pred-Sandy
 GWC - Sandy Clay - GC
 Mixed with some Asphalt

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 20498
 Location - North: _____ East: _____
 Date: 7/8/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE/MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 22'
 Company: TERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL [Signature]DATE 7-23-98

TOP BOTTOM OF CORE IN BOX	TOP BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (MEASUREMENT)	SAMPLE NUMBER	FIELD TIME ANAL	DETERING ANAL	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 3 10.0 to 20.0 ft	Run #4	10.0-13.0 ft	Recovery 4.0 ft including 0.3 ft of slough.				CL SC	10.0		Sandy clay 10.0-13.0: Clayey sand with occasional gravel; top 0.5 ft olive gray (SY 4/2) to dk olive gray (SY 3/2); musty wet olive (SY 5/3-5/4) to olive yellow (2. SY 6/1); light gray mottling (especially bottom 0.5 ft) (2. SY 7/0); granitic (some rotten) and quartzite gravel to 3 cm; sand fine, subangular to subround, plastic, moist; root hairs 10.7 to 11.2 ft.
	Run #5	13.0-16.0 ft	Recovery 2.5 ft (mostly slough)				CL	13.0		Sandy clay 13.0-13.5: Clayey sand with occasional gravel; olive (SY 5/3 to 5/4) with olive yellow to yellow clay; small fractured (SY 6/8 to SY 7/8) plastic/moist
							CL	14.0		13.5-15.1: Clayey sand with occasional gravel; dark gray to very dark gray (SY 4/1 to 3/1); granitic and quartzite gravel to 2.5 cm - fractured, moist, plastic, root hairs throughout; massive, poorly graded. Sand - fine grained
							GC	15.0		15.1-15.5: Sandy gravel; brown (10YR 5/3), fractured quartzite to 0.5 cm, in mat to c/s sand matrix, wet ← just at very bottom!
Box 3 of 3 16.0 to 19.0 ft	Run #6	16.0-19.0 ft	Recovery 1.7 ft including 0.5 ft of possible slough. Rest of core filled with slough/clay/sand/gravel				GC	16.0		15.5-16.0 No Recovery
							GC	16.0		16.0-16.5 Sandy Gravel as above 15.1-15.5 Very wet
							CL	17.0		16.5-16.9: Clayey sand to yellow brown (10YR 6/4) to brownish yellow (10YR 6/5); fine sand, firm, possibly laminated, plastic moist
							CL	17.0		16.9-17.7: Clayey sand at top sand declines down, grades from clayey sand to clayey silt. RPK 17.7-18.0
Run #7	19.0-22.0 ft	Recovery 3.0 ft including 0.2 ft of slough						19.0		No Recovery 17.7-19.0 ft flowing. Core barrel filled with soupy clay/sand (fine) Gravel (≤ 1 cm, angular) mess. Top 0.5 ft in core box may be real or may be slough - not shown here. RPK/7.8.98
								20.0		19.0-21.8: Clayey silt. moist; firm, dries out and becomes crumbly at bottom.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible

overlying sand above to light gray at bottom (mottled)
 2. SY 7/1 to 7/2, may be bedded, sandy top sand
 disappears quickly down, firm, plastic, moist.

* 16.5-17.7. Clayey silt
 Top of Redrock 17.7

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 20499
 Location - North: _____ East: _____
 Date: 7/8/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 22.0'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Fred C. DringlerDATE 7-13-98

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INITIAL FIELD MEASUREMENT	SAMPLE NUMBER	FRAC/TYPE ARKSE	BEARING ARKSE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
Box 343 20.0-22.0 ft	Run #17 19.0-22.0 ft	Recovery 3 ft including 0.26 gravelly slough						20.0		
								21.0		
								22.0		
								21.8		No Recovery 21.8 - 22.0 ft.
										Bedrock probably between 21.8 and 22.0 ft.
								23.0		
								24.0		
								25.0		
								26.0		
								27.0		
								28.0		
								29.0		
								30.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 1 OF 3

Surface Elevation: _____
Area: NORTH - PA
Total Depth: 20.5'
Company: TIERRA Project No.: _____
Sample Type: PUSH / CONTINUOUS CORE

APPROVAL

DATE _____

CAPTION OF CORE IF BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRacture Attitude	BEDDING Angle	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 162 0.0 - 12.5	Run No 2 4.5 - 8.3	Rec. 3.3						0.0		0.0 - 0.5 Asphalt
								1.0		0.5 - 1.4 - Root zone - Not Recovered.
								2.0		1.4 - 4.5 - Clayey Gravel. Very Dark Gray (10YR-3/1) - some roots at top. Clay stiff - Est. med high plasticity. Color becomes sandy in lower 0.5'. A interval with color change to brown (10YR-4/3) - sandy
								3.0	GC	4.5 - 7.5 - Silty clay - some brownish sand & gravel - color yellowish (10YR-6/10) with dark yellowish brown (10YR-4/2) from 4.5' - 5.0'. Changing to dark gray (10YR-3/1) (10YR-4/2) to 6.3' from 6.3' - 7.5' Pred. very dark brown (10YR-3/1) with very pale brown (10YR-7/2) and some green clay - some damp Est med plasticity.
								4.0		7.5 - 8.5 - No Rec
								5.0		8.5 - 9.5 - Silty clay - some gravel. Gravel abundant in top half of interval (possibly slopesh) Color grad. olive gray (5Y-5/2) with some friabilizing (yellowish - 10YR-7/6)
								6.0	CL	Est med imp plasticity. Friable if damp
								7.0		9.8' - 12.2' Silty clay - some sd & gravel - clay pred. Dark grayish brown (10YR-4/2) - Roots throughout interval - Core sl. damp - friable - Est Med-Low plasticity. Gravel to + 1" - friable, sandy.
								8.0		12.2' - 12.5 - No Recovery
								9.0	CL	
10.0	CL									

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3Borehole Number: 20598

Surface Elevation: _____

Location - North: _____ East: _____

Area: NORTH - PADate: 7-13-98Total Depth: 20.5'Geologist: R. KOEHLER FC. F. G. 1988Company: TERRA Project No.: _____Drilling Equip.: GEOPAGE / MACROCORESample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOPOGRAPHY OF CORE HOLE	TOPOGRAPHY OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRACTURE ATAKE	BEDDING ATAKE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
	Run No. 3 12.5' - 12.5'	Run No. 3 12.5' - 12.5'					CL	10.0		12.5' - 14.3' - Clayey Gravel - Some silt & sd. - Gray (10YR-5/1) In upper half "for inches to olive gray (5Y. 5/2) in lower half of interval.
	Run No. 4 12.5' - 12.5'	Run No. 4 12.5' - 12.5'					CL	11.0		Red sandy zone in approx. middle of interval - Can dry to sl. damp - est med. plasticity, + 14.5' - 14.5' - Top of Caliche
	Run No. 5 16.5' - 30.5'	Run No. 5 16.5' - 30.5'					CL	12.0		Clay stone. Trace of calcareous scales. Color light olive brown (2.5Y - 5/3) to grayish brown (2.5Y - 5/2). Well defined contact with alluvium (based on grade at contact) core very slightly damp - moderately indurated. Few fractures but some fine stained zones (darker brownish yellow - 10YR-4/3 to yellowish brown 5/6). Core possibly reworked in upper portion of interval - becomes blocky (massive) with depth.
								13.0		X-16.2' - 16.5' No Recovery
								14.0		
								15.0		
								16.0		
								17.0		
								18.0		
								19.0		
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 3 OF 3

Surface Elevation: _____
Area: North PA Plume
Total Depth: 20.5'
Company: Terra Project No.: _____
Sample Type: Continuous Core

APPROVAL

DATE _____

[illegible]

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 20698
 Location - North: _____ East: _____
 Date: 07-14-88
 Geologist: R. KOEHLER R. E. Grigg
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 240
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

FORMATION OF CORE HOLE	TOP/BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRAC/TYPE ANGLE	REMARKS ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
								0.0		0.0 - 0.5' Asphalt
								0.5		0.5 - 1.2' Base Material - Gravel and clay
								1.0		1.2 - 1.9' sandy clay - some Gravel - Grayish Brown (5YR-3.5) Mat at top of core - some asphalt material with material Est. Medium plasticity - Dry
								2.0		
								3.0		1.9 - 3.9' Gravel - some sand - matrix Brownish Black (5YR-2) to Grayish Brown (5YR-3.5) Estimated Medium plasticity - Core Dry - Gravel well rounded, max. size 1/2" to 3/4" diam.
								4.0		3.9 - 4.5' sandy clay - 7% gravel - moderate yellowish brown (10YR-5.5) with some tan-yellowish gray (10YR-6.5) - Coarse - Est. Med. plasticity
								5.0		
								6.0		4.5 - 7.7' sandy clay - 10 material of gravel - some as sandy clay - 3.9 - 4.5'
								7.0		7.7 - 8.0' clay, gravel some broken cobbles - 2% matrix moderate yellowish brown (10YR-5.5) core dry - Est. Med. plasticity
								8.0		8.0 - 8.7' sand clay - some as 7.7 - 8.0'
								9.0		8.7 - 8.8' sandy clay - some gravel - with 0.15' cobble zone at top of interval. Matrix of gravel Colors moderate yellowish brown (10YR-5.5) and tan yellowish brown (10YR-6.5)
								10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 20672
 Location - North: _____ East: _____
 Date: 07-14-88
 Geologist: R. KOEHLER F. Grash
 Drilling Equip.: GEOPHOS / MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 24.0'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP-BOTTOM OF CORE IN BOX	TOP-BOTTOM OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENTS)	SAMPLE NUMBER	FINAL-TIME ANGLE	BLINDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
Box 2 of 3 10.4 - 22.2'	Run 16.3 8.5' - 12.5'	Recovery 2.8'					CL	10.0		6.7 - 9.9 - Coarse sand - Est. med. plasticity - some continuous material, 9.8' - 10.8' silty (cl) - some sand - gl. damp - sh. phable - pale yellowish brown (10yr. 4/2) with some dark yellowish orange (10yr. 4/6) streaks & mottling. Est. poorly med. plasticity.
	Run 16.4 12.5' - 18.5'	Recovery 2.9'					CL	11.0		10.8' - 11.4' - Gravelly clay - matrix pale yellowish brown (10yr. 4/2) with dark yellowish orange (10yr. 4/6) streaks & spots. Est. low to med. plasticity, sh. damp.
	Run 16.5 18.5' - 20.5'	Recovery 3.3'					GC	12.0		11.4' - 12.5' - No Recovery
							GC	13.0		12.5' - 13.1' - Gravelly clay - some ac. H ₂ O 10.8' - 11.4'
							GC	14.0		13.1' - 13.9' - clay - Tr. sh. - silty & gran. Pale - yellowish green (10yr. 4/2) with dark yellowish orange (10yr. 4/6) streaks & spots. sh. damp - sh. phable - Est. med. plasticity.
							GC	15.0		13.9' - 15.2' - Gravelly clay - clayey gravel - matrix dark yellowish brown (10yr. 4/6) - gravel well graded, Fred quartzite - Est. med. plasticity (matrix).
							GC	16.0		15.2' - 16.5' - No Recovery
							GC	17.0		16.5' - 19.2' - clayey gravel - some 19.2' - 19.9' - 15.2' except very sandy at top of interval
							GC	18.0		
							GC	19.0		
							GC	20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3Borehole Number: 20698

Surface Elevation: _____

Location - North: _____ East: _____

Area: NORTH-PADate: 07-14-98Total Depth: 240'Geologist: R. KOCHLER J.F. GrassbyCompany: TIERRA Project No.: _____Drilling Equip.: GEOPROBE/MACROCORESample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

DEPTH OF CORE HOLE	FORMATION	REMARKS	LOGGING SUPERVISOR	DATE	SAMPLE DESCRIPTION
19.8'					No Recovery
19.8' - 20.4'					FG 19.8' - 20.4'
20.4' - 20.5'					Clayey Gravel
20.5' - 20.6'					(Same as 13.9' - 15.2') recovered
20.6' - 20.7'					as slough and as possible lost
20.7' - 20.8'					Core from 19.8' - 20.6' Measuring
20.8' - 20.9'					from bottom of core the top of
20.9' - 21.0'					bedrock should be at approx.
21.0' - 21.1'					20.4' then top of the
21.1' - 21.2'					lost core was recovered
21.2' - 21.3'					
21.3' - 21.4'					
21.4' - 21.5'					
21.5' - 21.6'					
21.6' - 21.7'					
21.7' - 21.8'					
21.8' - 21.9'					
21.9' - 22.0'					
22.0' - 22.1'					
22.1' - 22.2'					
22.2' - 22.3'					
22.3' - 22.4'					
22.4' - 22.5'					
22.5' - 22.6'					
22.6' - 22.7'					
22.7' - 22.8'					
22.8' - 22.9'					
22.9' - 23.0'					
23.0' - 23.1'					
23.1' - 23.2'					
23.2' - 23.3'					
23.3' - 23.4'					
23.4' - 23.5'					
23.5' - 23.6'					
23.6' - 23.7'					
23.7' - 23.8'					
23.8' - 23.9'					
23.9' - 24.0'					

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

1) Badly broken core, accurate footage measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 20798
 Location - North: _____ East: _____
 Date: 7/15/90
 Geologist: DR. KOEHLER J. BOYLAN
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 29'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

LOGGING SUPERVISOR

APPROVAL Fred [Signature]DATE 9-7-99

LOCATION OF CORE IN BOX	TOP OF CORE OR INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUCTUATE ABOVE	BEDDING ABOVE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH (FEET)	SOIL / LITHOLOGIC LOG	SAMPLE DESCRIPTION
	0.0	0.0						0.0		NO RECOVERY 0.0-1.2' Asphalt, Fill - asphalt is 0.0-0.5', Fill 0.5-1.2', then geomembrane at top. Excavated for manhole installation, so no core recovered.
	1.2	1.2						1.2		Mixed asphalt & fill - predominantly black. Geomembrane at top. Slightly moist. Some fine gravel component. Grades to organic- rich clay at base.
	2.0	2.0						2.0		
	2.3	2.3						2.3		Clay with silt and traces sand and gravel - mottled colors, generally lightening below 3.0'. Above this, predominantly dusty brown to dusty yellowish brown (5YR to 10YR 2/2); below, predominantly moderate to dark yellowish brown (10YR 5/4 to 4/2). Sl. moist. Gravelly at 3.5-3.9', less so 3.9-4.5'. Gravels mainly quartzite, 70.5%.
	5.2	5.2						5.0		NO RECOVERY 5.0-5.2'
	5.2	5.2						5.2		Same as above, 2.3-5.2' w/coloration similar to that below 3.0'. As with above material, colors are mottled, including reds, olive grays, browns, but predominantly as stated above. Sl. moist. Breakage pattern more chippy below 7.0'.
	7.6	7.6						7.6		NO RECOVERY, 7.6-8.0'
	8.0	8.0						8.0		Same as above, 5.2-7.6; predominant color now ~ moderate yellowish brown (6YR 5/4). Sl. moist. Occasional zones of imported bedrock (reworked bedrock, some of which are siltstone to very fine grained sandstone. (See especially 8.0-8.1 (1.2').) Trace scattered gravels, mainly quartzite.
	11.3	11.3						10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 2 CF 3

Surface Elevation: _____
Area: NORTH - PA
Total Depth: 29'
Company: TERRA Project No.: _____
Sample Type: PUSH / CONTINUOUS CORE

APPROVAL Frank Longobardi

DATE 9-7-99

TOP OF CORE IN BOX	TOP BOTTOM OF INITIAL FEET OF CORE IN RUN FIELD MEASUREMENT	SAMPLE NUMBER	FUNCTIONAL NAME	DEPOSIT NAME	GRAVEL SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SONG/ CORRELATION LOG	SAMPLE DESCRIPTION
Box 2 of 3 : 10.1 - 19.0'	Run 4 cont'd see previous page						CL	10.0	see previous page
	11.3 11.3							11.0	
	11.3 11.3							11.3	Same as above, 8.0-11.3'. Chippy breaking pattern. Single gravel clast ($\frac{1}{2}$ " @ base of run, in place (broken by crew); small ($\frac{1}{2}$ " sandy (med-fine gr.) pocket @ 13.0-13.1' contains whitish-pinkish grains (Kspar?). Occasional carbonaceous fragments, some w/woody appearance. Very similar in appearance, overall, to bedrock claystone - except for clastics and alluvial clay zone @ 11.5'.
	Run 5: 3.5 incl. 0.3' slough							12.0	
	11.3 14.3							13.0	
	14.3 14.3							14.3	
	14.3 14.3							14.3	Same as above 11.3-14.3. color changes below 14.7 to dark yellowish brown, 10YR 4/2.
	Run 6: 2.3' incl. 0.2' slough							15.0	Gravel lens @ 15.0-15.3'; 15.7'; below 15.7' lens, traces gravel in clay. Slightly moist; moist to wet @ 15.7'; but no free water - just squishy clay. Gravels to > 1"
	14.3 16.3							16.0	
	16.3 16.3							16.3	Same as above, 14.3-16.3, w/gravel lenses @ 16.7-17.0', 17.2-17.4'. Saturated. Gravels to > 1". Traces roots @ bottom of recovery.
	Run 7: 1.5' incl. 0.3' slough							17.0	
	16.3 19.0							17.5	
	19.0 19.0							18.0	NO RECOVERY
	19.0 19.0							19.0	(19.0) 17.5-19.0'
Box 3 of 3	Run 8: 1.2' incl. 0.5' slough							19.7	Clayey gravel to gravelly clay - Same as above, 16.3-17.5, but more gravel. Saturated, gropy. Fresh Kspar clast @ base of recovery. Dark yellowish brown (10YR 4/2).
	19.0 23.0							20.0	NO RECOVERY 19.7-23.0'

2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3Borehole Number: 20798

Surface Elevation: _____

Location - North: _____ East: _____

Area: NORTH-PADate: 7/15/98 - 8/07/98Total Depth: 29'Geologist: R. KOEHLER J. Baylan & F. GrigsbyCompany: TIERRA

Project No.: _____


Drilling Equip.: GEOPROBE/MACROCORESample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

SAMPLE DESCRIPTION



NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

1) Badly broken core, accurate footage measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible.

457 450

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 20898
 Location - North: _____ East: _____
 Date: 07-16-98
 Geologist: R. KOEHLER W. F. Grigsby
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 16.0'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/LOCATION OF CORE HOLE	TOP/LOCATION OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	STRUCTURE ALIAS	DETERMINED ALIAS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGICAL LOG	SAMPLE DESCRIPTION
								0.0		0.0' - 0.6' - Gravelly sand - same silt - Mixed with some Asphalt - Dominant color Brownish Black (SYR-4) because of Asphalt.
								0.6	SM	
								1.0	SM	
								1.3		1.0' - 1.3' - Gravelly sand - Pink yellowish Brown (10YR-6/2) sand poorly graded - Fred 6 - Gravel - poorly graded Fred 1/4" - 1/2" - Fill Material - No Asphalt.
								2.0	C	
								3.0		1.3' - 2.3' Gravelly clay - Fred Dark yellowish Brown (10YR-4/2) sl. damp - Dense - Gravel content of dark red siltstone just up to 2" in length.
								4.0		2.3' - 4.0' - No Recovery
								5.0		4.0' - 5.6' - Clay - Tr. sd & Gravel - color Fred. Brownish gray (SYR-4) with some Dusty yellow (SY-4.4) streaks.
								6.0	CR	Percent Gravel zone from 7.8-8.0 7.8' - 8.0' Core dry - dense -
								7.0		8.0' - 9.1' Clayey Gravel with some sd. - tan <u>light</u> <u>tan</u> <u>EL</u> <u>Wet</u>
								8.0		
								9.0	GC	9.1' - 15.7' Gravelly Clay - Tr. sd. Brownish Gray (SYR-4) - Reworked Debris & clumps. Damp.
								10.0	CL	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 20898
 Location - North: _____ East: _____
 Date: 07-16-88
 Geologist: F. Grady
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: North PD
 Total Depth: 16.0
 Company: Tierra Project No.: _____
 Sample Type: Continuous Core

RMRS LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP-BOTTOM OF CORE IN BOX	TOP-BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FINAL TIME ANGLE	BLINDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGICAL LOG	SAMPLE DESCRIPTION
12.6 - 16.0	Run 16.0	Run 4.0						10		
	Run 16.3	Run 4.0						11		
								12		
								13		
								14		
								15		
								16		Top of bedrock - Claystone - Brownish Gray (SP - th) some darker yellow (SP - clay) (Fe O) streaks - some looking horizontal bedding - sl. domp.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

Page 27 of 28

45452

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 20998
 Location - North: _____ East: _____
 Date: 08-18-98
 Geologist: F. Griegsby
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: North PA Plume
 Total Depth: 11.0'
 Company: Terraviva Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP OF CORE INDEX	TOP OF CORE OR INTERVAL FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FRAC-TURE ALERT	RELATIVE ALERT	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH (FEET)	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
							0		0-1.3' Silty Clay - some gravel & sd. - top soil interval - some roots - Pale Yellowish Brown (OYR-4/2)
						CL	1		To Dark Yellowish Brown (OYR-4/2) some med. yellowish Brown (OYR-5/4) FeO staining - core dry - wh - friable.
							2		1.3-2.2' Silty Clay - Fr. gravel - Fill - same as above except composed of some claystone fragments. More abundant FeO staining. less gravel
						CL	3		some roots 2.2-4.0' No Rec.
							4		4.0-4.8' clay - some silt, Fr. Gravel sd. Grayish Brown, top (OYR-3/2) very sl. damp - dense to moderate, wh. - 4.8-6.4' Clay - some silt.
						CL	5		Color change to Yellowish Brown (OYR-5/4) - core sl. damp - friable
						CL	6		6.4-8.0' Clay - some gravel - clay similar to above with gravel intervals. and some zones of dark yellowish orange (OYR-6/6) med. heavy FeO staining - core sl. damp - friable.
						CL	7		8.0-9.3' Clay - same as 4.8-6.4
							8		9.3-10.0' Clay - light olive gray (5Y-6/1) with moderate yellowish Brown (OYR-5/4) Intermixed fragments - clay & claystone fragments - core cohesive - very sl. damp.
						CL	9		Predominantly Brownish Gray (5YR-4/4) becomes more compact - FG.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 2098
 Location - North: _____ East: _____
 Date: 08-18-98
 Geologist: F. Grigsby
 Drilling Equip.: Geo probe

Surface Elevation: _____
 Area: North FA Plume
 Total Depth: 11-0'
 Company: TerraTemp Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUORESCENCE ANALYSIS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
6-1/2 282	8-0-10 8-0-10	2-6'					10		10.0 - 10.6 - TOP of 15' core - Transitioned - probably reworked - Predominately Brownish Gray (SYR-4)
							11		Becomes more competent at bottom of interval. some consolidated structure
							12		10.6 - 11.0 - No Recovery
							13		Measured Depth = 10.9'
							14		Top of bed rock should be adjusted to 10.3'
							15		
							16		
							17		
							18		
							19		
							20		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

457454

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 21098
 Location - North: _____ East: _____
 Date: 07-20-98
 Geologist: R. KOEHLER F.G.F. Griggs
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 20.0'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

LOCATION OF CORE INDEX	TOPOGRAPHY OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUCTUATION ANGLE	BLEEDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL / LITHOLOGICAL LOGS	SAMPLE DESCRIPTION
								0.0		2.0 - 3.3' - Gravelly clay - some sd. - color moderate yellowish brown (10YR. 5/4) with dark yellowish brown (10YR. 4/2) to 2.7' color changes to dark yellowish brown (10YR. 2/2) at that depth.
							GC	2.0		clayey zone at 1.6 to 2.0' and 2.7' to 3.3' sandy interval at 2.0 - 2.2' & gravel zone at 1.2 - 1.3'. Core dry - clay dense to indurated somewhat staining (dark yellowish orange, 10YR. 6/6) in upper half of interval.
								4.0		zone wx. - probably fill.
							CL			3.3 - 4.0' - No Recovery
							CL	5.0		4.0 - 4.8' - Gravelly clay - some sd. 2.7' to 3.3' above except more gravel. Color dusky yellowish brown (10YR. 4/2) - very dense, - dry -
							GM	6.0		4.8 - 6.0' sandy clay - moderate yellowish brown (5YR. 4/4) to moderate brown (5YR. 3/4) - core very sd. damp - sd. friable.
							CL	7.0		6.0' - 6.5' - sandy gravel - some clay matrix moderate brown (5YR. 4/2). sd. damp - friable.
							GM	8.0		6.5' - 7.4' - sandy clay - moderate brown (5YR. 4/4) - very sd. damp - med. friable.
							CL	9.0		7.4' - 8.0' Gravelly sand - some clay
							GC	10.0		8.0' - 10.0' (5Y. 6/2) to moderate

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 2 OF 2

Surface Elevation: _____

Area: NORTH-PA

Total Depth: 20.0'

Company: TERRA Project No.:

Sample Type: PUSH / CONTINUOUS CORE

DATE _____

DATE _____

LOCATION OF CORE HOLE	FORMATION OF INTERVAL	FEET OF CORE UNRECOVERED (FIELD RECOVERY)	SAMPLE NUMBER	FLUID TYPE AND PRESSURE	BLENDING RATIO	GRAIN SIZE DISTRIBUTION	LOG SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG
Box 3 of 3 9.6' - 18.2'	Run No. 2 11.0' - 14.0'	Rec'd 3.5'						10.0	7.4-9.0 continued Brown (SYR. 4/4) abundant FeO staining. - Core well ex. - (very sl. damp. Mod. friable to friable - sandy clay.
								11.0	9.0-9.5 sandy clay - Dark yellowish brown (10YR. 4/2) with some moderate yellowish brown (10YR. 5/4) streaks & flecks - some orange flecks - This may be slough.
								12.0	9.5-10.6' Gravelly Clay - Some to abundant sand. Moderate yellowish brown (10YR. 5/4) & pale yellowish brown (10YR. 6/4) abundant FeO staining light brown (5YR. 5/6) - core very friable to mod. friable - depending on sand content. Very sl. damp. - wx.
	Run No. 3 14.0' - 17.0'	Rec'd 2.8'						13.0	10.6'-12.0' NO Recovery
								14.0	12.0'-12.6' Gravelly Clay - same as 9.5'-10.6'.
								15.0	12.6'-16.4' - Gravelly sand - Red. Light Brown (SYR. 5/6) - Damp - sand well graded - Int. Wx - oxidized.
Box 3 of 3 18.2' - 20.0'	Run No. 6 17.0' - 20.0'	Rec'd 3.0'						16.0	16.4-18.2' Clayey sd. - Tr. gravel. Sl. well graded. Dark yellowish orange (10YR. 6/6) to light brown (5YR. 5/6) - sl. damp.
								17.0	18.2-20.0' Top of bedrock - soft claystone - heavily oxidized into 2nd core (FeO - dark yellowish brown 10YR. 6/6) - Rest is pale yellowish brown (10YR. 6/6) smeared with
								18.0	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight. *(badly distorted core) Bottom 4 ft*

- 1) Badly broken core, accurate footage measurements not possible. *interior consist of claystone*
- 2) Core breaks cannot be matched, accurate footage measurements not possible. *cracks - indurated & brecciated*

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 21198
 Location - North: _____ East: _____
 Date: 7/21/98
 Geologist: R. KOEHLER J. Boylan
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 29.5'
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Paul D. HigleyDATE 9-7-99

TOP OF CORE BLOCK	TOP OF CORE OR INTERVAL	FEET OF CORE INITIAL MEASUREMENT	SAMPLE NUMBER	FLUCTUATION ANAL	BEDDING ANAL	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
0.0	0.0	0.0					SM	0.0		
	RUN						SC	0.0		
	1:	2.8						1.0		
	00-							2.0		
	4.0							3.0		
								4.0		
								5.0		
								6.0		
								7.0		
								8.0		
								9.0		
								10.0		
								11.0		
								12.0		
								13.0		
								14.0		
								15.0		
								16.0		
								17.0		
								18.0		
								19.0		
								20.0		
								21.0		
								22.0		
								23.0		
								24.0		
								25.0		
								26.0		
								27.0		
								28.0		
								29.0		
								30.0		

Box 1 of 9

4.0 4.0
 4.0 4.0
 RUN
 2:
 4.0- 4.0
 8.0 0.4'
 slough
 overpacked
 so despite
 the math
 recovery
 probably
 ~100%
 3.0 3.0
 3.0 3.0
 RUN
 3:
 8.0- 4.0'
 11.0 incl.
 0.8'
 slough

silty sand to sand-clay mixture 4% silt - dark brown (10YR 4/3, 5/3) to dark yellowish brown (10YR 4/4). Dry to sl. moist. Natural horizontal partings (may relate to frequency of hammer blows) Rooted in top 0.5'. Scattered trace gravel, typically fine grained, 1/4 gravel lens (1/4 gravels to >1") at 1.3-1.4'. Dark splotches (black; organic debris?) w/ Fe-oxide pockets common @ 2.3-2.8'. Finer (more SC than SM) below 2.8'.

NO RECOVERY
 2.8 - 4.0

Same as above but lacking the coarse silty sand material. Gradual bottom contact. Dark yellowish brown (10YR 2/4) to sil. brown (10YR 4/3). Sl. moist. Fe-oxide stained areas, stringers common. Silty clay mixture depth.

Silty clay - dark brown (10YR 4/3). Sl. moist to moist. Trace v.f.g. sand. Rare gravel clasts typically < 1/2" diam. Occasional black carbonaceous flecks & pockets of Fe-staining.

NO RECOVERY (Note: below 4.0' line was overpacked and incl. some slough material recovery might have been 100%)
 7.6 - 8.0

Same as above, 5.5-7.6'. Moist.

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 21198
 Location - North: _____ East: _____
 Date: 7/21/98
 Geologist: MR. KOEHLER J. BOYLAN
 Drilling Equip.: GEOPAGE / MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 29.5'
 Company: TERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Paul DrigbyDATE 9-7-99

TOP OF CORE IN BOX	TOP OF CORE	FEET OF CORE IN INTERVAL FIELD	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC TEXT
↑ 9.8	see previous page		CL	10.0	Same as above, 5.5-7.6'
	11.0	11.0		11.0	
	11.0	11.0		11.0	
Box 2 of 4 : 9.8' - 17.0'	Run	4: 40		12.0	Same as above, 5.5-7.6'. Moist, increased gravel content - still trace, but coarser (to >1" diam.) not as rare.
	11.0	ind.		13.0	
	14.0	08 slough		14.0	
	14.3	14.3		15.0	
	14.3	14.3		15.0	
	Run	5: 40		16.0	Same as above, 10.0-14.0'. Below 15.3', increased sand, gravel, with color change to strong brown (7.5YR 4/6). Almost to SC, but clay still dominates. Transitional to SC below ~16.2', and some pockets to GC.
	17.0	3.9' ind.		17.0	
	17.0	1.0' slough		18.0	
	17.0	17.0		19.0	
	17.0	17.0		20.0	
	17.0	17.0		21.0	
	17.0	17.0		22.0	
	17.0	17.0		23.0	
	17.0	17.0		24.0	
	17.0	17.0		25.0	
	17.0	17.0		26.0	
	17.0	17.0		27.0	
	17.0	17.0		28.0	
	17.0	17.0		29.0	
	17.0	17.0		30.0	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3

Borehole Number: 21199

Surface Elevation: _____

Location - North: _____ East: _____

Area: NORTH - PA

Date: 7/21/98

Total Depth: 29.5'

Geologist R. KOEHLER - J. BOYLAN / F. Griggsby

Company: TIERRA Project No.: _____

Drilling Equip.: GEOPROBE / MACROCORE

Sample Type: PUSH/CONTINUOUS

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

DEPTH OF CORE FEET	TOP OF CORE FEET	RELATIVE ELEVATION OF CORE FEET	FIELD MEASUREMENTS	SAMPLE NUMBER	FLUID SAMPLE	BLENDING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGY LOG	SAMPLE DESCRIPTION
17.0	20.0	20.0	RUN 7: 4.0 incl. 1.0 slough				SC	20.0			Same as above, 17.0-20.0'. Similar mottling, clay pockets, gravel contents, w/ some zones to CL, some to GC - but overall, SC.
20.0-23.0	23.0	23.0					CL	23.0			23.0-23.7' - Grovelly Clay - some to abundant sand. light gray (5YR-7). some silty brown (7.5YR-5 $\frac{1}{2}$) sandy intervals - core friable - wet - wx.
23.0-25.0	25.0	25.0					GC	25.0			23.7'-25.0' - No Recovery 25.0'-25.6' - Clayey gravel-sand to abundant sand - pink FL. Light olive gray (5Y-4) with some light brownish gray (5YR 4) mottling - Core wet - clay sticky & friable - Core becomes more sandy & friable with depth - Int. wx. Some inter-med clay stn. frag. 25.6-28.0 - No Recovery *
25.0-29.5	29.5	29.5					TD	29.0			28.0-28.6' - Claystone - Top of bedrock - Dark yellowish brown (6.5YR 4 $\frac{1}{2}$) with moderate yellowish brown (6.5YR 5 $\frac{1}{2}$) - Core sl. damp-sloughy Above is Wet, Core mod. indurated. Depth could be deeper - hole open to TD when setting well casing. 28.6-29.5' - NO Recovery

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(i) Badly broken core, accurate footage measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible.

* - Abundant wet sandy clay
slough above 28.0'

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: 21298
 Location - North: _____ East: _____
 Date: 08-19-98
 Geologist: P. Grady - Rigel Log
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: _____
 Total Depth: 20.5'
 Company: Terra Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP OF CORE IN BOX	POSITION OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUORESCENCE ATRIAL	BLINDERS ATRIAL	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
								0		0-1.1' - No sample - Fill dug out for flash mount
								1		
							CL	2		1.1-3.9' - Gravelly clay - some silty - pred. mod. yellowish brown (10YR-5/4) Core - off w _x - dry - dense - Horizontal induced fractures. Some FeO staining.
								3		
								4		3.9-4.0' - probably recovered in run No. 2
								5		4.0-7.0' - sandy clay - some silt - moderate brown (5YR-4) core slightly damp - friable - sand varies to very sandy to mod. sandy - becomes clayey in lower 0.2' of interval.
							CL	6		
								7		7.0-8.0' - sandy Gravel - some clay - color pred. light brown (5YR-6) core sl. damp, friable - Gravel to broken cobbles to small (well graded) - Quartzite & granite fragments.
							GM	8		
								9		8.0-11.0' - same as 7.0-8.0' - sandy Gravel
							GM	10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: 21298
 Location - North: _____ East: _____
 Date: 08-18-98
 Geologist: F. Grigsby - Rig & Log
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: _____
 Total Depth: 20.5
 Company: Tierra Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	FLUIDS/ARISE	DETERMINED ARISE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOG LOG	SAMPLE DESCRIPTION
Box 2 of 3 9.4' - 17.0'	Run 13.3						GM	10		
	Run 13.4	11.0' - 14.0'					CL	11		11.0' - 13.1' - Sandy clay - some gravel - Moderate brown (5YR-4.5) in sandier intervals. Moderate yellowish brown (10YR-5.5) in clayey intervals. - (12.4' - 13.1') - core damp - friable to sticky & phable. - some scattered large gravel.
		Rec. 4.0' (5' length in hole)						12		
							SC	13		13.1' - 14.0' - Clayey sand - some gravel - Moderate brown (5YR-4.5) damp - friable to phable -
							SC	14		14.0' - 14.4' - Clayey sd. - same as 13.1' - 14.0' - wet
								15		14.4' - 16.6' - sandy gravel - light brown (5YR-6.5) to light brown (5YR-6.5) - Large grain throughout heavily oxidized zone - yellowish red (5YR-7.5) in lower 2' of interval. - core saturated.
							GM	16		16.6' - 17.0' - coarse sd. - some clay - light brown (5YR-6.5) to light brown (5YR-6.5)
							CL	17		16.6' - 18.1' - sandy clay - some gravel - damp phable - pale yellowish brown (10YR-6.5) -
								18		18.1' - 19.2' - Clayey sd. - to gravel - Lt brown (5YR-6.5) - wet - sd. well graded - fine to coarse - str. & beds, red (red)
							SC	19		TOP OF BEDROCK
Box 3 of 3 17.0' - 20.5'	Run 16.6	17.0' - 20.0'						20		19.2' - 21.0' - Claystone - pale yellowish brown (10YR-6.5) - some grayish orange (10YR-7.5) - staining - abundant nodules
	Rec. 3.3'									

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 21398
 Location - North: _____ East: _____
 Date: 08-25-98
 Geologist: F. Griggsby, R.G. & Log
 Drilling Equip.: Geo Probe

Surface Elevation: _____
 Area: N. FA PLUME
 Total Depth: 16.0'
 Company: Tierra Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP OF CORE IN BOX	TOP OF CORE INTERVAL FEET OF CORE IN INTERVAL (FIELD MEASUREMENTS)	SAMPLE NUMBER	FRACTURE ANALYSIS	BEARING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION	
Box 1 of 2 0.0' - 9.9'	Run No. 1 0.0' - 4.0' Re. 2.3'					ML	0		0.0' - 0.2' - clayey silt - Top soil/ Dark yellowish Brown (10YR-4h) Dry - friable - roots & grass.	
						GC	1		0.2' - 2.3' sandy Gravel - some clay - Pinkish Gray (5YR-8h) with spotty Dark yellowish Brown (10YR-4h) and Dark yellowish orange (10YR-4h) sediments - Gravel	
							2		Fine, large - some broken cobbles Fine quartzite - core dry - friable.	
							3		2.3' - 4.0' - No Recovery	
								4		4.0' - 4.5' - sandy Gravel - same as 0.2' - 2.3' Abrupt color change to moderate Brown (5YR-4h) at
						GC	5		4.3' to 4.5' with some intermixed yellowish gray (5Y-7h) clay streaks. Very strongly oxidized layer of moderate reddish Brown (5YR-6h) (10YR-4h) at contact with underlying sediments.	
						CI	6		4.5' - 8.0' clay - some Gravel & silt Tr. sd. brownish black (5YR-4h) large gravel spread throughout interval. Numerous roots at top of interval with some throughout entire interval - (old soil) horizon covered with fill) Estimated med. plasticity - Dry & dense.	
							7			
							8			
							CI	9		8.0' - 10.3' - Sandy Clay - some gravel - Dark yellowish Brown (10YR-4h) to approx 9.3' - color change to moderate yellowish Brown (10YR-5h) to 9.9' - 10.3' SS/cl at 9.9' - 10.3' - core med. friable - Very st. damp -

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 2 OF 2

Surface Elevation: _____
Area: _____
Total Depth: 16.0'
Company: Tierra Project No.: _____
Sample Type: Continuous Core

APPROVAL

DATE _____

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: 21498
 Location - North: _____ East: _____
 Date: 8-20-98 / 8-24-98
 Geologist: T. LUTHERER, F. Grogby
 Drilling Equip.: GEO PROBE

Surface Elevation: _____
 Area: P.A.
 Total Depth: 15.0'
 Company: TIERRA Project No.: _____
 Sample Type: CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	THICKNESS ALIAS	REMARKS ALIAS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGICAL LOG	SAMPLE DESCRIPTION
	RUN 1 0-1.0	REC 1.0						0		0-1.0 Clayey Silty Sand, Mod. Brown to Pale Yellowish Brown (5YR 3/4 to 10YR 6/2) grad very fine to fine, trace gravel, trace roots, locally very silty, locally damp.
	RUN 2 1.0-5.0	REC 4.0						1		Sandy Silty Clay Mod. Brown (5YR 4/4) Sand A/A, trace broken lithic gravel, damp, locally moist.
								2		Sand, Mod. Brown (5YR 4/4) grad fine to med. some coarse, some to med. clay, silty P/A, moist.
								3		Clay Mod. Brown (5YR 4/4) with traces sand - broken lithic gravel A/A damp.
								4		
								5		5.0' - 9.0' - Gravelly Clay - some sd. Dark yellowish brown (10YR 4/2) grading to moderate yellowish brown (10YR 5/2) at top foot of interval. Some speckly grayish drab (10YR 7/4) red stain. clay st. damp - very sticky - st. med plasticity. some interbedded clay lenses.
								6		
								7		
								8		
								9		9.0' - 9.9' - Gravelly Clay moderate yellowish brown (10YR 5/2) at top of interval - medium gray (NS) at bottom of interval.
								10		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 21498
 Location - North: _____ East: _____
 Date: 08-24-98
 Geologist: E. Griggs
 Drilling Equip.: Geoprobe

Surface Elevation: _____
 Area: N. P.D. Plume
 Total Depth: 15.0'
 Company: Tier 1 Project No.: _____
 Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP OF CORE IN BOX	TOP OF CORE INTERVAL	FEET OF CORE INTERVAL RECOVERED	SAMPLE NUMBER	FRAC. TYPE AIR	BLINDERS AIR	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL INTERVAL LOG	SAMPLE DESCRIPTION
9.0' - 9.9'	9.0' - 9.9'	9.0' - 9.9'						10		9.0 - 9.9' - Cont. Clay changes from sticky to mod. indurated. - large gravel lost at contact of bed rock.
9.9' - 13.0'	9.9' - 13.0'	9.9' - 13.0'						11		9.9' - 13.0' - TOP of Bedrock - Claystone - mottled appearance - Color intermediate moderate yellowish brown (10YR 5/4) and pale yellowish brown (10YR 6/2). Core appears very reworked - some carbonaceous material, some MnO ₂ , and abundant root staining. - Core mod indurated
13.0' - 15.0'	13.0' - 15.0'	13.0' - 15.0'						12		13.0 - 15.0' - Claystone mod. yellowish brown (10YR 5/4) at top of interval - grading to red - pale yellowish brown (10YR 6/4) 10 lower 2/3 of interval. TOP of From 13.2' - 13.4' well oxidized interval (dark yellowish orange - 10YR 6/6 with mottling modules - possibly some fractures. - Core showed drilling of indurated fractures when removed from tube. Accounts for excess recovery in interval below Splogh - Core dry, mod. indurated. Measured TD: 15.0'
								13		
								14		
								15		
								16		
								17		
								18		
								19		
								20		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

PAGE 2 OF 2

Surface Elevation: _____
Area: N. PA. PLUME
Total Depth: 15.0'
Company: TIERRA Project No.: _____
Sample Type: CONTINUOUS COR

APPROVAL

二六三

UNIT	THICKNESS	DESCRIPTION	REMARKS
0	0.0 - 0.5	Gravelly clay, some sd. and silt, Pale yellowish brown (10YR. 6/2) grading to moderate brown (5YR. 7/4) - Gravel med. size quartz. Color very sl. damp. Mod. friable - Wx.	Run No. 1 0.0 - 0.5
1	0.5 - 2.9	Silty clay - some sd. - Grayish brown (5YR. 3/2) at top - Dark yellowish brown at bottom (10YR. 4/2) - Mod. friable very sl. damp - Wx.	Run No. 2 0.5 - 2.9
2	2.9 - 4.0	No test recovery	Run No. 3 2.9 - 4.0
3	4.0 - 4.5	Clay - some sd. & silt. Dark yellowish brown (10YR. 4/2) - Very sl. damp - friable	Run No. 4 4.0 - 4.5
4	4.5 - 6.6	Clayey Gravel - some sd. Dark yellowish brown (10YR. 4/2) grading to moderate yellowish brown (10YR. 5/4) very sl. damp, non friable - Wx. - Gravel from broken cobbles to small - some clayey zones	Run No. 5 4.5 - 6.6
5	6.6 - 7.0	Clayey sd. - Tr. gravel Brown (7.5YR. 5/4) - mod. friable - OX (Wx) very sl. damp	Run No. 6 6.6 - 7.0
6	7.0 - 11.7	Clay - Brownish Gray (5YR. 4/1) - composed of predominantly reworked bedrock clay sh fragments - very sl. damp - friable to st. clay - some gray carbonaceous material & some spotty FeO stained material. Diff. lit to determine accurate	Run No. 7 7.0 - 11.7
7	11.7 - 10.0		Run No. 8 11.7 - 10.0

NOTES: General: JSCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible

470
4/10/71

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: BH 21698
 Location - North: _____ East: _____
 Date: 08/27/99
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE/MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 20.0 ft
 Company: TIERRA Project No.: _____
 Sample Type: PUSH/CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Paul AngelyDATE 9-7-99

TOP/Bottom of Core Interval	TOP/Bottom of Interval	Interval	Feet of Core Recovered	Sample Number	Final Time	Ultimate Area	Gravel Size Distribution	USCS Symbol	Depth in Feet	Soil/ Lithology	Sample Description
Box 1 of 4 0.0 to 8.3 ft.											
		Run #1 0.0-3.5 ft.	Recovery 3.5 ft.						0.0		0.0-3.3 ft; clay/sand/gravel; yellowish brown (10YR 5/6) with occasional mottling, with light olive gray (5Y 6/2); subround to round gravel up to 2.5 cm, some pieces fractured by coring, quartzite in part; fine quartz sand; pinpoint patches of caliche; firm; slightly plastic; slightly moist.
									1.0		
									2.0		
									3.0		subangular to subround, poorly sorted, quartz and igneous rock frags, hard, dry, pulverized by coring.
									3.3		
		Run #2 3.5-3.8	Recovery 0.3					SC	3.5		3.3-3.5 Sand, pale vel (10R 6/4); medium to coarse
								SC	3.8		3.5-3.8 Sand as above 3.3-3.5
		Run #3 3.8-4.6	No Core Taken						4.0		Pre-probe with 1.5 inch solid point to get through hard zone.
								SC	4.6		4.1-5.0 Sand as above 3.3-3.5 ft.
		Run #4 4.6-7.0 ft.	Recovery 2.5 ft. (Hard, brown, 3.8-4.34)					SC	5.0		5.0-6.0 Clayey Sand; mottled pale vel (10R 6/4) to yellowish brown (10YR 5/6); medium to coarse grained quartz and igneous rock frags, qtz is rounded and frosted, clay content variable, clay parts plastic, gravel lag at bottom, moist.
								CL	6.0		6.0-7.0 Clay; mottled yellowish brown (10YR 5/6) to light gray (10YR 7/1), firm, plastic, slightly moist, possibly caliche patches, carbonaceous patches.
		Run #5 7.0-10.0 ft.	Recovery 4.0 ft including 1.0 ft of slough					CL	7.0		7.0-10.0 Clay as above 6.0-7.0 ft. More gray than brown. Occasional small rock chip (<0.5 cm) looks like it could be made of clay clasts. Root hairs to at least 8.3 ft. Still carbonaceous. Some FeO staining - Dark yellowish orange (10YR - 6/6)
									8.0		
									8.3		
									9.0		
									10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: BH21698
 Location - North: _____ East: _____
 Date: 8/27/99
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 20.0 ft
 Company: TERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Fred [Signature]DATE 9-7-99

TOP OF CORE IN BOX	TOP OF CORE INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE THICKNESS	FIXED TIME ANALYSIS	BLANKING ANALYSIS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOGICAL LOG	SAMPLE DESCRIPTION
Box 2 of 4 8.3-13.7 ft.	Run#6 8.0-12.0 ft.	Recovery 4.0 ft including 1.0 ft slough					CL	10.0		10.0-11.5 ft. Clay as above 6.0-7.0 and 7.0-10.0 More yellowish brown material (FeO) No Root Hairs LESS CARBONACEOUS
	Run#7 12.0-14.0 ft.	Recovery 4.0 ft.					SC	11.5		11.5-12.0 ft. Clayey sand, yellowish brown (10YR 5/8) to light olive gray (5Y 6/2), fine quartz sand, well sorted, firm, a piece of gravel (5 mm), calcite vein fill, moist
	Run#8 14.0-16.0 ft.	Recovery 4.0 ft.					SC	12.0		12.0-12.7 Clayey sand; as above 11.5-12.0 calcite(?) vein fill near bottom.
	Run#9 16.0-18.0 ft.	Recovery 4.0 ft.					CL	12.7		12.7-14.0 Clay; yellowish brown (10YR 5/8) to gray (2.5 Y N6), crumbly, firm, only slightly plastic, slightly moist, some conchoidal fractures root hair at 13.0 ft,
	Run#10 18.0-20.0 ft.	Recovery 4.0 ft.					CL	14.0		14.0-16.0 Clay; as above 12.7-14.0 ft More crumbly and fractured, almost dry, hard, not plastic.
							CL	15.0		14.9-15.1 fine sandy zone
										Bedrock contact approximately 13-15 ft.
							CL	16.0		16.0-18.0, Clay, as above 12.7-14.0 and 14.0-16.0
							CL	17.0		Even more crumbly and fractured, almost dry hard, not plastic.
										Mostly grayish brown (2.5 Y 5/2) some oxidation stains (16.0-17.0 ft)
							CL	18.0		18.0-20.0 ft. Clay, as above 16-18.0 ft.
								20.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

- (1) Badly broken core, accurate footage measurements not possible.
- (2) Core breaks cannot be matched, accurate footage measurements not possible.

* - Entire interval extensively
 reworked. NO definite Bedrock
 Pick F.H.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: BH21778
 Location - North: _____ East: _____
 Date: 08/31/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 26.0 ft.
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Fred GrigelyDATE 9-7-99

UNIT OF CORE RECOVERY	UNIT OF RECOVERY	FEET OF CORE IN INTERVAL MEASURED	SAMPLE NUMBER	FIGURE AREA	DEPTH IN FEET	SOIL TYPE LOG	SAMPLE DESCRIPTION
Not Saved					0.0		0.0 to 1.1 Excavated to install flash mount well casing. Material not saved
					1.1		Material dug out similar to material 1.1 to 3.1 ft.
					1.1		1.1 to 3.1 ft; Clay Sand Gravel, Clayey Gravel R.G. 9/7/99 some sd.
					2.0		
					3.0		
					3.1		No Recovery 3.1 to 5.0 ft dark brown (7.5 YR 4/4) quarter gravel max 2 cm, mostly fractured, angular well graded but poorly sorted, not plastic, bricky, med.
					4.0		
					5.0		Clayey Gravel
					5.0		5.0 to 3.0 ft. Clay, Sand Gravel as above 1.1 to 3.1 ft. sandy clay Compare more clayey intervals 7.0 to 7.2 and 7.5 to 7.8 ft. R.G. 9-7-99
					6.0		
					7.0		
					8.0		Clayey Gravel - some sd.
					8.0		8.0 to 10.0 ft; Clay Sand Gravel as above 1.1 to 3.1 ft R.G. 9-7-99
					9.0		
					10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: BH21798
 Location - North: _____ East: _____
 Date: 08/31/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 26.0 ft
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Freel ThigleyDATE 9-7-99

LOCATION OF CORE BOX	LOCATION OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASURED)	SAMPLE NUMBER	FLUORESCENCE	BEARING	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL / LITHOLOGICAL LOG	SAMPLE DESCRIPTION
1.0-11.8 RPK 4/31	Run #3 8.0-11.0 ft	Recovery 2.0 ft (No loss)					GC	10.0		10.0-11.0 ft No Recovery
Box 1 of 3	Run #4 11.0-14.0 ft	Recovery 1.4 ft					GC	11.0		Clayey Gravel - some sd 11.0-11.8 Clay Sand Gravel As above 11-13.1 ft FG 9/7/99
							GC	11.8		FG 9/7/99 Clayey Gravel - some sd.
							GC	12.0		11.8-12.4 Clay Gravel top 0.2 ft olive (SY 5/3, 1/5) black (SY 2 5/2), rounded gravel to 2.5 cm sand, well sorted, plastic, moist, fine.
							GC	12.4		abrupt color change / contrast, root hairs in black material
							GC	13.0		No Recovery 12.4 to 14.0 ft
Box 2 of 3	Run #5 14.0-17.0 ft	Recovery 4.0 ft					CL	14.0		Sandy Clay - some Gravel 14.0-17.0 Clay, Sand, Gravel as above 11.8-12.0 ft olive to dark olive (SY 4/2 to SY 3/2), rounded gray
							CL	15.0		gravel to 2 cm, quartzite, fine sand, well graded poorly sorted, soft, plastic, moist
							CL	16.0		Gravel mostly quartzite but also feldspathic igneous rock fragments, sand is similar. One light olive gray patch at 15 ft (SY 6/3)
							CL	17.0		FG 9/7/99 Sandy Clay - some Gravel
							CL	18.0		17.0-18.9 Clay, Sand, Gravel as above 14.0-17.0 Much less gravel. More sand than clay? moist, soft, plastic.
							CL	18.9		Log at bottom sandy clay str.
							CL	19.0		Top of Bedrock FG 9/7/99
							CL	20.0		18.9-20.0 Sandy Clay (light gray to SY N6) with patches and grains of olive yellow (2.5 SY 6/8), fine sand, soft, plastic, moist, limonitic nodules, caliche in pinpoints

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3

Borehole Number: BH21798
 Location - North: _____ East: _____
 Date: 08/31/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 26.0ft
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Frederick DringDATE 9-7-99

LOCATION OF CORE HOLE	LOCATION OF HOLE	RECOVERY FEET OF CORE INITIAL MEASUREMENT	SAMPLE NUMBER	FLUCTUATION ANGLE	REMARKS ANGLE	CLUSTER DISTANCE	USCS SYMBOL	DEPTH FEET	SOIL TEMPERATURE	SAMPLE DESCRIPTION
Box 3 of 3	Run #7 20.0-23.0 ft.	Recovery 3.7 ft including 0.8 ft of wet sample slough	OMIT	SC				20.0		20.0-21.7 Sandy clay as above 18.9-20.0 Less caliche (mostly near base of 21.1 to 21.2) Sandy zones in bottom 1 ft.
								21.0		
								21.7		
								22.0		21.7-22.7 Clay, Gray (7.5YR 4/6-4/5) with strong brown streaks (7.5YR 5/6-5/8), may be made of clay clasts, soft plastic to blocky, fracture, carbonaceous, moist.
								22.7		
Box 3 of 3	Run #8 23.0-26.0 ft.	Recovery 3.5 ft including 0.5 ft slough (may be more slough?)	OMIT	SC				23.0		23.0-24.0 Clay, olive brown (2.5Y 4/3) to gray (2.5Y 5/1), with strong brown stains & fractures (7.5YR 5/8), slight plastic fine sand, fractures with limonite staining, some sand along fractures? fractures horizontal, stiff-moist.
								24.0		
								25.0		
								26.0		
								26.0		
TD=26.0ft. Bedrock contact about 24.0ft. changed to 18.9' - 16										

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Easily broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Corehole Number: 21898
Location - North: _____ East: _____
Date: 9-8-98
Geologist: F. Grigsby, Rig & Log
Drilling Equip.: Geoprobe

Surface Elevation: _____
Area: N. PA. Rm
Total Depth: 22'
Company: TICOR Project No.: _____
Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____ DATE _____

[illegible]

NOTES: General: LSCS is modified for this loc as follows:

Materials amounts are estimated by % volume instead of % weight.

1*) Badly broken core, accurate footace measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 3 OF 3

Borehole Number: 21898
Location - North: _____ East: _____
Date: 9-8-98
Geologist: F. Grigby - R. G. 8206
Drilling Equip.: Geoprobe

Surface Elevation: _____
Area: N. DR. Plume
Total Depth: 32'
Company: Tierra Project No.: _____
Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____ DATE _____

TOP BOTTOM OF CORE HOLE	TOP BOTTOM OF HOLE	FLET OF CORE HOLE (FEET)	SAMPLE NUMBER	DIAMETER INCHES	DEPTH FEET	SOIL/ ROCK TYPE
8013-83	19.8'-22.0'	RUN No. 6	19.0'-22.0'	Rec. 4.0'	0.750' x 4"	
					20	18.3' - 22.0' Continued Very reworked. Did not reach undisturbed bedrock. - Core dry - Non friable to sl. friable. Some fine calcareous filled fractures.
					21	
					22	
					23	
					24	
					25	
					26	
					27	
					28	
					29	
					30	
					31	
					32	
					33	
					34	
					35	
					36	
					37	
					38	
					39	
					40	
					41	
					42	
					43	
					44	
					45	
					46	
					47	
					48	
					49	
					50	
					51	
					52	
					53	
					54	
					55	
					56	
					57	
					58	
					59	
					60	
					61	
					62	
					63	
					64	
					65	
					66	
					67	
					68	
					69	
					70	
					71	
					72	
					73	
					74	
					75	
					76	
					77	
					78	
					79	
					80	
					81	
					82	
					83	
					84	
					85	
					86	
					87	
					88	
					89	
					90	
					91	
					92	
					93	
					94	
					95	
					96	
					97	
					98	
					99	
					100	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(*) Badly broken core, accurate footage measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2

Borehole Number: BH 21998
 Location - North: _____ East: _____
 Date: 09/01/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH - PA
 Total Depth: 20.0
 Company: TIERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Fred ShipleyDATE 9-8-99

DEPTH OF CORE IN BOX	TOP/BOTTOM OF INTERVAL	FEET OF CORE INITIAL FIELD MEASUREMENT	SAMPLE NUMBER	FLUORESCENCE ANALYSIS	ULTRAVIOLET ANALYSIS	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGICAL LOGS	SAMPLE DESCRIPTION
								0.0		No Core 0.0-1.0, Dug away to make hole for flush mount-housing.
								1.0		No Recovery clayey Gravel - some sd
								1.0		1.0-3.7 Clay, sand, Gravel; yellowish brown (10YR 5/6), Subround to fractured gravel up to 3.5 cm, quartzites, fine to coarse sand; granular, not plastic, slightly moist.
								2.0		poorly sorted, well rounded.
								3.0		
								3.7		
								4.0		No Recovery 3.7-5.0 ft.
								5.0		clayey Gravel - some sd
								5.0		5.0-7.0 Clay, sand, Gravel; 2.0-3.7 ft.
								6.0		Becomes more moist and plastic towards bottom of interval. Grayish green (10G 4/6) clay (nodules?) at 6.5 ft.
								7.0		No Recovery 7.0-8.0 ft.
								8.0		8.0-9.1, clay, sand, Gravel; 5.0-8.0 moist, plastic
								9.0		9.0-9.1 Sand/Gravel lag (gravel < 1.0 cm) Plastic (SY 2.5/6)
								9.1		9.1-9.9 Clay with clay nodules; olive gray (5Y 4/2) with patches of yellowish brown (10YR 5/6), clay nodules, dark gray (10YR 4/1), < 5mm, plastic, moist, poorly sorted & graded
								9.9		No Recovery 9.9-11.0 ft.
								10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Borehole Number: 21998
 Location - North: _____ East: _____
 Date: 09/01/98
 Geologist: R. KOEHLER
 Drilling Equip.: GEOPHOS / MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 20.0 ft.
 Company: TERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Paul KingDATE 9-8-99

TOP/BOTTOM OF CORE INTERVAL	DEPTH OF CORE INTERVAL (FEET)	SAMPLE NUMBER	THICKNESS (INCHES)	DEPTH (FEET)	USCS SYMBOL	DEPTH (FEET)	SOIL / LITHOLOGICAL LOG	SAMPLE DESCRIPTION
Run #3 8.0-11.0 ft Recovery 1.9 ft.	10.0							No Recovery 9.9 ft to 11.0 ft
Run #4 11.0-14.0 ft Recovery 1.9 ft including 0.3 ft of wet clayey sand slush.	11.0							11.0-12.6 ft; Clay with nodules, occasional gravel with nodules, sand as marked; olive gray at top (SY 4/2) grades down to yellowish brown (10YR 5/3) brown 0.2 ft dark olive gray (SY 3/3) gravel rounded up to 3 cm, sand and gravel discovered from clay, plastic, soft, moist to wet.
	12.0							
	12.5							
	13.0							No recovery 12.6-14.0 ft.
	14.0							
Run #5 14.0-17.0 ft Recovery 2.6 ft including 0.9 ft of wet sandy slush.	14.0							14.0-14.6 Node CL, with gravel as above 11.0-12.6 ft. Wet sandy gravelly clay. 5G-9-5-99
	14.6							14.6-15.8; Clay, sandy, smooth, dark olive gray to black (SY 3/2) to (SY 2.5/2); rounded gravel (isn't a fragment - feldspathic) up to 3.5 cm, fine sand, soft, plastic, massive, wet. May be old soil, trace root hairs.
	15.3							
	16.0							15.3-17.0 ft No Recovery.
	17.0							17.0-18.5 ft, gravelly clay - some
Run #6 17.0-20.0 ft Recovery 3.3 ft including 0.8 ft of wet sandy slush.	17.0							17.0-18.5 ft, Clay, sandy, gravel as above, 14.6-15.8 11.5 olive brown (2.5Y 5/3) fractured gravel dominant in 18.5 to 19.5 interval - 2.5 to 3.0 cm (feldspathic) soft, plastic, moist to wet.
	18.0							18.5-19.5 - clayey No obvious root hairs 60% - some broken cobbles - some
	18.5							
	19.0							18.7-20.0 No Recovery RPK 9/1/98
	19.5							19.5-20.0 No Recovery
	20.0							

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

T.D. = 20.0 ft. Not in Bedrock

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 3

Borehole Number: B# 22098

Surface Elevation: _____

Location - North: _____ East: _____

Area: NORTH - PADate: 09/02/98

Total Depth: _____

Geologist: R. KOEHLER / J. BoylanCompany: TIERRA

Project No.: _____

Drilling Equip.: GEOPROBE / MACROCORESample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Paul C. GrigleyDATE 9-8-99

TOP OF CORE IN BOX	TOP OF CORE OF INTERVAL	FEET OF CORE IN INTERVAL (FIELD MEASURE)	SAMPLE NUMBER	FRAC-TURE MARK	BLINDING MARK	UNUSUAL DISTURBANCE	USCS SYMBOL	DEPTH IN FEET	SOIL/ LITHOLOG LOG	SAMPLE DESCRIPTION
								0.0		0.0-1.0 Flash mount - well casing hole. No material cored or saved.
								1.0		NO RECOVERY <u>sandy Gravel - some clay</u> <u>9-8-99</u>
								2.0		1.0-3.2 ft. Clay, Sand, Gravel, yellowish brown (10YR 5/3), Quartzite and Feldspathic gravel up to 2.5 cm fractured, pieces < 2.5 cm may be rounded, fine to coarse quartz and feldspathic sand, massive, soft, slightly plastic, moist, loc - 0.5 ft wet.
								3.0		
								3.2		
								4.0		3.2-5.0 No Recovery
								5.0		<u>sandy Gravel - more clay than</u> <u>9-8-99 above</u>
								5.0		5.0-6.3 ft. clay, sand, gravel as above 1.0 to 3.2 ft. yellowish brown (10YR 5/3), top grades to olive gray (5Y 4/2) at bottom, wet for most of sample except bottom 0.5 ft where it is just moist.
								6.0		
								6.3		
								7.0		Purified water (100ml) out of core liner
								7.0		6.3-7.0 No Recovery
								8.0		
								9.0		<u>sandy Clay - some silt & Gravel</u>
								9.0		Sandy, silty clay w/ gravel - predominantly light yellowish brown to light olive brown (2.5Y 6/3 - 2.5Y 5/3), mottled. Some zones sandier, some more clay-rich. Moist to wet. Gravel is mainly quartzite.
								10.0		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 3

Borehole Number: BH 22098
 Location - North: _____ East: _____
 Date: _____
 Geologist: R. KOEHLER / J. Boylan
 Drilling Equip.: GEOPROBE / MACROCORE

Surface Elevation: _____
 Area: NORTH-PA
 Total Depth: 31.0'
 Company: TERRA Project No.: _____
 Sample Type: PUSH / CONTINUOUS CORE

EG&G LOGGING SUPERVISOR

APPROVAL Fred C. SnigleyDATE 9-8-99

LOCATION OF CORE IN BOX	IDENTIFICATION OF CORE	FEET OF CORE RECOVERED FIELD MEASUREMENT	SAMPLE NUMBER	PICTURE ANGLE	DETAILS ANGLE	GRANULE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL LITHOLOGIC LOG	SAMPLE DESCRIPTION
	Run #3 9.0-13.0 ft	Recovery 2.1 ft including 0.4 ft of slough					CL / SC	10.0		see previous page
								10.7		
								11.0		
								12.0		
								13.0		
	Run 4: 13.0-17.0	2.4 (incl. 0.9' slough)					CL	14.0		10.7-13.0 ft No Recovery
								14.5		sandy clay - some gravel & silt
								15.0		Same as above, 9.0-10.7, but not as sandy.
								16.0		
								17.0		
	Run #5 17.0-21.0 ft	Recovery 1.2 ft including 0.2 ft of sandy silt & clay					C2	17.95		NO RECOVERY 14.5-17.0
								18.0		sandy clay - Tr. gravel
								19.0		17.0-17.95 ft clay with gravel - in previous sand as above, in color, then 0.1 ft black silt & silt + vest olive gray (SY 4/2) rounded gravel to 0.5 in quantities, plastic, moist, soft.
								20.0		17.95-21.0 No Recovery

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

U.S. DEPARTMENT OF ENERGY ROCKY FLATS PLANT

ROCKY FLATS PLANT BOREHOLE LOG

FORM GT-1A REV. 1

PAGE 2 OF 3

Borehole Number: 22198

Location - North: _____ East: _____

Date: 7-9-98

Geologist: F. Grigsby

Drilling Equip.: Geoprobe

Surface Elevation: _____

Area: N. PA Flume

Total Depth: 23'

Company: Terra

Sample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL

DATE

SAMPLE DESCRIPTION

Box 1 of 3

Run No. 3

Run No. 4
11.0' - 14.0'
Rec. 2.3'

Box 2 of 3

Run No. 5
14.0' - 17.0'
Rec. 3.0'

Run No. 6
17.0' - 20.0'
Rec. 4.0'

Slough area, 1' thick

Box 3

6.1 - 8.4 - Cont. Gravel at
T-8.20' to T-8.40' FG

8.4' - 9.6' - Sandy gravel.
same clay. Matrix. Fine
yellowish brown (v. 4.2).
Starts 15" well graded.
Fred. gravel. Bottom of core is wet

9.6' - 11.0' - No Rec

11.0' - 12.8' - Sandy clay -
T-8 gravel at T-8.20' interval -
Red grayish orange (v. 4.2)
Core sl. damp - mod. friable -
weathered.

12.8' - 14.0' - No Rec.

14.0' - 17.0' - clayey sd. -
Pale yellowish brown (v. 4.2)
and Dark yellowish orange (v. 4.6)
Sl. damp - mod. friable - some
very sandy intervals - mix

17.0' - 18.3' - sandy clay - same

18.3' - 21.0' - clayey sandstone -
Dark yellowish orange (v. 4.2) and
Grayish orange (v. 4.4) and
Pale yellowish brown (v. 4.2) and
Abundant siltstone mixed with clay.
Deposits questionable - Core Drying -
May be Laminar Chert - Sands v. 4.6
to f. 6. - Silt clay to rounded gravel
(wet sandy or gravelly sand)

NOTES: General: USGS is modified for this log as follows:
Materials amounts are estimated by % volume instead of % weight.
1) Badly broken core, accurate footage measurements not possible.
2) Core breaks cannot be matched, accurate footage measurements not possible

483
986

Page 3 of 3

Surface Elevation: _____
Area: _____
Total Depth: _____
Company: _____ Project No.: _____
Sample Type: _____

APPROVAL

(2) 111

SAMPLE DESCRIPTION

2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 1 OF 2Borehole Number: 22298

Surface Elevation: _____

Location - North: _____ East: _____

Area: NPA - Nuclear PlumeDate: 09-14-98

Total Depth: _____

Geologist: F. Grigsby - R. g. B. LogCompany: Tierra Project No.: _____Drilling Equip.: GeoprobeSample Type: Continuous Core

EG&G LOGGING SUPERVISOR

APPROVAL _____

DATE _____

TOP/BOTTOM OF CORE BOX	TOP/BOTTOM OF INTERVAL	DEPT OF CORE INTERVAL (FEET)	SAMPLE NUMBER	STRUCTURAL STRAT	DIPPING ANGLE	GRAIN SIZE DISTRIBUTION	USCS SYMBOL	DEPTH IN FEET	SOIL/ THICK LOG	SAMPLE DESCRIPTION
								0	AA	0.0' - 0.6' - Asphalt
								0.6' - 1.15'		Sand & gravel - red BSS - Geomembrane at bottom of hole - Material Discarded.
								1.15' - 1.6'	CL	Gravelly, Clay - Tr. sd Dark Yellowish Brown (10YR-4.2) Est. med to high plasticity. Some blocky (N1) asphaltic matrix material (SPOR 1) - Fill material
								1.6' - 2.9'	GM	Sandy Gravel - Abundant asphalt - Brownish Black (5YR-4.1) Fill material - friable -
								2.9' - 4.2'	CL	Sandy Clay - Tr. gravel Moderate Yellowish Brown (10YR-5.5) with light olive gray (5Y-4.2). Est. med. plasticity. Wx - Clay var. slightly damp, sh. sh. b.
								4.2' - 4.5'	CL	Sand clay - Tr. gravel Bg gravel clast at top of interval Brownish Black (5YR-4.1)
								4.5' - 5.0'		No Rec.
								5.0' - 5.4'	CL	Sandy clay - same as 2.9' - 4.2'
								5.4' - 6.0'		Sandy clay - same as 4.2' - 4.5'
								6.0' - 7.4'		Sandy Clay - Tr. gravel - Dark Yellowish Brown (10YR-4.2) grading to moderate Yellowish Brown (10YR-5.5). Sand var. interval more sandy than above - mod. friable, Wx.
								7.4' - 8.7'	CL	Gravelly, Clay - some sd. Red. Moderate Yellowish Brown (10YR-5.5) - some fair yellowish Brown (10YR-6.2) - Gravel to broken cobble size - SAND & gravel matrix.
								8.7' - 10.0'	CL	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

ROCKY FLATS PLANT BOREHOLE LOG

PAGE 2 OF 2

Sorehole Number: 22298
Location - North: _____ East: _____
Date: 09-14-98
Geologist: F. Grigsby, Rg & Log
Drilling Equip.: Geoprobe

Surface Elevation: _____
Area: N. PA Nitrate Plume
Total Depth: 20.0'
Company: Terra Project No.: _____
Sample Type: Composite Core

EG&G LOGGING SUPERVISOR

APPROVAL

DATE _____

TOP OF CORE OR CORRELATION MARK	POSITION OF INTERVAL	FEET OF CORE INTERVAL (FIELD MEASUREMENT)	SAMPLE NUMBER	DESCRIPTION ALONG CORE	DIAMETER INCHES	DEPTH IN FEET	SOIL/ LITHOLOGIC LOG	SAMPLE DESCRIPTION
	Run No. 3	9.0' - 12.0'				10		<u>7.4-8.7-</u> Cont.
	Run No. 4	12.0' - 15.0'				11		Core varies from med. friable to non friable. - Est. plasticity is Low to med. - Int. Wx., sh. damp
	Run No. 5	15.0' - 18.0'				12		<u>8.7-16.6'-</u> Silty clay - some sd. - Color varies from Dark yellowish orange (dayr. 6/2) and Grayish orange (dayr. 7/4) to Pale yellowish brown (dayr. 6/2) in interbedded dayr. intervals.
	Run No. 6	18.0' - 20.0'				13		Soil content varies - Entire interval heavily weathered. Ironstone nodules at bottom of interval.
	Run No. 7	20.0' - 22.0'				14		
	Run No. 8	22.0' - 24.0'				15		
	Run No. 9	24.0' - 26.0'				16		
	Run No. 10	26.0' - 28.0'				17		<u>16.6-20.0'. Top of (Conglomerate & Bedrock)</u>
	Run No. 11	28.0' - 30.0'				18		Claystone - Tr. silt. - Pale yellowish brown (dayr. 6/2) some Grayish Orange (dayr. 7/4) no staining. - Core very st. damp & med. indurated.
	Run No. 12	30.0' - 32.0'				19		
	Run No. 13	32.0' - 34.0'				20		

NOTES: General: JSCS is modified for this log as follows:

*Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

2) Core breaks cannot be matched, accurate footage measurements not possible



Appendix C.2

1998 Well Construction Logs *Diagrams*

Best Available Copy

487
490

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: #00198 PROJECT NAME: 983-Plume Characterization PROGRAM RMRS-ER
 SCREENED FORMATION: Bedrock Siltstone DRILLING CONTRACTOR: UNIVERSAL IT CORPORATION
 DRILLING METHOD: GEOPROBE MAREPPE DATE DRILLED: 03/17/98 DATE COMPLETED: 03/17/98
 RIG GEOLOGIST: J Cox / J TUTH LOGGING GEOLOGIST: Jim Cox / J. TUTH
 COMPLETED DEPTH (FT): 16.4 ESTIMATED DEPTH TO BEDROCK (FT): 8.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): 15.25* DATE MEASURED: 3/23/98
 COMPLETED WATER LEVEL (FT): DAY DATE MEASURED: 5/4/98

PROTECTIVE CASING, TOP (FT): 1 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 1 ft. ABOVE GS
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC Sch. 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: Hydrated Agassiz Granular Bentonite Plus Curing
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC Sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.5' Below
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Hydrated Agassiz Granular Bentonite Plus Curing
 BENTONITE SEAL, BOTTOM (FT): 10.4
 FILTER PACK, TOP (FT): 10.4
 FILTER PACK TYPE: 16/40 silica sand BRAND: CLS CSS
 SURFACE CASING, BOTTOM (FT): 11.4 SCREEN, TOP (FT): 11.4
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 16.2 TYPE: PVC sch 40 BRAND: CLS-
 SUMP, TOP (FT): 16.2 TYPE: PVC sch 40 end cap
 FILTER PACK, BOTTOM (FT): 16.4
 BACKFILL, TOP (FT): NA TYPE: NA
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): 16.4
 TOTAL DEPTH (FT): 16.4

ALL MEASUREMENTS WILL BE MADE FROM GROUND SURFACE.

REMARKS: completed in borehole #00198A Bentonite Hydrated w/ 1 gal. of Distilled water & purged on 4/27/98

COMPLETED BY: Jim Cox IT CORPORATION DATE: 3/18/98

CHECKED BY: WJ IT DATE: 3/23/98

44T488

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 00296 PROJECT NAME: Ryan's P-1 AOSPAD Plant PROGRAM: RNRS-E12
 SCREENED FORMATION: weathered BZ. DRILLING CONTRACTOR: UNIVERSAL IT CORP.
 DRILLING METHOD: Gas probe wash pipe DATE DRILLED: 3/25/98 DATE COMPLETED: 3/25/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 12.5' ESTIMATED DEPTH TO BEDROCK (FT): 2.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): 9.69' DATE MEASURED: 3/26/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98

PROTECTIVE CASING, TOP (FT): 1.0' (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 1.0'
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: Hydrated Agassiz Gran. Bentonite
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40 Plus 16
 PROTECTIVE CASING, BOTTOM (FT): 1.0'
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Hydrated Agassiz Gran. Bnt.
 BENTONITE SEAL, BOTTOM (FT): 6.3' Plus (chip)
 FILTER PACK, TOP (FT): 6.3'
 FILTER PACK TYPE: 16/40 Silica Sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 7.5' SCREEN, TOP (FT): 7.5'
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 12.3 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 12.3 TYPE: PVC sch 40 end cap
 FILTER PACK, BOTTOM (FT): 12.5
 BACKFILL, TOP (FT): NA TYPE: _____
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): 12.5
 TOTAL DEPTH (FT): 12.5

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: hydrated bentonite w/ about < 1 gal. of distilled water. Put on 4/22 - 300 ml.

COMPLETED BY: Jim Cox DATE: 4/16/98
 CHECKED BY: DAN GRAMMING DATE: 4/8/98


489
442

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 00398 weather PROJECT NAME: 903 PAD/Ryan's PTH/UMS PROGRAM: RMRS-EIR
 SCREENED FORMATION: Bedrock siltstone DRILLING CONTRACTOR: UNIVERSAL/IT CORPORATION
 DRILLING METHOD: See probe + backfill DATE DRILLED: 3/23/98 DATE COMPLETED: 3/23/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox IT CORP.
 COMPLETED DEPTH (FT): 15.0' ESTIMATED DEPTH TO BEDROCK (FT): 9.3
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): _____ INITIAL WATER LEVEL (FT): 13.42 DATE MEASURED: 3/26/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98
 PROTECTIVE CASING, TOP (FT): 0.8' (FROM GROUND SURFACE)




ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: Completed in Borehole #00398 - some moisture in clay at below 14' otherwise dry - 1 ft steel weight from drillers tape lodged in filter pack at 14.6 - 13.6 contained
 COMPLETED BY: Jim Cox DATE: 3/23/98
 CHECKED BY: DAN GRAVERDING DATE: 4/8/98

490
483

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 0049BPROJECT NAME: Ryan's PAFB PAD PLUMEPROGRAM: RMRS-EXERSCREENED FORMATION: Washoe BR / Cultivation DRILLING CONTRACTOR: UNIVERSAL / IT CORP.DRILLING METHOD: GEOPOLAR MARIPOSA DATE DRILLED: 3/25/98DATE COMPLETED: 3/25/98RIG GEOLOGIST: JIM COXLOGGING GEOLOGIST: JIM COXCOMPLETED DEPTH (FT): 14.0ESTIMATED DEPTH TO BEDROCK (FT): 9.7BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0QUANTITY OF FLUIDS LOST
DURING DRILLING (GAL): NAINITIAL WATER LEVEL (FT): 13.34' BGSDATE MEASURED: 5/26/98COMPLETED WATER LEVEL (FT): DRYDATE MEASURED: 5/5/98PROTECTIVE CASING, TOP (FT): 1.10' (FROM GROUND SURFACE)SURFACE CASING (STICKUP), TOP (FT): 1.0'SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC Sch 40SURFACE SEAL, TOP (FT): 0.0 TYPE: Agri-set Bentonite Plug (Chi)PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC Sch 40PROTECTIVE CASING, BOTTOM (FT): 1.0' 0.9'IF SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NAAPPLICABLE SECONDARY CASING, I.D. (IN): NA TYPE: NACENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NAGROUT SEAL, TOP (FT): NA TYPE: NABENTONITE SEAL, TOP (FT): 0.0 TYPE: Agri-set Grout BentBENTONITE SEAL, BOTTOM (FT): 7.8' Hydrated Bentonite Plug (Chi)FILTER PACK, TOP (FT): 7.8'FILTER PACK TYPE: 14/40 Silica Sand BRAND: CSSSURFACE CASING, BOTTOM (FT): 9.0' SCREEN, TOP (FT): 9.0'SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"SCREEN, BOTTOM (FT): 13.8 TYPE: PVC Sch 40 BRAND: NASUMP, TOP (FT): 13.5 TYPE: PVC Sch 40 end capFILTER PACK, BOTTOM (FT): 14.0BACKFILL, TOP (FT): NA TYPE: NABACKFILL, BOTTOM (FT): NASUMP, BOTTOM (FT): 14.0TOTAL DEPTH (FT): 14.0ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACEREMARKS: Hydrated Bentonite Slurry w/ 1/4 gal of Distilled waterCOMPLETED BY: Jim Cox IT DATE: 3/25/98CHECKED BY: Dan Gammann DATE: 4/8/98491
449

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 00598 PROJECT NAME: 903 PAD/2/HAAS 27 PLUME PROGRAM: RMRS - BR
 SCREENED FORMATION: weathered BR. DRILLING CONTRACTOR: UNIVERSAL / ITCORP
 DRILLING METHOD: Geoprobe DATE DRILLED: 3/24/98 DATE COMPLETED: 3/24/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 20.4 ESTIMATED DEPTH TO BEDROCK (FT): 5.4
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 03/24/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98
 PROTECTIVE CASING, TOP (FT): 0.9' (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 0.9'
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC Sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: Aquadag Gran Bentonite
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC Sch 40 Plus (Ch)
 PROTECTIVE CASING, BOTTOM (FT): 1.1'
 IF SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 APPLICABLE SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Hydrated Bentonite Plus (Ch)
 BENTONITE SEAL, BOTTOM (FT): 9.0'
 FILTER PACK, TOP (FT): 9.0'
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 10.4' SCREEN, TOP (FT): 10.4
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 20.2 TYPE: PVC Sch 40 BRAND: NA
 SUMP, TOP (FT): 20.2 TYPE: PVC Sch 40 threaded cap
 FILTER PACK, BOTTOM (FT): 20.4
 BACKFILL, TOP (FT): NA TYPE: NA
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): 20.4
 TOTAL DEPTH (FT): 20.4

REMARKS: Bentonite hydrated w/ < 1 quart of water. - During construction top riser (1.4') snapped at threads and replaced. - some minor amount of bentonite fell into well.

COMPLETED BY: Jim Cox DATE: 3/24/98

CHECKED BY: Dan Graeber DATE: 4/8/98

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 00698 PROJECT NAME: 903PA/RANDS PIT PUMP PROGRAM: RMR5-ER
 SCREENED FORMATION: methane BR. DRILLING CONTRACTOR: UNIVERSAL 117 CORP.
 DRILLING METHOD: Geoprobe DATE DRILLED: 3/24/98 DATE COMPLETED: 3/24/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 18.2 ESTIMATED DEPTH TO BEDROCK (FT): 10.0
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): 13.15 * DATE MEASURED: 3/25/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98

PROTECTIVE CASING, TOP (FT): 1.0' (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 1.0'
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch. 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: Hydrated Bentonite Plug (chip)
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch. 40
 PROTECTIVE CASING, BOTTOM (FT): 1.0'
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Hydrated Bentonite Plug (chip)
 BENTONITE SEAL, BOTTOM (FT): 12.2
 FILTER PACK, TOP (FT): 12.2
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 13.2 SCREEN, TOP (FT): 13.2
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 18.0 TYPE: PVC sch. 40 BRAND: NA
 SUMP, TOP (FT): 18.0 TYPE: PVC sch. 40 threaded end cap.
 FILTER PACK, BOTTOM (FT): 18.2
 BACKFILL, TOP (FT): NA TYPE: NA
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): NA
 TOTAL DEPTH (FT): 18.2

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: Hydrated bentonite w/ 1 gal of distilled water.
* Pugged on 4/22/98 - 75 ml.

COMPLETED BY: Jim Cox DATE: 4/6/98

CHECKED BY: Dan Grawinsky DATE: 4/8/98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: DD798PROJECT NAME: 903 PAD/EVANS PIT PLANE PROGRAM: RM25 - ERSCREENED FORMATION: weathered BRDRILLING CONTRACTOR: UNIVERSAL - IT CORPDRILLING METHOD: GEO PROBEDATE DRILLED: 3/26/98 DATE COMPLETED: 3/26/98RIG GEOLOGIST: Jim CoxLOGGING GEOLOGIST: Jim CoxCOMPLETED DEPTH (FT): 14.1ESTIMATED DEPTH TO BEDROCK (FT): 5.0BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"


QUANTITY OF FLUIDS LOST

DURING DRILLING (GAL): NAINITIAL WATER LEVEL (FT): 13.63DATE MEASURED: 03/26/98COMPLETED WATER LEVEL (FT): DRYDATE MEASURED: 5/5/98PROTECTIVE CASING, TOP (FT): 0.90' (FROM GROUND SURFACE)SURFACE CASING (STICKUP), TOP (FT): 0.90'SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch. 40SURFACE SEAL, TOP (FT): 0.0 TYPE: Hydrated Bentonite Plus (Ch.)PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch. 40PROTECTIVE CASING, BOTTOM (FT): 1.1'IF
APPLICABLESECONDARY CASING, TOP (FT): NA BOTTOM (FT): NASECONDARY CASING, I.D. (IN): NA TYPE: NACENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NAGROUT SEAL, TOP (FT): NA TYPE: NABENTONITE SEAL, TOP (FT): 0.0' TYPE: Hydrated Bentonite Plus (Ch.)BENTONITE SEAL, BOTTOM (FT): 7.7'FILTER PACK, TOP (FT): 7.7'FILTER PACK TYPE: 16/40 silica sand BRAND: CSSSURFACE CASING, BOTTOM (FT): 9.1' SCREEN, TOP (FT): 9.1'SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"SCREEN, BOTTOM (FT): 13.9 TYPE: PVC sch 40 BRAND: NASUMP, TOP (FT): 14.1 TYPE: PVC sch 40 threaded end capFILTER PACK, BOTTOM (FT): 14.1BACKFILL, TOP (FT): NA TYPE: NABACKFILL, BOTTOM (FT): NASUMP, BOTTOM (FT): 14.1TOTAL DEPTH (FT): 14.1ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.REMARKS: Hydrated w/ 1/4 gal of distilled waterCOMPLETED BY: Jim CoxDATE: 4/6/98CHECKED BY: DAN GRAVELDINGDATE: 4/8/98494
4/6

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 00896 PROJECT NAME: 903 PAD/RVANS PIT PLUME PROGRAM: RMPS-ER
 SCREENED FORMATION: weathered BR DRILLING CONTRACTOR: UNIVERSAL / IT CORP.
 DRILLING METHOD: Geoprobe DATE DRILLED: 3/27/98 DATE COMPLETED: 3/27/98
 RIG GEOLOGIST: DAN GRAVELDING LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 16.1 ESTIMATED DEPTH TO BEDROCK (FT): 4.0
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/1/98
 DURING DRILLING (GAL): NA COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: Hydrated Bentonite w/ 1/2 gal of distilled water.


COMPLETED BY: Jim Cox DATE: 4/6/98

CHECKED BY: DAN GRAVELDING DATE: 4/8/98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: CC998 PROJECT NAME: 903 PAD/RYAN'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: Wichita BR/dln DRILLING CONTRACTOR: UNIVERSAL IT CORPORATION
 DRILLING METHOD: Geoprobe DATE DRILLED: 4/1/98 DATE COMPLETED: 4/1/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 10.0' ESTIMATED DEPTH TO BEDROCK (FT): 4.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/1/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: Hydrated Bentonite w/ spray bottle

COMPLETED BY: Jim Cox

DATE: 4/6/98

CHECKED BY:

DAN GRAMMING

DATE: 4/8/98

496
498

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01098 PROJECT NAME: 903 PAD/RXAD'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: Permian Sandstone DRILLING CONTRACTOR: IT CORP / UNIVERSAL
 DRILLING METHOD: Geo Probe DATE DRILLED: 4/10/98 DATE COMPLETED: 4/10/98
 RIG GEOLOGIST: Don Greenberg LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 12.4 ESTIMATED DEPTH TO BEDROCK (FT): 10.9
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 not encountered

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/14/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 4/29/98

PROTECTIVE CASING, TOP (FT): 0.90 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.90
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: gran. bent. hydrated w/ spray
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.80
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 4.0-3.4 TYPE: Bent. Plug (NOT HYDRATE)
 BENTONITE SEAL, BOTTOM (FT): 6.4'
 FILTER PACK, TOP (FT): 6.4'
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 7.4' SCREEN, TOP (FT): 7.4'
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 12.2 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 12.2 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 12.4
 BACKFILL, TOP (FT): NA TYPE: _____
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): 12.4
 TOTAL DEPTH (FT): 12.4

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: Jim Cox (from logbook)DATE: 4/10/98CHECKED BY: [Signature]DATE: 5.11.98

497
445

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01198PROJECT NAME: 903 PAD/RYAN'S PIT PLANE PROGRAM: RMS-ERSCREENED FORMATION: WBR / COLL.DRILLING CONTRACTOR: IT / UNIVERSALDRILLING METHOD: GeopackDATE DRILLED: 4/9/98DATE COMPLETED: 4/9/98RIG GEOLOGIST: Jim CoxLOGGING GEOLOGIST: Jim CoxCOMPLETED DEPTH (FT): 20.4ESTIMATED DEPTH TO BEDROCK (FT): 18.8BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"QUANTITY OF FLUIDS LOST
DURING DRILLING (GAL): 0INITIAL WATER LEVEL (FT): DRYDATE MEASURED: 4/17/98COMPLETED WATER LEVEL (FT): DRYDATE MEASURED: 4/29/98PROTECTIVE CASING, TOP (FT): 1.10

(FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 1.10SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40SURFACE SEAL, TOP (FT): 0.0TYPE: gran. bentonite hydratePROTECTIVE CASING, I.D. (IN): 1.5"TYPE: PVC sch 40PROTECTIVE CASING, BOTTOM (FT): 0.60IF
APPLICABLESECONDARY CASING, TOP (FT): NABOTTOM (FT): NASECONDARY CASING, I.D. (IN): NATYPE: NACENTRALIZER, O.D. (IN): NATOP (FT): NABOTTOM (FT): NAGROUT SEAL, TOP (FT): NATYPE: NABENTONITE SEAL, TOP (FT): 3.0TYPE: Bent used plus.NOT HYDRATEDBENTONITE SEAL, BOTTOM (FT): 9.3FILTER PACK, TOP (FT): 9.3FILTER PACK TYPE: 16/40 silica sandBRAND: CSSSURFACE CASING, BOTTOM (FT): 10.4SCREEN, TOP (FT): 10.4SCREEN SLOT SIZE (.000 IN): NASCREEN, I.D. (IN): NASCREEN, BOTTOM (FT): 20.2TYPE: PVC sch 40BRAND: NASUMP, TOP (FT): 20.2TYPE: PVC sch 40 threaded end capFILTER PACK, BOTTOM (FT): 20.4BACKFILL, TOP (FT): NATYPE: NABACKFILL, BOTTOM (FT): NASUMP, BOTTOM (FT): 20.4TOTAL DEPTH (FT): 20.4ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.REMARKS: partner well to 01198ACOMPLETED BY: Jim CoxDATE: 4/9/98CHECKED BY: RZjDATE: 5.11.98498
200

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 0129B PROJECT NAME: 903 PAD/RYAN'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: W3R/COLL DRILLING CONTRACTOR: IT/UNIVERSITY
 DRILLING METHOD: GEOPROBE DATE DRILLED: 4/8/98 DATE COMPLETED: 4/8/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 18.3 ESTIMATED DEPTH TO BEDROCK (FT): 16.3
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): _____ INITIAL WATER LEVEL (FT): 13.67 DATE MEASURED: 4/9/98
 COMPLETED WATER LEVEL (FT): 14.31 DATE MEASURED: 4/28/98
 PROTECTIVE CASING, TOP (FT): 1.0' (FROM GROUND SURFACE) (52)
 SURFACE CASING (STICKUP), TOP (FT): 1.0'
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: gran. bent. Hydrated w/spray
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.7'
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 3.0 TYPE: MED BENTONITE PLUG
 BENTONITE SEAL, BOTTOM (FT): 12.1 NOT HYDRATED
 FILTER PACK, TOP (FT): 12.1
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 13.3 SCREEN, TOP (FT): 13.3
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 18.1 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 15.1 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 18.3
 BACKFILL, TOP (FT): NA TYPE: _____
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): NA 18.3
 TOTAL DEPTH (FT): 18.3
 REMARKS: SAMPLED ON 4/28/98

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Jim CoxDATE: 4/9/98CHECKED BY: [Signature]DATE: 5.11.98

499
501

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: C1398 PROJECT NAME: 903 PAD/RXAD'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: Weathered BL/Columbian DRILLING CONTRACTOR: UNIVERSAL / IT CORP.
 DRILLING METHOD: Augercase DATE DRILLED: 4/1/98 DATE COMPLETED: 4/1/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 9.0' ESTIMATED DEPTH TO BEDROCK (FT): 6.4
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/1/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 5/5/98
 PROTECTIVE CASING, TOP (FT): 0.90' (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 0.90'
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: Gran. Bent. Hydrated
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.80'
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 0.0' TYPE: Granular Bentonite Hydrated
 BENTONITE SEAL, BOTTOM (FT): 2.9'
 FILTER PACK, TOP (FT): 2.9'
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 4.0' SCREEN, TOP (FT): 4.0'
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 8.8' TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 8.8' TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 9.0' 7/ug
 BACKFILL, TOP (FT): 9.0' TYPE: Bentonite (chip) NOT Hydrated
 BACKFILL, BOTTOM (FT): 10.15'
 SUMP, BOTTOM (FT): 9.0'
 TOTAL DEPTH (FT): 10.1'

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: Gran. Bent. Hydrated slowly w/ spray bottle of Distilled water.

COMPLETED BY: Jim Cox DATE: 4/6/98

CHECKED BY: DAN GARDNER DATE: 4/8/98

500
808

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01498 PROJECT NAME: 903 PAD/RVAD'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: weathered BZ/calvin DRILLING CONTRACTOR: UNIVERSAL/IT CORP.
 DRILLING METHOD: Auger DATE DRILLED: 4/1/98 DATE COMPLETED: 4/1/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 10.0 ESTIMATED DEPTH TO BEDROCK (FT): 6.4
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/1/98
 COMPLETED WATER LEVEL (FT): 7.34 DATE MEASURED: 5/5/98
 PROTECTIVE CASING, TOP (FT): 0.90' (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 0.90'
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0' TYPE: Granular Bent. Hydrated.
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40 w/spray
 PROTECTIVE CASING, BOTTOM (FT): 0.80'
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0' TYPE: Granular Bent. Hydrated w/spray
 BENTONITE SEAL, BOTTOM (FT): 4.0'
 FILTER PACK, TOP (FT): 4.0'
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 5.0' SCREEN, TOP (FT): 5.0'
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 9.8 TYPE: PVC sch 40 BRAND: NA
 SUMP, TOP (FT): 9.8' TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 10.0'
 BACKFILL, TOP (FT): 10.0' TYPE: Bentonite Chip NET
 BACKFILL, BOTTOM (FT): 10.2' HYDRATED
 SUMP, BOTTOM (FT): 10.18'
 TOTAL DEPTH (FT): 10.2'

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: hydrated Granular Bent. slowly w/ Distilled
Water from a spray bottle. SAMPLED on 4/28/98

COMPLETED BY: Jim Cox DATE: 4/6/98

CHECKED BY: Dan Gaborczyk DATE: 4/8/98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01598 PROJECT NAME: 903 PAD/RVAD'S PIT PLANE PROGRAM RMR5-ER
 SCREENED FORMATION: CELESTIUM DRILLING CONTRACTOR: IT / UNIVERSAL
 DRILLING METHOD: geoprobe DATE DRILLED: 04/17/98 DATE COMPLETED: 04/17/98
 RIG GEOLOGIST: Zane Tute LOGGING GEOLOGIST: Zane Tute
 COMPLETED DEPTH (FT): 10.2 ESTIMATED DEPTH TO BEDROCK (FT): 7.0
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): Dry DATE MEASURED: 4/17/98
 COMPLETED WATER LEVEL (FT): Dry DATE MEASURED: 4/24/98
 PROTECTIVE CASING, TOP (FT): 0.9 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.9
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: granular bentonite, hydro spray
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.80
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Granular Bentonite, hydro spray
 BENTONITE SEAL, BOTTOM (FT): 2.2
 FILTER PACK, TOP (FT): 2.2
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 3.2308 SCREEN, TOP (FT): 3.2308
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 8.0 TYPE: PVC sch 40 BRAND: NA
 SUMP, TOP (FT): 8.0 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): NA
 BACKFILL, TOP (FT): 8.2 TYPE: Bentonite chip
 BACKFILL, BOTTOM (FT): 10.2
 SUMP, BOTTOM (FT): 8.2
 TOTAL DEPTH (FT): 10.2

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS:

COMPLETED BY: Zane TuteDATE: 4/17/98CHECKED BY: RZDATE: 5-11-98

304 002

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01698PROJECT NAME: 903 PAD/RYAN'S PIT PUMPPROGRAM: RMRS-ERSCREENED FORMATION: 032/002DRILLING CONTRACTOR: IT / UNIVERSALDRILLING METHOD: geoprobeDATE DRILLED: 4/21/99DATE COMPLETED: 4/21/99RIG GEOLOGIST: Jim CoxLOGGING GEOLOGIST: Jim CoxCOMPLETED DEPTH (FT): 16.2ESTIMATED DEPTH TO BEDROCK (FT): 15.3BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST

DURING DRILLING (GAL): 0INITIAL WATER LEVEL (FT): 10.67DATE MEASURED: 4/29/99 rising?COMPLETED WATER LEVEL 10.67DATE MEASURED: 5-4-99PROTECTIVE CASING, TOP (FT): 1.0 (FROM GROUND SURFACE)SURFACE CASING (STICKUP), TOP (FT): 1.0SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40SURFACE SEAL, TOP (FT): 0.0 TYPE: Granular Bent. Hydrate w/sprayPROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40

PROTECTIVE CASING, BOTTOM (FT): _____

IF
APPLICABLESECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____SECONDARY CASING, I.D. (IN): NA TYPE: _____CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____GROUT SEAL, TOP (FT): NA TYPE: _____BENTONITE SEAL, TOP (FT): 3.0 TYPE: MED. BENT PLUGBENTONITE SEAL, BOTTOM (FT): 10.2FILTER PACK, TOP (FT): 10.2FILTER PACK TYPE: 16/40 silica sand BRAND: CSSSURFACE CASING, BOTTOM (FT): 11.2 SCREEN, TOP (FT): 11.2SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"SCREEN, BOTTOM (FT): 16.0 TYPE: PVC sch 40 BRAND: _____SUMP, TOP (FT): 16.0 TYPE: PVC sch 40 threaded end capFILTER PACK, BOTTOM (FT): 16.2BACKFILL, TOP (FT): NA TYPE: _____BACKFILL, BOTTOM (FT): NASUMP, BOTTOM (FT): 16.2TOTAL DEPTH (FT): 16.2

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.COMPLETED BY: Jim CoxDATE: 4/27/99CHECKED BY: P ZjDATE: 5-11-99

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01798PROJECT NAME: 903 PAD/RYAN'S PIT PUMP PROGRAM: RMS-ER

SCREENED FORMATION: _____

DRILLING CONTRACTOR: IT / UNIVERSALDRILLING METHOD: geoprobeDATE DRILLED: 4/21/98 DATE COMPLETED: 4/21/98RIG GEOLOGIST: Jim CoxLOGGING GEOLOGIST: Jim CoxCOMPLETED DEPTH (FT): 8.0

ESTIMATED DEPTH TO BEDROCK (FT): _____

BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"QUANTITY OF FLUIDS LOST
DURING DRILLING (GAL): 0INITIAL WATER LEVEL (FT): 12.1DATE MEASURED: 4/22/98COMPLETED WATER LEVEL (FT): 7.54 BGSDATE MEASURED: 4/24/98PROTECTIVE CASING, TOP (FT): 0.90 (FROM GROUND SURFACE)SURFACE CASING (STICKUP), TOP (FT): 0.90SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40

SURFACE SEAL, TOP (FT): _____ TYPE: _____

PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40

PROTECTIVE CASING, BOTTOM (FT): _____

IF
APPLICABLESECONDARY CASING, TOP (FT): NA

BOTTOM (FT): _____

SECONDARY CASING, I.D. (IN): NA

TYPE: _____

CENTRALIZER, O.D. (IN): NA

TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL, TOP (FT): NA

TYPE: _____

BENTONITE SEAL, TOP (FT): 0.0TYPE: Gran. Bent. Hydraulic
w/sprng Dist. WatBENTONITE SEAL, BOTTOM (FT): 2.0FILTER PACK, TOP (FT): 2.0FILTER PACK TYPE: 16/40 silica sand BRAND: CSSSURFACE CASING, BOTTOM (FT): 3.0SCREEN, TOP (FT): 3.0SCREEN SLOT SIZE (.000 IN): 0.010SCREEN, I.D. (IN): 3/4"SCREEN, BOTTOM (FT): 7.8TYPE: PVC sch 40

BRAND: _____

SUMP, TOP (FT): 7.8TYPE: PVC sch 40 threaded end capFILTER PACK, BOTTOM (FT): 8.0BACKFILL, TOP (FT): NA

TYPE: _____

BACKFILL, BOTTOM (FT): NASUMP, BOTTOM (FT): 8.0TOTAL DEPTH (FT): 8.0ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____


COMPLETED BY: Jim CoxDATE: 4/27/98CHECKED BY: [Signature]DATE: 5.11.98

504

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01848 PROJECT NAME: 903 PAD/RYAN'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: _____ DRILLING CONTRACTOR: IT / UNIVERSAL
 DRILLING METHOD: geogrobs DATE DRILLED: 4/22/98 DATE COMPLETED: 4/22/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 8.2 ESTIMATED DEPTH TO BEDROCK (FT): _____
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/23/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 4/24/98
 PROTECTIVE CASING, TOP (FT): 0.90 (FROM GROUND SURFACE)



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Jim Cox DATE: 4/27/98
 CHECKED BY: RJ DATE: 5-11-98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01998 PROJECT NAME: 903 PAO/RYAN'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: WBR/COLL. DRILLING CONTRACTOR: IT/UNIVERSAL
 DRILLING METHOD: geoprobe DATE DRILLED: 4/23/99 DATE COMPLETED: 4/23/99
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 4.5 ESTIMATED DEPTH TO BEDROCK (FT): 2.4
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/24/99
 COMPLETED WATER LEVEL (FT): 2.25' bgs DATE MEASURED: 4/24/99 rising
 PROTECTIVE CASING, TOP (FT): 1.0 (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 1.0
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): _____ TYPE: _____
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): _____
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Granular Bent
 BENTONITE SEAL, BOTTOM (FT): 1.5 Hydrated w/ spray
 FILTER PACK, TOP (FT): 1.5
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 2.5 SCREEN, TOP (FT): 2.5
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 4.3 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 4.3 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 4.5
 BACKFILL, TOP (FT): 4.5 TYPE: MED. BENT PLUG
 BACKFILL, BOTTOM (FT): 8.0
 SUMP, BOTTOM (FT): 4.5 7.5
 TOTAL DEPTH (FT): 8.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____
 COMPLETED BY: Jim Cox DATE: 5/5/99
 CHECKED BY: [Signature] DATE: 5.11.98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 02098 PROJECT NAME: 903 PAD/RYAN'S PIT PLUME PROGRAM: RMES-ER
 SCREENED FORMATION: WBR/COAL DRILLING CONTRACTOR: IT/UNIVERSAL
 DRILLING METHOD: geoprobe DATE DRILLED: 4/22/99 DATE COMPLETED: 4/22/99
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 4.9 ESTIMATED DEPTH TO BEDROCK (FT): 3.0
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/23/99
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 4/29/98
 PROTECTIVE CASING, TOP (FT): 0.90 (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 0.90
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.90 TYPE: NA
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.90
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Granular Bent Hydrated w/ spray
 BENTONITE SEAL, BOTTOM (FT): 2.0
 FILTER PACK, TOP (FT): 2.0
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 2.4 SCREEN, TOP (FT): 2.9
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 4.7 TYPE: PVC sch 40 BRAND: NA
 SUMP, TOP (FT): 4.7 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 4.9
 BACKFILL, TOP (FT): 4.9 TYPE: MED. BENT PLUG
 BACKFILL, BOTTOM (FT): 6.1
 SUMP, BOTTOM (FT): 4.9
 TOTAL DEPTH (FT): 6.1
 REMARKS: NA

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Jim Cox DATE: 5/5/99
 CHECKED BY: [Signature] DATE: 5/11/98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 02198 PROJECT NAME: 903 PAD/RYAN'S PIT PLUME PROGRAM: RMKS-ER
 SCREENED FORMATION: WBR/LOL DRILLING CONTRACTOR: IT/UNIVERSAL
 DRILLING METHOD: geoprobe DATE DRILLED: 4/13/98 DATE COMPLETED: 4/13/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 8.0 ESTIMATED DEPTH TO BEDROCK (FT): 4.5
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/14/98
 DURING DRILLING (GAL): _____ COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 4/29/98

PROTECTIVE CASING, TOP (FT): 0.90 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.90
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: Gran. Bent. Hydrated w/ spray
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.85
 IF SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 APPLICABLE SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Granular Bent. Hydrated w/ spray
 BENTONITE SEAL, BOTTOM (FT): 2.0
 FILTER PACK, TOP (FT): 2.0
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 3.0 SCREEN, TOP (FT): 3.0
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 7.8 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 7.8 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 8.0
 BACKFILL, TOP (FT): 8.0 TYPE: Bentonite Plug (chip)
 BACKFILL, BOTTOM (FT): 12.0 NOT HYDRATED.
 SUMP, BOTTOM (FT): 8.0
 TOTAL DEPTH (FT): 12.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: Jim CoxDATE: 4/15/98CHECKED BY: [Signature]DATE: 5-11-98

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 02298 PROJECT NAME: 903 PAD/RXAD'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: W. SANDSTONE/ALUM. CLAY DRILLING CONTRACTOR: IT CORP. / UNIVERSAL
 DRILLING METHOD: GEOPHONE DATE DRILLED: 9/16/98 DATE COMPLETED: 11/10/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 8.3 ESTIMATED DEPTH TO BEDROCK (FT): 4.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/13/98
 COMPLETED WATER LEVEL (FT): 0.2Y DATE MEASURED: 4/29/98
 PROTECTIVE CASING, TOP (FT): 1.0 (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 1.0
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: gran. bent. hydrated w/ spray distilled water
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.7
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): NA
 SECONDARY CASING, I.D. (IN): NA TYPE: NA
 CENTRALIZER, O.D. (IN): NA TOP (FT): NA BOTTOM (FT): NA
 GROUT SEAL, TOP (FT): NA TYPE: NA
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: gran. bent. hydrated w/ spray distilled water
 BENTONITE SEAL, BOTTOM (FT): 2.3'
 FILTER PACK, TOP (FT): 2.3'
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 3.3' SCREEN, TOP (FT): 3.3'
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 8.3 TYPE: PVC sch 40 BRAND: NA
 SUMP, TOP (FT): 8.1 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 8.3
 BACKFILL, TOP (FT): NA TYPE: NA
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): 8.3
 TOTAL DEPTH (FT): 8.3
 REMARKS: NA

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Jim Cox DATE: 4/10/98
 CHECKED BY: [Signature] DATE: 5.11.98

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 03198 PROJECT NAME: SPPRP PROGRAM: NA
 SCREENED FORMATION: UHSU/bedrock DRILLING CONTRACTOR: TEG
 DRILLING METHOD: geoprobe DATE DRILLED: 2/12/98 DATE COMPLETED: 2/12/98
 RIG GEOLOGIST: Tim House LOGGING GEOLOGIST: Tim House
 COMPLETED DEPTH (FT): 12 ESTIMATED DEPTH TO BEDROCK (FT): 2.8
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 3/4 in, 2 in borehole

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): None INITIAL WATER LEVEL (FT): _____ DATE MEASURED: _____
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 5 ft (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 5 ft

SURFACE CASING, I.D. (IN): 3/4 in TYPE: Sch 80

SURFACE SEAL TOP (FT): None TYPE: _____

PROTECTIVE CASING, I.D. (IN): 2 TYPE: Sch 40 Avc

PROTECTIVE CASING, BOTTOM (FT): 5 ft

IF SECONDARY CASING, TOP (FT): None BOTTOM (FT): _____
 APPLICABLE SECONDARY CASING, I.D. (IN): None TYPE: _____

CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL TOP (FT): None TYPE: _____

BENTONITE SEAL TOP (FT): 0 TYPE: Wyoming granular bentonite

BENTONITE SEAL BOTTOM (FT): 5.75

FILTER PACK, TOP (FT): 5.75

FILTER PACK TYPE: Colorado Silica Sand BRAND: 16-40 CSSI

SURFACE CASING, BOTTOM (FT): 7.0 SCREEN, TOP (FT): 7.0

SCREEN SLOT SIZE (.000 IN): .010 SCREEN, I.D. (IN): 3/4

SCREEN, BOTTOM (FT): 12.0 TYPE: Sch 80 BRAND: Geoprobe Systems

SUMP, TOP (FT): None TYPE: _____

FILTER PACK, BOTTOM (FT): 12.0

BACKFILL, TOP (FT): None TYPE: _____

BACKFILL, BOTTOM (FT): None

SUMP, BOTTOM (FT): None

TOTAL DEPTH (FT): 12.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: expandable well point @ 12.0

COMPLETED BY: T.P. House DATE: 2/12/98

CHECKED BY: _____ DATE: _____

518 5/10

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 03298 PROJECT NAME: SPRRP PROGRAM: NA
 SCREENED FORMATION: Alluvium/Bedrock DRILLING CONTRACTOR: TEC
 DRILLING METHOD: geoprobe DATE DRILLED: 2/12-2/13/98 DATE COMPLETED: 2/13/98
 RIG GEOLOGIST: Tim Lovseth LOGGING GEOLOGIST: Tim Lovseth
 COMPLETED DEPTH (FT): 25 ESTIMATED DEPTH TO BEDROCK (FT): 23
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): _____

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): None INITIAL WATER LEVEL (FT): _____ DATE MEASURED: _____
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 5.24 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 5 ft
 SURFACE CASING, I.D. (IN): 3/4 in TYPE: Sch 80
 SURFACE SEAL TOP (FT): none TYPE: _____
 PROTECTIVE CASING, I.D. (IN): 2 TYPE: Sch 40 PVC
 PROTECTIVE CASING, BOTTOM (FT): 5 ft
 IF APPLICABLE SECONDARY CASING, TOP (FT): none BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): none TYPE: _____
 CENTRALIZER, O.D. (IN): none TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): none TYPE: _____
 BENTONITE SEAL TOP (FT): 0 TYPE: Wyoming granular bentonite
 BENTONITE SEAL BOTTOM (FT): 18
 FILTER PACK, TOP (FT): 18
 FILTER PACK TYPE: 16-40 BRAND: Colorado Silty Sand
 SURFACE CASING, BOTTOM (FT): 20 SCREEN, TOP (FT): 20
 SCREEN SLOT SIZE (.000 IN): .010 SCREEN, I.D. (IN): 3/4 in
 SCREEN, BOTTOM (FT): 25 TYPE: Sch 80 BRAND: Geoprobe Systems
 SUMP, TOP (FT): none TYPE: _____
 FILTER PACK, BOTTOM (FT): 25
 BACKFILL, TOP (FT): none TYPE: _____
 BACKFILL, BOTTOM (FT): none
 SUMP, BOTTOM (FT): none
 TOTAL DEPTH (FT): 25
 REMARKS: expendable well pt @ 25.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: T.P. Lovseth DATE: 2/13/98

CHECKED BY: _____ DATE: _____

88 511

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 03398 PROJECT NAME: Solar Ponds Phase 1 PROGRAM: NA
 SCREENED FORMATION: Alluvium/Bedrock DRILLING CONTRACTOR: TEG
 DRILLING METHOD: Geoprobe DATE DRILLED: 2/17/98 DATE COMPLETED: 2/17/98
 RIG GEOLOGIST: Tim Lovseth LOGGING GEOLOGIST: Tim Lovseth
 COMPLETED DEPTH (FT): 19 ESTIMATED DEPTH TO BEDROCK (FT): 16.5
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): _____ INITIAL WATER LEVEL (FT): _____ DATE MEASURED: _____
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 5 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 5
 SURFACE CASING, I.D. (IN): 3/4 TYPE: Sch 80
 SURFACE SEAL, TOP (FT): none TYPE: _____
 PROTECTIVE CASING, I.D. (IN): 2 TYPE: Sch 40
 PROTECTIVE CASING, BOTTOM (FT): 5
 IF APPLICABLE SECONDARY CASING, TOP (FT): none BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): none TYPE: _____
 CENTRALIZER, O.D. (IN): none TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): none TYPE: _____
 BENTONITE SEAL TOP (FT): 0 TYPE: Wyoming Bentonite
 BENTONITE SEAL BOTTOM (FT): 12
 FILTER PACK, TOP (FT): 14 1/2
 FILTER PACK TYPE: 16-40 BRAND: Colorado Silica Sand
 SURFACE CASING, BOTTOM (FT): 14 SCREEN, TOP (FT): 14
 SCREEN SLOT SIZE (.000 IN): .010 SCREEN, I.D. (IN): 3/4
 SCREEN, BOTTOM (FT): 19 TYPE: Sch 80 BRAND: Geoprobe
 SUMP, TOP (FT): none TYPE: _____
 FILTER PACK, BOTTOM (FT): 19
 BACKFILL, TOP (FT): none TYPE: _____
 BACKFILL, BOTTOM (FT): none
 SUMP, BOTTOM (FT): none
 TOTAL DEPTH (FT): 19
 REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: Tim Lovseth DATE: 2/17/98

CHECKED BY: _____ DATE: _____

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 03494 PROJECT NAME: Solar Ponds Phase PROGRAM: NA
 SCREENED FORMATION: Alluvium/Bedrock DRILLING CONTRACTOR: IEG
 DRILLING METHOD: Geoprobe DATE DRILLED: 2/17-2/18/98 DATE COMPLETED: 2/18/98
 RIG GEOLOGIST: Tim House LOGGING GEOLOGIST: Tim House
 COMPLETED DEPTH (FT): 16 ESTIMATED DEPTH TO BEDROCK (FT): 13 Ft
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 3/4

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): _____ DATE MEASURED: _____
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 5 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 5
 SURFACE CASING, I.D. (IN): 3/4 TYPE: Sch 80
 SURFACE SEAL TOP (FT): none TYPE: _____
 PROTECTIVE CASING, I.D. (IN): 2 TYPE: 2\" sch 40 Pvc
 PROTECTIVE CASING, BOTTOM (FT): _____
 IF APPLICABLE SECONDARY CASING, TOP (FT): none BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): none TYPE: _____
 CENTRALIZER, O.D. (IN): none TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): none TYPE: _____
 BENTONITE SEAL TOP (FT): 0 TYPE: Wyoming Bentonite
 BENTONITE SEAL BOTTOM (FT): 10
 FILTER PACK, TOP (FT): 10
 FILTER PACK TYPE: 16-40 BRAND: Colorado Silica Sand
 SURFACE CASING, BOTTOM (FT): 11 SCREEN, TOP (FT): 11
 SCREEN SLOT SIZE (.000 IN): 010 SCREEN, I.D. (IN): 3/4
 SCREEN, BOTTOM (FT): 16 TYPE: Sch 80 BRAND: Geoprobe Systems
 SUMP, TOP (FT): none TYPE: _____
 FILTER PACK, BOTTOM (FT): 16
 BACKFILL, TOP (FT): none TYPE: _____
 BACKFILL, BOTTOM (FT): none
 SUMP, BOTTOM (FT): none
 TOTAL DEPTH (FT): 16

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: _____

COMPLETED BY: Justin L. [Signature] DATE: 2/18/98

CHECKED BY: _____ DATE: _____

NEW WELL ID# 03998

U.S. Department of Energy Rocky Flats Plant

Form GT.6B

(Rev. 3)

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 03198 PROJECT NAME: 983 PAD/RYAN'S PIT PLUME PROGRAM: RMS-ER
 SCREENED FORMATION: W32 / COLUMBIA DRILLING CONTRACTOR: IT / UNIVERSAL
 DRILLING METHOD: Geoprobe DATE DRILLED: 4/23/98 DATE COMPLETED: 4/23/98
 RIG GEOLOGIST: Jim Cox LOGGING GEOLOGIST: Jim Cox
 COMPLETED DEPTH (FT): 8.0 ESTIMATED DEPTH TO BEDROCK (FT): 8.0
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/27/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 4/28/98
 PROTECTIVE CASING, TOP (FT): 1.0 (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 1.0
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): _____ TYPE: _____
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): _____
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: Granular Bent.
 BENTONITE SEAL, BOTTOM (FT): 2.0 Hydrated 2/5 prang
 FILTER PACK, TOP (FT): 2.0
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 3.0 SCREEN, TOP (FT): 3.0
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 7.8 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 7.8 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 8.0
 BACKFILL, TOP (FT): 8.0 TYPE: MED. BENT. PLUG
 BACKFILL, BOTTOM (FT): 10.0
 SUMP, BOTTOM (FT): 8.0
 TOTAL DEPTH (FT): 10.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: Jim Cox DATE: 5/5/98

CHECKED BY: PZj DATE: 5/11/98

546 514

NEW WELL ID# 04098

U.S. Department of Energy Rocky Flats Plant

Form GT.6B

(Rev. 3)

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 03248

PROJECT NAME: 903 PAD/RYAN'S PIT PLUME

PROGRAM: RMLS-ER

SCREENED FORMATION:

DRILLING CONTRACTOR: IT/UNIVERSAL

DRILLING METHOD: auger

DATE DRILLED:

DATE COMPLETED:

RIG GEOLOGIST: Jim Cox

LOGGING GEOLOGIST: Jim Cox

COMPLETED DEPTH (FT): 7.9

ESTIMATED DEPTH TO BEDROCK (FT):

BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST

DURING DRILLING (GAL): 0

INITIAL WATER LEVEL (FT): DRY

DATE MEASURED: 4/27/98

COMPLETED WATER LEVEL (FT): DRY

DATE MEASURED: 4/28/98

PROTECTIVE CASING, TOP (FT): 1.0 (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): 1.0

SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40

SURFACE SEAL, TOP (FT): TYPE:

PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40

PROTECTIVE CASING, BOTTOM (FT):

IF
APPLICABLE

SECONDARY CASING, TOP (FT): NA BOTTOM (FT):

SECONDARY CASING, I.D. (IN): NA TYPE:

CENTRALIZER, O.D. (IN): NA TOP (FT): BOTTOM (FT):

GROUT SEAL, TOP (FT): NA TYPE:

BENTONITE SEAL, TOP (FT): 0.0 TYPE: Granular Bent

BENTONITE SEAL, BOTTOM (FT): 2.0

Hydrated w/ spray

FILTER PACK, TOP (FT): 2.0

FILTER PACK TYPE: 16/40 silica sand BRAND: CSS

SURFACE CASING, BOTTOM (FT): 2.9 SCREEN, TOP (FT): 2.9

SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"

SCREEN, BOTTOM (FT): 7.7 TYPE: PVC sch 40 BRAND:

SUMP, TOP (FT): 2.7.7 TYPE: PVC sch 40 threaded end cap

FILTER PACK, BOTTOM (FT): 7.9

BACKFILL, TOP (FT): 7.9 TYPE: BENT. PLUG MED

BACKFILL, BOTTOM (FT): 14.1

SUMP, BOTTOM (FT): 7.9

TOTAL DEPTH (FT): 14.1

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS:

COMPLETED BY: Jim Cox

DATE: 5/5/98

CHECKED BY:

DATE: 5.11.98

5/11/98

Groundwater Monitoring Well and Piezometer Report

NEW WELL ID # **04198** **SL 5/24/98**

LOCATION CODE: **C3348** PROJECT NAME: **903 PAD/RYAN'S PIT PLUME PROGRAM** **RMS-ER**

SCREENED FORMATION: **IT / UNIVERSAL** DRILLING CONTRACTOR: **IT / UNIVERSAL**

DRILLING METHOD: **geoprobe** DATE DRILLED: **4/27/98** DATE COMPLETED: **4/27/98**

RIG GEOLOGIST: **Jim Cox** LOGGING GEOLOGIST: **Jim Cox**

COMPLETED DEPTH (FT): **13.0** ESTIMATED DEPTH TO BEDROCK (FT): **2.0**

BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): **2.0**

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): **0**

INITIAL WATER LEVEL (FT): **DRY** DATE MEASURED: **4/27/98**

COMPLETED WATER LEVEL (FT): **DRY** DATE MEASURED: **4/24/98**

PROTECTIVE CASING, TOP (FT): **1.0** (FROM GROUND SURFACE)

SURFACE CASING (STICKUP), TOP (FT): **1.0**

SURFACE CASING, I.D. (IN): **3/4"** TYPE: **PVC sch 40**

SURFACE SEAL, TOP (FT): **1.0** TYPE: **PVC sch 40**

PROTECTIVE CASING, I.D. (IN): **1.5"** TYPE: **PVC sch 40**

PROTECTIVE CASING, BOTTOM (FT): **1.0**

IF APPLICABLE SECONDARY CASING, TOP (FT): **NA** BOTTOM (FT): **NA**

SECONDARY CASING, I.D. (IN): **NA** TYPE: **NA**

CENTRALIZER, O.D. (IN): **NA** TOP (FT): **NA** BOTTOM (FT): **NA**

GROUT SEAL, TOP (FT): **NA** TYPE: **NA**

BENTONITE SEAL, TOP (FT): **0.0** TYPE: **Granular Bent.**

BENTONITE SEAL, BOTTOM (FT): **6.9** TYPE: **Hydrated w/spray**

FILTER PACK, TOP (FT): **6.9**

FILTER PACK TYPE: **16/40 silica sand** BRAND: **CSS**

SURFACE CASING, BOTTOM (FT): **8.0** SCREEN, TOP (FT): **8.0**

SCREEN SLOT SIZE (.000 IN): **0.010** SCREEN, I.D. (IN): **3/4"**

SCREEN, BOTTOM (FT): **12.8** TYPE: **PVC sch 40** BRAND: **NA**

SUMP, TOP (FT): **12.8** TYPE: **PVC sch 40 threaded end cap**

FILTER PACK, BOTTOM (FT): **13.0**

BACKFILL, TOP (FT): **13.0** TYPE: **Bent. Plug. M60**

BACKFILL, BOTTOM (FT): **18.1**

SUMP, BOTTOM (FT): **13.0**

TOTAL DEPTH (FT): **18.1**

REMARKS: **ALL MEASUREMENTS WILL BE MADE FROM GROUND SURFACE.**

COMPLETED BY: **Jim Cox**DATE: **5/5/98**CHECKED BY: **P. J. J.**DATE: **5.11.98**

5/8 5/16

NEW WELL ID# 04298

U.S. Department of Energy Rocky Flats Plant

JL 5/29/98

Form GT.6B

(Rev. 3)

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 01198A PROJECT NAME: 903 PAD/RVAD'S PIT PLUME PROGRAM: RMRS-ER
 SCREENED FORMATION: COLLUVIUM/SOIL DRILLING CONTRACTOR: IT/UNIVERSAL
 DRILLING METHOD: SCREW DATE DRILLED: 4/9/98 DATE COMPLETED: 4/9/98
 RIG GEOLOGIST: JIM COX LOGGING GEOLOGIST: JIM COX
 COMPLETED DEPTH (FT): 6.0 ESTIMATED DEPTH TO BEDROCK (FT): 18.8
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.0"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): 0 INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 4/10/98
 COMPLETED WATER LEVEL (FT): DRY DATE MEASURED: 4/29/98
 PROTECTIVE CASING, TOP (FT): 0.90 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.90
 SURFACE CASING, I.D. (IN): 3/4" TYPE: PVC sch 40
 SURFACE SEAL, TOP (FT): 0.0 TYPE: gran. bent hydrated w/ spray
 PROTECTIVE CASING, I.D. (IN): 1.5" TYPE: PVC sch 40
 PROTECTIVE CASING, BOTTOM (FT): 0.80
 IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL, TOP (FT): NA TYPE: _____
 BENTONITE SEAL, TOP (FT): 0.0 TYPE: granular bent hydrated w/ spray
 BENTONITE SEAL, BOTTOM (FT): 2.9
 FILTER PACK, TOP (FT): 2.9
 FILTER PACK TYPE: 16/40 silica sand BRAND: CSS
 SURFACE CASING, BOTTOM (FT): 4.0 SCREEN, TOP (FT): 4.0
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 3/4"
 SCREEN, BOTTOM (FT): 5.8 TYPE: PVC sch 40 BRAND: _____
 SUMP, TOP (FT): 5.8 TYPE: PVC sch 40 threaded end cap
 FILTER PACK, BOTTOM (FT): 6.0
 BACKFILL, TOP (FT): NA TYPE: _____
 BACKFILL, BOTTOM (FT): NA
 SUMP, BOTTOM (FT): 6.0
 TOTAL DEPTH (FT): 6.0
 REMARKS: partner well to 01198

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY:

JIM COX

DATE:

4/9/98

CHECKED BY:

[Signature]

DATE:

5-11-98

544 517

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 10049 PROJECT NAME: BLDG. 123 PROGRAM: GROUNDWATER
 SCREENED FORMATION: ALLUVIUM DRILLING CONTRACTOR: TERRA
 DRILLING METHOD: GEOPRIBE DATE DRILLED: 7/30-31/98 DATE COMPLETED: 7/31/98
 RIG GEOLOGIST: J. BOYLAN LOGGING GEOLOGIST: _____
 COMPLETED DEPTH (FT): 9.0 ~~8.8~~ ESTIMATED DEPTH TO BEDROCK (FT): NOT PENETRATED
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): N/A INITIAL WATER LEVEL (FT): 3.38 DATE MEASURED: 7/31/98
 COMPLETED WATER LEVEL (FT): 4.44 DATE MEASURED: 8/3/98

PROTECTIVE CASING, TOP (FT): 0.0 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.5 below ground FLUSH MOUNT
 SURFACE CASING, I.D. (IN): 0.75 TYPE: Sch. 40 PVC
 SURFACE SEAL, TOP (FT): ~0.7 below ground TYPE: concrete
 PROTECTIVE CASING, I.D. (IN): 8 TYPE: STEEL MANHOLE SKIRT
 PROTECTIVE CASING, BOTTOM (FT): 1.0
 IF APPLICABLE SECONDARY CASING, TOP (FT): 0.2 below ground BOTTOM (FT): 1.5
 SECONDARY CASING, I.D. (IN): 2.0 TYPE: Sch 40 PVC
 CENTRALIZER, O.D. (IN): N/A TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): N/A TYPE: _____
 BENTONITE SEAL TOP (FT): 1.0 TYPE: GRANULAR BENTONITE
 BENTONITE SEAL BOTTOM (FT): 2.87 2.9
 FILTER PACK, TOP (FT): 2.9
 FILTER PACK TYPE: 16/40 SILICA SAND BRAND: CSS1
 SURFACE CASING, BOTTOM (FT): 3.8 (3.77) SCREEN, TOP (FT): 3.8 (3.77)
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 0.75
 SCREEN, BOTTOM (FT): 8.65 TYPE: SCH 40 PVC BRAND: _____
 SUMP, TOP (FT): 8.65 TYPE: TURBID END-CAP (NOT TRUE SUMP)
 FILTER PACK, BOTTOM (FT): 9.0
 BACKFILL, TOP (FT): 9.0 TYPE: NATIVE MATERIALS
 BACKFILL, BOTTOM (FT): 11.0
 SUMP, BOTTOM (FT): 8.8
 TOTAL DEPTH (FT): 11.0

REMARKS: ① SECONDARY CASING INSTALLED TO ENABLE USE OF 2" LOCKING
② HOLE COLLAPSED BELOW 8.8'

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: T. LUTHERER / J. BOYLAN DATE: 7/31/98
 CHECKED BY: _____ DATE: _____

500 518

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 10198 PROJECT NAME: Bldg. 123 PROGRAM: GROUNDWATER
 SCREENED FORMATION: ALLUVIUM DRILLING CONTRACTOR: TERRA
 DRILLING METHOD: GEOPROBE DATE DRILLED: 8/10/98 DATE COMPLETED: 8/14/98
 RIG GEOLOGIST: BOYLAN LOGGING GEOLOGIST: _____
 COMPLETED DEPTH (FT): 13.2 ESTIMATED DEPTH TO BEDROCK (FT): NOT PENETRATED
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): N/A INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 8/10/98
 COMPLETED WATER LEVEL (FT): 12.69 DATE MEASURED: 8/13/98

PROTECTIVE CASING, TOP (FT): 0.0 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.5 below ground FLUSH MOUNT
 SURFACE CASING, I.D. (IN): 0.75 TYPE Sch. 40 PVC
 SURFACE SEAL TOP (FT): ~0.6 below ground TYPE CONCRETE
 PROTECTIVE CASING, I.D. (IN): 8 TYPE STEEL MANHOLE SKIRT
 PROTECTIVE CASING, BOTTOM (FT): 1.0
 IF APPLICABLE SECONDARY CASING, TOP (FT): 0.2 BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): 2.0 TYPE Sch 40 PVC
 CENTRALIZER, O.D. (IN): N/A TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): N/A TYPE _____
 BENTONITE SEAL TOP (FT): 1.95 TYPE GRANULAR BENTONITE
 BENTONITE SEAL BOTTOM (FT): 4.9
 FILTER PACK, TOP (FT): 4.9
 FILTER PACK TYPE: 16/40 SILICA SAND BRAND: CSS1
 SURFACE CASING, BOTTOM (FT): 5.26 SCREEN, TOP (FT): 5.26
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 0.75
 SCREEN, BOTTOM (FT): 13.06 TYPE Sch 40 PVC BRAND: _____
 SUMP, TOP (FT): 13.06 TYPE THREADED END-CAP (NOT TRUE SUMP)
 FILTER PACK, BOTTOM (FT): 13.21
 BACKFILL, TOP (FT): 13.21 TYPE NATIVE MATERIALS
 BACKFILL, BOTTOM (FT): 13.3
 SUMP, BOTTOM (FT): 13.21
 TOTAL DEPTH (FT): 13.3

REMARKS: ① SECONDARY CASING INSTALLED TO ENABLE USE OF 2" LOCKING J-CAP.

COMPLETED BY: J BOYLAN DATE: 8/10/98

CHECKED BY: _____ DATE: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

504519

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 10298 PROJECT NAME: BLDG. 123 PROGRAM: GROUNDWATER
 SCREENED FORMATION: ALLUVIUM DRILLING CONTRACTOR: TERRA
 DRILLING METHOD: GEOPRIDE DATE DRILLED: 8/4-5/98 DATE COMPLETED: 8/5/98
 RIG GEOLOGIST: J. BOYLAN LOGGING GEOLOGIST: _____
 COMPLETED DEPTH (FT): 15.66 ESTIMATED DEPTH TO BEDROCK (FT): NOT PENETRATED
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): N/A INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 8/5/98
 COMPLETED WATER LEVEL (FT): 6.73 DATE MEASURED: 8/11/98
 PROTECTIVE CASING, TOP (FT): 0.0 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.6 below ground FLUSH MOUNT
 SURFACE CASING, I.D. (IN): 0.75 TYPE: Sch. 40 PVC
 SURFACE SEAL TOP (FT): 0.7 below ground TYPE: CONCRETE
 PROTECTIVE CASING, I.D. (IN): 8 TYPE: STEEL MANHOLE SKIRT
 PROTECTIVE CASING, BOTTOM (FT): 1.0
 IF APPLICABLE SECONDARY CASING, TOP (FT): 0.3 BOTTOM (FT): 1.6
 SECONDARY CASING, I.D. (IN): 2.0 TYPE: Sch 40 PVC
 CENTRALIZER, O.D. (IN): N/A TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): N/A TYPE: _____
 BENTONITE SEAL TOP (FT): 1.1 TYPE: GRANULAR BENTONITE
 BENTONITE SEAL BOTTOM (FT): 3.8
 FILTER PACK, TOP (FT): 3.8
 FILTER PACK TYPE: 16/40 SILICA SAND BRAND: CSS 1
 SURFACE CASING, BOTTOM (FT): 5.84 SCREEN, TOP (FT): 5.84
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 0.75
 SCREEN, BOTTOM (FT): 15.6 TYPE: SCH 40 PVC BRAND: _____
 SUMP, TOP (FT): 15.6 TYPE: THREADED END-CAP (NOT TRUE SUMP)
 FILTER PACK, BOTTOM (FT): 15.66
 BACKFILL, TOP (FT): 15.66 TYPE: NATIVE MATERIALS
 BACKFILL, BOTTOM (FT): 16.0
 SUMP, BOTTOM (FT): 15.66
 TOTAL DEPTH (FT): 16.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: ① SECONDARY CASING INSTALLED TO ENABLE USE OF 2" LOCKING J-CAP
② BOREHOLE
WAS COLLAPSED BELOW 15.66'
DATA

COMPLETED BY: J. BOYLAN DATE: 8/5/98

CHECKED BY: _____ DATE: _____

802 520

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 10348 PROJECT NAME: BLDG. 123 PROGRAM: GROUNDWATER
 SCREENED FORMATION: ALLUVIUM DRILLING CONTRACTOR: TERRA
 DRILLING METHOD: GEOPROBE DATE DRILLED: 8/11/98 DATE COMPLETED: 8/13/98
 RIG GEOLOGIST: J. BOYAN LOGGING GEOLOGIST: _____
 COMPLETED DEPTH (FT): 11.26 ESTIMATED DEPTH TO BEDROCK (FT): NOT PENETRATED
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST INITIAL WATER LEVEL (FT): DRY DATE MEASURED: 8/11/98
 DURING DRILLING (GAL): N/A COMPLETED WATER LEVEL (FT): 8.25 DATE MEASURED: 8/17/98

PROTECTIVE CASING, TOP (FT): 0.0 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.5 below ground FLUSH MOUNT
 SURFACE CASING, I.D. (IN): 0.75 TYPE: Sch. 40 PVC
 SURFACE SEAL TOP (FT): ~0.7 TYPE: CONCRETE
 PROTECTIVE CASING, I.D. (IN): 2 TYPE: STEEL MANHOLE SKIRT
 PROTECTIVE CASING, BOTTOM (FT): 1.0
 IF SECONDARY CASING, TOP (FT): 0.3 BOTTOM (FT): _____
 APPLICABLE SECONDARY CASING, I.D. (IN): 2.0 TYPE: Sch 40 PVC
 CENTRALIZER, O.D. (IN): N/A TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): N/A TYPE: _____
 BENTONITE SEAL TOP (FT): 2.1 ^{SEE NOTE 3} TYPE: GRANULAR BENTONITE
 BENTONITE SEAL BOTTOM (FT): 4.75
 FILTER PACK, TOP (FT): 4.75
 FILTER PACK TYPE: 16/40 SILICA SAND BRAND: CSS1
 SURFACE CASING, BOTTOM (FT): 5.31 SCREEN, TOP (FT): 5.31
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 0.75
 SCREEN, BOTTOM (FT): 11.11 TYPE: Sch 40 PVC BRAND: _____
 SUMP, TOP (FT): 11.11 TYPE: TURFED END-CAP (NOT TRUE SUMP)
 FILTER PACK, BOTTOM (FT): 11.26
 BACKFILL, TOP (FT): N/A TYPE: _____
 BACKFILL, BOTTOM (FT): N/A
 SUMP, BOTTOM (FT): 11.26
 TOTAL DEPTH (FT): 11.26

REMARKS: ① SECONDARY CASING INSTALLED TO ENABLE USE OF 2" LOCKING J-CAP.
② WELL INSTALLED IN 5TH ATTEMPTED BOREHOLE (SHALLOW REFUSAL IN PREVIOUS 4). OBSERVED UNUSUAL GROUND CONDITIONS AT FINAL LOC. (NEAR REFUSAL @ 1.4', THEN BURSTED TO 2.1', VARIABLE FILL W/ BENTONITE ABOVE 2.1' - INDICATES VOID IS PRESENT. HOWEVER, CORE SHOWED NOTHING UNUSUAL)
 COMPLETED BY: J. Boyan DATE: 8/13/98

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

CHECKED BY: _____ DATE: _____

803 521

ORR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 10498 PROJECT NAME: Bldg. 123 PROGRAM: GROUNDWATER
 SCREENED FORMATION: ALLUVIUM DRILLING CONTRACTOR: TERRA
 DRILLING METHOD: GEPROBE DATE DRILLED: 8/7/98 DATE COMPLETED: 8/13/98
 RIG GEOLOGIST: J. BOYLAN LOGGING GEOLOGIST: _____
 COMPLETED DEPTH (FT): 12.1 ESTIMATED DEPTH TO BEDROCK (FT): NOT PENETRATED
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): N/A INITIAL WATER LEVEL (FT): 5.57 DATE MEASURED: 8/7/98
 COMPLETED WATER LEVEL (FT): 5.42 DATE MEASURED: 8/12/98

PROTECTIVE CASING, TOP (FT): 0.0 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.5 below ground **FLUSH MOUNT**
 SURFACE CASING, I.D. (IN): 0.75 TYPE: Sch. 40 PVC
 SURFACE SEAL, TOP (FT): -0.7 TYPE: CONCRETE
 PROTECTIVE CASING, I.D. (IN): 8 TYPE: STEEL MANHOLE SKIRT
 PROTECTIVE CASING, BOTTOM (FT): 1.0
 IF APPLICABLE SECONDARY CASING, TOP (FT): 0.35 BOTTOM (FT): 1.46
 SECONDARY CASING, I.D. (IN): 2.0 TYPE: Sch 40 PVC
 CENTRALIZER, O.D. (IN): N/A TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): N/A TYPE: _____
 BENTONITE SEAL TOP (FT): 0.65 TYPE: GRANULAR BENTONITE
 BENTONITE SEAL BOTTOM (FT): 2.0
 FILTER PACK, TOP (FT): 2.0
 FILTER PACK TYPE: 16/40 SILICA SAND BRAND: CSS1 **PLUS CAVED "FLOWING" SANDS - SEE NOTE ②**
 SURFACE CASING, BOTTOM (FT): 6.12 SCREEN, TOP (FT): 6.12
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 0.75
 SCREEN, BOTTOM (FT): 11.93 TYPE: SCH 40 PVC BRAND: _____
 SUMP, TOP (FT): 11.93 TYPE: THREADED END-CAP (NOT TRUE SUMP)
 FILTER PACK, BOTTOM (FT): 12.1 (SEE NOTE ②)
 BACKFILL, TOP (FT): N/A TYPE: NATIVE MATERIALS
 BACKFILL, BOTTOM (FT): N/A
 SUMP, BOTTOM (FT): 12.08 ≈ 12.1
 TOTAL DEPTH (FT): 12.1

ALL MEASUREMENTS WILL BE MADE FROM GROUND SURFACE.

REMARKS: ① SECONDARY CASING INSTALLED TO ENABLE USE OF 2" LOCKING J-
 ② HOLE COLLAPSED DURING ADDITION OF FILTER PACK: ADDED ENOUGH FOR ~3-4' OF ANNULUS, YET DEPTH SUDDENLY UP TO 2.0'. EXPECT MIXED FILTER PACK & NATIVE MATERIALS, WHICH LOOK LIKE FILL (MODERATELY CLEAN SANDS).
 COMPLETED BY: J. BOYLAN DATE: 8/7/98

CHECKED BY: _____

DATE: _____

529 528

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 10598 PROJECT NAME: BLDG. 123 PROGRAM: GROUNDWATER
 SCREENED FORMATION: ALLUVIUM DRILLING CONTRACTOR: TIERRA
 DRILLING METHOD: GEOPROBE DATE DRILLED: 8/6/98 DATE COMPLETED: 8/13/98
 RIG GEOLOGIST: J. BOYLAN LOGGING GEOLOGIST: _____
 COMPLETED DEPTH (FT): 8.22 ESTIMATED DEPTH TO BEDROCK (FT): NOT PENETRATED
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): N/A INITIAL WATER LEVEL (FT): 4.60 DATE MEASURED: 8/7/98
 COMPLETED WATER LEVEL (FT): 4.67 DATE MEASURED: 8/11/98

PROTECTIVE CASING, TOP (FT): 0.0 (FROM GROUND SURFACE)
 SURFACE CASING (STICKUP), TOP (FT): 0.6 below ground FLUSH MOUNT
 SURFACE CASING, I.D. (IN): 0.75 TYPE: Sch. 40 PVC
 SURFACE SEAL TOP (FT): ~0.7 TYPE: CONCRETE
 PROTECTIVE CASING, I.D. (IN): 8 TYPE: STEEL MANHOLE SKIRT
 PROTECTIVE CASING, BOTTOM (FT): 1.0
 IF APPLICABLE SECONDARY CASING, TOP (FT): 0.4 BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): 2.0 TYPE: Sch 40 PVC
 CENTRALIZER, O.D. (IN): N/A TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): N/A TYPE: _____
 BENTONITE SEAL TOP (FT): 0.8 TYPE: GRANULAR BENTONITE
 BENTONITE SEAL BOTTOM (FT): 1.7
 FILTER PACK, TOP (FT): 1.7
 FILTER PACK TYPE: 16/40 SILICA SAND BRAND: CSS1
 SURFACE CASING, BOTTOM (FT): 2.26 SCREEN, TOP (FT): 2.26
 SCREEN SLOT SIZE (.000 IN): 0.010 SCREEN, I.D. (IN): 0.75
 SCREEN, BOTTOM (FT): 8.07 TYPE: SCH 40 PVC BRAND: _____
 SUMP, TOP (FT): 8.07 TYPE: THREADED END-CAP (NOT TRUE SUMP)
 FILTER PACK, BOTTOM (FT): 8.22
 BACKFILL, TOP (FT): 8.22 TYPE: NATIVE MATERIALS
 BACKFILL, BOTTOM (FT): APPROX. 9.5
 SUMP, BOTTOM (FT): 8.22
 TOTAL DEPTH (FT): APPROX. 9.5 (1" HOLE BELOW 8.22')
 REMARKS: ① SECONDARY CASING INSTALLED TO ENABLE USE OF 2" LOCKING J-CAP.
② HOLE COLLAPSED BELOW 8.22'.

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: J. BOYLAN DATE: 8/16/98

CHECKED BY: _____ DATE: _____

JRR 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20098 PROJECT NAME: North PA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe / Push / Hammer DATE DRILLED: 6/23-27/98 DATE COMPLETED: 6/25/98
 FIG GEOLOGIST: R. KOEHLER LOGGING GEOLOGIST: F. GRIGSBY
 COMPLETED DEPTH (FT): 22.26 ft subsurf. ESTIMATED DEPTH TO BEDROCK (FT): Between 18.0 and 19.4 ft subsurf. = 6 ft.
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 3 inches

QUANTITY OF FLUIDS LOST
 DURING DRILLING (GAL): N4

INITIAL WATER LEVEL (FT): 7.1 ft subsurf DATE MEASURED: 6-25-98

COMPLETED WATER LEVEL (FT): 7.71 ft subsurf DATE MEASURED: 7-1-98

PROTECTIVE CASING, TOP (FT): 0.0 FROM GROUND SURFACE

SURFACE CASING (STICKUP), TOP (FT): 0.55 ft ss

FLUSH
MOUNT

SS =
Subsurface

SURFACE CASING, I.D. (IN): 3/4 inch TYPE: Sch 40 PVC

SURFACE SEAL TOP (FT): 0.3 ft ss TYPE: Aquaseal Granular Bentonite

PROTECTIVE CASING, I.D. (IN): 3 inch TYPE: Cist Iron Flush Main

PROTECTIVE CASING, BOTTOM (FT): 1.08 ft ss

IF APPLICABLE SECONDARY CASING, TOP (FT): 0.37 ft ss BOTTOM (FT): 2.37 ft ss

SECONDARY CASING, I.D. (IN): 2 inch TYPE: Sch 40 PVC

CENTRALIZER, O.D. (IN): N4 TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL TOP (FT): N4 TYPE: _____

BENTONITE SEAL TOP (FT): 0.3 ft ss TYPE: Aquaseal Granular Bentonite

BENTONITE SEAL BOTTOM (FT): 10.0 ft ss

FILTER PACK TOP (FT): 10.0 ft ss

FILTER PACK TYPE: 16-40 silica sand BRAND: Colorado Silica Sand Inc.

SURFACE CASING, BOTTOM (FT): 12.33 ft ss SCREEN, TOP (FT): 12.33 ft ss

SCREEN SLOT SIZE (100 IN): 0.010 inch SCREEN, I.D. (IN): 3/4 inch

SCREEN, BOTTOM (FT): 21.76 ft ss TYPE: Sch 40 PVC BRAND: N4

SUMP TOP (FT): 21.96 TYPE: Sch 40 PVC w/ pig valve

FILTER PACK, BOTTOM (FT): 22.26 ft ss

BACKFILL TOP (FT): N4 TYPE: _____

BACKFILL, BOTTOM (FT): N4

SUMP, BOTTOM (FT): 22.26

TOTAL DEPTH (FT): 22.26

ALL MEASUREMENTS
 WILL BE MADE FROM
 GROUND SURFACE

REMARKS: _____

COMPLETED BY: Robert Koehler DATE: 7/2/99

CHECKED BY: F. Grigsby DATE: 2-25-99

586 524

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20198 PROJECT NAME: North PA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe/ Push/ Hammer DATE DRILLED: 4/29/98 DATE COMPLETED: 7/1/98
 RIG GEOLOGIST: R. Koehler LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH (FT): 9.96 ft sub surf. ESTIMATED DEPTH TO BEDROCK (FT): 9.5 to 16.0 ft FG
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 inch

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): N4 DATE MEASURED: _____
 COMPLETED WATER LEVEL (FT): 7.51 ft SS DATE MEASURED: 7/2/98

PROTECTIVE CASING, TOP (FT): 0.0 ft FROM GROUND SURFACE:

SURFACE CASING, STICKUP, TOP (FT): 0.63 ft SS

Flush
Mount

SS =
Subsurface

SURFACE CASING, I.D. (IN): 3/4 inch TYPE: PVC Sch 40

SURFACE SEAL, TOP (FT): 0.3 ft SS TYPE: Aquaset Granular Bentonite

PROTECTIVE CASING, I.D. (IN): 2 inch TYPE: PVC Sch 40 Cost: Tron Flush Mount
8 inch RPK 7/2/98

PROTECTIVE CASING, BOTTOM (FT): 1.08 ft SS

IF APPLICABLE SECONDARY CASING, TOP (FT): 0.33 ft SS BOTTOM (FT): 2.33 ft SS

SECONDARY CASING, I.D. (IN): 2 inch TYPE: PVC Sch 40

CENTRALIZER, I.D. (IN): N4 TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL, TOP (FT): N4 TYPE: _____

BENTONITE SEAL, TOP (FT): 0.8 ft SS TYPE: Aquaset Granular Bentonite

BENTONITE SEAL, BOTTOM (FT): 4.0 ft SS

FILTER PACK, TOP (FT): 4.0 ft SS

FILTER PACK TYPE: 16-40 Silica Sand BRAND: Colomda Silica Sand Inc.

SURFACE CASING, BOTTOM (FT): 4.93 ft SS SCREEN, TOP (FT): 4.08 ft SS

SCREEN SLOT SIZE (000 IN): 0.010 inch SCREEN, I.D. (IN): 3/4 inch

SCREEN, BOTTOM (FT): 9.77 ft SS TYPE: Sch 40 PVC BRAND: N4

SUMP, TOP (FT): 9.77 ft SS TYPE: Sch 40 PVC w/ pop rivets

FILTER PACK, BOTTOM (FT): 10.0 ft SS

BACKFILL, TOP (FT): 10.0 ft SS TYPE: Aquaset Granular Bentonite

BACKFILL, BOTTOM (FT): 16.0 ft SS

SUMP, BOTTOM (FT): 9.96 ft SS

TOTAL DEPTH (FT): 16.0 ft SS

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: R. Koehler DATE: 7/2/98

CHECKED BY: F. Grigsby DATE: 02/25/99

587 525

522 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20298 PROJECT NAME: North PA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra 1 RPK 7/2/98
 DRILLING METHOD: Geoprobe/Push/Hammer DATE DRILLED: 7-2-98 DATE COMPLETED: 7-2-98
 FIG GEOLOGIST: R. Koehler LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH (FT): 11.54 ft ss ESTIMATED DEPTH TO BEDROCK (FT): 11.4 ft ss
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 inch

QUANTITY OF FLUIDS LOST: NA INITIAL WATER LEVEL (FT): Dry DATE MEASURED: 7/2/98
 DURING DRILLING (GAL): NA COMPLETED WATER LEVEL (FT): NA DATE MEASURED: NA

PROTECTIVE CASING, TOP (FT): 0.0 ft FROM GROUND SURFACE:

SURFACE CASING (STICKUP), TOP (FT): 0.42 ft ss Flush Mount SS= Subsurface

SURFACE CASING, I.D. (IN): 3/4 inch TYPE PVC Sch 40

SURFACE SEAL, TOP (FT): 0.8 ft TYPE Aquasol Granular Bentonite

PROTECTIVE CASING, I.D. (IN): 8 inch TYPE Cst Iron Flush mount

PROTECTIVE CASING, BOTTOM (FT): 1.08 ft ss

IF APPLICABLE SECONDARY CASING, TOP (FT): 0.21 ft ss BOTTOM (FT): 2.21 ft ss
 SECONDARY CASING, I.D. (IN): 2 inch TYPE Sch 40 PVC

CENTRALIZER, I.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL, TOP (FT): NA TYPE _____

BENTONITE SEAL, TOP (FT): 0.8 ft ss TYPE Aquasol Granular Bentonite

BENTONITE SEAL, BOTTOM (FT): 4.6 ft ss

FILTER PACK, TOP (FT): 4.6 ft ss

FILTER PACK TYPE: 16-40 silica sand BRAND: C.S.S.T.

SURFACE CASING, BOTTOM (FT): 6.57 ft ss SCREEN, TOP (FT): 6.57 ft ss

SCREEN SLOT SIZE (100 IN): 0.010 inch SCREEN, I.D. (IN): 3/4 inch

SCREEN, BOTTOM (FT): 11.19 ft ss TYPE PVC sch 40 BRAND: NA

SUMP, TOP (FT): 11.19 ft ss TYPE PVC Sch 40 w/ pop rivets

FILTER PACK, BOTTOM (FT): 11.6 ft ss

BACKFILL, TOP (FT): 11.6 ft ss TYPE Aquasol Granular Bentonite

BACKFILL, BOTTOM (FT): 13.3 ft ss 11.6 ft ss

SUMP, BOTTOM (FT): 11.54 ft ss

TOTAL DEPTH (FT): 13.3 ft ss

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: R. Koehler Michael Koehler DATE: 7/2/98


CHECKED BY: F. Grigsby Paul Grigsby DATE: 02/25/99

528 526

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20398 PROJECT NAME: North RA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tieva
 DRILLING METHOD: Geoprobe / Push / Hammer DATE DRILLED: 7/6/98 DATE COMPLETED: 7/7/98
 RIG GEOLOGIST: R. Koenig LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH (FT): 23 ESTIMATED DEPTH TO BEDROCK (FT): 19.5-19.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 inch nd

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): 10.7 ft. DATE MEASURED: 7/7/98
 COMPLETED WATER LEVEL (FT): 10.22 ft DATE MEASURED: 7/8/98
 PROTECTIVE CASING, TOP (FT): 0.0 FROM GROUND SURFACE:



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: Robert MuellerDATE: 7-8-98CHECKED BY: F. GrigsbyDATE: 02/25/99

58557

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20498 PROJECT NAME: North PA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe/Push/Hammer DATE DRILLED: 7-7-98 DATE COMPLETED: 7-9-98
 LOG GEOLOGIST: R. Koehler LOGGING GEOLOGIST: R. Koehler / F. Grigsby
 COMPLETED DEPTH (FT): 22.25 ft ss ESTIMATED DEPTH TO BEDROCK (FT): 21.0-22.0 ft
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 inch

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL.): NA INITIAL WATER LEVEL (FT): 11.31 ft ss DATE MEASURED: 7/9/98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 0.0 ft FROM GROUND SURFACE:

SURFACE CASING (STICKUP), TOP (FT): 0.53 ft ss Flush Mount SS = subsurface

SURFACE CASING, I.D. (IN): 3/4 inch TYPE PVC Sch. 40

SURFACE SEAL TOP (FT): 0.7 ft ss TYPE Aquaset Granular Bentonite

PROTECTIVE CASING, I.D. (IN): 0.82 ft TYPE Cast Iron flush mount

PROTECTIVE CASING, BOTTOM (FT): 1.08 ft ss.

IF SECONDARY CASING, TOP (FT): 0.55 ft ss BOTTOM (FT): 2.25 ft ss
 APPLICABLE

SECONDARY CASING, I.D. (IN): 2 inch TYPE PVC Sch 40

CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL TOP (FT): NA TYPE _____

BENTONITE SEAL TOP (FT): 0.7 ft ss TYPE Aquaset Granular Bentonite

BENTONITE SEAL BOTTOM (FT): 10.5 ft ss

FILTER PACK TOP (FT): 10.5 ft ss

FILTER PACK TYPE: 16-40 Silica Sand BRAND: Colorado Silica Sand Inc.

SURFACE CASING, BOTTOM (FT): 12.35 ft ss SCREEN, TOP (FT): 12.35 ft ss

SCREEN SLOT SIZE (100 IN): 0.010 inch SCREEN, I.D. (IN): 3/4 inch

SCREEN, BOTTOM (FT): 21.98 ft ss TYPE PVC Sch 40 BRAND: NA

SUMP TOP (FT): 21.98 ft ss TYPE PVC Sch 40 w/pup rivets

FILTER PACK, BOTTOM (FT): 22.25 ft ss

BACKFILL TOP (FT): NA TYPE _____

BACKFILL BOTTOM (FT): NA

SUMP, BOTTOM (FT): 22.25 ft ss

TOTAL DEPTH (FT): 22.25 ft ss

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.


COMPLETED BY: Robert Koehler DATE: 7/9/98

CHECKED BY: Fred Grigsby DATE: 2/26/99

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20598 PROJECT NAME: PA North Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe, Continuous Core DATE DRILLED: 07-13-98 DATE COMPLETED: 07-13-98
 FIG GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH FT: 21.0 ESTIMATED DEPTH TO BEDROCK FT: 74.5
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2.14

QUANTITY OF FLUIDS LOST DURING DRILLING GALL: NA INITIAL WATER LEVEL FT: None DATE MEASURED: 07-13-98
 COMPLETED WATER LEVEL FT: - DATE MEASURED: _____
 PROTECTIVE CASING, TOP FT: 0.0 FROM GROUND SURFACE: (Flush Mount)



SURFACE CASING, STICKUP, TOP FT: -0.7 EGS
 SURFACE CASING, DOWN, IN: 3/4 TYPE: PVC Sch. 40
 SURFACE SEAL, TOP FT: 0.9 TYPE: Agglomerate Granular Bentonite
 PROTECTIVE CASING, DOWN, IN: 0.82 TYPE: Flush Mount
 PROTECTIVE CASING, BOTTOM FT: 1.1
 IF APPLICABLE SECONDARY CASING, TOP FT: -0.25 BOTTOM FT: 2.25
 SECONDARY CASING, DOWN, IN: 2.14 TYPE: PVC Sch. 40
 CENTRALIZER, DOWN, IN: NA TOP FT: _____ BOTTOM FT: _____
 GROUT SEAL, TOP FT: NA TYPE: _____
 BENTONITE SEAL, TOP FT: 1.1 TYPE: Granular Bentonite
 BENTONITE SEAL, BOTTOM FT: 4.7
 FILTER PACK, TOP FT: 4.7
 FILTER PACK TYPE: 16-40 Silica Sand BRAND: CSEI
 SURFACE CASING, BOTTOM FT: 5.7 SCREEN, TOP FT: 5.7
 SCREEN SLOT SIZE: 100 MM 0.10 in SCREEN, DOWN, IN: 3/4
 SCREEN, BOTTOM FT: 15.2 TYPE: PVC Sch. 40 BRAND: CLE
 SUMP, TOP FT: 15.2 TYPE: Perforated PVC
 FILTER PACK, BOTTOM FT: 15.2
 BACKFILL, TOP FT: 15.2 TYPE: Granular Bentonite
 BACKFILL, BOTTOM FT: 21.0
 SUMP, BOTTOM FT: 15.5
 TOTAL DEPTH FT: 21.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE


REMARKS: _____

COMPLETED BY: Fred Grigsby DATE: 07-14-98
 CHECKED BY: _____ DATE: _____

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20698 PROJECT NAME: PA N. Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierney
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 07-14-98 DATE COMPLETED: _____
 FIG. GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH: 21.9 ESTIMATED DEPTH TO BEDROCK: 20.4
 BORE-OLE DIAMETER IN SCREENED INTERVAL (IN): 2.14

QUANTITY OF FLUIDS LOST DURING DRILLING GALS: NA INITIAL WATER LEVEL FT: NONE DATE MEASURED: 07-14-98
 COMPLETED WATER LEVEL FT: _____ DATE MEASURED: _____
 PROTECTIVE CASING, TOP FT: 0.0 FROM GROUND SURFACE (Flush Mount)



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: Fred C. Grigsby DATE: 07-14-98
 CHECKED BY: _____ DATE: _____

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20798 PROJECT NAME: North PA Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 07-16-98 DATE COMPLETED: 07-16-98
 FIG GEOLOGIST: T. Roydon / F. Grigsby LOGGING GEOLOGIST: F. Grigsby / J. Boylston
 COMPLETED DEPTH: 27.2 ESTIMATED DEPTH TO BEDROCK: 26.2
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL FT: 15.71 DATE MEASURED: 07-16-98
 COMPLETED WATER LEVEL FT: _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP FT: 0.0 FROM GROUND SURFACE: (Flush Mount)

SURFACE CASING STOCKUP, TOP FT: -0.6 (BGS)

SURFACE CASING, I.D. IN: 3/4" TYPE: PVC Sch. 40

SURFACE SEAL, TOP FT: 0.9' TYPE: Aquaset Granular Bentonite

PROTECTIVE CASING, I.D. IN: 0.824" TYPE: FLUSH MOUNT

PROTECTIVE CASING, BOTTOM FT: 1.1'

APPLICABLE SECONDARY CASING, TOP FT: 0.25 (BGS) BOTTOM FT: 2.25

SECONDARY CASING, I.D. IN: 2.125" TYPE: PVC Sch. 40

CENTRALIZER, I.D. IN: NA TOP FT: _____ BOTTOM FT: _____

GROUT SEAL, TOP FT: NA TYPE: _____

BENTONITE SEAL, TOP FT: 1.1 TYPE: Granular Bentonite

BENTONITE SEAL, BOTTOM FT: 14.4'

FILTER PACK, TOP FT: 14.4'

FILTER PACK TYPE: 16-40 Silica Sand BRAND: GSSI

SURFACE CASING, BOTTOM FT: 15.4' SCREEN, TOP FT: 15.4'

SCREEN SLOT SIZE (IN): 10/10 in SCREEN, I.D. IN: 3/4 in

SCREEN, BOTTOM FT: 26.9 TYPE: PVC Sch. 40 BRAND: LEI

SUMP, TOP FT: 26.9 TYPE: PVC Cap - Riveted

FILTER PACK, BOTTOM FT: 27.2'

BACKFILL, TOP FT: 27.2 TYPE: Granular Bentonite

BACKFILL, BOTTOM FT: 29.0'

SUMP, BOTTOM FT: 27.2'

TOTAL DEPTH, FT: 29.0'

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Frederic C. Grigsby DATE: 03-01-99

CHECKED BY: _____ DATE: _____

83531

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20898 PROJECT NAME: PA-North Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe-Continuous Core DATE DRILLED: 07-17-98 DATE COMPLETED: 07-17
 RIG GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH (FT): 16.1 ESTIMATED DEPTH TO BEDROCK (FT): 15.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 in

QUANTITY OF FLUIDS LOST DURING DRILLING GAIN: NA INITIAL WATER LEVEL (FT): None DATE MEASURED: 07-17-98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 0-0 FROM GROUND SURFACE (Flush Mount)

SURFACE CASING STICKUP, TOP (FT): -0.5 (BGS)

SURFACE CASING, DIA. (IN): 3/4 in TYPE: PVC-Sch. 40

SURFACE SEAL TOP (FT): -0.7 TYPE: Granular Bentonite

PROTECTIVE CASING, DIA. (IN): 0.824 TYPE: Flush Mount

PROTECTIVE CASING, BOTTOM (FT): 1.1

IF APPLICABLE SECONDARY CASING, TOP (FT): -0.3 (BGS) BOTTOM (FT): 2.3

SECONDARY CASING, DIA. (IN): 2 in TYPE: PVC-Sch. 40

CENTRALIZER, DIA. (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL TOP (FT): NA TYPE: _____

BENTONITE SEAL TOP (FT): 1.1 TYPE: Granular Bentonite

BENTONITE SEAL BOTTOM (FT): 7.0

FILTER PACK, TOP (FT): 7.0

FILTER PACK TYPE: 16-40 Silica sand BRAND: CSSI

SURFACE CASING, BOTTOM (FT): 7.8 SCREEN, TOP (FT): 7.8

SCREEN SLOT SIZE (000 IN): 10/10 in SCREEN, DIA. (IN): 3/4 in

SCREEN, BOTTOM (FT): 15.8 TYPE: PVC Sch. 40 BRAND: CEI

SUMP, TOP (FT): 15.8 TYPE: PVC Cap Riveted

FILTER PACK, BOTTOM (FT): 16.1

BACKFILL, TOP (FT): NA TYPE: _____

BACKFILL, BOTTOM (FT): NA

SUMP, BOTTOM (FT): 16.1

TOTAL DEPTH (FT): 16.1

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: Fred C. Grigsby DATE: 03-01-99

CHECKED BY: _____ DATE: _____

534 532

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20998 PROJECT NAME: PA - N. Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Thermo Environmental
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 08-18-98 DATE COMPLETED: 08-18-98
 FIG GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH FT: 10-9' ESTIMATED DEPTH TO BEDROCK FT: 10-3'
 BOREHOLE DIAMETER IN SCREENED INTERVAL IN: 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING GALL: NA INITIAL WATER LEVEL FT: Dry DATE MEASURED: 08-18-98
 COMPLETED WATER LEVEL FT: _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP FT: 1-2' FROM GROUND SURFACE:

SURFACE CASING STOCKUP, TOP FT: 0-9'

SURFACE CASING, I.D. IN: 3/4 in TYPE: PVC Sch. 40

SURFACE SEAL, TOP FT: GL TYPE: Bentonite Gravel

PROTECTIVE CASING, I.D. IN: 2 in TYPE: PVC Sch. 40

PROTECTIVE CASING, BOTTOM FT: 0-8'

APPLICABLE SECONDARY CASING, TOP FT: NA BOTTOM FT: _____
 SECONDARY CASING, I.D. IN: NA TYPE: _____

CENTRALIZER, I.D. IN: NA TOP FT: _____ BOTTOM FT: _____

GROUT SEAL, TOP FT: NA TYPE: _____

BENTONITE SEAL, TOP FT: GL TYPE: Granular Bentonite (Agassiz)

BENTONITE SEAL, BOTTOM FT: 4-9'

FILTER PACK, TOP FT: 4-9'

FILTER PACK TYPE: 16-40 Silica Sand BRAND: CSSI

SURFACE CASING, BOTTOM FT: 5-9' SCREEN, TOP FT: 5-9'

SCREEN SLOT SIZE: 10/10 in SCREEN, I.D. IN: 3/4 in

SCREEN, BOTTOM FT: 10-6' TYPE: PVC Sch. 40 BRAND: CEI

SUMP, TOP FT: 10-6' TYPE: PVC Cap - Routed

FILTER PACK, BOTTOM FT: 10-9'

BACKFILL, TOP FT: NA TYPE: _____

BACKFILL, BOTTOM FT: NA

SUMP, BOTTOM FT: 10-9'

TOTAL DEPTH FT: 10-9'

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: Original Construction Form Done 08/18/98

Revised 03-01-98

COMPLETED BY: Fred C. Grigsby DATE: 03-01-99

CHECKED BY: _____ DATE: _____

535 533

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 20998 PROJECT NAME: N. PA. PLUME PROGRAM:
 SCREENED FORMATION: AIUV DRILLING CONTRACTOR: Tierra Environmental
 DRILLING METHOD: Geoprobe DATE DRILLED: 08-18-98 DATE COMPLETED: 08-18-98
 RIG GEOLOGIST: E. Grigsby LOGGING GEOLOGIST: E. Grigsby
 COMPLETED DEPTH (FT): 10.9' ESTIMATED DEPTH TO BEDROCK (FT): 10.3'
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): Dry DATE MEASURED: 08-17-98
 COMPLETED WATER LEVEL (FT): DATE MEASURED:

PROTECTIVE CASING, TOP (FT): 7.2' (OK) FROM GROUND SURFACE 7.2' (OK)
OK

SURFACE CASING (STICKUP), TOP (FT): 2.9' (OK)

SURFACE CASING, I.D. (IN): 3/4" TYPE PVC

SURFACE SEAL, TOP (FT): 2.2' TYPE Bentonite granules

PROTECTIVE CASING, I.D. (IN): 2 TYPE PVC

PROTECTIVE CASING, BOTTOM (FT): 6.3'

IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT):
 SECONDARY CASING, I.D. (IN): NA TYPE

CENTRALIZER, O.D. (IN): NA TOP (FT): BOTTOM (FT):

GROUT SEAL, TOP (FT): NA TYPE NA

BENTONITE SEAL, TOP (FT): 6.2' TYPE Bentonite granules

BENTONITE SEAL, BOTTOM (FT): 4.9'

FILTER PACK, TOP (FT): 4.9'

FILTER PACK TYPE: Sand Seal BRAND: CSE-5

SURFACE CASING, BOTTOM (FT): 5.7' SCREEN, TOP (FT): 5.9'

SCREEN SLOT SIZE (100 IN): 100 SCREEN, I.D. (IN): 3/4

SCREEN, BOTTOM (FT): 10.9' TYPE PVC BRAND:

SUMP, TOP (FT): NA TYPE NA PVC end cap (not true sump)

FILTER PACK, BOTTOM (FT): 10.9'

BACKFILL, TOP (FT): NA TYPE NA

BACKFILL, BOTTOM (FT): NA

SUMP, BOTTOM (FT): NA 10.9

TOTAL DEPTH (FT): 10.9'

REMARKS:

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Fred C. Drigels DATE: 08-18-98


CHECKED BY: DATE:

536 534

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21098 PROJECT NAME: PA - North Platte PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 07-20-98 DATE COMPLETED: 07-20-98
 FIG GEOLOGIST: F. Griggley LOGGING GEOLOGIST: F. Griggley
 COMPLETED DEPTH (FT): 20.0 ESTIMATED DEPTH TO BEDROCK (FT): 18.2
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): None DATE MEASURED: 07-20-98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: Fred C. Driggley DATE: 03-01-99

CHECKED BY: _____ DATE: _____

53A 535

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21198 PROJECT NAME: PA - North Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Terra
 DRILLING METHOD: Geoprobe Continuous Core DATE DRILLED: 07-22-98 DATE COMPLETED: 07-22-98
 LOGGING GEOLOGIST: J. Boylan / F. Grigsby LOGGING GEOLOGIST: J. Boylan / F. Grigsby
 COMPLETED DEPTH: 29.5' ESTIMATED DEPTH TO BEDROCK: 28.0'
 BORE-HOLE DIAMETER IN SCREENED INTERVAL: 2 in.

QUANTITY OF FLUIDS LOST: _____ INITIAL WATER LEVEL: 13.9' DATE MEASURED: 07-22-98
 DURING DRILLING: NA COMPLETED WATER LEVEL: _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP: 0.75' FROM GROUND SURFACE:

SURFACE CASING, STICKUP, TOP: 0.5'

SURFACE CASING, I.D. IN: 3/4 in TYPE: PVC Sch. 40

SURFACE SEAL, TOP: GL TYPE: Granular Bentonite - Aquasol

PROTECTIVE CASING, I.D. IN: 2" TYPE: PVC Sch. 40

PROTECTIVE CASING, BOTTOM: 1.25'

APPLICABLE SECONDARY CASING, TOP: NA BOTTOM: _____

SECONDARY CASING, I.D. IN: NA TYPE: _____

CENTRALIZER, I.D. IN: NA TOP: _____ BOTTOM: _____

GROUT SEAL, TOP: NA TYPE: _____

BENTONITE SEAL, TOP: GL TYPE: Granular Bentonite

BENTONITE SEAL, BOTTOM: 8.0'

FILTER PACK, TOP: 8.0'

FILTER PACK TYPE: 16-40 Silica Sd. BRAND: SSI

SURFACE CASING, BOTTOM: 14.7' SCREEN, TOP: 14.7'

SCREEN SLOT SIZE: 100 M - 010 SCREEN, I.D. IN: 3/4"

SCREEN, BOTTOM: 29.1' TYPE: PVC Sch 40 BRAND: CEI

SUMP, TOP: 29.1' TYPE: PVC Cap - Riveted

FILTER PACK, BOTTOM: 29.4'

BACKFILL, TOP: NA TYPE: _____

BACKFILL, BOTTOM: NA

SUMP, BOTTOM: 29.4'

TOTAL DEPTH: 29.5'

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: Filter Pack would not flow to bottom of hole - most of screen in formation s/d gravel

COMPLETED BY: Fred C. Grigsby DATE: 03-01-99

CHECKED BY: _____ DATE: _____

536

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21298 PROJECT NAME: N-PA PLUME PROGRAM: _____
 SCREENED FORMATION: Ba2 DRILLING CONTRACTOR: TERRA Environmental
 DRILLING METHOD: Geoprobe DATE DRILLED: 08-19-98 DATE COMPLETED: 08-19-98
 RIG GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH FT: 20.0 ESTIMATED DEPTH TO BEDROCK FT: 19.1
 BOREHOLE DIAMETER IN SCREENED INTERVAL IN: 2

QUANTITY OF FLUIDS LOST DURING DRILLING GAL: NA INITIAL WATER LEVEL FT: _____ DATE MEASURED: _____
 COMPLETED WATER LEVEL FT: _____ DATE MEASURED: _____
 PROTECTIVE CASING TOP FT: 20.1 FROM GROUND SURFACE: (Flush Mount)
 SURFACE CASING STICKUP TOP FT: -0.3
 SURFACE CASING I.D. IN: 0.75 TYPE: PVC
 SURFACE SEAL TOP FT: GL TYPE: Cement (Quickcrete)
 PROTECTIVE CASING I.D. IN: 8 in TYPE: Flush Mount
 PROTECTIVE CASING BOTTOM FT: 1.0 (Bottom of Flush Mount)
 SECONDARY CASING TOP FT: _____ BOTTOM FT: _____
 SECONDARY CASING I.D. IN: 2 in TYPE: PVC
 CENTRALIZER I.D. IN: NA TOP FT: NA BOTTOM FT: NA
 GROUT SEAL TOP FT: NA TYPE: _____
 BENTONITE SEAL TOP FT: 1.0 TYPE: Bentonite Gravel
 BENTONITE SEAL BOTTOM FT: 9.0
 FILTER PACK TOP FT: 9.0
 FILTER PACK TYPE: Silica Sand (10-40) BRAND: CSSS
 SURFACE CASING BOTTOM FT: 10.07 SCREEN TOP FT: 10.07
 SCREEN SLOT SIZE 100 IN: -0.10 SCREEN I.D. IN: 0.75
 SCREEN BOTTOM FT: 19.7 TYPE: PVC BRAND: CEI
 SUMP TOP FT: NA TYPE: Screw on Cap/Riveted plug
 FILTER PACK BOTTOM FT: 20.0
 BACKFILL TOP FT: 20.0 TYPE: Natural
 BACKFILL BOTTOM FT: 21.0
 SUMP BOTTOM FT: NA 20.0
 TOTAL DEPTH FT: 21.0

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: Hole deepened to 21.0' during
Clear out run. Original depth was 20.0'

COMPLETED BY: Fred Grigsby DATE: 08-20-98
 CHECKED BY: _____ DATE: _____

538 537

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21398 PROJECT NAME: NPA PLUMES PROGRAM: _____
 SCREENED FORMATION: Qal DRILLING CONTRACTOR: Terra Environmental
 DRILLING METHOD: Geoprobe DATE DRILLED: 08-25-98 DATE COMPLETED: 08-25-98
 LOGGING GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH (FT): 16.0 ESTIMATED DEPTH TO BEDROCK (FT): 13.1
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): Dry DATE MEASURED: 08-25-98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 1.0 FROM GROUND SURFACE:

SURFACE CASING STICKUP, TOP (FT): 0.7

SURFACE CASING, ID (IN): 0.75 TYPE: PVC

SURFACE SEAL, TOP (FT): GL TYPE: Bentonite Granules

PROTECTIVE CASING, ID (IN): 2 TYPE: PVC

PROTECTIVE CASING, BOTTOM (FT): 1.0

APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____

SECONDARY CASING, ID (IN): NA TYPE: _____

CENTRALIZER, ID (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL, TOP (FT): NA TYPE: _____

BENTONITE SEAL, TOP (FT): GL TYPE: _____

BENTONITE SEAL, BOTTOM (FT): 6.0

FILTER PACK, TOP (FT): 6.0

FILTER PACK TYPE: 16-40 Subclass BRAND: CSSI

SURFACE CASING, BOTTOM (FT): 7.1 SCREEN, TOP (FT): 7.1

SCREEN SLOT SIZE (X100 IN): 10/10 SCREEN, ID (IN): 0.75

SCREEN, BOTTOM (FT): 13.7 TYPE: PVC Sch. 40 BRAND: CEI

SUMP, TOP (FT): 13.7 TYPE: PVC Cap/Riveted

FILTER PACK, BOTTOM (FT): 14.0

BACKFILL, TOP (FT): 14.0 TYPE: Bentonite Granules

BACKFILL, BOTTOM (FT): 16.0

SUMP, BOTTOM (FT): FC NA 14.3

TOTAL DEPTH (FT): 16.0

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: Fred Grigsby

DATE: 08-25-98

CHECKED BY: _____

DATE: _____

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE 21498 PROJECT NAME N. PA. Plume PROGRAM
 SCREENED FORMATION Gal DRILLING CONTRACTOR Terra
 DRILLING METHOD Geoprobe DATE DRILLED 08-24-98 DATE COMPLETED 08-24-98
 FIG GEOLOGIST F. Grigsby LOGGING GEOLOGIST F. Grigsby
 COMPLETED DEPTH 11.0' ESTIMATED DEPTH TO BEDROCK 9.9'
 BOREHOLE DIAMETER IN SCREENED INTERVAL 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING NA INITIAL WATER LEVEL Dry DATE MEASURED 08-24-98
 COMPLETED WATER LEVEL DATE MEASURED
 PROTECTIVE CASING TOP GL FROM GROUND SURFACE (Flush Mount)

SURFACE CASING STOCKUP TOP -0.4' BGL Flush Mount
 SURFACE CASING ID IN 0.75 TYPE PVC
 SURFACE SEAL TOP -1.0' BGL TYPE Ready Mix Cement
 PROTECTIVE CASING ID IN 8 TYPE Metal Flush Mount
 PROTECTIVE CASING BOTTOM -1.0' BGL
 IF APPLICABLE SECONDARY CASING TOP -0.2' BGL BOTTOM 2.2' BGL
 SECONDARY CASING ID IN 2 TYPE PVC
 CENTRALIZER ID IN NA TOP BOTTOM
 GROUT SEAL TOP TYPE
 BENTONITE SEAL TOP -1.0' BGL TYPE Bentonite Gravel
 BENTONITE SEAL BOTTOM 5.0'
 FILTER PACK TOP 5.0'
 FILTER PACK TYPE 16-40 Silica Sand BRAND CSSB
 SURFACE CASING BOTTOM 6.0' SCREEN TOP 6.0'
 SCREEN SLOT SIZE 100 IN 0.10 SCREEN ID IN 0.75
 SCREEN BOTTOM 10.7' TYPE PVC BRAND CEI
 SLUR TOP 10.7' TYPE PVC Cap/Rivet
 FILTER PACK BOTTOM 11.0'
 BACKFILL TOP 11.0' TYPE Bentonite Gravel
 BACKFILL BOTTOM 15.0'
 SUMP BOTTOM 11.0'
 TOTAL DEPTH 15.0'

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS COMPLETED BY Fred Grigsby DATE 08-25-98CHECKED BY DATE

541539

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21598 PROJECT NAME: PA - N. Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 8/26/98 DATE COMPLETED: 8/26/98
 RIG GEOLOGIST: F. Engasby LOGGING GEOLOGIST: F. Engasby
 COMPLETED DEPTH: 14.0 ESTIMATED DEPTH TO BEDROCK: 13.0
 BOREHOLE DIAMETER IN SCREENED INTERVAL: 2 in

QUANTITY OF FLUIDS LOST: NA INITIAL WATER LEVEL: None DATE MEASURED: 8/26/98
 DURING DRILLING: NA COMPLETED WATER LEVEL: _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP FT: 0.85 FROM GROUND SURFACE

SURFACE CASING, STICKUP, TOP FT: 0.7

SURFACE CASING, I.D. IN: 3/4 in TYPE: PVC Sch. 40

SURFACE SEAL, TOP FT: GL TYPE: Acquiset-Granular Bentonite

PROTECTIVE CASING, I.D. IN: 2 in TYPE: PVC Sch. 40

PROTECTIVE CASING, BOTTOM FT: 1.5

APPLICABLE SECONDARY CASING, TOP FT: NA BOTTOM FT: _____

SECONDARY CASING, I.D. IN: NA TYPE: _____

CENTRALIZER, I.D. IN: NA TOP FT: _____ BOTTOM FT: _____

GROUT SEAL, TOP FT: NA TYPE: _____

BENTONITE SEAL, TOP FT: GL TYPE: _____

BENTONITE SEAL, BOTTOM FT: 5.0

FILTER PACK, TOP FT: 5.0

FILTER PACK TYPE: 16-40 Silica Sd. BRAND: CSSS

SURFACE CASING, BOTTOM FT: 6.1 SCREEN, TOP FT: 6.1

SCREEN SLOT SIZE: 100 IN: 10/10 in SCREEN, I.D. IN: 3/4 in

SCREEN, BOTTOM FT: 13.7 TYPE: PVC Sch. 40 BRAND: CEE

SUMP, TOP FT: 13.7 TYPE: PVC CAP/Rivet

FILTER PACK, BOTTOM FT: 14.0

BACKFILL, TOP FT: 14.0 TYPE: Granular Bentonite

BACKFILL, BOTTOM FT: 15.0

SUMP, BOTTOM FT: 14.0

TOTAL DEPTH, FT: 15.0

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

COMPLETED BY: Fred C. Dringby DATE: 03-04-99

CHECKED BY: _____ DATE: _____

548 540

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: BH21698 PROJECT NAME: North PA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: TIERRA
 DRILLING METHOD: Geoprobe/Push/Hammer DATE DRILLED: 08/27/98 DATE COMPLETED: 08/27/98
 FIG GEOLOGIST: R. KOEHLER LOGGING GEOLOGIST: R. KOEHLER
 COMPLETED DEPTH (FT): 21.6 ft ESTIMATED DEPTH TO BEDROCK (FT): 13.5 ft
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 inch

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): _____ DATE MEASURED: _____
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): 1.2 ft FROM GROUND SURFACE:

SURFACE CASING (STICKUP), TOP (FT): 0.9 ft

SURFACE CASING, I.D. (IN): 3/4 inch TYPE: PVC, Sch 40

SURFACE SEAL TOP (FT): Surface TYPE: PDSCo Granular Bentonite

PROTECTIVE CASING, I.D. (IN): 2 inch TYPE: PVC, Sch. 40

PROTECTIVE CASING, BOTTOM (FT): 0.8 ft

IF APPLICABLE SECONDARY CASING, TOP (FT): NA BOTTOM (FT): _____
 SECONDARY CASING, I.D. (IN): NA TYPE: _____

CENTRALIZER, I.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL TOP (FT): NA TYPE: _____

BENTONITE SEAL TOP (FT): Surface TYPE: PDSCo Granular Bentonite

BENTONITE SEAL BOTTOM (FT): 4.8 ft

FILTER PACK, TOP (FT): 4.8 ft

FILTER PACK TYPE: 16-40 silica sand BRAND: Colo Silica Sand Inc

SURFACE CASING, BOTTOM (FT): 5.91 ft SCREEN, TOP (FT): 5.91 ft

SCREEN SLOT SIZE (000 IN): 0.010 inch SCREEN, I.D. (IN): 3/4 inch

SCREEN, BOTTOM (FT): 15.3 ft TYPE: PVC, Sch 40 BRAND: NA

SUMP, TOP (FT): 15.3 ft Approximately Bottom of Slotted Interval to end cap
PVC endcap with Pop-Rivets

FILTER PACK, BOTTOM (FT): 15.8 ft

BACKFILL, TOP (FT): 15.8 ft TYPE: PDSCo Granular Bentonite

BACKFILL, BOTTOM (FT): 20 ft

SUMP, BOTTOM (FT): 15.3 ft

TOTAL DEPTH (FT): 20 ft

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: R. KOEHLER DATE: 8/27/98


543 541

522 3/31/94

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: BH21798 PROJECT NAME: North PA Plume PROGRAM: Groundwater
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: TIERRA RPK
 DRILLING METHOD: Grabber/Push/Hammer DATE DRILLED: 08/31/98 DATE COMPLETED: 08/09/01/9
 FIG GEOLOGIST: R. KOEHLER LOGGING GEOLOGIST: R. KOEHLER
 COMPLETED DEPTH (FT): 26.0 ft ESTIMATED DEPTH TO BEDROCK (FT): 24.0 ft
 SCREEN HOLE DIAMETER IN SCREENED INTERVAL (IN): 2 inch

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): Dry DATE MEASURED: 8/31/98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____
 PROTECTIVE CASING, TOP (FT): 0.0 ft FROM GROUND SURFACE: flush mount



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: _____

COMPLETED BY: ROBERT KOEHLERRobert KoehlerDATE: 08/31/98

549 54/2

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21898 PROJECT NAME: North PA Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tiering
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 9/8/98 DATE COMPLETED: 9/8/98
 FIG GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH FT: 22.0' ESTIMATED DEPTH TO BEDROCK FT: 18.3'
 BOREHOLE DIAMETER IN SCREENED INTERVAL IN: 2 in

QUANTITY OF FLUIDS LOST DURING DRILLING GALS: NA INITIAL WATER LEVEL FT: Dry DATE MEASURED: 9/8/98
 COMPLETED WATER LEVEL FT: _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP FT: 0.0' FROM GROUND SURFACE: Fresh Mount

SURFACE CASING STICKUP, TOP FT: 0.4' (BGL)

SURFACE CASING, ID. IN: 3/4" TYPE: PVC Sch. 40

SURFACE SEAL, TOP FT: 0.7' (BGL) TYPE: Bentonite Grout

PROTECTIVE CASING, ID. IN: 8 in TYPE: Flush Mount

PROTECTIVE CASING, BOTTOM FT: 1.1'

APPLICABLE SECONDARY CASING, TOP FT: 10.3' (BGL) BOTTOM FT: 2.3'

SECONDARY CASING, ID. IN: 2 in TYPE: PVC Sch. 40

CENTRALIZER, ID. IN: NA TOP FT: _____ BOTTOM FT: _____

GROUT SEAL, TOP FT: NA TYPE: _____

BENTONITE SEAL, TOP FT: 1.1' TYPE: Proprietary Grout/Bentonite

BENTONITE SEAL, BOTTOM FT: 11.0'

FILTER PACK, TOP FT: 11.0'

FILTER PACK TYPE: 16-40 - Submerged BRAND: CSSB

SURFACE CASING, BOTTOM FT: 12.2' SCREEN, TOP FT: 12.2'

SCREEN SLOT SIZE: 100 Mesh SCREEN, ID. IN: 3/4"

SCREEN, BOTTOM FT: 21.7' TYPE: PVC Sch. 40 BRAND: CEL

SUMP, TOP FT: 21.7' TYPE: PVC Cap/Rivet

FILTER PACK, BOTTOM FT: 22.0'

BACKFILL, TOP FT: NA TYPE: _____

BACKFILL, BOTTOM FT: NA

SUMP, BOTTOM FT: 22.0'

TOTAL DEPTH FT: 22.0'

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Fred Grigsby DATE: 3/11/99


CHECKED BY: _____ DATE: _____

543 543

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 21998 PROJECT NAME: North PA Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 9/1/98 DATE COMPLETED: 9/1/98
 RIG GEOLOGIST: R. Hochler LOGGING GEOLOGIST: R. Hochler
 COMPLETED DEPTH (FT): 20.0' ESTIMATED DEPTH TO BEDROCK (FT): NA
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2"

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): Top DATE MEASURED: 9/1/98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE

REMARKS: _____

COMPLETED BY: Robert KoehlerDATE: 3/1/99CHECKED BY: Frank DrigalskyDATE: 3/1/99

546 544

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 22098 PROJECT NAME: North PA Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 9/2/99 DATE COMPLETED: 9/3/99
 RIG GEOLOGIST: R. Koehler, J. Boylen LOGGING GEOLOGIST: R. Koehler, J. Boylen
 COMPLETED DEPTH (FT): 25.0' ESTIMATED DEPTH TO BEDROCK (FT): Unknown
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): None DATE MEASURED: 9/3/99
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____

PROTECTIVE CASING, TOP (FT): GL FROM GROUND SURFACE/Flush Mount

SURFACE CASING (STICKUP), TOP (FT): 0.4' (AGL)

SURFACE CASING, I.D. (IN): 3/4 in TYPE: PVC Sch-40

SURFACE SEAL, TOP (FT): -0.7 TYPE: Granular Bentonite

PROTECTIVE CASING, I.D. (IN): 8 in TYPE: Flush Mount

PROTECTIVE CASING, BOTTOM (FT): 1.1

IF APPLICABLE SECONDARY CASING, TOP (FT): 0.2 (AGL) BOTTOM (FT): 2.2'

SECONDARY CASING, I.D. (IN): 2 in TYPE: PVC Sch-40

CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____

GROUT SEAL, TOP (FT): NA TYPE: _____

BENTONITE SEAL, TOP (FT): GL TYPE: Granular Bentonite

BENTONITE SEAL, BOTTOM (FT): 6.5'

FILTER PACK, TOP (FT): 6.5'

FILTER PACK TYPE: 16-40 Silica Sand BRAND: CSSS

SURFACE CASING, BOTTOM (FT): 10.4' SCREEN, TOP (FT): 10.4'

SCREEN SLOT SIZE (000 IN): .010 in SCREEN, I.D. (IN): 3/4"

SCREEN, BOTTOM (FT): 24.7 TYPE: PVC Sch-40 BRAND: CEI

SUMP, TOP (FT): 24.7 TYPE: PVC Cap/Rivet

FILTER PACK, BOTTOM (FT): 25.0'

BACKFILL, TOP (FT): NA TYPE: _____

BACKFILL, BOTTOM (FT): NA

SUMP, BOTTOM (FT): 25.0'

TOTAL DEPTH (FT): 25.0'

REMARKS: _____

ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

COMPLETED BY: Robert Koehler

DATE: 3/1/99

CHECKED BY: Frank Drigdy


DATE: 3/1/99

547 545

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 22198 PROJECT NAME: North PA Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Tierra
 DRILLING METHOD: Geoprobe - Continuous Core DATE DRILLED: 9/9/98 DATE COMPLETED: 9/10/98
 FIG GEOLOGIST: F. Grigsby LOGGING GEOLOGIST: F. Grigsby
 COMPLETED DEPTH (FT): 20.0 - 17.6 ESTIMATED DEPTH TO BEDROCK (FT): Unknown
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): NA INITIAL WATER LEVEL (FT): 11.07 DATE MEASURED: 9/10/98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____
 PROTECTIVE CASING, TOP (FT): 0.0 FROM GROUND SURFACE: Flush Mount



ALL MEASUREMENTS
WILL BE MADE FROM
GROUND SURFACE.

REMARKS: _____

COMPLETED BY: Fred C. Grigsby, Fred Grigsby DATE: 3/1/99

CHECKED BY: _____ DATE: _____

548 546

Groundwater Monitoring Well and Piezometer Report

LOCATION CODE: 22298 PROJECT NAME: North PA Plume PROGRAM: _____
 SCREENED FORMATION: Alluvium DRILLING CONTRACTOR: Terra
 DRILLING METHOD: Ceoprobe - Continuous Core DATE DRILLED: 9/14/98 DATE COMPLETED: 9/14/98
 FIG GEOLOGIST: F. Grigsky LOGGING GEOLOGIST: F. Grigsky
 COMPLETED DEPTH (FT): 20.0 16.4 ESTIMATED DEPTH TO BEDROCK (FT): 16.6
 BOREHOLE DIAMETER IN SCREENED INTERVAL (IN): 2 in.

QUANTITY OF FLUIDS LOST DURING DRILLING (GAL): _____ INITIAL WATER LEVEL (FT): 2 DATE MEASURED: 9/14/98
 COMPLETED WATER LEVEL (FT): _____ DATE MEASURED: _____
 PROTECTIVE CASING, TOP (FT): 0.0 FROM GROUND SURFACE: Flush Mount

SURFACE CASING (STICKUP), TOP (FT): -0.4 (BGL)
 SURFACE CASING, I.D. (IN): 3/4 in TYPE PVC-Sch. 40
 SURFACE SEAL TOP (FT): -0.7 TYPE Granular Bentonite
 PROTECTIVE CASING, I.D. (IN): 8 in TYPE Flush Mount
 PROTECTIVE CASING, BOTTOM (FT): -1.1
 IF APPLICABLE SECONDARY CASING, TOP FT: -0.2 (BGL) BOTTOM FT: -2.2
 SECONDARY CASING, I.D. (IN): 2 in TYPE PVC-Sch. 40
 CENTRALIZER, O.D. (IN): NA TOP (FT): _____ BOTTOM (FT): _____
 GROUT SEAL TOP (FT): NA TYPE _____
 BENTONITE SEAL TOP (FT): -1.1 TYPE Granular Bentonite
 BENTONITE SEAL BOTTOM (FT): -5.5
 FILTER PACK, TOP (FT): -5.5
 FILTER PACK TYPE: 16-40 Silica Sand BRAND: CSSB
 SURFACE CASING, BOTTOM (FT): -6.5 SCREEN, TOP (FT): -6.5
 SCREEN SLOT SIZE (100 IN): .010 in SCREEN, I.D. (IN): 3/4 in
 SCREEN, BOTTOM (FT): -16.1 TYPE PVC-Sch. 40 BRAND: CLE
 SUMP, TOP (FT): -16.1 TYPE PVC cap/Recept
 FILTER PACK, BOTTOM (FT): -16.4
 BACKFILL, TOP (FT): -16.4 TYPE Granular Bentonite
 BACKFILL, BOTTOM (FT): -16.4 to 20.0
 SUMP, BOTTOM (FT): -16.4
 TOTAL DEPTH (FT): -20.0
 REMARKS: _____

ALL MEASUREMENTS
 WILL BE MADE FROM
 GROUND SURFACE

COMPLETED BY: Fred Drigby DATE: 3/1/99

CHECKED BY: _____ DATE: _____

549/549 547/547



Figure 1-2

Rocky Flats Environmental
Technology Site Map

EXPLANATION

Standard Map Features

- Buildings
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences
- Rocky Flats boundary
- Heavy duty paved roads
- Medium duty paved roads
- Light duty paved roads
- Dirt roads
- Railroads

DATA SOURCE:
Buildings, fences, hydrography, roads and other
features were digitized from aerial photography
acquired by EGIS, Inc., Las Vegas,
Digitized from the orthophotograph, 1/85

Scale = 1 : 28720
1 inch represents approximately 2393 feet

700 0 1400 2800ft


State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
P.O. Box 484
Golden, CO 80402-0484

MAP ID: 87-0063

September 27, 1999



N:\Srv\projects\ly88\rtca-rp\rtca_figures\site\map\item\map.aml

Figure 4-1
North Industrial Area
Potentiometric Surface

Well Classifications

- Plume Definition
- Plume Extent
- Building D&D
- Water Level
- Non-IMP


- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells
- Surface Water
- Monitoring Locations

Potentiometric Surface Contours - Fall 1998

- Water Level Contour
- Dashed where inferred
- Intermediate Water Level Contour
- Dashed where inferred
- Approximate extent of Unsaturated Area

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads



U.S. Department of Energy
 Rocky Flats Environmental Technology Site

**Rocky Mountain
 Remediation Services, L.L.C.**
 Geographic Information Systems Group
 Rocky Flats Environmental Technology Site
 P.O. Box 240
 Golden, CO 80622-0240

MAP ID: 86-085

September 27, 1998

NT:SVR W:\projects\ly99\flta-rpl\hss\18_vocs\figure4-1.voc=fall_water

Figure 4-2
North Industrial Area
Trichloroethene
in Groundwater Wells

Well Classifications

- Plume Definition
- Plume Extent
- Building D&D
- Water Level
- Non-IMP


- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells
- Surface Water
- Monitoring Locations

VOC Groundwater Plumes

- Trichloroethene concentration equal to or greater than 5 ug/L
- Trichloroethene concentration equal to or greater than 500 ug/L

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads



Scale = 1:2500
 1 inch represents approximately 216 feet



State Plane Coordinate Projection
 Colorado Central Zone
 NAD83 (NAD27)

U.S. Department of Energy
 Rocky Flats Environmental Technology Site

Rocky Mountain
 Remediation Services, L.L.C.
 Geographic Information Systems Group
 P.O. Box 464
 Golden, CO 80432-0464

MAP ID: RH-0085

September 27, 1999




Figure 4-4
North Industrial Area
Chloroform
in Groundwater Wells

Well Classifications

- Plume Definition
- Plume Extent
- Building D&D
- Water Level
- Non-IMP

- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells
- Surface Water
- Monitoring Locations

VOC Groundwater Plumes


- Chloroform concentration equal to or greater than 100 ug/L
- Chloroform concentration equal to or greater than 10000 ug/L

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads



Scale = 1:2500
 1 inch represents approximately 210 feet




State Plane Coordinate Projection
 Colorado Central Zone
 Datum: NAD27

U.S. Department of Energy
 Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
 Geographic Information Systems Group
 Rocky Flats Environmental Technology Site
 Golden, CO 80422-5464

September 28, 1999

MAP ID: 40-0385



[illegible]

- Plume Definition
- Plume Extent
- Building D&D
- Water Level
- Non-IMP

○ Alluvial Walls
△ Bedrock Walls
◇ Alluvial/Bedrock Walls
✦ Surface Water Monitoring Locations

☐ 1,1-Dichloroethene concentration equal to or greater than 7 ug/L

☐ Buildings and other structures
☒ Solar Evaporation Ponds (SEP)

Lakes and ponds
Streams, ditches, or other
drainage features

Fences and other barriers

Contour (20-Foot)

Paved roads

Dirt roads

Scale = 1:2590
1 inch represents approximately 216 feet

State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

**Rocky Mountain
Remediation Services, L.L.C.**
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 464
Golden, CO 80432-0464

MAF ID: 00-00385

September 23, 1994

Figure 4-6
North Industrial Area
Vinyl Chloride
in Groundwater Wells

Well Classifications

- Plume Definition
- Plume Extent
- Building D&D
- Water Level
- Non-IMP

- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells
- Surface Water
- Monitoring Locations

VOC Groundwater Plumes

- Vinyl Chloride concentration equal to or greater than 2 ug/L
- Vinyl Chloride concentration equal to or greater than 200 ug/L

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads

Scale = 1:2500
 1 inch represents approximately 210 feet


State Plane Coordinate Projection
 Colorado Central Zone
 Datum: NAD83





U.S. Department of Energy
 Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
 Geographic Information Systems Group
 Rocky Flats Environmental Technology Site
 Golden, CO 80402-2464

MAP ID: 06-0305

September 28, 1999



	PU&D Yard Monitoring Well
	Groundwater Monitor Well UHSU Surficial Material
	Groundwater Monitor Well UHSU Bedrock
	Groundwater Monitor Well UHSU Bedrock

Parameter	Location	Concentration
Borehole Locations	Groundwater Intercept System	
Landfill Slurry wall	Composite VOC Groundwater (100 X MCL)	
	Composite VOC Groundwater (concentration equal to MCL)	
PU&D Yard IHSS		

Buildings and other structures

Lakes and ponds


Streams, ditches, or other drainage features

Fences and other barriers

Contour (5-Foot)

Paved roads

Dirt roads



Scale = 1 : 3810
1 inch represents approximately 318 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site


**Rocky Mountain
Remediation Services, L.L.C.**
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 484
Golden, CO 80402-0484

MAP ID: 99-0440

September 27, 1999

Figure 4-8
Groundwater Intercept and
Diversion System Layout
at the Present Sanitary Landfill
1998

- EXPLANATION**
- Groundwater Monitor Well
 - ⊕ UHSU Surficial Material
 - ⊕ Groundwater Monitor Well
 - UHSU Bedrock
 - Groundwater Monitor Well
 - LHSU Bedrock
 - ◆ Surface Water Monitoring Locations
 - Landfill Groundwater Monitoring Wells
 - All Other Existing Wells
 - Abandoned Wells
 - IHSS 166.1, 166.2 and 166.3
 - W Slurry Wall
 - GW Intercept System - Perforated
 - GW Intercept System - Non-Perforated
 - Individual Hazardous Substance Site
 - East Landfill Pond
 - Tanks
 - Fences and other barriers
 - Contour (20-Foot)
 - Paved roads
 - Dirt roads



Scale = 1 : 2930
 1 inch represents approximately 244 feet

State Plane Coordinate Projection
 Colorado Central Zone
 Datum: NAD27

U.S. Department of Energy
 Rocky Flats Environmental Technology Site

Rocky Mountain
 Remediation Services, L.L.C.
 Geomatrix Information Systems Group
 Rocky Flats Environmental Technology Site
 P.O. Box 424
 Golden, CO 80402-0424

MAP ID: 99-0266
 September 27, 1999




Figure 4-9
Location Map
IHSS 118.1 Wells

- IHSS 118.1 Wells**
- Alluvial Wells
 - △ Bedrock Wells
 - ◇ Alluvial/Bedrock Wells
 - ★ Surface Water Monitoring Locations
 - Location of IHSS 118.1
- Standard Map Features**
- Buildings and other structures
 - ▨ Solar Evaporation Ponds (SEP)
 - Lakes and ponds
 - Streams, ditches, or other drainage features
 - Fences and other barriers
 - Contour (20-Foot)
 - == Paved roads
 - Dirt roads

Scale = 1 : 1030
 1 inch represents approximately 86 feet


25 0 50 100 ft

State Plane Coordinate Projection
 Colorado Central Zone
 Datum: NAD27

U.S. Department of Energy
 Rocky Flats Environmental Technology Site

Rocky Mountain
 Remediation Services, L.L.C.
 Geographic Information Systems Group
 Rocky Flats Environmental Technology Site
 Golden, CO 80402-6484

MAP ID: 98-0365 September 27, 1999



NT_Srvr_W:\projects\hy99\rtca-rp\hss118_vocs\hss-118.mxd

Figure 5-1
Building 123 Location Map
with D&D Monitoring Wells

EXPLANATION

IMP Well Type

D&D Monitoring

Standard Map Features

Buildings and other structures

Demolished Buildings


Streams, ditches, or other drainage features

Fences and other barriers

Contour (5-Foot)

Paved roads

Dirt roads



Scale = 1 : 760
1 inch represents approximately 63 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

**Rocky Mountain
Remediation Services, L.L.C.**
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 484
Golden, CO 80402-0484

MAP ID: nca-rpt
Golden, CO 80402-5484
September 27, 1999

149

Figure 5-2

Building 779 Location Map
with D&D Monitoring Wells


EXPLANATION

IMP Well Type

- Water Quality Flow Monitoring
- Industrial Area Flow Monitoring
- Background Flow Monitoring
- Demolition & Destruction Monitoring
- Non-IMP

Standard Map Features

- Buildings
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (5-Foot)
- Paved roads
- Dirt roads



Scale = 1 : 780
1 inch represents 65 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
Rocky Flats Environmental Technology Site
P.O. Box 484
Golden, CO 80632-0484

MAP ID: rfa-rpt

September 28, 1999





Figure 6-1
Mound Site Plume Area

EXPLANATION

- Selected IHSS Boundaries
- Approximate Location of Collection Trench
- Approximate Location of Piping and Treatment System
- Approximate Location of 72" Storm Sewer
- Large Diameter Culvert
- Recent Geoprobe Sampling Locations
- SWDES Holding Tank

Standard Map Features

- Buildings and other structures
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (5-Foot)
- Rocky Flats boundary
- Paved roads
- Dirt roads



Scale = 1:1400
1 inch represents approximately 117 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, LLC
Geographic Information Systems Group
P.O. Box 442
Golden, CO 80423-0442

MAP ID: 98-0000

September 27, 1999












Figure 6-2
Plan View of Reactive
Barrier Treatment System
Solar Ponds Plume


EXPLANATION

- LHSU Bedrock Monitoring Well
○ UHSU Bedrock Monitoring Well
● Bedrock/Alluvium Monitoring Well
○ Alluvium Monitoring Well
□ Collection Trench

Standard Map Features

- | | |
|---|--|
|  | Buildings and other structures |
|  | Solar Evaporation Ponds (SEP) |
|  | Lakes and ponds |
|  | Streams, ditches, or other drainage features |
|  | Fences and other barriers |
|  | Contour (20-Foot) |
|  | Paved roads |
|  | Dirt roads |

DATA SOURCE: Topography, bathymetry, hydrographic tracks and other data were obtained from the NOAA National Oceanic and Atmospheric Administration (NOAA) and the U.S. Geological Survey (USGS). The bathymetry was obtained from the NOAA National Oceanic and Atmospheric Administration (NOAA) and the U.S. Geological Survey (USGS). The topography was obtained from the NOAA National Oceanic and Atmospheric Administration (NOAA) and the U.S. Geological Survey (USGS). The hydrographic tracks were obtained from the NOAA National Oceanic and Atmospheric Administration (NOAA) and the U.S. Geological Survey (USGS). The other data were obtained from the NOAA National Oceanic and Atmospheric Administration (NOAA) and the U.S. Geological Survey (USGS).



Scale = 1 : 3800
1 inch represents approximately 317 feet




State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

**Rocky Mountain
Remediation Services, L.L.C.**
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 484
Golden, CO 80432-0484

MAP ID: 98-0245

September 28, 1989



NT_Srvr:\projects\fy98\98-0245\sampleloc-spond\ac_nitrate_con-uhsu.aml

Figure 6-3
East Trenches Plume Study Area

- Tetrachloroethene concentration equal to or greater than 5 ug/L
- Tetrachloroethene concentration equal to or greater than 500 ug/L

Planned Location of Groundwater Collection System

Proposed Monitoring Wells

Sampled Well Location (Installed 1988)

Existing Data Location

Surface Water Sample Points

Standard Map Features

Buildings and other structures

Lakes and ponds

Streams, ditches, or other drainage features

Fences and other barriers

Contour (5-Foot)

Rocky Flats boundary

Paved roads

Dirt roads

DATA SOURCES:
Topographic map and data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.
Groundwater data provided by the U.S. Geological Survey, Denver, Colorado, 1988.

Scale = 1 : 2920
1 inch represents approximately 243 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27


U.S. Department of Energy
Rocky Flats Environmental Technology Site



Rocky Mountain Remediation Services, LLC
Environmental Technology Site
Rocky Flats Environmental Technology Site
Colorado, 80502-0044

MAP ID: 98-0236

September 27, 1999



NT_Srv:\Projects\98\rfes-rp\98-0236\pce_plume_maps\new-wells-pce_plume_b-n.tml

The map shows a topographic representation of a site with contour lines indicating elevation. Key features include:

- IHSS 112 903 PAD**: A large rectangular area on the left side of the map.
- Ryan's Pit**: A small circular feature labeled with an arrow pointing to it.
- Monitoring Points**: Numerous points are marked with triangles and labeled with alphanumeric codes:
 - PCM 150**: PCE U, TCE 42
 - PCM 13**: PCE U, TCE 12
 - PCM 460**: PCE 23, TCE 500
 - PCM 112**: PCE U, TCE 9
 - PCM 113**: PCE U, TCE 12
 - PCM 114**: PCE U, TCE 12
 - PCM 115**: PCE U, TCE 12
 - PCM 116**: PCE U, TCE 12
 - PCM 117**: PCE U, TCE 12
 - PCM 118**: PCE U, TCE 12
 - PCM 119**: PCE U, TCE 12
 - PCM 120**: PCE U, TCE 12
 - PCM 121**: PCE U, TCE 12
 - PCM 122**: PCE U, TCE 12
 - PCM 123**: PCE U, TCE 12
 - PCM 124**: PCE U, TCE 12
 - PCM 125**: PCE U, TCE 12
 - PCM 126**: PCE U, TCE 12
 - PCM 127**: PCE U, TCE 12
 - PCM 128**: PCE U, TCE 12
 - PCM 129**: PCE U, TCE 12
 - PCM 130**: PCE U, TCE 12
 - PCM 131**: PCE U, TCE 12
 - PCM 132**: PCE U, TCE 12
 - PCM 133**: PCE U, TCE 12
 - PCM 134**: PCE U, TCE 12
 - PCM 135**: PCE U, TCE 12
 - PCM 136**: PCE U, TCE 12
 - PCM 137**: PCE U, TCE 12
 - PCM 138**: PCE U, TCE 12
 - PCM 139**: PCE U, TCE 12
 - PCM 140**: PCE U, TCE 12
 - PCM 141**: PCE U, TCE 12
 - PCM 142**: PCE U, TCE 12
 - PCM 143**: PCE U, TCE 12
 - PCM 144**: PCE U, TCE 12
 - PCM 145**: PCE U, TCE 12
 - PCM 146**: PCE U, TCE 12
 - PCM 147**: PCE U, TCE 12
 - PCM 148**: PCE U, TCE 12
 - PCM 149**: PCE U, TCE 12
 - PCM 150**: PCE U, TCE 12
 - PCM 151**: PCE U, TCE 12
 - PCM 152**: PCE U, TCE 12
 - PCM 153**: PCE U, TCE 12
 - PCM 154**: PCE U, TCE 12
 - PCM 155**: PCE U, TCE 12
 - PCM 156**: PCE U, TCE 12
 - PCM 157**: PCE U, TCE 12
 - PCM 158**: PCE U, TCE 12
 - PCM 159**: PCE U, TCE 12
 - PCM 160**: PCE U, TCE 12
 - PCM 161**: PCE U, TCE 12
 - PCM 162**: PCE U, TCE 12
 - PCM 163**: PCE U, TCE 12
 - PCM 164**: PCE U, TCE 12
 - PCM 165**: PCE U, TCE 12
 - PCM 166**: PCE U, TCE 12
 - PCM 167**: PCE U, TCE 12
 - PCM 168**: PCE U, TCE 12
 - PCM 169**: PCE U, TCE 12
 - PCM 170**: PCE U, TCE 12
 - PCM 171**: PCE U, TCE 12
 - PCM 172**: PCE U, TCE 12
 - PCM 173**: PCE U, TCE 12
 - PCM 174**: PCE U, TCE 12
 - PCM 175**: PCE U, TCE 12
 - PCM 176**: PCE U, TCE 12
 - PCM 177**: PCE U, TCE 12
 - PCM 178**: PCE U, TCE 12
 - PCM 179**: PCE U, TCE 12
 - PCM 180**: PCE U, TCE 12
 - PCM 181**: PCE U, TCE 12
 - PCM 182**: PCE U, TCE 12
 - PCM 183**: PCE U, TCE 12
 - PCM 184**: PCE U, TCE 12
 - PCM 185**: PCE U, TCE 12
 - PCM 186**: PCE U, TCE 12
 - PCM 187**: PCE U, TCE 12
 - PCM 188**: PCE U, TCE 12
 - PCM 189**: PCE U, TCE 12
 - PCM 190**: PCE U, TCE 12
 - PCM 191**: PCE U, TCE 12
 - PCM 192**: PCE U, TCE 12
 - PCM 193**: PCE U, TCE 12
 - PCM 194**: PCE U, TCE 12
 - PCM 195**: PCE U, TCE 12
 - PCM 196**: PCE U, TCE 12
 - PCM 197**: PCE U, TCE 12
 - PCM 198**: PCE U, TCE 12
 - PCM 199**: PCE U, TCE 12
 - PCM 200**: PCE U, TCE 12
 - PCM 201**: PCE U, TCE 12
 - PCM 202**: PCE U, TCE 12
 - PCM 203**: PCE U, TCE 12
 - PCM 204**: PCE U, TCE 12
 - PCM 205**: PCE U, TCE 12
 - PCM 206**: PCE U, TCE 12
 - PCM 207**: PCE U, TCE 12
 - PCM 208**: PCE U, TCE 12
 - PCM 209**: PCE U, TCE 12
 - PCM 210**: PCE U, TCE 12
 - PCM 211**: PCE U, TCE 12
 - PCM 212**: PCE U, TCE 12
 - PCM 213**: PCE U, TCE 12
 - PCM 214**: PCE U, TCE 12
 - PCM 215**: PCE U, TCE 12
 - PCM 216**: PCE U, TCE 12
 - PCM 217**: PCE U, TCE 12
 - PCM 218**: PCE U, TCE 12
 - PCM 219**: PCE U, TCE 12
 - PCM 220**: PCE U, TCE 12
 - PCM 221**: PCE U, TCE 12
 - PCM 222**: PCE U, TCE 12
 - PCM 223**: PCE U, TCE 12
 - PCM 224**: PCE U, TCE 12
 - PCM 225**: PCE U, TCE 12
 - PCM 226**: PCE U, TCE 12
 - PCM 227**: PCE U, TCE 12
 - PCM 228**: PCE U, TCE 12
 - PCM 229**: PCE U, TCE 12
 - PCM 230**: PCE U, TCE 12
 - PCM 231**: PCE U, TCE 12
 - PCM 232**: PCE U, TCE 12
 - PCM 233**: PCE U, TCE 12
 - PCM 234**: PCE U, TCE 12
 - PCM 235**: PCE U, TCE 12
 - PCM 236**: PCE U, TCE 12
 - PCM 237**: PCE U, TCE 12
 - PCM 238**: PCE U, TCE 12
 - PCM 239**: PCE U, TCE 12
 - PCM 240**: PCE U, TCE 12
 - PCM 241**: PCE U, TCE 12
 - PCM 242**: PCE U, TCE 12
 - PCM 243**: PCE U, TCE 12
 - PCM 244**: PCE U, TCE 12
 - PCM 245**: PCE U, TCE 12
 - PCM 246**: PCE U, TCE 12
 - PCM 247**: PCE U, TCE 12
 - PCM 248**: PCE U, TCE 12
 - PCM 249**: PCE U, TCE 12
 - PCM 250**: PCE U, TCE 12
 - PCM 251**: PCE U, TCE 12
 - PCM 252**: PCE U, TCE 12
 - PCM 253**: PCE U, TCE 12
 - PCM 254**: PCE U, TCE 12
 - PCM 255**: PCE U, TCE 12
 - PCM 256**: PCE U, TCE 12
 - PCM 257**: PCE U, TCE 12
 - PCM 258**: PCE U, TCE 12
 - PCM 259**: PCE U, TCE 12
 - PCM 260**: PCE U, TCE 12
 - PCM 261**: PCE U, TCE 12
 - PCM 262**: PCE U, TCE 12
 - PCM 263**: PCE U, TCE 12
 - PCM 264**: PCE U, TCE 12
 - PCM 265**: PCE U, TCE 12
 - PCM 266**: PCE U, TCE 12
 - PCM 267**: PCE U

Dirt roads

MAP ID: 88-0238




Figure 6-5

VOC Investigation Borehole Location Map 903 Pad

EXPLANATION

VOC Boreholes Completed in 1998

Groundwater Monitoring Well

Soil Gas Concentrations > 100 ppm

Individual Hazardous
Substance Site
(HSS T12)

Standard Map Features

Lakes and ponds


Streams, ditches, or other
drainage features

Fences and other barriers

Paved roads

Dirt roads

DATA SOURCE:
Buildings, fences, hydrography, roads and other
features shown on this map were obtained from
aerial photography and ground truthing data
collected by E&S of R&S, Las Vegas,
Digitized from the orthophotograph, 1985



Scale = 1 : 890
1 inch represents approximately 74 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
300 South 44th
Golden, CO 80423-464

MAP ID: rfa-rpt

September 28, 1998

N:\T_Srv\w\projects\98\rfes\rfes-903pad.mxd




Figure 6-6
Trench 1
Site Location

EXPLANATION

- Contours (5' intervals)
- Trench 1 Tent
- Trench 1

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Paved roads
- Dirt roads

DATA SOURCE:
Buildings, fences, hydrography, roads and other features were digitized from the orthophotograph
captured by ESRI, Inc., Las Vegas, NV
Digitized from the orthophotograph, 1995

Scale = 1 : 2500
1 inch represents approximately 249 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
P.O. Box 444
Golden, CO 80602-0444

MAP ID: 99-0457

September 28, 1999

NT_Srvr:\projects\ty99\99-0437\trench1.nam

Figure 7-1
Real-Time
Groundwater Monitoring
Well Locations


EXPLANATION

- Groundwater well with real time water level monitoring
- Groundwater well added to real time water level monitoring program during 1999

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Paved roads
- Dirt roads

DATA SOURCE:
Buildings, fences, hydrography, roads and other structures from 1994 aerial fly-over data captured by EG&G RSI, Las Vegas.
Digitized from the orthophotographs, 1996



Scale = 1:21330
1 inch represents approximately 1778 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
Rocky Mountain Remediation Group
P.O. Box 464
Golden, CO 80602-0464

MAP ID: 88-0191

September 28, 1999



NT:\Srv\proj\env\98\8\ten-rp\rota_figures\fig_62\wtr-level-nl.mxd


Figure 7-2
CY1998
Well Abandonments and
Completions

- EXPLANATION**
- 1998 Groundwater Monitoring Well Abandonments
 - 1998 Groundwater Monitoring Well Completions

Standard Map Features

- Buildings and other structures
- Solar Evaporation Ponds (SEP)
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Paved roads
- Dirt roads

DATA SOURCE:
Buildings, fences, hydrography, roads and other features shown on this map were obtained by EGIS, Inc., Las Vegas, NV, from the orthophotograph, 1995.



Scale = 1 : 8980
1 inch represents approximately 748 feet




State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
Boulder, CO 80402-9464

MAP ID: 98-0430

September 28, 1998






Plate 1

IMP Monitoring Well Location Map

EXPLANATION

IMP Well Type

- Water Quality Flow Monitoring
- Industrial Area Flow Monitoring
- Background Flow Monitoring
- D&D Monitoring
- Non-IMP

Standard Map Features

- Buildings
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contours (20' Intervals)
- Roads
- Rocky Flats Boundary

DATA SOURCE:
Buildings, fences, hydrography, roads and other features were digitized from aerial data captured by EG&G RSL Las Vegas. Digitized from the orthophotographs. 1/95

DISCLAIMER:
The data shown on this map is for informational purposes only. It is not intended to be used for legal or regulatory purposes. The data is not guaranteed to be accurate or complete. The user assumes all responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scale = 1 : 7200
1 inch represents 600 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:



MAP ID: 1999

rfa

ADMIN RECORD

September 23, 1999

500-A-003946



Plate 9

Water Level Change Map

1996 - 1998

Fourth Quarter Data


- Groundwater Monitoring Well (with change in water level)
- Contour depicting Positive Change in Water Level
- Contour depicting Negative Change in Water Level
- Contour depicting Zero Change in Water Level

Standard Map Features

- Buildings and other structures
- Solar evaporation ponds
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads

DATA SOURCE:
Buildings, fences, hydrography, roads and other structures from 1994 aerial fly-over data captured by EG&G RSL, Las Vegas. Digitized from the orthophotographs. 1995 topography contours were derived from digital elevation model (DEM) data captured by the same fly-over. The DEM data was processed by the Remote Sensing Lab, Las Vegas, NV, 1994 Aerial Flyover at ~ 10 meter resolution. DEM post-processing performed by MK, Winter 1997.

DISCLAIMER:
This map is the property of Rocky Mountain Remediation Services, LLC. It is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Rocky Mountain Remediation Services, LLC. This map is provided as a service to the client and is not to be used for any purpose other than the one for which it was prepared. The user assumes all liability for any use of this map.



Scale = 1 : 7760
1 inch represents approximately 647 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:



Rocky Mountain Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 1000
Golden, CO 80402-0484

MAP ID: 99-0381

ADMIN/REG/CD

August 13, 1999

1: 2,000,000

1: 2,000,000

1: 2,000,000

Water Level Change Map
1996 - 1998

Second Quarter Data

- Groundwater Monitoring Well
(with change in water level)
- Contour depicting Positive
Change In Water Level
- Contour depicting Negative
Change In Water Level
- Contour depicting Zero
Change In Water Level

Standard Map Features

- Buildings and other structures
- Solar evaporation ponds
- Lakes and ponds
- Streams, ditches, or other
drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads

DATA SOURCE:
Topographic maps, hydrography, roads and other structures from 1994 aerial flyover data captured by EG&G RSL, Las Vegas. Digitized from the orthophotographs, 1995 Topology (contours) were derived from digital elevation model (DEM) data by Morrison Knudsen (MK) using ESRI Arc TIN and Arc Hydro software. The DEM data was captured by the Remate, Spectralab, Las Vegas, NV, 1994 Aerial Flyover at ~ 10 meter resolution. DEM post-processing performed by MK, Winter 1997.

DISCLAIMER:
This map was prepared by Rocky Mountain Remediation Services, L.L.C. and was prepared by the company as a product of its business. It is not intended to be used for any other purpose. The user assumes all responsibility for the use of this map. The user acknowledges that the use of this map represents that its use would not infringe privately owned rights.


Scale = 1 : 7760
1 inch represents approximately 647 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:



Rocky Mountain Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
1600 West 10th Avenue
Golden, CO 80402-0464




Plate 7

Nitrate Concentration

in Groundwater, 1991-1998 (Avg.)

- Nitrate concentration equal to or greater than 10 mg/L (as N)
- Nitrate concentration equal to or greater than 1000 mg/L (as N)

Nitrate Concentration (mg/L)

- 0 - 1
- 1 - 5
- 5 - 10
- 10 - 100
- 100 - 1000
- > 1000

- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells

Standard Map Features

- Buildings and other structures
- Solar evaporation ponds
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads

Scale = 1 : 3180

1 inch represents 265 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:

FMRS Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 484
Golden, CO 80402-0464

MAP ID: rfa-rpt

September 01, 1999

Plate 6

Water Quality Parameters
in Groundwater
RFCAs Wells, 1998

Well Classifications

- Plume Definition
- Plume Extent
- Performance Monitoring
- Drainage
- Boundary
- RCRA
- D&D
- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells
- Surface Water
- Monitoring Locations

Standard Map Features

- Buildings and other structures
- Solar evaporation ponds
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads

NS = Not Sampled
LW = Lack of Water
BDL = Below Detectable Limit
All results in milligrams per liter (mg/L)

Scale = 1:7090
1 inch represents approximately 59.1 feet



State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:



Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
P.O. Box 484
Golden, CO 80402-0484

MAP ID: 99-0331

ADMIN: REC-22

2/28

September 02, 1999

30-47-003946



Plate 5
VOCs in Groundwater
RFCAs Wells, 1998


Well Classifications

- Plume Definition
- Plume Extent
- Performance Monitoring
- Drainage
- Boundary
- △ RCRA
- ◇ D&D
- Alluvial Wells
- Bedrock Wells
- ◇ Alluvial/Bedrock Wells
- ★ Surface Water
- Monitoring Locations

Standard Map Features

- Buildings and other structures
- Solar evaporation ponds
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads


US
M = 3000 ft
LW = Lack of Water
RD = Below Detectable Limit



U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:
RMRS
Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
Rocky Flats Environmental Technology Site
Golden, CO 80402-0464

MAP ID: 99-0352-ADMIN-RECCAD-8-27 September 01, 1999



11000 10999 10998 10997 10996 10995 10994 10993 10992 10991 10990 10989 10988 10987 10986 10985 10984 10983 10982 10981 10980 10979 10978 10977 10976 10975 10974 10973 10972 10971 10970 10969 10968 10967 10966 10965 10964 10963 10962 10961 10960 10959 10958 10957 10956 10955 10954 10953 10952 10951 10950 10949 10948 10947 10946 10945 10944 10943 10942 10941 10940 10939 10938 10937 10936 10935 10934 10933 10932 10931 10930 10929 10928 10927 10926 10925 10924 10923 10922 10921 10920 10919 10918 10917 10916 10915 10914 10913 10912 10911 10910 10909 10908 10907 10906 10905 10904 10903 10902 10901 10900 10899 10898 10897 10896 10895 10894 10893 10892 10891 10890 10889 10888 10887 10886 10885 10884 10883 10882 10881 10880 10879 10878 10877 10876 10875 10874 10873 10872 10871 10870 10869 10868 10867 10866 10865 10864 10863 10862 10861 10860 10859 10858 10857 10856 10855 10854 10853 10852 10851 10850 10849 10848 10847 10846 10845 10844 10843 10842 10841 10840 10839 10838 10837 10836 10835 10834 10833 10832 10831 10830 10829 10828 10827 10826 10825 10824 10823 10822 10821 10820 10819 10818 10817 10816 10815 10814 10813 10812 10811 10810 10809 10808 10807 10806 10805 10804 10803 10802 10801 10800 10799 10798 10797 10796 10795 10794 10793 10792 10791 10790 10789 10788 10787 10786 10785 10784 10783 10782 10781 10780 10779 10778 10777 10776 10775 10774 10773 10772 10771 10770 10769 10768 10767 10766 10765 10764 10763 10762 10761 10760 10759 10758 10757 10756 10755 10754 10753 10752 10751 10750 10749 10748 10747 10746 10745 10744 10743 10742 10741 10740 10739 10738 10737 10736 10735 10734 10733 10732 10731 10730 10729 10728 10727 10726 10725 10724 10723 10722 10721 10720 10719 10718 10717 10716 10715 10714 10713 10712 10711 10710 10709 10708 10707 10706 10705 10704 10703 10702 10701 10700 10699 10698 10697 10696 10695 10694 10693 10692 10691 10690 10689 10688 10687 10686 10685 10684 10683 10682 10681 10680 10679 10678 10677 10676 10675 10674 10673 10672 10671 10670 10669 10668 10667 10666 10665 10664 10663 10662 10661 10660 10659 10658 10657 10656 10655 10654 10653 10652 10651 10650 10649 10648 10647 10646 10645 10644 10643 10642 10641 10640 10639 10638 10637 10636 10635 10634 10633 10632 10631 10630 10629 10628 10627 10626 10625 10624 10623 10622 10621 10620 10619 10618 10617 10616 10615 10614 10613 10612 10611 10610 10609 10608 10607 10606 10605 10604 10603 10602 10601 10600 10599 10598 10597 10596 10595 10594 10593 10592 10591 10590 10589 10588 10587 10586 10585 10584 10583 10582 10581 10580 10579 10578 10577 10576 10575 10574 10573 10572 10571 10570 10569 10568 10567 10566 10565 10564 10563 10562 10561 10560 10559 10558 10557 10556 10555 10554 10553 10552 10551 10550 10549 10548 10547 10546 10545 10544 10543 10542 10541 10540 10539 10538 10537 10536 10535 10534 10533 10532 10531 10530 10529 10528 10527 10526 10525 10524 10523 10522 10521 10520 10519 10518 10517 10516 10515 10514 10513 10512 10511 10510 10509 10508 10507 10506 10505 10504 10503 10502 10501 10500 10499 10498 10497 10496 10495 10494 10493 10492 10491 10490 10489 10488 10487 10486 10485 10484 10483 10482 10481 10480 10479 10478 10477 10476 10475 10474 10473 10472 10471 10470 10469 10468 10467 10466 10465 10464 10463 10462 10461 10460 10459 10458 10457 10456 10455 10454 10453 10452 10451 10450 10449 10448 10447 10446 10445 10444 10443 10442 10441 10440 10439 10438 10437 10436 10435 10434 10433 10432 10431 10430 10429 10428 10427 10426 10425 10424 10423 10422 10421 10420 10419 10418 10417 10416 10415 10414 10413 10412 10411 10410 10409 10408 10407 10406 10405 10404 10403 10402 10401 10400 10399 10398 10397 10396 10395 10394 10393 10392 10391 10390 10389 10388 10387 10386 10385 10384 10383 10382 10381 10380 10379 10378 10377 10376 10375 10374 10373 10372 10371 10370 10369 10368 10367 10366 10365 10364 10363 10362 10361 10360 10359 10358 10357 10356 10355 10354 10353 10352 10351 10350 10349 10348 10347 10346 10345 10344 10343 10342 10341 10340 10339 10338 10337 10336 10335 10334 10333 10332 10331 10330 10329 10328 10327 10326 10325 10324 10323 10322 10321 10320 10319 10318 10317 10316 10315 10314 10313 10312 10311 10310 10309 10308 10307 10306 10305 10304 10303 10302 10301 10300 10299 10298 10297 10296 10295 10294 10293 10292 10291 10290 10289 10288 10287 10286 10285 10284 10283 10282 10281 10280 10279 10278 10277 10276 10275 10274 10273 10272 10271 10270 10269 10268 10267 10266 10265 10264 10263 10262 10261 10260 10259 10258 10257 10256 10255 10254 10253 10252 10251 10250 10249 10248 10247 10246 10245 10244 10243 10242 10241 10240 10239 10238 10237 10236 10235 10234 10233 10232 10231 10230 10229 10228 10227 10226 10225 10224 10223 10222 10221 10220 10219 10218 10217 10216 10215 10214 10213 10212 10211 10210 10209 10208 10207 10206 10205 10204 10203 10202 10201 10200 10199 10198 10197 10196 10195 10194 10193 10192 10191 10190 10189 10188 10187 10186 10185 10184 10183 10182 10181 10180 10179 10178 10177 10176 10175 10174 10173 10172 10171 10170 10169 10168 10167 10166 10165 10164 10163 10162 10161 10160 10159 10158 10157 10156 10155 10154 10153 10152 10151 10150 10149 10148 10147 10146 10145 10144 10143 10142 10141 10140 10139 10138 10137 10136 10135 10134 10133 10132 10131 10130 10129 10128 10127 10126 10125 10124 10123 10122 10121 10120 10119 10118 10117 10116 10115 10114 10113 10112 10111 10110 10109 10108 10107 10106 10105 10104 10103 10102 10101 10100 10099 10098 10097 10096 10095 10094 10093 10092 10091 10090 10089 10088 10087 10086 10085 10084 10083 10082 10081 10080 10079 10078 10077 10076 10075 10074 10073 10072 10071 10070 10069 10068 10067 10066 10065 10064 10063 10062 10061 10060 10059 10058 10057 10056 10055 10054 10053 10052 10051 10050 10049 10048 10047 10046 10045 10044 10043 10042 10041 10040 10039 10038 10037 10036 10035 10034 10033 10032 10031 10030 10029 10028 10027 10026 10025 10024 10023 10022 10021 10020 10019 10018 10017 10016 10015 10014 10013 10012 10011 10010 10009 10008 10007 10006 10005 10004 10003 10002 10001 10000 9999 9998 9997 9996 9995 9994 9993 9992 9991 9990 9989 9988 9987 9986 9985 9984 9983 9982 9981 9980 9979 9978 9977 9976 9975 9974 9973 9972 9971 9970 9969 9968 9967 9966 9965 9964 9963 9962 9961 9960 9959 9958 9957 9956 9955 9954 9953 9952 9951 9950 9949 9948 9947 9946 9945 9944 9943 9942 9941 9940 9939 9938 9937 9936 9935 9934 9933 9932 9931 9930 9929 9928 9927 9926 9925 9924 9923 9922 9921 9920 9919 9918 9917 9916 9915 9914 9913 9912 9911 9910 9909 9908 9907 9906 9905 9904 9903 9902 9901 9900 9899 9898 9897 9896 9895 9894 9893 9892 9891 9890 9889 9888 9887 9886 9885 9884 9883 9882 9881 9880 9879 9878 9877 9876 9875 9874 9873 9872 9871 9870 9869 9868 9867 9866 9865 9864 9863 9862 9861 9860 9859 9858 9857 9856 9855 9854 9853 9852 9851 9850 9849 9848 9847 9846 9845 9844 9843 9842 9841 9840 9839 9838 9837 9836 9835 9834 9833 9832 9831 9830 9829 9828 9827 9826 9825 9824 9823 9822 9821 9820 9819 9818 9817 9816 9815 9814 9813 9812 9811 9810 9809 9808 9807 9806 9805 9804 9803 9802 9801 9800 9799 9798 9797 9796 9795 9794 9793 9792 9791 9790 9789 9788 9787 9786 9785 9784 9783 9782 9781 9780 9779 9778 9777 9776 9775 9774 9773 9772 9771 9770 9769 9768 9767 9766 9765 9764 9763 9762 9761 9760 9759 9758 9757 9756 9755 9754 9753 9752 9751 9750 9749 9748 9747 9746 9745 9744 9743 9742 9741 9740 9739 9738 9737 9736 9735 9734 9733 9732 9731 9730 9729 9728 9727 9726 9725 9724 9723 9722 9721 9720 9719 9718 9717 9716 9715 9714 9713 9712 9711 9710 9709 9708 9707 9706 9705 9704 9703 9702 9701 9700 9699 9698 9697 9696 9695 9694 9693 9692 9691 9690 9689 9688 9687 9686 9685 9684 9683 9682 9681 9680 9679 9678 9677 9676 9675 9674 9673 9672 9671 9670 9669 9668 9667 9666 9665 9664 9663 9662 9661 9660 9659 9658 9657 9656 9655 9654 9653 9652 9651 9650 9649 9648 9647 9646 9645 9644 9643 9642 9641 9640 9639 9638 9637 9636 9635 9634 9633 9632 9631 9630 9629 9628 9627 9626 9625 9624 9623 9622 9621 9620 9619 9618 9617 9616 9615 9614 9613 9612 9611 9610 9609 9608 9607 9606 9605 9604 9603 9602 9601 9600 9599 9598 9597 9596 9595 9594 9593 9592 9591 9590 9589 9588 9587 9586 9585 9584 9583 9582 9581 9580 9579 9578 9577 9576 9575 9574 9573 9572 9571 9570 9569 9568 9567 9566 9565 9564 9563 9562 9561 9560 9559 9558 9557 9556 9555 9554 9553 9552 9551 9550 9549 9548 9547 9546 9545 9544 9543 9542 9541 9540 9539 9538 9537 9536 9535 9534 9533 9532 9531 9530 9529 9528 9527 9526 9525 9524 9523 9522 9521 9520 9519 9518 9517 9516 9515 9514 9513 9512 9511 9510 9509 9508 9507 9506 9505 9504 9503 9502 9501 9500 9499 9498 9497 9496 9495 9494 9493 9492 9491 9490 9489 9488 9487 9486 9485 9484 9483 9482 9481 9480 9479 9478 9477 9476 9475 9474 9473 9472 9471 9470 9469 9468 9467 9466 9465 9464 9463 9462 9461 9460 9459 9458 9457 9456 9455 9454 9453 9452 9451 9450 9449 9448 9447 9446 9445 9444 9443 9442 9441 9440 9439 9438 9437 9436 9435 9434 9433 9432 9431 9430 9429 9428 9427 9426 9425 9424 9423 9422 9421 9420 9419 9418 9417 9416 9415 9414 9413 9412 9411 9410 9409 9408 9407 9406 9405 9404 9403 9402 9401 9400 9399 9398 9397 9396 9395 9394 9393 9392 9391 9390 9389 9388 9387 9386 9385 9384 9383 9382 9381 9380 9379 9378 9377 9376 9375 9374 9373 9372 9371 9370 9369 9368 9367 9366 9365 9364 9363 9362 9361 9360 9359 9358 9357 9356 9355 9354 9353 9352 9351 9350 9349 9348 9347 9346 9345 9344 9343 9342 9341 9340 9339 9338 9337 9336 9335 9334 9333 9332 9331 9330 9329 9328 9327 9326 9325 9324 9323 9322 9321 9320 9319 9318 9317 9316 9315 9314 9313 9312 9311 9310 9309 9308 9307 9306 9305 9304 9303 9302 9301 9300 9299 9298 9297 9296 9295 9294 9293 9292 9291 9290 9289 9288 9287 9286 9285 9284 9283 9282 9281 9280 9279 9278 9277 9276 9275 9274 9273 9272 9271 9270 9269 9268 9267 9266 9265 9264 9263 9262 9261 9260 9259 9258 9257 9256 9255 9254 9253 9252 9251 9250 9249 9248 9247 9246 9245 9244 9243 9242 9241 9240 9239 9238 9237 9236 9235 9234 9233 9232 9231 9230 9229 9228 9227 9226 9225 9224 9223 9222 9221 9220 9219 9218 9217 9216 9215 9214 9213 9212 9211 9210 9209 9208 9207 9206 9205 9204 9203 9202 9201 9200 9199 9198 9197 9196 9195 9194 9193 9192 9191 9190 9189 9188 9187 9186 9185 9184 9183 9182 9181 9180 9179 9178 9177 9176 9175 9174 9173 9172 9171 9170 9169 9168 9167 9166 9165 9164 9163 9162 9161 9160 9159 9158 9157 9156 9155 9154 9153 9152 9151 9150 9149 9148 9147 9146 9145 9144 9143 9142 9141 9140 9139 9138 9137 9136 9135 9134 9133 9132 9131 9130 9129 9128 9127 9126 9125 9124 9123 9122 9121 9120 9119 9118 9117 9116 9115 9114 9113 9112 9111 9110 9109 9108 9107 9106 9105 9104 9103 9102 9101 9100 9099 9098 9097 9096 9095 9094 9093 9092 9091 9090 9089 9088 9087 9086 9085 9084 9083 9082 9081 9080 9079 9078 9077 9076 9075 9074 9073 9072 9071 9070 9069 9068 9067 9066 9065 9064 9063 9062 9061 9060 9059 9058 9057 9056 9055 9054 9053 9052 9051 9050 9049 9048 9047 9046 9045 9044 9043 9042 9041 9040 9039 9038 9037 9036 9035 9034 9033 9032 9031 9030 9029 9028 9027 9026 9025 9024 9023 9022 9021 9020 9019 9018 9017 9016 9015 9014 9013 9012 9011 9010 9009 9008 9007 9006 9005 9004 9003 9002 9001 9000 8999 8998 8997 899

Radionuclides in Groundwater
RFCAs Wells, 1998

Well Classifications

- Plume Definition
- Plume Extent
- Performance Monitoring
- Drainage
- Boundary
- RCRA
- D&D
- Alluvial Wells
- Bedrock Wells
- Alluvial/Bedrock Wells
- Surface Water Monitoring Locations

Standard Map Features

- Buildings and other structures
- Solar evaporation ponds
- Lakes and ponds
- Streams, ditches, or other drainage features
- Fences and other barriers
- Contour (20-Foot)
- Paved roads
- Dirt roads

one Uranium value above 8.0 pCi/L

NS = Not Sampled
NA = Not Analyzed
LW = Lack of Water


All results in pCi/L

Scale = 1:7090
1 inch represents approximately 591 feet

State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:



Rocky Mountain
Remediation Services, L.L.C.
Geographic Information Systems Group
P.O. Box 468
Golden, CO 80402-0464